



- <<
- < Prev
- Page 1 of 3 ▾
- Next >
- >>

<p style="text-align: right;">SS78NE/108 7749 8821 1"247</p> <p style="text-align: center;">— SECTIONS OF BOREHOLES AT MORFA BANK —</p> <p>BORE N^o 4A</p> <p>STARTED :- 16th SEPT. 1939.</p> <p>GROUND LEVEL = 14.92 A.O.D. FINISHED :- 26th OCT. 1939.</p>			
STRATA.	THICKNESS.	TOTAL DEPTH.	REMARKS.
CLAY.	9'-0"	9'-0"	
PEAT.	5'-0"	14'-0"	
GRAVEL.	5'-8"	19'-8"	
CLAY & COBBLES.			
WATER LEVEL.		W.L. 28'-2"	STRUCK WATER WHICH ROSE TO 3'-6" ABOVE TOP OF BOREHOLE.
	12'-0"	31'-8"	
CLAY, GRAVEL & COBBLES.	8'-6"	40'-2"	
FINE GRAVEL & COBBLES.	3'-6"	43'-8"	
SAND.	5'-7"	49'-3"	
CLAY & COBBLES.	4'-1"	53'-4"	
COBBLES, SAND & FINE GRAVEL.	5'-0"	58'-4"	
COBBLES & SAND.	4'-0"	62'-4"	
PENNANT COBBLES WITH COAL TRACES.	5'-0"	67'-4"	
ROCK.	1'-6"	68'-10"	
	1'-3"	69'-4"	
	3"	70'-9"	
PENNANT.	3'-8"	74'-8"	

British Geological Survey

British Geological Survey

British Geological Survey

Handwritten signature or text