SPR EA1N and EA2 PROJECTS



DEADLINE 2 – COMMENTS ON EXQ1 RESPONSES – 1.4 CONSTRUCTION

Interested Party: SASES IP Reference Nos. 20024106 and 20024110

Issue: 4

Question	Торіс	Question (if any)	Applicant Response or Statement	SASES Comment
1.4.1	Timelines worst case	Timelines The ES states that 3 years is assumed for onshore construction, with 2 years for construction and 1 year for commissioning. The assessment for cumulative effects states that onshore construction would occur sequentially, with the duration doubling. a) Does this mean that construction of the two projects could take 6 years sequentially? b) Please confirm (with reference to relevant Application Documents) the worst-case construction assumption. Do the application documents reflect this worst-case assumption?	a) An initial high-level indicative programme was developed for the ES and presented in Section 6.9 of Chapter 6 Project Description (APP- 054). This highlight the durations of construction for individual parts of each Project. Activities in different parts of the onshore development area will run in parallel with the longest period required for construction of the substation (30 months). In all, it is expected that the total duration of construction will be three years for one Project. It should be noted that the works for the National Grid substation is expected to be up to 48 months, although this would include works for both Projects. If the Projects were constructed sequentially, back to back, construction would take 6 years. b)	The Applicant's response seems to have considered only two scenarios : concurrent or consecutive implementations). The Applicant has applied in Draft DCO for a 7 years' time limit to commence work. Consequently, in the event of Scenario 2 (sequential project implementation) and given the pessimistic prospects of winning sufficient funding through the Contracts for Difference process as expressed below (Response to 1.4.15), the worst case scenario could be Project 1 Starts : year 1 Project 2 starts : year 7 Project duration (each project) ; 3

			For the worst case, each onshore assessment chapter (Chapters 18 – 26 (APP-066 – 074, Chapter 27 (APP- 075) and Chapters 29 (APP-077) all have a stand-alone appendix (Appendix X.2 in each case – e.g. 18.2, 19.2 etc) which considers the two potential cumulative scenarios for the Projects on an impact by impact basis for construction. This justifies in each case the worst case for each impact which is then carried across to the impact assessment within the relevant chapter. In many cases the worst case is the same for either scenario. However, for some receptors having multiple disturbance events (i.e. sequential construction) represents the worst case (for example see table A22.3 in Appendix 22.2 (APP-502).	years Therefore, Worst case Start-to- Finish duration (both projects) could be 9 years.
			Project Description [APP-054]	
1,4.3	Overlapping projects and the two scenarios	Paragraph 17 refers to two cumulative assessment scenarios which are described briefly in paragraph 18. • How are overlapping programmes covered by these two scenarios?	Paragraph 18 introduces the two scenarios. In terms of how these are reflected in the project description, Appendix 6.4 Cumulative Project Description (APP-453) provides a full comparison of infrastructure footprints etc. The tables from Appendix 6.4 (APP-453) are then used to inform the cumulative worst case for each receptor topic. Each receptor topic	Consent for both projects must take account of onshore environmental and human impact, for which almost certainly the least worst case would be concurrent (Scenario 1). The Applicant should be required to assess impact for Scenario 2 in quantitative terms.

	chapter has a stand-alone appendix	It is not practicable for the
	(Appendix X.2 in each case – e.g.	Applicant to model every possible
	18.2, 19.2 etc) which considers the	overlapping projects scenario.
	two potential cumulative scenarios for	However, it should be possible to
	the Projects on an impact by impact	exercise the Applicant's computer
	basis for construction. The two	based quantitative models for a
	scenarios presented cover the two	scenario 3:
	extremes of construction scenarios	That is far work on Draiget 2 to
	possible. Temporally – Parallel	That is for work on Project 2 to
	construction results in the shortest	commence midway through Project 1 development timescale
	possible duration. This can either	r development limescale
	result in a best case (e.g. in relation to	and to predict forecast data for:
	the shortest overall duration of an	Peak resource requirements by
	effect) or a worst case (e.g. in relation	type
	to traffic the worst case is a result of	
	having the most vehicles in the	construction and transport traffic
	shortest time). Sequential construction	peak volumes,
	results in the longest possible duration	 HGV junction waiting times
	(whether construction is back to back	 predicted noise at sensitive
	or there is a gap). This can either result in a worst case (e.g. overall	receptors
	duration of disturbance to residents)	·
	or a best case (e.g. in relation to traffic	• etc
	the vehicle numbers are spread over	Consent for Project 2 should be
	a greater time, reducing daily peaks).	dependent on scenario(s) leading
	For the two examples given above,	to least worst impact.
	any scenario in between parallel of	
	sequential construction (i.e. partial	
	overlap) remains with the assessment	
	envelop (i.e. partial parallel and partial	
	sequential construction). In some	
	cases the assumptions used in the	
	project alone assessment are so	
	precautionary that cumulative impacts	
	can be no worse than project alone	

		under either scenario. For example (Appendix 22.2 Onshore Ecology CIA (APP-502) section 22.3.3, para 20 "The assessment for proposed East Anglia TWO project alone assumes that all the improved grassland (6.4ha) and all the semi-improved grassland habitat (9.4ha) within the onshore development area could be temporarily impacted by the construction of a single project (with a footprint of 77ha) as the worst case scenario. The addition of the proposed East Anglia ONE North project cannot increase the total area of grassland within the onshore development area therefore the project alone worst case cannot be exceeded." The Applicants are confident that, given that there are no blanket assumptions over the worst case and each impact in each receptor topic has been considered individually, that the worst case has been assessed in every case. The Applicants recognise that some clarification may be useful regarding Appendix 6.4 and a revised version will be submitted at Deadline 3.	
1.4.15	Paragraph 310 says that "Cables will be placed directly underground without ducting, although ducting may be used in	a) The scenario described would reduce impacts, as per the rationale applied to East Anglia ONE and East Anglia THREE. The determining factor	General The Applicant has announced on 26/11/2019 that it intended to combine three projects (East

some or all of the route.". a) Bearing in mind that there are	in terms of which construction scenario is adopted will be the	Anglia One North, Two and Three) into one single delivery programme
two projects proceeding side by side onshore, should the	outcome of the Contract for Difference (CfD) auction, scheduled to be held by	with a capacity of 3,100 megawatts (MW), to be known as The East
onshore cables be laid in ducts throughout, with a view to	the UK Government in 2021 and every two years thereafter. Depending	Anglia Hub. The three projects would be procured together to
reducing the construction impacts in the event that the	on the auction prices achieved, the auctions could see 1 to 2 gigawatts of	leverage their scale with a continuous installation programme.
projects are constructed consecutively rather than	new offshore wind being deployed every year in the 2020s. Whilst the	Ref. https://www.scottishpowerrenewabl
concurrently? . b) What would be the advantages and	precise level of Government funding for each round of future CfD auctions	es.com/news/pages/iberdrolas sco ttishpower renewables to create
disadvantages of installing ducts for the second project at the same time as installing the	is yet to be announced, it is clear that the Government is continuing to drive the offshore wind sector to reduce	the_3100_mw_east_anglia_hub_of fshore_wind_development.aspx
ducts and cables for the first project? And c) if the onshore	costs. Recent CfD auctions have seen significant reductions in the cost of	In other words, the Applicant intends to deliver a Programme of
works were carried out separately for each project, is it	offshore wind projects. In 2015, CfD Round 1 (in which East Anglia ONE	Work comprising three projects EA3, EA1N and EA2.
intended that the haul road would remain in place between	successfully secured its CfD), achieved an average clearing price of	The Applicant should have
the construction of the first and second projects?	approximately £117/MWh. In 2017, CfD Round 2 achieved prices as low	submitted with each project DCO submission its Programme Plan
	as £58/MWh. The offshore wind CfD prices for CfD Round 3 in 2019 were	indicating as a minimum and inter alia the planned sequencing of and
	lower still at around £40/MWh. All indications are that this downward	interdependencies between the component projects.
	pressure will continue into the 2021 CfD auction, when the Projects are	ExA cannot be expected to assess overall benefit versus cost to the
	expected to enter the Round 4 CfD auction. This reduction in CfD strike	environment and human impact if only individual independent project
	price represents a significant challenge for the offshore wind sector	proposals are put forward for approval without the context of a
	to reduce construction costs, and is likely to result in only the most	formal Programme Plan indicating key project dependencies and

worst case assumes 19 jointing bays along the onshore cable route. The jointing bays would need to be accessed via a haul road. Cables would be pulled through the ducts across the full-length of the onshore cable route. • The advantage would be to reduce the intrusiveness of the cable pulling when compared to open trenching for the second project. The footprint for impacts would be the same as per parallel construction, however some repeated impacts would be avoided or reduced in magnitude for the second project. • There are no disadvantages from this approach in terms of environmental impact O Requirement 29 of the dratt DCO (APP-023) requires that any land which is used temporarily for construction of the onshore works and not uttimately incorporated into permanent works or approved landscaping must be reinstated within twelve months of completion of the relevant stage of the works or such other period as the relevant planning authority may approve. The assumption would therefore be that the haul road will be removed and the land reinstated where there is a gap between the construction of the first project and the sacond project.
with the relevant planning authority

			that works are not to be reinstated within the twelve month period. This flexibility is intended to cover the situation where it would make sense (for example, from an environmental perspective) for temporary works to remain in place between the construction of one project and the construction of the second (i.e. where removal and reconstruction of the temporary works may give rise to more impacts than leaving them in place between the construction of the first and second projects might).	
1.4.17	Permanent Cable Corridor Easement 20m	Paragraph 329 states that "Post construction, a permanent cable corridor easement of approximately 20m in width is anticipated" except for where a wider corridor is needed, for example where HDD is used, and Plate 6.20 shows an	 a) Within the permanent cable corridor easement there is space for spoil storage where any digging is required to access the cable for maintenance. b) The same permanent easement width is required if the cables are laid directly or in ducts and what is being sought is comparable with similar schemes. 	Re: a) There no mention in 7.1 Cable Statement of any specific areas along the cable route designated for Spoil Storage. In view of their potential environmental / community impact, these areas must be specified before consent.
1.4.18	Highways special crossing techniques	Table 6.25 lists all the locations where the onshore cable route crosses the public highway and paragraph 366 says that "some crossing locations will require special crossing techniques". Paragraph 368 says that "the use of an onshore HDD is only for consideration where	a) The Onshore Crossing Schedule can be found in Appendix 7 of this document. b) It is intended that open trenching be used in all cases where the cable route crosses the public highway. The process for open trenching for road crossings, which will maintain traffic use at all times, is described in Chapter 6 Project	

		the onshore cable route crosses the Leiston- Aldeburgh SSSI/Sandlings SPA. However, an open-cut crossing technique is preferred" a) Please provide an onshore crossing schedule and plan giving, for each obstacle to be crossed by the cables, an ID, sheet number, type and description of obstacle (eg woodland, hedgerow, highway, public right of way, footpath, river, utility) and your proposed crossing method. b) Is it intended that trenchless techniques be used where the onshore cable route crosses the public highway to minimise impacts on traffic and access to property? c) Is it intended that trenchless techniques be used where the onshore cable route crosses the Leiston Aldeburgh SSSI/Sandlings SPA? d) If not, please explain what technique you intend to use and why	Description (APP-054) sections 6.7.3.10.4 & 6.7.3.10.5. The Applicants therefore do not consider that trenchless techniques are necessary to cross these roads in this instance. c) The EIA and draft DCO provide for either a trenchless and open-trench solution at the SPA crossing. The Outline SPA Crossing Method Statement (ExA.AS-3.D1.V1) which has been submitted at Deadline 1, provides more information. This crossing is the subject of ongoing discussion with the LPAs, Natural England and the RSPB. d) The Outline SPA Crossing Method Statement presents and justifies the Applicants' preferred solution for crossing the SPA, which is the open trench technique.	
			Outline Code of Construction Practice [APP-578]	
1.4.24	B1122 and B1143 crossings open	With reference to oral submissions at OFHs 1 – 3 (7 – 9 October) raising concerns	Within Table 26.4, Chapter 26 Traffic and Transport of the ES (APP-074), the Applicant has committed to no	SASES welcomes the Applicant's confirmation and commitments here (and reiterated in its Deadline

	at all times	about the extent of road	roads being fully closed to install the	1 submission : 'Applicants'
		closures and diversions likely to	Projects' cables under the public	Responses to Examining
		be caused by cable trenching,	highway. The Applicant will therefore	Authority's Written Questions
		the Applicant is requested to	ensure that the B1122 Aldeburgh	Appendix 7 Onshore Crossing)'
		respond to these points, and	Road will remain open at all times and	with regard to ensuring that the
		comment on the possible use of	minimise disruption by implementing	B1122 Aldeburgh Road would
		HDD to mitigate this particular	the following measures (if required): •	remain open at all times and that a
		construction effect. Can HDD be	The road crossings will be completed	safe route would be maintained for
		used to further limit the extent of	in two stages maintaining one traffic	pedestrians through the works area
		diversions due to road	lane in each direction; • Traffic will be	along the B1122.
		crossings?	controlled through temporary traffic	
			signals; • A safe route will be	
			maintained for pedestrians through	
			the works area along the B1122I. •	
			The Applicant will consult with the	
			relevant highway authority and local	
			stakeholders to develop a final Travel	
			Plan as part of the discharge of	
			requirements process. This will accord	
			with the Outline Travel Plan (APP-	
			588) in line with Requirement 28 of	
			the draft DCO. • Advanced signing will	
			be implemented to assist drivers in	
			finding alternative routes; and • The	
			works will be staggered (i.e. not	
			closing a lane on the B1122 at the	
			same time as the B1069). The	
			Applicants note that the onshore cable	
			route does not cross Sizewell Gap	
			and therefore this road will not be	
			affected as a result of trenching	
			works. As per their response to	
			question 1.2.66, the Applicants	
			consider that there is insufficient	
			lateral space to accommodate a	
L	1	I	1	

			trenchless crossing methodology at the B1122 crossing	
1.4.34	Noise and vibration monitoring	Paragraph 79 says in respect of noise and vibration management that "a programme of monitoring may be required." and paragraph 85 says that "If it is deemed by the Local Planning Authority that during construction monitoring of construction noise is necessary, then the locations of such monitoring will be agreed in advance with the Local Planning Authority.". a) Surely a programme will be required on a project of this scale in order to optimise mitigation? And b) should the programme start with baseline measurements taken before site clearance starts?	It is the Applicants' understanding that the monitoring methodology set out within the Outline CoCP (APP-578) will only be implemented where issues arise (i.e. in the event of the Project receiving a noise complaint) or where noisy construction activities are anticipated to be undertaken in close proximity to noise sensitive receptors. The measures in relation to noise set out within the final approved CoCP prepared post-consent and in accordance with the Outline CoCP (APP-578) will be based upon the detailed design of the Project and the construction methods to be employed by the appointed contractor. The Applicants do not consider it appropriate to commit to monitoring at this time, when the worst case construction noise assessed and presented within Chapter 25 Noise and Vibration of the ES (APP-073) may not materialise during construction. The Applicants will consult with the relevant planning authority through the post-consent stage when discharging requirements and throughout construction to establish the requirement for site- specific monitoring. Requirement 22	The Outline CoCP should include a specification for regular unsolicited noise monitoring of and reporting on specific sensitive locations to be determined by the Local Planning Authority (LA) . Where a given threshold has been exceeded, it should trigger an automatic notification to the LA. Regular reporting summaries should be posted and available to all stakeholders on a publicly accessible internet location.

			of the draft DCO (APP-023) includes the preparation of a construction phase noise and vibration management plan as part of the CoCP, which must be approved before works commence.	
1.4.36	River Hundred Crossing	2 Paragraph 104 says that the crossing of the Hundred River will be a trenched crossing, requiring a temporary bridge or culvert for the haul road, and temporary dams, flumes and pumps to minimise upstream impoundment and maintain flows downstream, all with the attendant risk of flooding and surface water pollution. • Please explain why trenchless methods such as HDD are not proposed for this crossing	Please refer to the answers provided for question 1.2.66.	In view of the high level of fluvial flood risk in this area, we ask that the Applicant shall be required to provide measures within a R. Hundred Crossing Plan that avoid any risk of flooding at homes in Gipsy Lane, immediately downstream of the proposed crossing and that pumps be selected and sited such that noise disturbance at homes in the vicinity is minimal.
1.4.37	Onshore cable corridor widths	Cable corridor widths onshore ES Appendix 6.4 'Cumulative Project Description' [APP-453] states that the onshore cable route width would generally be no wider than 64m if the two projects were constructed concurrently i.e. 32m for each project. However, R12(14) refers to the following working widths: a) where the cables cross the Sandlings SPA the	All working widths listed in Requirement 12(14) are correct for a single project in either construction scenario. Further explanations for these working widths is set out in sections 6.7.3.1.1 and 6.7.3.1.2 of ES Chapter 6 Project Description (APP- 054). How reduced working widths are applied in either construction scenario is set out in Table A6.1 in ES Appendix 6.4 (APP-453). The Applicants recognise that some	SASES supports the need for the Applicant to provide considerably more clarification on the working widths for each scenario and each method of construction still under consideration within a revised ES Appendix 6.4 'Cumulative Project Description'. This might be more appropriately titled 'EA1N/ EA2 In Combination Project Description'.

working width of the onshore cable route must not exceed— (i) 16.1 metres, in the event that open cut trenching is used; (ii) 90 metres, in the	clarification may be useful regarding Appendix 6.4 and a revised version will be submitted at Deadline 3.	
---	---	--