



Norfolk Vanguard Offshore Wind Farm Appoint 17 2

Appendix 17.3

Stage 2 Geoarchaeological Reporting

Environmental Statement

Volume 3 - Appendices

Applicant: Norfolk Vanguard Limited Document Reference: 6.2.17.3

RHDHV Document Reference: PB4476-005-0173

Pursuant to APFP Regulation: 5(2)(a)

Date: June 2018
Revision: Version 1

Author:

Photo: Kentish Flats Offshore Wind Farm





Environmental Impact Assessment Environmental Statement

Document Reference: PB4476-005-0173

June 2018

For and on behalf of Norfolk Vanguard Limited									
Approved by: Ruari Lean, Rebecca Sherwood									
Signed:									
Date: 8 th June 2018									



Norfolk Vanguard Offshore Wind Farm

Stage 2 Geoarchaeological Recording



Ref: 112380.03 March 2018



© Wessex Archaeology Ltd 2017, all rights reserved.

Portway House Old Sarum Park Salisbury Wiltshire SP4 6EB

www.wessexarch.co.uk

Wessex Archaeology Ltd is a Registered Charity no. 287786 (England & Wales) and SC042630 (Scotland)

Disclaimer

The material contained in this report was designed as an integral part of a report to an individual client and was prepared solely for the benefit of that client. The material contained in this report does not necessarily stand on its own and is not intended to nor should it be relied upon by any third party. To the fullest extent permitted by law Wessex Archaeology will not be liable by reason of breach of contract negligence or otherwise for any loss or damage (whether direct indirect or consequential) occasioned to any person acting or omitting to act or refraining from acting in reliance upon the material contained in this report arising from or connected with any error or omission in the material contained in the report. Loss or damage as referred to above shall be deemed to include, but is not limited to, any loss of profits or anticipated profits damage to reputation or goodwill loss of business or anticipated business damages costs expenses incurred or payable to any third party (in all cases whether direct indirect or consequential) or any other direct indirect or consequential loss or damage.



Stage 2 Geoarchaeological recording and deposit modelling

Prepared for:

Royal HaskoningDHV Rightwell House Bretton Peterborough PE3 8DW

Prepared by:

Wessex Archaeology Portway House Old Sarum Salisbury SP4 6EB

www.wessexarch.co.uk

March 2018

Report Ref 112380.03



Quality Assurance

Project Code	112380	Accession Code	Client Ref.	
Planning Application Ref.		Ordnance Survey (OS) national grid reference (NGR)		

Version	Status*	Prepared by	Checked and Approved By	Approver's Signature	Date				
v01	Е	Alex Brown	DRN		13/10/17				
File:	W:\Proje	ects\112380_Reports	s\112380_Vang	uard_Stage 2	ı				
V02	F	Alex Brown	DRN		01/11/17				
File:	W:\Projects\112380_Reports\112380_Vanguard_Stage 2_v2_Nov2017								
	F	Alex Brown	DRN		20/02/18				
File:	W:\Proje	ects\112380_Reports	s\Submitted\112	380_Vanguard_Stage 2_Fe	b18				
V03	F	Alex Brown	DRN		19/03/18				
File:	W:\Proje	ects\112380_Reports	s\Submitted\112	380_Vanguard_Stage 2_v3					
V03	F	Alex Brown/ Claire Mellett	DRN		23/03/18				
File:	W:\Proje	ects\112380_Reports	s\Submitted\112	380_Vanguard_Stage 2_v3					

^{*} I = Internal Draft; E = External Draft; F = Final

DISCLAIMER

THE MATERIAL CONTAINED IN THIS REPORT WAS DESIGNED AS AN INTEGRAL PART OF A REPORT TO AN INDIVIDUAL CLIENT AND WAS PREPARED SOLELY FOR THE BENEFIT OF THAT CLIENT. THE MATERIAL CONTAINED IN THIS REPORT DOES NOT NECESSARILY STAND ON ITS OWN AND IS NOT INTENDED TO NOR SHOULD IT BE RELIED UPON BY ANY THIRD PARTY. TO THE FULLEST EXTENT PERMITTED BY LAW WESSEX ARCHAEOLOGY WILL NOT BE LIABLE BY REASON OF BREACH OF CONTRACT NEGLIGENCE OR OTHERWISE FOR ANY LOSS ON DAMAGE (WHETHER DIRECT INDIRECT OR CONSEQUENTIAL) OCCASIONED TO ANY PERSON ACTING OR OMITTING TO ACT OR REFRAINING FROM ACTING IN RELIANCE UPON THE MATERIAL CONTAINED IN THIS REPORT ARISING FROM OR CONNECTED WITH ANY ERROR OR OMISSION IN THE MATERIAL CONTAINED IN THE REPORT. LOSS OR DAMAGE AS REFERRED TO ABOVE SHALL BE DEEMED TO INCLUDE, BUT IS NOT LIMITED TO, ANY LOSS OF PROFITS OR ANTICIPATED PROFITS DAMAGE TO REPUTATION OR GOODWILL LOSS OF BUSINESS OR ANTICIPATED BUSINESS DAMAGES COSTS EXPENSES INCURRED OR PAYABLE TO ANY THIRD PARTY (IN ALL CASES WHETHER DIRECT INDIRECT OR CONSEQUENTIAL) OR ANY OTHER DIRECT INDIRECT OR CONSEQUENTIAL LOSS OR DAMAGE.



Stage 2 Geoarchaeological recording and deposit modelling

Contents

v i 1 1
1
1
2
6
6
6
7
7
7
8
10
11
11 11
1 1
11
13
13
13
14
14
15
15
15
16
16 16
16



8	REFERENCES	16
9	APPENDIX	19
9.1	Vibrocore records	19

Figures

Figure 1: Site location

Figure 2: Norfolk Vanguard East, geophysics and borehole location. Figure 3: Norfolk Vanguard West, geophysics and borehole location.

Figure 4: Norfolk Vanguard offshore cable corridor, geophysics and borehole location.

Figure 5: Transect NV East.
Figure 6: Transect NV West.
Figure 7: Transect OCC-NV West.

Tables

Table 1: Stages of geoarchaeological assessment and recording. Table 2: Geological units identified within the Vanguard region.

Table 3: Vibrocores selected for stage 2 recording.

Table 4: Recommendations for stage 3 palaeoenvironmental assessment and dating.



Stage 2 Geoarchaeological recording and deposit modelling

Summary

Wessex Archaeology (WA) have been commissioned by Royal HaskoningDHV to undertake a Stage 2 geoarchaeological recording and deposit modelling of geotechnical logs in support of the proposed Norfolk Vanguard East (NV East) and Norfolk Vanguard West (NV West) Offshore Wind Farm (OWF).

The Stage 2 work forms part of ongoing investigations in advance of the proposed wind farm development, located in the southern North Sea basin, 47 km (NV West) and 89 km (NV East) east of Bacton, north Norfolk, respectively. The proposed offshore cable corridor (OCC) extends from the Norfolk coast near Happisburgh for 90 km to NV West and 100km to NV East.

Twenty-three vibrocore sequences were identified for Stage 2 geoarchaeological recording with very high (VC074, VC076 VC085) high (VC079, VC089, VC095, VC101, VC107 and VC116) and medium (VC070, VC075, VC080, VC081, VC084, VC086, VC088, VC092, VC97 VC103, VC104, VC117, VC118 and VC119) geoarchaeological potential.

An outline stratigraphic model for the site includes eight key stratigraphic units, comprising Pliocene-Lower Pleistocene (**Unit 1**), Lower-Middle Pleistocene (**Unit 2**) and Anglian (**Unit 3**) deposits of limited geoarchaeological potential. **Unit 4** is either Ipswichian or Lower Devensian date related to the Eem or Lower Brown Bank Formation (**Unit 4**). **Unit 1** to **Unit 4** were too deeply buried to be present in the vibrocores. **Unit 5** corresponds to the Brown Bank Formation, considered to represent a shallow lagoon environment. It is uncertain whether the lagoon sediments formed during the early Devensian, or over a longer period into the late Devensian. It is possible that the lagoon may have dried up, exposing sediment to erosion and wind. **Unit 6** corresponds to the Twente Formation, representing a thin deposit of periglacial windblown sand up to 1m thick tentatively identified in areas across NV West. In places **Unit 5** and **Unit 6** are overlain by Holocene peat and alluvium (**Unit 7**), in cases also preserved in pre-transgression palaeochannels (e.g. **VC074**). Post-transgression marine sands (**Unit 8**) represent the final marine inundation of the site.

Stage 3 palaeoenvironmental assessment is recommended on vibrocores VC074, VC076, VC079, VC085 and VC107, focusing on Unit 5, 6 and 7 of greatest geoarchaeological potential. Stage 3 work will comprise OSL dating of Unit 5 in vibrocores VC079 and VC107, in order to determine the depositional history of the Brown Bank Formation and refine our understanding of the archaeological and geoarchaeological potential of this unit. Palaeoenvironmental assessment and radiocarbon dating is recommended on Holocene peat and alluvial sediments (Unit 7) in vibrocores VC074, VC076 and VC085. The peat and over/underlying minerogenic deposits have the greatest potential for radiocarbon dating and are most likely to preserve the widest range of palaeoenvironmental remains (pollen, diatoms, foraminifera, ostracods), providing data on past landscape and environmental change and evidence for human activity and impact. Limited assessment is also recommended on Unit 6 to determine whether these deposits represent aeolian sands tentatively recorded across the site.

The geoarchaeological potential of the Vanguard OWF site lies in the deposits of the Upper Brown Bank (**Unit 5**) distributed widely across NV East, NV West the OCC, **Unit 6** (Twente Formation) of possible aeolian origin identified across NV West, and deposits of peat (**Unit 7**) contained within



channels and sealing the Upper Brown Bank and Twente Formation across NV West and parts of the OCC. Overall, the deposits of **Units 5, 6 and 7** contain the greatest archaeological potential to understand the physical development of the landscape, reconstruct patterns of environmental change and investigate evidence for potential human activity and human-environment relationships.



Stage 2 Geoarchaeological recording and deposit modelling

Acknowledgements

This work was commissioned by Royal HaskoningDHV. The report was compiled by Dr. Alex Brown. Illustrations were prepared by Nancy Dixon. The project was managed on behalf of Wessex Archaeology by Dan Atkinson and David Norcott.



Stage 2 Geoarchaeological recording and deposit modelling

1 INTRODUCTION

1.1 Project background

- 1.1.1 Wessex Archaeology (WA) have been commissioned by Royal HaskoningDHV to undertake a Stage 2 geoarchaeological recording and deposit modelling of geotechnical logs in support of the proposed Norfolk Vanguard Offshore Wind Farm (**Figure 1**).
- 1.1.2 Norfolk Vanguard comprises two distinct areas, Norfolk Vanguard West (NV West) and Norfolk Vanguard East (NV East) ("the Offshore Wind Farm (OWF) sites"). An offshore cable corridor joins the OWF sites to the landfall at Happisburgh South.
- 1.1.3 The Stage 2 work forms part of ongoing investigations in advance of the proposed wind farm development, located in the southern North Sea basin, 47 km (NV West) and 89 km (NV East) east of Bacton, north Norfolk, respectively. The proposed offshore cable corridor extends from the Norfolk coast near Happisburgh for 90 km to NV West and 100km to NV East (**Figure 1**).
- 1.1.4 The location of the proposed wind farm and cable corridor are of particular prehistoric archaeological interest, located in an area that at the height of the last ice age formed part of a vast habitable plain connecting Britain with the rest of the European continent. This landscape was then progressively drowned by rising post-glacial sea-levels with full marine conditions occurring across the southern North Sea basin by ca. 7000 BP.
- 1.1.5 An initial Stage 1 geoarchaeological review of vibrocore logs from 65 locations identified twenty-three vibrocore sequences with very high (VC074, VC076 VC085) high (VC079, VC089, VC095, VC101, VC107 and VC116) and medium (VC070, VC075, VC080, VC081, VC084, VC086, VC088, VC092, VC97 VC103, VC104, VC117, VC118 and VC119) geoarchaeological potential (Wessex Archaeology, 2017a). The vibrocore sequences are subjected to Stage 2 geoarchaeological recording, along with deposit modelling of these and other relevant geotechnical records from the site, with recommendations made for Stage 3 palaeoenvironmental assessment where considered appropriate.

1.2 Scope of report

1.2.1 To help frame geoarchaeological investigations of this nature, WA has developed a fivestage approach, encompassing different levels of investigation appropriate to the results obtained, accompanied by formal reporting of the results at the level achieved. The stages are summarised below (**Table 1**).



Table 1: Stages of geoarchaeological assessment and recording.

Stage	Method	Description
1	Review	A desk-based archaeological review of the borehole, vibrocore and CPT logs generated by geotechnical contractors. Aims to establish the likely presence of horizons of archaeological interest and broadly characterise them, as a basis for deciding whether and what Stage 2 archaeological recording is required. The Stage 1 report will state the scale of Stage 2 work proposed.
2	Geoarchaeological Recording and deposit modelling	Archaeological recording of selected retained or new core samples will be undertaken. This will entail the splitting of the cores, with each core being cleaned and recorded. The Stage 2 report will state the results of the archaeological recording and will indicate whether any Stage 3 work is warranted.
3	Sampling and Assessment	Dependent upon the results of Stage 2, sub-sampling and palaeoenvironmental assessment (pollen, diatoms and foraminifera) may be required. Subsamples will be taken if required. Assessment will comprise laboratory analysis of the samples to a level sufficient to enable the value of the palaeoenvironmental material surviving within the cores to be identified. Subsamples will also be taken and/or retained at this stage in case scientific dating is required during Stage 4. Some scientific dating (e.g. radiocarbon or Optically Stimulated Luminescence (OSL)) may be undertaken at this stage to provide chronological context. The Stage 3 report will set out the results of each laboratory assessment together with an outline of the archaeological implications of the combined results, and will indicate whether any Stage 4 work is warranted.
4	Analysis and Dating	Full analysis of pollen, diatoms and/or foraminifera assessed during Stage 3 will be undertaken. Typically, Stage 4 will be supported by scientific dating (e.g. radiocarbon or OSL) of suitable subsamples. Stage 4 will result in an account of the successive environments within the coring area, a model of environmental change over time, and an outline of the archaeological implications of the analysis.
5	Final Report	If required Stage 5 will comprise the production of a final report of the results of the previous phases of work for publication in an appropriate journal. This report will be compiled after the final phase of archaeological work, whichever phase that is.

2 GEOARCHAEOLOGICAL BACKGROUND

- 2.1.1 The geology of the area has been outlined as part of an earlier palaeogeographic assessment of the study area (Wessex Archaeology, 2017b), combining a review of the, geotechnical, geophysical and known geological data. This identified a series of geological units across the broader area, outlined in **Table 2**, and shown in **Figures 2-7**.
- 2.1.2 The Geological Units identified by Wessex Archaeology are listed against the corresponding units identified by Fugro (2017c). It should be noted that Fugro used deeper digital seismic data which will have aided interpretation of deeper units such as Westkapelle Ground Formation; the Wessex stratigraphic units by comparison were interpreted using shallow



- analogue sub-bottom profiler data and as such there was less confidence in interpreting those deeper units identified by Fugro.
- 2.1.3 Geotechnical investigations, comprising both **CPT** (cone penetrometer tests) and **VC** (vibrocore) operations, were undertaken by Fugro EMU Limited, with onshore laboratory and reporting undertaken by Fugro GeoConsulting Limited (Fugro, 2017a). Wessex Archaeology subsequently undertook an initial geoarchaeological review of geotechnical logs (Wessex Archaeology 2017a) prior to the current report.
- 2.1.4 Geophysical survey data was acquired in 2012 by Emu Limited (NV East) (Emu Ltd, 2013), and in 2016 by Fugro Survey B. V. (NV West and OCC) (Fugro, 2016, 2017b, 2017c), and subsequently reviewed by Wessex Archaeology as part of a palaeogeographic assessment of geophysical data within the Norfolk Vanguard OWF area (Wessex Archaeology, 2017b).

Table 2: Geological units of geoarchaeological potential identified within the Vanguard region (after Wessex Archaeology, 2017b).

Geological units identified by Wessex Archaeology are accompanied by corresponding units identified by Fugro (Fugro, 2017c)

WA Unit	Fugro Unit	Geological Unit	Age	Geoarchaeological potential
8	A1	Holocene seabed sediments	Post- transgression (MIS 1)	Gravelly sand with shell fragments, sand waves and ripples indicate sediment is mobile. Low potential in areas of mobile sediment: basal contact may cover old land surfaces.
7	A2	Holocene sediments	Pre-transgression (MIS 2–1)	Fluvial, estuarine and terrestrial (including peat) deposits. Shallow infilled depressions or channels with potential for preserved organic material of palaeoenvironmental significance.
6	В	Twente Formation	Upper Devensian (MIS 2)	Thin layer of aeolian periglacial sand. Potential to contain in-situ and derived archaeological and palaeoenvironmental material
5	С	Upper Brown Bank Formation	Early/Mid Devensian (MIS 5d-3)	Clayey silty sand infilling channels or hollows and deposited in an intertidal/lagoon environment. Potential for <i>in-situ</i> Lower Palaeolithic artefacts. Middle Palaeolithic artefacts may be associated with channel edges dependent on age of infill. Basal contact may cover old land surface
4	C/D	Lower Brown Bank Formation / Eem Formation	Ipswichian or Lower Devensian (MIS 5e–5d)	Silty sand and sandy silt. Possible intertidal or shallow marine deposit. Insitu Lower Palaeolithic artefacts may be protected. Middle Palaeolithic artefacts may be associated with channel edges dependent on age of infill. Basal contact may cover old land surface
3	Е	Swarte Bank Formation	Anglian (MIS 12)	Silty sandy clays associated with the Anglian glaciation. Unlikely to contain archaeological material.



2	F	Yarmouth Formation	Lower to Middle Pleistocene (MIS >13)	Silty sand with occasional shell fragments, deposited as part of marine delta complex. Low potential, unlikely to contain archaeology or deposits of palaeoenvironmental significance.
1	I	Westkapelle Ground Formation	Pliocene – Lower Pleistocene (MIS 103-63)	Deltaic silty clays and sands. Pre-date earliest occupation; of no archaeological interest

- 2.1.5 Where age estimates are available these are expressed in millions of years (MA), thousands of years (Ka), and within the Holocene epoch as years before present (BP). These dates are supplemented, where known, with the comparable Marine Isotope Stage (MIS) where odd numbers indicate an interglacial period and numbers a glacial period.
- 2.1.6 The Pleistocene geological history of the North Sea basin is dominated by repeated glacial/interglacial cycles, resulting in rising and falling sea-levels and deposition of terrestrial, marine and glacially-derived sediments.
- 2.1.7 Only one glacial episode is thought to have affected the southern North Sea during the Anglian period (ca. 480–423ka), although subsequent glacial episodes will have affected the region as a result of changing sea-levels. The exact southern extent of the Anglian glaciation is debated, although bathymetric data suggests part of the Anglian ice sheet may have extended as far south as offshore Felixstowe (Emu, 2009).
- 2.1.8 Palaeolandscape features are more likely to be preserved off the East Anglian coast as the area has only experienced one glacial advance. Further to the north (north of the North Norfolk coast) similar palaeolandscape features are likely to have been removed during the subsequent Saalian and Devensian glacial advances.
- 2.1.9 Geophysical and geotechnical data have been used to devise a basic stratigraphy for the study area, comprising eight units covering the Pleistocene and Holocene (**Table 2**). These comprise both terrestrial and fluvial sediments associated with palaeochannels, floodplains, periglacial aeolian deposits, lagoon and lacustrine environments.
- 2.1.10 **Unit 1** pre-dates the earliest human occupation of Britain and is unlikely to contain archaeological or palaeoenvironmental remains, and is therefore of limited geoarchaeological relevance. **Unit 2** is contemporary with the terrestrial Cromer Forest Bed Formation (> MIS 13) which has produced some of the earliest evidence for the hominin occupation of Britain (Parfitt *et al.* 2010, Ashton *et al.* 2014). **Unit 3** deposits are associated with the Anglian glaciation and therefore unlikely to contain archaeological material. **Unit 3** has not been definitely recognised on geophysical data within the NV OWFs (Fugro 2017c; WA 2017b).
- 2.1.11 **Unit 4** is of uncertain age, but may contain either the Eem Formation, dating to the Ipswichian, or Lower Brown Bank Formation deposits of Lower Devensian Age (Cameron *et al.* 1992). The Eem Formation is described as shelly and muddy sands representing a shallow marine/intertidal environment, whilst the Upper Brown Bank Formation comprises clayey silts and sands infilling channels and/or hollows, deposited within an intertidal/lagoon environment. **Unit 4** has only been sporadically identified in NV West compared to NV East, and tentatively identified in some areas of the OCC (**Figures 2-4**).
- 2.1.12 Humans were absent from the area during the development of the Eem and Lower Brown Bank Formations (**Unit 4**), although the geoarchaeological potential of the Upper Brown



Bank Formation (**Unit 5**) is considered to be higher, although variable, dependent on the presence/absence of suitable features. **Unit 5** is present as a blanket deposit across the whole of NV East and NV West, and is interpreted as a shallow lagoon environment, comprising clayey silty sands. The presence of organic material within the sediment has been suggested in places by accumulations of shallow gas revealed during geophysical surveys. A number of internal features have been identified within **Unit 5** that have been interpreted as possible internal erosion surfaces. It is possible that the lagoon may have periodically dried up, exposing previously submerged sediment as dryland and resulting in the observed internal erosion surfaces. **Unit 5** becomes more intermittent along the OCC and is absent from approximately 30km from landfall (**Figure 4**).

- 2.1.13 The geophysical surveys hint at a complex deposition history for **Unit 5**, suggesting a multiperiod, multi-phase unit rather than continuous deposition of lagoon sediment; this has implications for the archaeological potential of the deposits.
- 2.1.14 The Upper Brown Bank Formation is overlain across NV East by recent post-transgression sea bed sediments (**Unit 8**), varying in thickness from a thin veneer to sand banks up to 15m thick.
- 2.1.15 Overlying the Upper Brown Bank Formation in some areas is the Twente Formation (Unit 6), comprising a thin deposit of sand up to 1m thick and interpreted as a periglacial aeolian (windblown) sand deposit of Upper Devensian age. Unit 6 has been tentatively identified in vibrocores VC075, VC076 and VC088 but has not been identified along the OCC (Figure 2 and 4). The extent of the Twente Formation shown on Figure 3 is based on BGS data as it could not be confidently identified on the seismic data (Fugro, 2017b).
- 2.1.16 **Unit 6** would have formed after the retreat of the Devensian ice sheet, with wind transporting loose sediment southward across the largely unvegetated periglacial landscape. Similar windblown sands (also called coversands) have been found across East Anglia and continental Europe (Crombe *et al.* 2012). In places these form small dune ridges within low-lying wetland landscapes that would have been favourable locations for settlement with potential for recovery of *in situ* archaeological material.
- 2.1.17 Overlying the Pleistocene sediments is a sequence of early Holocene deposits (Unit 7 and Unit 8). Surveys and coring in this area have identified terrestrial deposits, including peat, which are thought to have been deposited prior to and during the early-mid Holocene marine transgression of the southern North Sea basin. The peat deposits form either on the top of the Upper Brown Bank Formation, on top of windblown sands, or within Holocene channels, all indicated on the geophysical surveys, and in the former two as areas of high amplitude reflectors (Figure 3). In the latter case, geophysical surveying identified 12 pretransgression shallow channel features, some also corresponding with high amplitude features (e.g. channel 75112, Figure 3). Some of these cores appear to show a gradual upward transition from saltmarsh to peat (VC085), in turn sealed by muds (classified together as Unit 7), providing evidence of the progressive inundation of terrestrial landscapes as a result of rising post-glacial sea-levels (Cooper et al. 2008). Where peat deposits are preserved on the top of the Upper Brown Bank Formation these may equally indicate peat formation during the Late Devensian. These deposits, and particularly the peat, are of high palaeoenvironmental potential.
- 2.1.18 The progressive inundation of North Sea palaeolandscapes occurred over an extended time scale, with particularly rapid sea-level rise occurring during the early Holocene (11,500–7000 cal. BP) and fully marine conditions across the North Sea by probably around 6000 cal. BP (Ward et al. 2006). Marine sediments deposited since the Holocene transgression typically comprise sands, gravels and muds (Unit 8).



3 AIMS AND OBJECTIVES

- 3.1.1 The principal aims of the Stage 2 geoarchaeological recording of vibrocores are as follows:
 - Describe retained vibrocore sequences;
 - Undertake deposit modelling of described vibrocores and geotechnical logs;
 - Interpret sedimentary sequences and landscape represented by retained vibrocores, geotechnical logs and deposit modelling;
 - Make recommendations for further Stage 3 palaeoenvironmental assessment where appropriate, with reference to key research questions and regional/national period specific and maritime research agendas.

4 METHODS

4.1 Geoarchaeological recording of vibrocores

4.1.1 A total of 22 vibrocores were subject to Stage 2 geoarchaeological recording, located across NV West, NV East and the OCC (Figure 2-4), a 23rd vibrocore (VC119) of medium priority was not present amongst cores sent to Wessex Archaeology. An initial review and monitoring of geotechnical logging identified a series of vibrocores of very high, high, medium and low geoarchaeological priority (Wessex Archaeology, 2017a). Samples of very high and high priority were set aside for Stage 2 recording, whilst those of medium priority were opened under geoarchaeological supervision at the Fugro laboratory in Wallingford and selected samples returned to Wessex Archaeology. The vibrocores and their location are listed below in Table 3. The remaining low priority vibrocores were described by a suitably experienced geotechnical engineer and the logs reviewed to ensure no further geoarchaeologically significant sequences were missed.

Table 3: Vibrocores selected for Stage 2 recording. Green = very high priority, orange = high priority, blue = medium priority cores previously recorded and returned to Wessex Archaeology. * = vibrocore not present.

Vibrocore location and priority											
Norfolk Vanguard West	Norfolk Vanguard West Norfolk Vanguard East Offshore Cable Corridor										
VC070	VC092	VC116									
(2.7-2.9, 5.7-6 m)	(2.7-3 m)	(0-6.35 m)									
VC074	VC095	VC117									
(0-5.6 m)	(0-6.30 m)	(1-1.5 m)									
VC075	VC097	VC118									
(4.4-4.7 m)	(3.7-4.5 m)	(0.7-1.5, 3-4, 4.5-5 m)									
VC076	VC101	VC119*									
(0-4.35 m)	(0-6.10 m)	-									
VC079	VC103										
(0-5.25 m)	(3-3.5, 4-4.5 m)										
VC080	VC104										
(2-2.15 m)	(2.7-3, 5.7-6 m)										
VC081	VC107										
(1-2, 2.7-3 m)	(0-6.0 m)										



VC084
(3.1-3.2 m)
VC085
(0-5.85 m)
VC086
(4.25-4.50 m)
VC088
(3.25-3.6 m)
VC089
(0-6.30 m)

- 4.1.2 The vibrocores were opened in the Wessex Archaeology laboratory and described by a suitably experienced geoarchaeologist following Hodgson (1997), to include information such as:
 - Depth
 - Texture
 - Composition
 - Colour
 - Inclusions
 - Structure (bedding, ped characteristics etc)
 - Contacts between deposits
- 4.1.3 All deposit records were made using the standard Wessex Archaeology recording system. The detailed sediment descriptions and interpretations are tabulated in the **Appendix.**

4.2 Deposit modelling

- 4.2.1 Deposit modelling was undertaken in addition to Stage 2 geoarchaeological recording of vibrocores. This involved the use of all available vibrocore logs and associated geotechnical records (Fugro, 2017a).
- 4.2.2 The large distance between vibrocores (between 2.9 and 5.9 km) and localised nature of key deposit within discrete features is not ideally suited to the creation of Digital Elevation Models (DEMs) or thickness plots. Instead a series of linear transects (**Figures 5–7**) have been constructed to provide a representative cross-section illustrating the key stratigraphic units within NV West, NV East and the OCC. Interpretation of stratigraphic units has utilised the Wessex interpreted geophysical data (Wessex Archaeology, 2017b), illustrated on **Figures 2–4**, alongside geotechnical logs (Fugro, 2017a).
- 4.2.3 The Wessex interpreted geophysical data is used to determine the location of borehole transects in order to capture the full range of stratigraphic units. At this stage full integration of geophysics and geotechnical data through depth conversion has not been undertaken.

5 RESULTS

5.1 Stage 2 recording, assessment and deposit modelling

5.1.1 The Stage 2 geoarchaeological recording results are summarised below, with full vibrocore descriptions presented in the **Appendix**. The acquired vibrocores vary in length, including complete unopened vibrocore sequences (up to 6.3 m), and smaller sections (0.2–0.5 m)



- retained followed initial geotechnical logging and geoarchaeological monitoring at the Fugro Laboratory.
- 5.1.2 The results of the Stage 2 geoarchaeological recording are considered alongside the complete geotechnical dataset (Fugro, 2017a), including both **CPT** (cone penetrometer tests) and **VC** (vibrocore) logs, and Wessex interpreted geophysical data (Wessex Archaeology 2017b) (**Figures 2–4**), aiding the interpretation of palaeolandscape features and depositional processes, and in turn feeding into the identification of research questions and specific recommendations for Stage 3 palaeoenvironmental assessment.
- 5.1.3 The vibrocores are distributed across NV West (12), NV East (7) and the OCC (3) (**Table 3**). Every attempt has been made to assign deposits to the stratigraphic units detailed in **Table 2**. However, this hasn't been possible in all cases due to the complexity of the site and stratigraphy (comprising a range of topographic features and deposits), the large area covered by the windfarm development and the distance (3–6 km) separating individual vibrocores (**Figure 2-4**).
- 5.1.4 Any uncertainty as to the date and/or taphonomy of deposits serves as an opportunity to propose further works, detailed in **section 7** as part of the recommendations for Stage 3 assessment.

5.2 Vibrocore assessment

- 5.2.1 An outline stratigraphy has been devised for the study area comprising eight units (**Table 2**). Of these eight units, **Unit 1** to **Unit 4** are not present within the vibrocores due to the shallow depth of the samples (not exceeding a maximum depth of 6.30 m). **Unit 5**, where present, is also only partially represented, typically extending beyond the base of the vibrocores and reaching a maximum thickness of 17.54 m in **CPT095** (**Fugro, 2017**).
- 5.2.2 Of the units considered to be of geoarchaeological significance, the Stage 2 geoarchaeological recording of vibrocores has targeted **Unit 5** (Upper Brown Bank Formation) and **Unit 7** (Holocene pre-transgression sediments).
- 5.2.3 **Unit 4** (Eem Formation/Lower Brown Bank Formation) was considered to be too deeply buried to occur in the vibrocores. However, in **VC079**, Holocene post-transgression marine sands (**Unit 8**) are underlain by a very dark grey compact clayey silt, considered to represent the Upper Brown Bank Formation (**Unit 5**). **Unit 5** (0.30-4.55 m) in turn seals a dark grey shelly clayey sand, containing moderately poorly rounded gravels throughout, initially thought to represent Unit 4.
- 5.2.4 Among the retained vibrocores, similar silty fine to medium shelly sands are present in VC077 and VC086, and in the geotechnical records are present in several other vibrocores (VC092, VC098-VC100, VC111, VC114), typically as components of the silty/sandy clay (Unit 5). In the geotechnical logs (Fugro, 2017a) the sediment underlying Unit 5 is represented by a dense sand, instead considered to represent the shallow marine/lagoonal deposits of Unit 4. It is most likely therefore that the shelly clayey/silty sands in VC079 represent a component of Unit 5 rather than Unit 4, reflecting the internal variability and complex depositional history of the Upper Brown Bank Formation.
- 5.2.5 The Upper Brown Bank Formation (**Unit 5**) has been recorded in a large proportion of the vibrocores of very high (**VC074**, **VC085**, **VC089**), high (**VC079**, **VC095**, **VC101**, **VC107**, **VC116**) and medium priority (**VC070**, **VC084**, **VC092**, **VC097**, **VC103**, **VC104**).



- 5.2.6 Unit 5 varies in composition within and across vibrocores, typically a very dark grey compact clay to clayey silt (e.g. VC079, VC085, VC089 and VC101), but with varying components of fine sand (VC070 and VC074), silty sand (VC084), clayey sand (VC079) sandy clay (VC095) and sandy-silt (VC097 and VC116). Laminations are apparent in almost all vibrocores containing Unit 5, comprising both fine clay, silt and sand, in addition to occasional silty and sandy organic laminae (VC086, VC103, VC107) shelly inclusions, mottling and iron staining (VC104).
- 5.2.7 The vibrocores only include the upper portions of **Unit 5**, with the unsplit very high and high priority vibrocores containing between 3.2 m (**VC085**) to 5.2 m (**VC107**). Recording of the retained high and medium priority vibrocores (**Appendix**), along with existing CPT and vibrocore logs, (Fugro, 2017) indicate **Unit 5** varies in thickness from as little as 2.57 m (**VC088**) to 17.54 m (**CPT095**), and most often averaging between 5-9 m thick.
- 5.2.8 Several other vibrocores (**VC076**, **VC081**, **VC084**, **VC086**, **VC107**, **VC116**) include deposits of uncertain origin, but that may represent **Unit 5** (**Appendix**).
- VC076 includes a dark grey fine sand (4.0-4.35 m) directly underlying peat, either representing the Upper Brown Bank Formation (Unit 5) or possibly periglacial aeolian sands of the Twente Formation (Unit 6), both suggested in this area on the basis of geophysical surveys (Figure 3). Further bands of sand are recorded in geotechnical borehole logs, including VC076 (7.05-7.33 m) (Fugro, 2017a). These sandy bands within Unit 5 could represent distinct phases when parts of the lagoon are hypothesised to have dried out, aerially exposing sediment to aeolian action.
- 5.2.10 **VC081** includes a short section of dark greenish grey clay (2.7-3.0 m) that may represent the upper section of **Unit 5**, although this is difficult to determine for certain based on the short section of vibrocore available for recording.
- 5.2.11 **VC084** includes a thin deposit of very dark greenish grey silty sand (3.17-3.20 m), with a clear boundary to the overlying marine sands (**Unit 8**). The grey silty sand may represent **Unit 5**, although a certain identification is hampered by the small section (0.1 m) of vibrocore available for recording.
- VC086 is short section of vibrocore (4.25-4.50 m), comprising a dark greyish brown mottled silty-sand with distinct organic laminations. In this case it is difficult to determine if this represents the eroded upper surface of the Upper Brown Bank Formation (Unit 5) or a component of the overlying marine sands (Unit 8) that geotechnical logs describe including lamina of black clay and pockets of possible organic material and decomposed plant material.
- 5.2.13 VC107 comprises marine sands (Unit 8) underlain by a thin black silty-sand (0.52-0.80m), in turn overlying very dark greenish grey silty clay of the Upper Brown Bank Formation (Unit 5). There is a very sharp boundary at 0.80 m between Unit 5 and the overlying unit that may represent an erosional surface within Unit 5 or boundary with pre-transgression fluvial sediment (Unit 7), although no Holocene channels are suggested by the geophysics in this area (Figure 3).
- 5.2.14 **Unit 6** (Twente Formation) is described as thin layer of periglacial aeolian sand (**Table 2**), that although not definitely identified on the geophysical survey has been tentatively identified from geotechnical log descriptions in vibrocores **VC075**, **VC076** and **VC088**.
- 5.2.15 Stage 2 geoarchaeological recording identified potential aeolian sediment at the base of **VC075**, comprising a thin deposit of very dark grey slightly silty sand (4.67-4.70 m), with



- similar dark grey fine sands recorded in **VC076** (4-4.35 m), in both cases sealed by peat (**Unit 7**).
- 5.2.16 No aeolian sediments were recorded from retained samples of **VC088** (**Appendix**). However, a visual inspection of Fugro vibrocore photographs (Fugro, 2016) includes apparent sand deposits below black organic sediments, similar to **VC075** and **VC076**, and therefore suggestive of potential aeolian deposits. **VC085** also includes a dark grey medium sand (2.61-2.92 m) sealed by organic silty clay, that may also represent aeolian sediments.
- 5.2.17 Unit 7 comprise Holocene pre-transgression sediments, including semi-terrestrial peat, fluvial and estuarine deposits. Unit 7 has been recorded in six vibrocores (VC074, VC075, VC076, VC080, VC085 and VC088), and a possible further two vibrocores (VC081 and VC116).
- 5.2.18 Peat is present in five vibrocores (VC074, VC075, VC076, VC085 and VC088), varying in thickness between 0.35 m (VC088) and 0.80m (VC074) and composition from dark grey to black clayey peat with sandy bands (VC074) to dark brown to black fibrous peats (VC075 and VC076). Fragments of wood and land snails were observed in the VC074 peat, with plant remains visible in VC088.
- 5.2.19 The peat occurs in one of three main contexts, either resting on Upper Brown Bank Formation (Unit 5) or periglacial aeolian sands (Unit 6) (VC075, VC076 and possibly VC085), or forming part of a sequence of fluvial and estuarine deposits contained within Holocene pre-transgression palaeochannels (VC074 and VC085).
- 5.2.20 Vibrocore VC074 targeted a potential Holocene palaeochannel. Here the peat overlies a dark grey fine sand to slightly clayey silty fine sand (1.58-4.75 m) interpreted as channel fill, and including fragments of marine shell. However, the similarity in sediment between Unit 5 and Unit 7 makes it very difficult to identify the base of the channel and the interface between the two units.
- 5.2.21 Smaller retained samples include 0.15 m of organic sands (VC080), with organic sand and silts (1.28-1.49 m) underlying marine sands (Unit 8) in VC081, most probably overlying Unit
 5. In addition. VC116 only includes a dark greenish grey slightly sandy-silt with an abrupt boundary with Unit 5, although as stated above (section 5.2.14) it is uncertain at this stage if these sediments belong to Unit 7 or Unit 5.
- 5.2.22 Of the 22 vibrocores subjected to stage 2 geoarchaeological recording, 13 retain the uppermost deposits of Holocene post-transgression marine sands (VC074, VC076, VC079, VC081, VC084, VC085, VC089, VC095, VC101, VC103, VC107, VC116 and VC118). The marine sands vary in thickness from a thin veneer 0.3 m thick (VC079, VC089 and VC116) to over 3 m (VC076, VC084, VC103 and VC118), with geotechnical logs recording localised deeper deposits from VC073 (9.96m), VC108 (13.6 m) and VC109 (10.99 m). The sands vary in colour from predominantly yellowish brown to brown, light olive brown, greenish-black, greenish-grey, variably including occasional thin clay lamina, pockets of iron staining, black (possibly organic) staining and marine shell fragments.

5.3 Deposit modelling

5.3.1 Three linear transects have been constructed, providing a representative cross-section illustrating the range of deposits within NV East (**Figure 5**), NV West (**Figure 6**) and the Offshore Cable Corridor (OCC) (**Figure 7**).



Transect NV East

Transect NV East comprises six vibrocores (VC111, VC092, VC095, VC099, VC103 and VC107) oriented west-east across the southern section of NV East and the adjoining OCC (Figure 5). The vibrocores exhibit a gradual west to east incline in elevation from 38.9 to 34.8 m LAT (Lowest Astronomical Tide). The deposits are broadly similar, comprising post-transgression Holocene marine sands (Unit 8) overlying Upper Brown Bank Formation (Unit 5).

Transect NV West

- 5.3.3 Transect NV West comprises five vibrocores (VC070, VC075, VC080, VC085 and VC088) oriented southwest-northeast along the northern margins of NV West (Figure 6). The deposits exhibit a general west-east increase in elevation from 40.4 to 32.3 m LAT.
- 5.3.4 The vibrocores primarily comprise **Unit 8** (post-transgression marine sands) and **Unit 5** (Upper Brown Bank), but with deposits of Holocene peat (**VC075**, **VC085** and **VC088**) and organic sands (**VC080**) (**Unit 7**). The peat is no more than 0.36 m thick, and rests either on top of possible saltmarsh (**VC085**), Upper Brown Bank Formation (**VC080**) or periglacial windblown sands (**Unit 6**) (**VC075**). Two peats are preserved in **VC075** separated by silty-clay, with the peat in **VC085** overlain by clayey-sand. The clayey-sand in **VC085** may represent low energy marine sediment or fluvial deposits relating to a nearby channel suggested by geophysical surveying approximately 300 m to the north.

Transect OCC-NV West

- Transect OCC-NV West comprises seven vibrocores (VC119, VC118, VC117, VC116, VC074, VC079 and VC084) oriented west-east to southwest-northeast along the offshore cable corridor and southern section of NV West (Figure 7). The transect covers approximately 30 km, with the vibrocores exhibiting an eastward reduction in elevation along the offshore cable corridor (44.3 to 47.7 m LAT), but rising steeply within NV West (max. 38.5 m LAT).
- 5.3.6 The deposits within the offshore cable corridor comprise post-transgression marine sands (**Unit 8**) underlain by Upper Brown Bank Formation (**Unit 5**). **Unit 8** is the only deposit recorded in **VC118** and **VC117**, up to 5 m thick, but present in **VC116** as a thin deposit (< 0.5 m) overlying a thin organic sandy silt (**Unit 7**) resting on **Unit 5**.
- 5.3.7 The deposits within NV West include a deep sequence of peat (0.80 m) and clayey to silty-sand (**Unit 7**) in **VC074** infilling a pre-transgression Holocene palaeochannel.

6 DISCUSSION

- 6.1.1 Initial Stage 1 assessment of vibrocores (Wessex Archaeology, 2017a) has been followed by a detailed Stage 2 geoarchaeological description of 22 retained vibrocore samples, supported by deposit modelling. Together, these stages of initial assessment and detailed description have revealed an extensive, and in places complex, sequence of Pleistocene and Holocene deposits across the study area. These deposits have been divided into a series of eight units conforming to an outline stratigraphic model for the site (after Wessex Archaeology, 2017b).
- 6.1.2 The outline stratigraphic model for the site comprises a sequence of deposits extending back to the Pliocene and Lower Pleistocene (**Unit 1**). **Unit 2** (Yarmouth Roads Formation) is contemporary with the deposits of the Cromer Forest Bed (> MIS 13), exposed along the East Anglian coast at sites such Happisburgh and Pakefield, and including archaeological evidence for the earliest hominin occupation of Britain was discovered (Parfitt *et al.* 2010;



- Ashton et al. 2014). The Cromerian interglacial was followed by the Anglian glaciation, although deposits dating to this period have not been definitively identified within the study area.
- 6.1.3 Unit 4, identified in places across NV East but more sporadically across NV West (Figures 3 and 4), are considered to belong either to the Eem Formation, dating to the Ipswichian, or the Lower Brown Bank Formation, dating to the Lower Devensian (Cameron et al. 1992). Eem Formation deposits are considered to represent a shallow marine environment, with the Lower Brown Bank interpreted as a lagoon deposit.
- 6.1.4 **Unit 4** is overlain by **Unit 5** (Upper Brown Bank Formation), extending across NV East and NV West and significant sections of the OCC (**Figures 2-7**). **Unit 5** dates to the Early/Middle Devensian, and may have continued to form into the Late Devensian (Limpenny *et al.* 2011). Internal features identified within the Upper Brown Bank Formation suggest a complex depositional history, including possible relict dunes and erosion surfaces (**Figure 3**) that formed during periods when the lagoon dried up.
- 6.1.5 Stage 2 geoarchaeological recording of retained high and medium priority vibrocores, alongside existing CPT and vibrocore logs (Fugro, 2017a), indicate that **Unit 5** varies between 3.2 and 17.54 m (averaging between 5-9 m thick), but only the top section of the Upper Brown Bank Formation is preserved within the retained vibrocores (max. 5.2m in **VC107**). **Unit 5** is typically recorded as a compact clay to clayey silt, but includes components of sand, silty and clayey sand, sandy clay and sandy silt, in addition to fine-coarse lamina, organic inclusions and shelly material.
- 6.1.6 The complexity in the Upper Brown Bank has been taken to suggest a multi-period, multi-phase unit of deposition, rather than necessarily a single continuous deposition of lagoon sediment. The Upper Brown Bank Formation is of potential archaeological significance as the low-lying wetlands and potential sand ridges may have presented opportunities for exploitation with settlement on areas of high ground.
- 6.1.7 Unit 5 is overlain in some areas by periglacial aeolian sands of the Twente Formation (Unit 6), although this unit was only tentatively identified in three vibrocores (VC075, VC076 and VC088), sealed by later Holocene peat deposits.
- 6.1.8 Pleistocene sediments are overlain by deposits of Holocene age, comprising either pretransgression semi-terrestrial, fluvial and estuarine deposits (**Unit 7**) or post-transgression seabed sediments (**Unit 8**). **Unit 7** includes peat deposits, representing the partially decayed remains of plants deposited in a waterlogged semi-terrestrial environment.
- 6.1.9 Peat was identified in five vibrocores (VC074, VC075, VC076, VC085 and VC088), varying in thickness between 0.35 m (VC088) and 0.80 m (VC074). The peat occurs either directly on the Upper Brown Bank Formation, on top of periglacial aeolian sands, or preserved within Holocene palaeochannels.
- 6.1.10 Relative to metres below Lowest Astronomical Tide (mLAT) the peat occurs between 36.7-37 m LAT (VC075) and 39.28-40.08 m LAT (VC074). The difference in altitudinal height of the peat may reflect differential lateral and vertical auto-compaction of a contemporaneous peat unit across NV West, or distinct episodes of peat formation under the background influence of fluctuating but rising post-glacial sea-levels. These peat deposits are likely to date prior to the final inundation of the southern North Sea basin which occurred between 8000-7000 cal. BP. Post-transgression seabed sediment (Unit 8) blanket the area.



7 RECOMMENDATIONS

7.1 Introduction

- 7.1.1 Based on the results of the geoarchaeological recording and deposit modelling of geotechnical samples a series of recommendations are made for further targeted geoarchaeological assessment, itemised below and in **Table 4**.
- 7.1.2 The selection of samples for Stage 3 palaeoenvironmental assessment is based on the geoarchaeological significance of the recorded units, the presence of organic material (most likely to preserve the widest range of palaeoenvironmental indicators), and the quality of the available samples.
- 7.1.3 Within the Stage 2 geoarchaeological recording, the deposits of highest geoarchaeological priority comprise **Unit 5** and **Unit 7**, dating to periods when the southern North Sea would have been suitable for occupation. Deposits considered to represent possible periglacial aeolian sands (**Unit 6**) are also recommended for limited further assessment in order to characterise these deposits and refine the outline stratigraphic model for the site.

Table 4: Recommendations for Stage 3 palaeoenvironmental assessment and scientific dating.

Vibrocore		Assessment								
	Pollen	Diatom	Foraminifera / ostracod	Plant macrofossil	14C dating	OSL	Particle size			
VC074	8	8	8	2	2	-	-			
VC075	-	-	-	-	-	-	3			
VC076	5	4	4	2	2	-	3			
VC079	-	10	10	-	-	2	-			
VC085	5	6	6	2	2	-	-			
VC089	-	-	-	-	-	2	-			
VC107	-	10	10	-	-	2	-			
Total	18	38	38	6	6	6	6			

7.2 Upper Brown Bank Formation (Unit 5)

- 7.2.1 Further Stage 3 assessment is recommended on **Unit 5** deposits vibrocores **VC079**, **VC089** and **VC107**, focusing on optically stimulated luminescence (OLS) dating of deposits identified as the Upper Brown Bank Formation (**Unit 5**).
- 7.2.2 The Upper Brown Bank Formation (**Unit 5**) is taken to represent a shallow lagoon deposit. The complexity of the Upper Brown Bank Formation has been taken to suggest a more complex depositional history for this unit, including periods when the lagoon may have periodically dried out, exposing sediments to erosion and wind blow. The lagoon shores and ridges of aeolian sand (**Unit 6**), would have provided potentially suitable locations for human settlement and activity.
- 7.2.3 It remains unclear, however, whether **Unit 5** was deposited over a short period early in the Devensian, or over a much longer period of time over the course of the early-late Devensian, perhaps punctuated by hiatuses in sediment accumulation. OSL dating of **Unit 5** will



- therefore provide an important opportunity to date these deposits and refine our understanding of the geoarchaeological and archaeological potential.
- 7.2.4 Although none of the vibrocores fully penetrate **Unit 5**, targeted OSL dates will nonetheless determine whether **Unit 5** continued to form over an extended time period later into the Devensian. Both vibrocores **VC079**, **VC089** and **VC107** comprise **Unit 5** overlain by post-transgression Holocene marine sands (**Unit 8**).
- 7.2.5 OSL dating from three vibrocores is preferable given the extensive area over which the vibrocores are distributed and the observed internal variability and complex formation processes of the Upper Brown Bank Formation.
- 7.2.6 It is not proposed to undertake pollen analysis on **Unit 5** as the Devensian date of these sediments covers a time when the environment would have been a cold tundra landscape with little in the way of substantial pollen-producing vegetation.
- 7.2.7 However, targeted foraminifera, ostracod and diatom assessment is recommended on two vibrocores containing **Unit 5** (**VC079** and **VC107**) in order to derive palaeoenvironmental data to characterise the environmental conditions occurring within the lagoon. **VC079** in particular includes coarser sediment inclusions from 45.35-46.05 m LATm, with distinct laminations present in both cores, that hint at variation in the energy of deposition within the Upper Brown Bank Formation.
- 7.2.8 Palaeoenvironmental assessment of **Unit 5** also provides a fundamental control for comparison with foraminifera, ostracod and diatom assessment of Holocene alluvium and sediments of uncertain date and taphonomy (**see section 7.4.5**).
- 7.2.9 In these circumstances, palaeoenvironmental assessment may be able to distinguish between a shallow freshwater lagoon environment (**Unit 5**) and marine, estuarine or even freshwater sediments contained with an early Holocene channel (**Unit 7**), representing a more time and cost-effective solution to OSL dating. OSL dating has only been recommended on **Unit 5** sediments in **VC097**, **VC089** and **VC107**.

7.3 Periglacial aeolian sands 'Twente Formation' (Unit 6)

- 7.3.1 Periglacial aeolian sands of the Twente Formation (**Unit 6**) have been tentatively identified in vibrocores **VC075**, **VC076** and **VC088**. Further Stage 3 assessment is recommended on probable aeolian sand from **VC075** and **VC076** in order to characterise this unit and refine the outline stratigraphy for the site (**Table 2**).
- 7.3.2 Assessment will involve limited particle size analysis to characterise the grain size distribution of the sediment. An aeolian hypothesis will be strengthened if the particle size distribution is unimodal, indicative of a well-sorted, single mode of transport and sediment source, and including a relatively small silt component. By comparison, the sediments are less likely to be aeolian in origin if the particle size distribution is polymodal, suggesting multiple sources and modes of transport.

7.4 Holocene deposits (Unit 7)

7.4.1 Further Stage 3 assessment is recommended on vibrocores **VC074**, **VC076** and **VC085**, focusing on the peat and over/underlying minerogenic deposits. These sediments have the highest geoarchaeological potential in terms of suitable deposits for dating and likely to contain the widest range of well-preserved palaeoenvironmental remains.



- 7.4.2 The peat in each of the vibrocores formed within a different environmental setting, within a pre-transgression palaeochannel (**VC074**), on possible aeolian sands (**VC076**), and as part of a transition from saltmarsh to peat (**VC085**). The base of the peats also vary slightly in elevation (40.08 to 37.5 m LAT), although this may be a function of post-depositional sediment auto-compaction.
- 7.4.3 However, palaeoenvironmental assessment and scientific dating is recommended on all three vibrocores to determine whether the organic deposits represent a contemporary phase of peat formation across the site, or form separate phases of peat formation within distinct environmental niches.
- 7.4.4 Moreover, the peat/alluvial interfaces represent specific marine regressive/transgressive episodes, and are best placed to consider the impact of climate change and sea-level rise on early Holocene landscapes and human communities within the southern North Sea basin.
- 7.4.5 Targeted foraminifera, ostracod and diatom assessment are also recommended on deposits in **VC074** and **VC085** where the similarity between **Unit 5** and **Unit 7** sediments raises some uncertainly as to where the interface lies between the two units.

7.5 Research questions

- 7.5.1 A series of research questions are proposed which will underpin the recommendations for Stage 3 assessment, taking into account regional research framework (Medlycott, 2011) and the national maritime research framework (Ransley et al. 2013).
- 7.5.2 Specific research questions include:
 - Determine the environments represented by the geophysics and geotechnical samples.
 - Reconstruct past landscape and environmental change, including sea-level rise, vegetation change, and evidence for human activity impact.
 - What is the depositional history of the Brown Bank Formation? Did it form relatively
 quickly in the early Devensian or accumulate as a more gradual deposit? What
 implications does this have for the archaeological and geoarchaeological potential of
 the deposits?
 - Do the peats represent a contemporary phase of peat formation across the site, or separate phases of peat formation within discrete environmental niches?

7.6 Palaeoenvironmental assessment methods

7.6.1 Palaeoenvironmental assessment will involve a suite of complementary techniques, comprising pollen, diatom, foraminifera and ostracods, supported by radiocarbon dating of suitable organic deposits (**Table 3**). Multiple techniques are typically assessed in accordance with Historic England guidelines on good practice in environmental archaeology (Historic England 2011) and geoarchaeology (Historic England, 2015), providing a comprehensive understanding of the depositional and environmental context of the sediments.

Pollen analysis

7.6.2 Pollen is one of the principal techniques used in environmental archaeology to investigate past vegetation environments and the impact of human communities on the landscape, the latter often evident as distinct phases of woodland clearance or specific land-use strategies



(e.g., cereal cultivation, creation of pastures or meadows). Pollen is best preserved in waterlogged organic and oxygen-free sediment, such as peat, where the pollen grains are most representative of the surrounding vegetation at the time of deposition. Marine/riverine sediments are not ideal for pollen assessment as the grains may be transported over long distances or suspended in the water column for significant periods of time.

Diatoms, foraminifera and ostracods

7.6.3 Diatoms (unicellular algae), foraminifera (marine protozoa) and ostracods (bivalve Crustacea) occur in a wide range of marine and semi-terrestrial environments (e.g. saltmarsh) and provide important comparative indicators on past coastal and riverine change. Assessment of sediments at peat-alluvial transitions can help to distinguish evidence for sea-level, coastal and riverine change not immediately apparent in the pollen record, including, the influence of storm/hide tide events on semi-terrestrial environments (perhaps visible as fine organic/mineral banding in sediments).

Particle size analysis

7.6.4 Particle size analysis is a technique that quantifies the size distribution of grains ≤2mm in a soil or sediment. It is a useful technique to help understand the formation processes of deposits. For example, aeolian sands should be moderately well-sorted and contain virtually no silt or gravel.

Radiocarbon dating

7.6.5 Radiocarbon dating is an established technique used for determining the date of a range of organic materials. AMS (Accelerator Mass Spectrometry) dating of slices of peat, or of short-lived material (seeds, twigs) recovered from the peat, will provide a secure chronological context for these deposits and the palaeoenvironmental assessment recommended on select boreholes. Where thick peats are present AMS dates from the top and base of the peat are recommended, where as one date will suffice for thin and relatively short-lived peats.

Optically Stimulated Luminescence (OSL)

7.6.6 OSL dating is an established technique for dating sediments that are too old to be dated using conventional methods such as radiocarbon dating. The advantage of OSL dating is that the method doesn't require organic material and has a range from around 100 to 300,000 years, and therefore suited to **Unit 5** sediments.

8 REFERENCES

- Ashton, N., Lewis, S G., De Groote, I., Duffy, S M., Bates, M., Bates, R., Hoare, P., Lewis, M., Parfitt, S A., Peglar, S., Williams, C., and Stringer, C, (2014). Hominin Footprints from Early Pleistocene Deposits at Happisburgh, UK. In: *PLoS ONE*, 9 (2), e88329.
- Cameron, T D J., Crosby, A., Balson, P S., Jeffery, D H., Lott, G K., Bulat, J. and Harrison, D J, (1992). *The Geology of the Southern North Sea.* British Geological Survey United Kingdom Offshore Regional Report. London, HMSO.
- Cooper, W S., Townsend, I H., and Balson, P S, (2008). A Synthesis of Current Knowledge on the Genesis of the Great Yarmouth and Norfolk Bank Systems. The Crown Estate.
- Crombé, P., Van Strydonck, M., Boudin, M., Van den Brande, T., Derese, C., Vandenberghe, D A G., Van den Haute, P., Court-Picon, M., Verniers, J.,



- Gelorini, V., Bos, J A A., Verbruggen, F., Antrop, M., Bats, M., Bourgeois, J., De Reu, J., De Maeyer, P., De Smedt, P., Finke, P A., Van Meirvenne, M., and Zwertvaegher, A, (2012). Absolute Dating (14C and OSL) of the Formation of Coversand Ridges Occupied by Prehistoric Hunter-Gatherers in NW Belgium. *Radiocarbon*, 54(3-4), 715-726.
- EMU Limited, (2009). *The Outer Thames Estuary Regional Environmental Characterisation*, London, GB ALSF/MEPF (DEFRA).
- EMU Limited (2013). *East Anglia FOUR Offshore Wind Farm Geophysical Survey Report*. Unpublished Client Report, Ref: 12/J/1/02/2066/1346 FINAL.
- English Heritage, (2011). A guide to the theory and practice of methods, from sampling and recovery to post-excavation, 2nd edition.

 https://content.historicengland.org.uk/images-books/publications/environmental-archaeology-2nd.pdf/
- Fugro, (2016). Measure and derived geotechnical parameters and final results. Annex 1 vibrocore photographs. Norfolk Vanguard Offshore Windfarm Geotechnical investigation report, UK Continental Shelf, North Sea. GEO50/R2/Rev.1
- Fugro, (2017a). Measured and derived geotechnical parameters and final results. Norfolk Vanguard Offshore Wind Farm Geotechnical investigation report, UK Continental Shelf, North Sea. GEO50/R2/Rev.2
- Fugro (Fugro Survey B.V.) (2017b). Geophysical investigation report. Volume 1 of 3: Operations & Calibrations. Norfolk Vanguard Offshore Wind Farm. Unpublished report, ref. GE050-R1.
- Fugro (Fugro Survey B.V.) (2017c). Report 1 of 3: Geophysical Investigation Report. Volume 3 of 3: Geophysical Route Survey. Norfolk Vanguard Offshore Wind Farm. Unpublished report, ref. GE050-R1.
- Historic England, (2015). Geoarchaeology: using Earth Sciences to understand the archaeological record. https://historicengland.org.uk/images-books/publications/geoarchaeology-earth-sciences-to-understand-archaeological-record/
- Hodgson, J M, (1997). *Soil Survey Field Handbook*, Harpenden, Soil Survey Technical Monograph No. 5.
- Limpenny, S E., Barrio Froján, C., Cotterill, C., Foster-Smith, R L., Pearce, B., Tizzard, L., Limpenny, D L., Long, D., Walmsley, S., Kirby, S., Baker, K., Meadows, W J., Rees, J., Hill, J., Wilson, C., Leivers, M., Churchley, S., Russell, J., Birchenough, A C., Green, S L. and Law, R J, (2011). *The East Coast Regional Environmental Characterisation*. MEPF.
- Medlycott, M, (2011). Research and archaeology revisited: a revised framework for the East of England. *East Anglian Archaeology* 24.
- Parfitt, S. A, Ashton, N M., Lewis, S G., Abel, R L., Coope, G R., Field, M H., Gale, R., Hoare, P G., Larkin, N R., Lewis, M D., Karloukovski, V., Maher, B A, Peglar, S M., Preece, R C., Whittaker, J E., and Stringer, C B, (2010). Early Pleistocene



- human occupation at the edge of the boreal zone in northwest Europe. In: *Nature*, 466 (7303), 229–33.
- Ransley, J., Sturt, F., Dix, J., Adams, J. and Blue, L, (2013). People and the sea: a maritime archaeological research agenda for England. York, Council for British Archaeology Research Report 171.
- Ward, I., Larcombe, P., and Lillie, M, (2006). The dating of Doggerland Post-Glacial geochronology of the southern North Sea. *Environmental Archaeology* 11, 207-218.
- Wessex Archaeology, (2017a). Vanguard Offshore Wind Farm, Stage 1 geoarchaeological review. Unpublished Client report, ref: 11480.01.
- Wessex Archaeology, (2017b). Norfolk Vanguard Offshore Wind Farm, marine archaeological technical report. Unpublished Client report, ref: 112380.02.



9 APPENDIX

9.1 Vibrocore records

Locatio	on:	455852.0 E 5864848.7 N	Vibrocore:	VC070	Comments: 112380 Vanguard VC070 (Medium priority)			
Level (1	top):	40.4 mLAT	Drg:					
D	epth	Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
2.70- 2.90	43.1- 43.2	5		Gley 1 N 3 very dark grey clay with fine sand. Occasional flecks of gley 1 N/2.5 black clay. General finning of sand down profile			Bank	Upper Bro
2.90- 5.70	43.2- 46.1	-		GAP – Section	ons not present			own ba
5.70- 6.00	46.1- 46.4	5		mottled thround N 2.5 black laminations	very dark grey clay ughout with gley 1 clay. Also, distinct of slightly organic fine sand between	Formation	Bank	Upper Brown bank formation



Location:		464000.9 E 5853015.0 N	Vibrocore:	VC074	Comments: 112380 – Vanguard VC074 (Very High priority)		
Level (top):		38.5 mLAT	Drg:				
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
0.00- 0.78	38.5- 39.28	8		Some linear 0.65 m to b 10YR 4/1	yellowish brown sand. Fairly s and stone free. iron staining from base. Darkening to dark grey at radual boundary.	Marine sands/sea bed	Marine sands
0.78- 1.58	39.28- 40.08	7		dark grey n 10YR 2/ s slightly claye 10YR 2/1 k peters out at becomes p horizontally throughout woody frag irregular interleaving 5/1 grey fir 1.42m. Frag	ayers of 10YR 4/1 medium sand and oft very organic, ey peat oxidising to black. Interleaving 0.88m and deposit ure peat. Faintly laminated with occasional ments. Layer of (3mm-3cm) of peat and 10YR ne sand at 1.22- ment of land snail p.) at 1.34m. Sharp	inundations due to fluctuations in water level.	Peat with fluctuations in water level
1.58- 4.75	40.08- 43.25	7		slightly clay profile to silt/fine sand of faint he throughout. I 2.5Y 5/2 gre silt between	ark grey fine sand, yey, fining down become coarse. Occasional areas orizontal banding regular patches of eyish brown coarse ten 4.00-4.75m. fragment at 2.65m.	Channel fill	Pre-transgression palaeochannel fill
4.75- 5.00	43.25- 43.5	5		Gley 2 2.5/1 sfine sand	5B bluish black silty	Upper Brown Bank Formation	Uppe
5.00- 5.60	43.5- 44.1	5		very fine sai	10Y greenish black nd with coarse silt clay. Homogenous horizontal banding re marine shell		Upper Brown Bank Formation



Location:		458998.4 E 5866965.6 N	Vibrocore:	VC075	Comments: 112380 Vanguard VC075 (Medium priority)			
Level (top):		32.3 mLAT	Drg:					
De	epth	Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
4.40- 4.45	36.7- 36.75	7			very dark brown but slightly fibrous boundary		Peat	
4.45- 4.51	36.75- 36.81	7			very dark brown Oxidises to 10YR oundary		Peat with periods inun	
4.51- 4.54	36.81- 36.84	7		clay. Some fi	ery dark grey silty ne rooting from the Clear boundary.			
4.54- 4.67	36.84- 36.97	7		peat. Highly	10 YR 2/1 black y organic. Clear ompact but with remains.		of stabilisation and dation	
4.67- 4.70	36.97- 37.0	6		10 YR 3/1 ve silty fine sand	ry dark grey slightly d.	Periglacial aeolian sands	Twente Formation	



Location:		458994.6 E 5863171.8 N	Vibrocore:	VC076	Comments: 112380 – Vanguard VC076 (Very High priority)			
Level (top):		34.0 mLAT	Drg:					
Depth		Unit	Samples	Sediment de	escription	Interpretation		
Mono	mLAT							
0.00- 3.60	34.0- 37.6	8		moderate s stones ar fragmented Laminations black slightl silty clay a 1.80-1.81m. of 2.5Y 2.5	nd with sparse to mall sub-rounded in whole and marine shell. of Gley 1 2.5/N by organic buttery t 1.42-1.43m and Intermittent layers 1.40 and 1.90m and 3.35-		Marine sands	
3.6- 4.00	37.6- 38.0	7		minerogenic 10YR 2/2 ve fibrous pea finely horiz throughout. 2.5/2 very	peat becoming ry dark brown fairly at. Compact and contally laminated Becoming 7.5YR dark brown and from 3.94 to base.	above.	Peat	
4.00- 4.35	38.0- 38.35	6		with patches brown. Visibl above to 2.5	grey fairly fine sand s of 2.5Y 4/3 olive le rooting from peat 7m. Fairly compact visible horizontal	sands	Twente Formation	



Location:		466749.7 E 5853859.1 N	Vibrocore:	VC079	Comments: 1123 VC079 (High Prio	_			
Level (top):		40.8 mLAT	Drg:						
D	epth	Unit	Samples	Sediment de	escription	Interpretation	Interpretation		
Mono	mLAT								
0.00- 0.30	40.8- 41.1	8		marine s	yellowish brown sand. Fairly with occasional shell fragments	Marine sands/sea bed	Marine sands		
0.30- 4.55	41.1- 45.35	5		compact slig silt. Silt is m bordering or some place throughout areas of high sparse marir No visil laminations, in areas Boundary is 'mixed up' v black silty cla	with occasional er clay content and he shell fragments. ble horizontal appears 'marbled' with more clay. gradual and a bit with Gley 1 2.5/N ay and some 10YR llowish brown iron		Upper Brown Bank Formation		
4.55- 5.25	45.35- 46.05	5		medium con with modera small rounde stones and throughout. dark yellowis clayey san poorly sorted sub rounded shell at 4	ry dark grey fine to npact clayey sand ate poorly sorted ed to sub rounded marine shell Band of 10YR 3/6 sh brown medium d with common d small rounded to stones and marine 1.58-4.62m. Sand ghtly down profile.		Formation		



Location:		462164.3 E 5869081.7 N	Vibrocore:	VC080	Comments: 112380 Vanguard VC080 (Medium priority)		
Level (top):		34.9 mLAT	Drg:				
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
2.00- 2.06	36.9- 36.96	7		10 YR 2/2 very dark brown silt. Sharp boundary		Organic silt.	Possible being inun
2.06- 2.07	36.96- 36.97	7			Clear boundary.	Organic sand with peat	
2.07- 2.15	36.97- 37.05	7		Mottled mix of 2.5 Y dark greyish brown and 2.5 Y 3/3 dark olive brown fine sand with laminations of 2.5 Y 2.5/1 black slightly organic fine sand.		Organic sand	peat development gchoked off by dation events.



Location:		464097.1 E 5865795.0 N	Vibrocore:	VC081	Comments: 112380 Vanguard VC081 (Medium priority)		
Level (top):		35.8 mLAT	Drg:				
D	epth	Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
1.00- 1.28	36.8- 37.08	8		10 YR 4/4 dark yellowish brown medium sand with common marine shell fragments. Abrupt boundary			Marine sands
1.28- 1.49	37.08- 37.29	8 or 7?		10 Y 3/1 very dark greenish grey clayey fine to medium sand. Marbled with gley 1 2.5/N, slightly organic silt with fine sand. Occasional marine shell fragments throughout. Band of 10YR 2/1 black, slightly organic clay between 1.41 and 1.45m		with possible eroded	Organic sands and silts
1.49- 2.70	37.29- 38.5			GAP – sections not present			
2.70- 3.00	38.5- 38.8	5?		Gley 1 10Y 3/1 very dark greenish grey clay with fine sand. Homogenous.			Upper Brown Bank Formation



Locatio	n:	469907.6 E 5855974.2 N	Vibrocore:	VC084	Comments: 112380 Vanguard VC084 (Medium priority)			
Level (t	op):	38.5 mLAT	Drg:					
Depth U		Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
3.10- 3.17	41.6- 41.67	8		10 YR 4/3 brown coarse sand mottled with Gley 1 3/N very dark grey slightly silty sand. Marine shell fragments throughout. Clear boundary.		Marine sands.	Marine Sands	
3.17- 3.20	41.67- 41.7	5?		Gley 1 3/1 very dark greenish probable Upper grey slightly silty sand. Bank Formation Compact			Upper Brown Bank Formation	



Locatio	n:	465321.2 E 5871195.8 N	Vibrocore:	VC085	Comments: 1123 VC085 (Very High		
Level (1	op):	35.4 mLAT	Drg:				
D	epth	Unit	Samples	Sediment de	escription	Interpretation	
Mono	mLAT						
0.00-	35.4- 36.4	8		medium sa marine sh fragmented) Becoming 2. down profile linear patche	marine shell (whole and		Marine sands
1.00- 1.74	36.4- 37.14	7		grey slightly medium sa profile with la 4/1 dark gre clay from 1.1	Gley 1 4/1 5GY dark greenish grey slightly clayey fine to medium sand fining down profile with laminations of 10YR 4/1 dark grey soft slightly silty clay from 1.10-1.43. Occasional marine shell throughout. Very		Intertidal channel fill
1.74- 2.10	37.14- 37.5	7		crumbly ve oxidising to Quite comhorizontal throughout.	ry dark brown soft, bry organic peat 10YR 2/1 black. spact with fine laminations Rare small woody sharp boundary.		Peat
2.10- 2.61	37.5- 38.01	7		organic silty minerogenic very silty of lightening to greyish be evidence of r	clay, almost a very peat becoming down profile and o 2.5Y 4/2 dark brown. Possible rooting apparent as patches in the top	Possible salt marsh with peat development.	?Salt marsh
2.61- 2.92	38.01- 38.32	5		sand with sol of 2.5Y 4/1 2.68-2.75 homogenous	indicating rooting	Formation	Upper Brown Bank Formation
2.92- 5.37	38.32- 40.77			becoming co from 3.62m. roots visible peat above laminations black from predominant Concentratio	grey very silty clay barse silt with depth Occasional vertical to 3.80m (?from /e). Very fine of Gley 1 2.5/N 3.80m, becoming from 4m to base. In of marine shell to 3.75-3.85. Sharp		Intertidal channel fills ?BROWN BANK FORMATION



Locatio	Location: 465321.2 5871195.6		Vibrocore:	VC085 Comments: 112380 – Va VC085 (Very High priorit				
Level (top): 35.4 mLAT Drg:								
Depth		Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
5.37- 5.85	40.77- 41.25			grey compac Faint horizor	5G dark greenish of plastic silty clay. Intal laminations of black throughout.	FORMATION	BANK	



Locatio	n:	469004.4 E 5869009.3 N	Vibrocore:	VC086	Comments: 112380 Vanguard VC086 (Medium priority)		
Level (top): 36.2 mLAT Drg:							
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
4.25- 4.50	40.45- 40.7	5 or 8?		dark greyish in places wi brown slight Distinct lam 2.5/1 black	brown but mottled ith 2.5Y 4/4 olive	Unsure if this is upper part of Unit 8 or lower part of Unit 5	Top of Upper Brown Bank Formation or base of post-transgression seabed sediments



Locatio	n:	468497.9 E 5873319.3 N	Vibrocore:	VC088	Comments: 112380 Vanguard VC088 (Medium priority)		
Level (t	top): 34.8 mLAT Drg :						
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
3.25- 3.45	38.05- 38.25	7		10 YR 3/1 very dark grey slightly minerogenic peat. Visible rare plant remains. Mottled with 10 YR 2/1.		Peat being choked off.	Peat being
3.45- 3.60	38.25- 38.40	7		10 YR 2/2 very dark brown Fibrous peat with common visible plant remains. Oxidises visibly to 10YR 2/1 black.		Peat	g choked off.



Location	on:	470432.2 E 5870045.7 N	Vibrocore:	VC089	Comments: 1123 VC089 (Very High	_		
Level (top):	37.4 mLAT	Drg:					
D	epth	Unit	Samples	Sediment de	escription	Interpretation		
Mono	mLAT							
0.00- 2.26	37.4- 39.64	8		medium sa with occasion fragments. E (Gley 1 4/1	nd. Homogenous onal marine shell Band of siltier grey 10Y dark greenish between 0.6 – 1m.	Marine sands/sea bed.	Marine sands	
2.26–6.30	39.64- 43.7	5		compact slig silt. Silt is malmost a fin Generally ho horizontal marbled withroughout. change in 2.5/N, blackmarbled with very dark General finir	Pronounced colour to Gley 1 (a, at 5.21m. Still of Gley 1 10Y 3/1, greenish grey. The greenish grey of silt and sand Rare marine shell		Upper Brown Bank Formation	



Locatio	Location: 484593.7 E 5848529.7 N		Vibrocore:	VC092	VC092 Comments: 112380 Vanguard VC092 (Medium priority)		
Level (t	op):	37.2 mLAT	Drg:				
De	epth	Unit	Samples	Sediment de	escription	Interpretation	
Mono	mLAT						
2.70- 3.00	39.9- 40.0	5		mottled with 10Y 4/1 dark and flecks of	1 dark grey clay bands of gley 1 greenish grey clay gley 1 N 2.5 black. staining. Becomes n profile.	Formation	Upper Brown Bank Formation



Location	on:	488002.0 E 5848006.4 N	Vibrocore:	VC095	Comments: 1123 VC095 (High prio			
Level (top):	34.8 mLAT	Drg:					
D	epth	Unit	Samples	Sediment de	escription	Interpretation		
Mono	mLAT							
0.00- 0.70	34.8- 35.5	8		10YR 5/4 yellowish brown medium sand. Fairly homogenous with occasional marine shell fragments throughout. Gradual boundary 0.6-0.7m		Marine sands		
0.70- 1.00	35.5- 35.8	8		slightly silty scoarse with	2.5/1 greenish black sand which is quite occasional marine gments. Abrupt			
1.00- 1.52	35.8- 36.32	8		medium sai sterile. Gi	10YR 4/4 dark yellowish brown medium sand. Compact and			Marine sands
1.52- 1.92	36.32- 36.72	8		greenish greclayey sand marine so	Y 3/1 very dark by compact slightly distributed with occasional shell fragments. areas of higher clay arp boundary.			nds
1.92- 2.00	36.72- 36.8	8			Dark grey coarse mmon marine shell Compact.			
2.00- 2.54	36.8- 37.34	8			rown medium sand onal marine shell and abrupt			
2.54- 3.91	37.34- 38.71	5		silt bordering Horizontal land throughout.	2.5/1 blueish blacking on fine sand. aminations of clay Very rare marine gments. Abrupt	Formation	Bank	Upper Brown Bank formation
3.91- 4.07	38.71- 38.87	5			Y 3/1 Very dark by very fine sandy enous.			vn Bank fı
4.07- 6.30	38.87- 41.1	5		clayey laminations	I very dark grey with common of fine sandy silt. c inclusions. Fewer from 6.09			ormation



Locatio	on:	492184.3 E 5854650.9 N	Vibrocore:	VC097	Comments: 1123 VC097 (Medium p	•		
Level (top):	37.5 mLAT	Drg:					
D	epth	Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
3.70- 3.97	41.2- 41.47	5		grey clay. Co	4/1 dark greenish ompact, sterile and s. Sharp boundary.			
3.97- 4.00	41.47- 41.5	5		Mottled gley 1 N 2.5 black fine sandy silt and 2.5 Y 5/3 light olive brown very fine sand.				
4.00- 4.05	41.5- 41.55	5		,	ery dark grey, very orupt boundary.	Intertidal channel fills, mainly low energy events.		
4.05- 4.50	41.55- 42.0	5		clay with lam profile) and 3/N very da	ninations (at 45° to mottling of gley 1 rk grey fine sand, unced and more			



Locatio	on:	495986.7 E 5855742.4 N	Vibrocore:	VC101	Comments: 1123			
Level (t	op):	35.5 mLAT	Drg:					
De	epth	Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
0.00- 0.46	35.5- 35.96	8		medium sa with rare	nd. Homogenous marine shell Darkening to 10YR	Marine sand/sea bed		
0.46- 1.00	35.96- 36.5	8			Y 3/1 very dark ey slightly clayey medium sand. marine shell		Ma	
1.00- 1.60	36.5- 37.1	8		10YR 5/4 yellowish brown medium sand, soft compaction. Sterile with diffuse boundary.			Marine sands	
1.60- 2.82	37.1- 37.32	8		grey mediur Amorphous finer 10YR between 2 Gradual char 4/1 dark gre	4/1 dark greenish m sand, compact. patch of slightly 5/4 clayey sand .05 and 2.3m. nge to gley 2 10BG eenish grey clayey fining down profile.			
2.82- 4.29	37.32- 39.79	5		compact clay coarse borde Generally mottled in p clay cont laminations	very dark grey yey silt. Silt is quite ering on fine sand. homogenous but blaces with higher tent. Horizontal of gley 1 2.5/2.5 ay. Clear boundary.		Upper Brown Bar	
4.29- 6.10	39.79- 41.6	5		grey comp homogenous laminations	GY dark greenish act clay. Fairly but with horizontal of gley 1 2.5/2.5 silty clay between 9m.		nk Formation	



Locatio	n:	495974.9 E 5847831.4	Vibrocore:	VC103	Comments: 1123 VC103 (Medium p		
Level (t	ор):	35.8 mLAT	Drg:				
De	epth	Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
3.00- 3.09	38.8- 38.89	8		2.5Y 5/2 greyish brown medium sand. Slightly mixed up with silty clay from below. Homogenous. Clear irregular boundary			Marine sands
3.09- 3.50	38.89- 39.3	5		Horizontal bands of 2.5Y 4/2 dark greyish brown silty clay (with small (<2mm) round mottles of 2.5Y 3/1 very dark grey) and 2.5Y 3/1 very dark grey very fine sand/coarse silt.			Brown bank foramtion
3.50- 4.00	39.3- 39.8	-		GAP		GAP – section not present	
4.00- 4.37	39.8- 40.17	5		2.5Y 4/1 dark grey silty clay with some very fine sand oxidising to 2.5Y 4/2 dark greyish brown. Fairly regular bands (<3cm) of 5Y 4/2 olive grey slightly silty fine sand. Clear irregular boundary.		with ?aeolian events on erosion surface.	Brown bank form events on erosior periods of
4.37- 4.50	40.17- 40.3	5		Laminations of 2.5Y 3/1 silty clay (with some very fine sand) and fine sand/coarse silt of the same colour. From 4.43m the laminae become very thin with layers of 7.5YR 2.5/1 black organic silt. Plant remains observed under microscope.		with ?aeolian events on erosion surface and short periods of stabilisation.	Brown bank formation with ?aeolian events on erosion surfaces and short periods of stabilisation.



Locatio	n:	499790.2 E 5860769.2 N	Vibrocore:	VC104	Comments: 1123 VC104 (Medium p			
Level (op):	40.0 mLAT	Drg:					
D	epth	Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
2.70- 3.00	42.7- 43.0	5		2.5 Y 4/2 dark greyish brown compact fine silty clay. Homogenous but with very sporadic iron staining. Thin lens of 2.5Y 7/1 light grey sand at 2.94m		Formation	Bank	Upper Bro
3.00- 5.70	43.0- 45.7	-		GAP – Section	ons not present			own Ba
5.70- 6.00	45.7- 46.0	5		2.5Y 3/3 dark olive brown clay. Fairly homogenous but there are thin lenses of 2.5 Y 8/4 pale yellow fine sand and 10 YR 3/1 very dark grey slightly organic fine sand between 5.74 and 5.75m		Formation	Bank	Upper Brown Bank Formation



Location:		499791.7 E 5848922.3 N	Vibrocore:	VC107	Comments: 112380 – Vanguard VC107 (High priority)		
Level (top):		36.7 mLAT	Drg:				
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
0.00- 0.52	36.7- 37.22	8		2.5Y 4/2 dark greyish brown medium slightly silty sand with patches of 2.5Y 4/3 olive brown. Frequent marine shell throughout. Clear irregular boundary			Marine sands
0.52- 0.80	37.22- 37.5	5 or 7		5Y 2.5/1 black compact fine silty sand with occasional amorphous patches of Gley 1 2.5/N black soft silty clay. Rare patches of organics. Very sharp boundary.		represents part of the Upper Brown Bank or Holocene pre-	Upper Brown Bank formation or Holocene?
0.80- 6.00	37.5- 42.7	5		greenish gredark greenisilty clay. Silt very fine lam silt throughd Occasional diack) lami appears to organic coespecially at very fine (1n 10YR 2/2 very 2.90-2.93.	y to Gley 1 5GY 4/1 sh grey compact content varies with inations of coarser but the sequence. larker (Gley 1 2.5/N nations of what be slightly more arse silty clay, t 3.45-3.50. Some nm) laminations of ery dark brown at Deposit becomes by and slightly appearance when		Upper Brown Bank formation




Location:		460846.7 E 5848268.4 N	Vibrocore:	VC 116 Comments: 112380 Vanguard VC116 (high priority)			
Level (top):		47.7 mLAT	Drg:				
Depth		Unit	Samples	Sediment description		Interpretation	
Mono	mLAT						
0-00- 0.25	47.7- 47.95	8		2.5Y 4/3 oliv sand/. Sharp	ve brown fine silty Boundary	Marine sands	Marine sands
0.25- 0.65	47.95- 48.25	7		grey very s Sand is fine marine shell	4/1 dark greenish lightly sandy silt. to medium. Rare fragments, mainly 0.38-0.40m. Abrupt	Intertidal channel fills, mainly low energy events	Intertidal channel fills
0.65- 1.31	48.25- 49.01	5		organic sand marine shell higher clay	black, fine slightly dy silt. Occasional fragments. Slightly content in places, 0.90-1.11m. Clear	Upper Brown Bank Formation	Bro
1.31- 5.30	49.01- 53.0	5		greenish g	minations. Sterile.		Brown Bank Formation
5.60- 6.35	53.0- 54.05	5		silt. Sollaminations to in places v			nation




Location:		457661.6 E 5844832.9 N	Vibrocore:	VC117	Comments: 112380 Vanguard VC117 (medium priority)			
Level (top):		46.4	Drg:					
Depth		Unit	Samples	Sediment description		Interpretation		
Mono	mLAT							
1.00- 1.32	47.4- 47.72	8?		fine sand, f (2.5Y 4/3 oli bands with laminations dark greenis clay. Thin (3 3/1 very of	ive brown) in wide occasional thin of Gley 1 10Y 4/1 h grey slightly silty mm) band of 10YR lark grey slightly sand at 1.16m.	marine events ?sand dunes or ?redeposited Aeolian sands	?Sand dunes/redeposited deposits with	
1.32- 1.43	47.72- 47.83	8?		fine sand and with very laminations yellowish bro Gley 1 2.5 sandy silt remains. concentrated 1.39m and t	thin (<2mm) of 10YR 4/6 dark own iron stain and i/N black organic with visible plant Bands are	events as indicated by iron staining and presence of organics.	s/redeposited Aeolian sands overlying tidal or estuarine deposits with short periods of stabilisation.	
1.43- 1.50	47.83- 47.9	8?		of 2.5Y 4/2	dark greyish brown and 2.5Y 4/3 olive	?shallow sub tidal or estuarine environment	or estuarine	





Location:			Mono:	VC 118	Comments: 112380 Vanguard VC 118 (Medium priority)			
Level (top):			Drg:					
Depth		Unit	Samples	Sediment de	escription	Interpretation		
Mono	mOD							
0.70-3.29				sand with t sandy clay of Amorphous 2.5Y 3/1 ver in a very thi 7.5YR 4/6 stain at 0.75i 1.45m. Oo shell. Sharp lined in a thii as describe	ve brown fine silty hin laminations of of the same colour. patches (<8cm) of ry dark grey ringed in (<1mm) band of strong brown iron m, 0.92m and 1.38-ccasional marine by wavy boundary n band of iron stain ed above. GAP 1.5-3.00 (sections	possible organic patches and iron staining.	Marine sands with	
3.29- 4.00				silty sand Horizontal la 2.5/N black s 3.41. Beco	with some clay. minations of Gley 1 sandy clay at 3.34-mes sandy clay 3.62-3.73. Rare	Organic marine sands	Marine sands with fluctuations in water energy	
4.00- 4.50				GAP – section	on not present	GAP	renerg)	
4.5- 5.00				sand with t sandy clay of Sandy clay and black	ve brown fine silty hin laminations of of the same colour. band at 4.60-4.63 patches with iron s above at 4.80 and	possible organic patches and iron	,	








Norfolk Vanguard East, geophysics and borehole location (interpretative geophysics after Wessex Archaeology, 2017b)















Wessex Archaeology Ltd registered office Portway House, Old Sarum Park, Salisbury, Wiltshire SP4 6EB Tel: 01722 326867 Fax: 01722 337562 info@wessexarch.co.uk www.wessexarch.co.uk

