

**Environmental Statement:** Volume 6, Annex 6.2 – Soil Survey Data

PINS Document Reference: A6.6.6.2 APFP Regulation 5(2)(a)

**Date:** May 2018





Liability

This report has been prepared by RPS, with all reasonable skill, care and diligence within the terms of their contract



**Environmental Impact Assessment** 

**Environmental Statement** 

Volume 6

Annex 6.2 - Soil Survey Data

Report Number: A6.6.6.2

Version: Final

Date: May 2018

This report is also downloadable from the Hornsea Project Three offshore wind farm website at: <a href="https://www.hornseaproject3.co.uk">www.hornseaproject3.co.uk</a>

Ørsted

5 Howick Place,

London, SW1P 1WG

© Orsted Power (UK) Ltd., 2018. All rights reserved

Front cover picture: Kite surfer near a UK offshore wind farms © Orsted Hornsea Project Three (UK) Ltd 2018.

Prepared by: RPS

Checked by: Sarah Drljaca

with Orsted Power (UK) Ltd.

Accepted by: Stuart Livesey

Approved by: Stuart Livesey







## **Table of Contents**

=	ural Land Classification Survey Data	
1.1 Su	rvey Methodology	1
1.2 Su	rvey Area – Representative Auger Boring Descriptions	1
List of Ta	bles	
Table 1.1:	Key to Auger Boring Descriptions	1
Table 1.2:	Agricultural land classification survey data for Grade 3a in Area 1 North	
Table 1.3:	Agricultural land classification survey data for Grade 3b land in Area 1 North	
Table 1.4:	Agricultural land classification survey data for Grade 2 land in Area 1 South	
Table 1.5:	Agricultural land classification survey data for Grade 3a land in Area 1 South	
Table 1.6:	Agricultural land classification survey data for Grade 2 land in Area 2 North.	2
Table 1.7:	Agricultural land classification survey data for Grade 3a land in Area 2 North.	2
Table 1.8:	Agricultural land classification survey data for Grade 3b land in Area 2 North.	3
Table 1.9:	Agricultural land classification survey data for Grade 2 land in Area 2 South	3
Table 1.10:	Agricultural land classification survey data for Grade 3a land in Area 2 South	3
Table 1.11:	Agricultural land classification survey data for Grade 2 land in Area 3.	
Table 1.12:	Agricultural land classification survey data for Grade 3a land in Area 3.	4
Table 1.13:	Agricultural land classification survey data for Grade 3b land in Area 4.	4
Table 1.14:	Agricultural land classification survey data for Grade 3a land in Area 5.	4
Table 1.15:	Agricultural land classification survey data for Grade 3b land in Area 5.	
Table 1.16:	Agricultural land classification survey data for Grade 4 land in Area 5.	5
Table 1.17:	Agricultural land classification survey data for Grade 2 land in Area 6 HVDC converter/HVAC	_
	substation.	5
Table 1.18:	Agricultural land classification survey data for Grade 3a land in Area 6 HVDC converter/HVAC	E
Table 1 10:	substation.	5
Table 1.19:	Agricultural land classification survey data for Grade 3b land in Area 6 HVDC converter/HVAC	_







# Acronyms

Acronym	Description
ALC	Agricultural Land Classification
EA	Environment Agency
HVAC	High Voltage Alternating Current
HVDC	High Voltage Direct Current

# Units

Unit	Description
%	Percentage (proportion)
m	Metre (distance)
km	Kilometre (distance)







# 1. Agricultural Land Classification Survey Data

## 1.1 Survey Methodology

- 1.1.1.1 This annex presents the results of the detailed Agricultural Land Classification (ALC) survey within the Hornsea Three land use and recreation study area (as defined in volume 3, chapter 6: Land Use and Recreation). The survey comprised:
  - A reconnaissance survey of the soils to identify the nature and ALC of the soil types identified from
    the study of published information. This included the use of hand auger borings and soil pits, where
    necessary to confirm the characteristics of soil profiles within each of the soil types; and
  - A detailed ALC survey of area where there would be permanent loss of agricultural land (i.e. the onshore HVAC booster station area and onshore HVDC converter/HVAC substation area), comprising hand auger borings taken at approximately 100 m intervals across the area and soil pits as necessary.
- 1.1.1.2 The key to auger borings are set out in Table 1.1 and described in Table 1.4 to Table 1.19. The locations of the auger borings and the ALC gradings are shown in annex 6.3: Agricultural Land Classification and Farm Holdings Figures. In some instances, the route of onshore cable corridor was refined after the ALC survey was undertaken, and so the area surveyed does not always align with the route. However, as these findings are still immediately adjacent to the onshore cable corridor, they still relevant as they provide an indication of the ALC soil grading within the onshore cable corridor.

## 1.2 Survey Area – Representative Auger Boring Descriptions

Table 1.1: Key to Auger Boring Descriptions.

Colours				
Vdb	Very dark brown			
Db	Dark brown			
В	Brown			
Yb	Yellowish brown			
Rb	Reddish brown			
Gb	Greyish brown			
G	Grey			
Sb	Strong brown			

Textures					
Msl	Medium sandy loam				
Lms	Loamy medium sand				
Ms	Medium sand				
Cs	Coarse sand				
Lfs	Loamy fine sand				
Fs	Fine sand				
Scl	Sandy clay loam				
Szl	Sandy silt loam				
Mcl	Medium clay loam				
Hcl	Heavy clay loam				
Hzcl	Heavy silty clay loam				
Sc	Sandy clay				
С	Clay				
Zc	Silty clay				
Oth	ners				
TSP	Topsoil stoniness pits (1cm sieve)				
WC	Wetness Class				
SPL	Slowly permeable layer				
Cdom	Common distinct ochreous mottles				
Mn	Manganese concretions				
Calc	Calcareous				
Occn	Occasional				







## 1.2.1 Area 1 North

Table 1.2: Agricultural land classification survey data for Grade 3a in Area 1 North

Boring Number	Depth	Colour	Texture	Description	Grade
L2	0 – 29	Db	Mxl	5% stone	
	29 – 45	В	Msl	5% stone	2-
	45 – 60	Yb	Lms	5-10% stone	3a
	60 – 100+	Pyb	ms		
L4	0 – 26	Db	Msl	5-10% stone (some brick)	
	26 – 45	В	Scl	(slightly calc)	3a
	45 – 70+		Chalk Marl		

Table 1.3: Agricultural land classification survey data for Grade 3b land in Area 1 North

L17	0 – 30	Db	Lms	2% stone	3b
	30 – 100+	Pyb	Ms	(paler with depth)	30

#### 1.2.2 **Area 1 South**

Table 1.4: Agricultural land classification survey data for Grade 2 land in Area 1 South.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 30	Db	Msl	5% stone	
102	30 – 60	В	Msl	5% stone	2
	60-100	Sb	Msl	5-10% stone	
	0 – 30	DB	Msl	2-3% stone	
113	30 – 60	В	Msl	2-3% stone	2
	60 – 100+	(b)	Lms	<2% stone	

Table 1.5: Agricultural land classification survey data for Grade 3a land in Area 1 South.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 26	Db	Msl	2% stone	
116	26 – 70	Yb	Lms		3a
	70 – 100+	Yb	Ms		
110	0 – 25	Db	Msl	3-5% stone	
	25- 40	В	Msl	3-5% stone	2-
	40 – 60	В	Lms		- 3a
	60 – 100+	yb	Ms		

### 1.2.3 Area 2 North

Table 1.6: Agricultural land classification survey data for Grade 2 land in Area 2 North.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 30	Db	Msl	5% stone	
205	30 – 45	Db	MsI	5% stone	2
205	45 – 65	В	Lms	5% stone	2
	65 - 100+	(b)	Lfs		
234	0 – 28	В	Msl	5% stone (TSP)	
	28 -60	В	MsI	5% stone (SP)	2
	60 – 100+	(b)	Msl	3-5% stone	

Table 1.7: Agricultural land classification survey data for Grade 3a land in Area 2 North.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 27	Db	Msl	10% stone (TSP)	
	27 – 37	В	Msl	5- 10% (SP 8% est)	
222	37 - 50	Yb	Lms		3a
	50 - 80	Pyb (bleached)	ms	Stony at base	
	IMP				







Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 28	Db	MsI	10% stone	
	28 – 40	В	MsI	10% stone	
000	40 – 60	Yb	Lms	5% stone	
223	60 – 80	Rb	Ms	Stony at base (assumed 5 – 10% below)	3a
	IMP				
	0 – 27	Db	MsI	3- 5% stone	- 3a
231	27 – 35	В	Msl (tending to lms)	3 – 5% stone	
231	35 – 60	В	Lms	3 – 5% stone	
	60 – 100+	Yb	Ms		
245	0 – 28	Db	Scl	5% stone	
	28 – 40	В	Scl	5% stone	WC III 3a
	40 – 60	Yb	Sc	mottled	
	60 – 85+	Gb	C/Sc	Mottled SPL	

Table 1.8: Agricultural land classification survey data for Grade 3b land in Area 2 North.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 25	Db	Msl	15% total (TSP) Notably stonier patches in field and stone picking	
219	25 – 45	В	Ims	10 – 15%	3b
	45 – 60	Sb	ms	Gritty and stony	
	IMP				
	0 – 26	Db	MsI (Ims tending)	10% stone	
	26 – 36	В	Lms	10% stone	
211	36 - 60	Sb	Ms	Becoming stonier with depth	3b
	60+	IMP			
247	0 – 30	Db	Msl (tending lms	15%+stone	

Boring Nun	nber	Depth	Colour	Texture	Description	Grade
	3	0 – 80+	Sb/yb	Ms	Tending to cs gritty and stony throughout	3b (stone and drought)

## 1.2.4 Area 2 South

Table 1.9: Agricultural land classification survey data for Grade 2 land in Area 2 South.

Boring Number	Depth	Colour	Texture	Description	Grade
050	0 – 30	Db	Msl	2% stone	0
259	30 – 100+	В	Szl		2
	0 – 28	Db	Mcl	<2%	
	28 – 40	В	Mszl		
278	40 – 50	(pb)	Mixed msl with some bleached fine sand		2
	50 – 70	(pb)	Mixed Sc with fine sand patches		
	70 – 100+	Sb	Cs and clay intermixed		

Table 1.10: Agricultural land classification survey data for Grade 3a land in Area 2 South.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 26	Db	Msl	5% stone	
255	26 – 35	В	Msl	5% stone	2-
255	35 – 60	Yb	Lms		3a
	60 – 100+	Yb	ms		
	0 – 27	Db	MsI	5-10% stone (TSP closer to 10%)	
265	27 – 45	В	Msl	5% stone	За
265	45 – 60	Yb	Lms	Gritty	
	60 – 90	Sb	M(c) s	Gritty (moving to coarse	







Boring Number	Depth	Colour	Texture	Description	Grade
	IMP			Hit stone (assume not base of profile)	
	0 – 27	Db	MsI	5-10%	
274	27 – 37	В	MsI	5% stone	3a
274	37 – 65	Yb	Lms	55 stone	Sa
	65- 95+	Sb/yb	Ms (tending to c)	Slightly gritty	

### 1.2.5 Area 3

Table 1.11: Agricultural land classification survey data for Grade 2 land in Area 3.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 28	Db	MsI	5% stone	
304	28 – 45	В	MsI	5% stone	2
	45 – 100+	Pb	Lms	Gritty and slightly stony (5% total)	_

Table 1.12: Agricultural land classification survey data for Grade 3a land in Area 3.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 30	Db	Scl	5% stone	
302	30 – 60	В	Sc	Mottled and mn	WCIII 3a
	60 – 90+	Gb	С	Mottled SPL	
	0 – 30	Db	Scl	2-5% stone	
314	30 – 45	В	Sc	Occn mottles and mn	WCIII 3a
	45 – 80+	Yb	С	Mottled and SPL	
	0 – 28	Db	Msl (moving to lms)	2% stone	
316	28 – 60	В	Lms	2% stone	3a
	60 – 100+	Yb	Ms		

## 1.2.6 Area 4

Table 1.13: Agricultural land classification survey data for Grade 3b land in Area 4.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 30	Db	Lms	5% stone (gritty)	
406	30 – 60	В	Lms	5% stone	3b
	60 – 100+	Yb	ms		
	0 – 28	Db	Lms	5-10% stone	
	28 – 40	В	Lms	5-10%stone	
409	40 – 95	Yb	Ms	10% stone and gritty	3b
	IMP				
	0 – 30	Db	Lms	2% stone	
435	30 – 100+	Yb	Ms	Stony patches throughout (5% total)	3b/4

### 1.2.7 Area 5

Table 1.14: Agricultural land classification survey data for Grade 3a land in Area 5.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 28	Db	msl	5% stone	
507	28 - 50	В	Msl	5% stone	3a
507	50 – 80	Yb	Lms	5-10% stone	j sa
	80 - 100+	Yb (pale)	Ms	10% gritty	
	0 – 30	Db	Scl	<2% stone (non calc)	
538	30 - 50	В	Scl/sc	Cdom and mn (mottled)	3a (WC III)
	50 – 80+	Gb	С	Calc mottled SPL	







Table 1.15: Agricultural land classification survey data for Grade 3b land in Area 5.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 27	Db	Lms	5-10% stone	
	27 – 35	В	Lms	10+% stone	
501	35 – 70	Yb	Ms	Stony and gritty 15+%	3b
	70 – 80		Ms becoming coarse and very stony		
	IMP				
517	0 – 28	Db	MsI	5% stone	3b
	28 – 45	В	Lms	5% stone	
	45 – 100+	Yb	Ms	5% stone	

Table 1.16: Agricultural land classification survey data for Grade 4 land in Area 5.

Boring Number	Depth	Colour	Texture	Description	Grade
515	0 – 20	Vdb/black	Humose hzcl		4
	20 -90+	G	Wet ac	Cdom SPL	

## 1.2.8 Area 6 HVDC converter/HVAC substation

Table 1.17: Agricultural land classification survey data for Grade 2 land in Area 6 HVDC converter/HVAC substation.

Boring Number	Depth	Colour	Texture	Description	Grade
	0 – 27	Db	Scl	5% stone	
	27 – 40	В	Scl	5% stone	
603	40 – 80		Chalky mcl	(20% + chalk) 5% stone	2
	80 +			Chalky marl	
626	0 -30	Db	Msl	5% -10% stone	2
	30 – 50	В	Scl	5% stone	
	50 – 100+	В	Sc	fdom	

Table 1.18: Agricultural land classification survey data for Grade 3a land in Area 6 HVDC converter/HVAC substation.

Boring Number	Depth	Colour	Texture	Description	Grade
606	0 – 27	Db	Scl	5% stone	3a (WCIII)
	27 – 35	В	Scl	5% stone	
	35 – 50	В	С	mottled	
	50 – 90	Gb	С	Mottled SPL (slightly calc)	
	90+			Becoming chalky	
617	0 – 27	Db	Scl	5% stone	3a (WCIII)
	27 – 35	В	McI	5% stone	
	35 – 80	Gb	С	Cdom plastic	
	80 – 100+			Becoming chalky	

Table 1.19: Agricultural land classification survey data for Grade 3b land in Area 6 HVDC converter/HVAC substation.

Boring Number	Depth	Colour	Texture	Description	Grade
628	0 – 28	Db	Msl	5% stone	3b
	28 – 40	Sb	Lms	2% stone	
	40 – 100+	Yb	Ms		



