

Vattenfall Wind Power Ltd Thanet Extension Offshore Wind Farm

Annex C to Appendix 34 of Deadline 3 Submission

– Offshore Project Description Assessed in the
Environmental Statement

Relevant Examination Deadline: 3

Submitted by Vattenfall Wind Power Ltd

Date: March 2019

Revision B

Drafted By:	GoBe Consultants Ltd
Approved By:	Daniel Bates
Date of Approval:	March 2019
Revision:	В

Revision A	Original Document submitted to the Examining Authority	
Revision B	Revised document submitted to the Examining Authority following consultation	
N/A		
N/A		

Copyright © 2019 Vattenfall Wind Power Ltd

All pre-existing rights retained

Contents

1	Maximum Design Parameters4
---	----------------------------

Tables

Table 1: Maximum design parameters assessed within he Thanet Extension Environment	al
Statement	4
Table 2: Maximum Disposal Volumes for Thanet Extension	24
Table 3: Maximum scour protection area for Thanet Extension	24
Table 4: Maximum scour protection volume for Thanet Extension	24
Table 5: Maximum cable protection area for Thanet Extension	25
Table 6: Maximum cable protection volume for Thanet Extension	26
Table 7: Maximum drill arising volume for Thanet Extension	26
Table 8: Maximum disturbance sediment volume for installation of cabling for Thanet	
Extension (excluding pre-sweeping)	27
Table 9: Maximum disturbance sediment volume for pre-sweeping for cable corridors for	
Thanet Extension	27
Table 10: Maximum infrastructure footprint for Thanet Extension Construction activities	28
Table 11: Maximum disturbance area for Thanet Extension O&M activities	29
Table 12: Maximum disturbance volume for Thanet Extension O&M activities	29



1 Maximum Design Parameters

- Volume 2, Chapter 1: Project Description (Offshore) (PINS Ref APP-042/ Application Ref 6.2.1) presented the proposed design envelope for the Thanet Extension Offshore Wind Farm (Thanet Extension). This clarification note should read in conjunction with PINS Ref APP-042/ Application Ref 6.2.1; and seeks to provide the maximum design envelope for the proposed Thanet Extension.
- This document should be read in conjunction with the "Project Description Transcription into the Environmental Statement" clarification note, in particular for the areas highlighted in the footnotes of this document.
- Table 1 presents the maximum design parameters presented within the chapter and have been assessed by the Applicant within the Environmental Statement (ES). Table 1 also provides any assumptions applied within the ES such as design parameters of met mast foundations.
- For ease of reference the calculated maximum total values assessed within the ES of their constituent parameters are presented in Table 2 to Table 12.

Table 1: Maximum design parameters assessed within he Thanet Extension Environmental Statement

Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.1	Development located in the North Sea approximately	8km
Paragraph 1.3.2	Electrical output capacity	Up to 340 MW
Paragraph 1.1.1	Wind Turbine Generators (WTGs)	Up to 34 Wind Turbine Generators
Paragraph 1.1.1	Meteorological mast (met mast) fixed to the seabed	up to one Meteorological Mast
Paragraph 1.1.1	Floating Lidar Device (FLD) and wave buoys fixed to the seabed	Up to one LIDAR device and up to one wave buoy
Paragraph 1.1.1	Offshore substation fixed to the seabed	Up to one Offshore Substation
Paragraph 1.1.1	Offshore subsea export cables and fibre optic cables	Up to four offshore export cables
Table 1.1	Total site area array (km²)	70
Table 1.1	Total OECC area (km²)	28
Table 1.1	Maximum WTG Size	12 MW+



Project Description	Parameter description	Maximum parameters
Chapter Ref		
Paragraph 1.4.15	Minimum WTG spacing	716 m x 480 m ⁱ
Provided in Application Ref 8.14.	Disposal	The disposal of inert material of natural origin.
Maximum des	sign envelope for WTGs	
Table 1.2	Minimum height of lowest blade tip above MHWS (m)	22
Table 1.2	Maximum blade tip height above HAT (m)	250
Table 1.2	Maximum rotor blade diameter (m)	220
Indicative max	kimum requirements for these oils and fluids for a	single WTG
Table 1.3	Grease (I)	2000
Table 1.3	Synthetic oil/ hydraulic oil (I)	2000
Table 1.3	Nitrogen (I)	200
Table 1.3	Transformer silicone oil (kg)	2000
Table 1.3	Sulphur hexafluoride (SF6) (kg)	100
Table 1.3	Water/ glycerol (I)	2000
Maximum des	sign envelope for WTG monopile foundations	
Table 1.4	Diameter of monopile (top) (m)	7.5
Table 1.4	Diameter of monopile (bottom) (m)	10
Table 1.4	Diameter of transition piece (top diameter at TP-tower interface) (m)	7.5
Table 1.4	Diameter of transition piece (bottom diameter at MP-TP interface) (m)	10
Table 1.4	Embedment depth (below seabed) (m)	75
Table 1.4	Drill diameter (m)	7.5
Table 1.4	Volume of drill arisings per pile (m³)	1,325
Table 1.4	Locations requiring drilling (%)	50
Table 1.4	Locations potentially installed by driven piling (%)	100
Table 1.4	Total drill arisings for WTG monopiles (m³)	19,627 ⁱⁱ

See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submissionAnnex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.

ⁱⁱ See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.



Project		Maximum
Description	Parameter description	parameters
Chapter Ref Table 1.4	Grout volume per foundation (m ³)	120
Table 1.4	Hammer energy (kJ)	5,000
Table 1.4	Number of blows per foundation	8,000
Table 1.4	Piling time per foundation (assuming issues such as low blow rate, refusal etc.) (hours)	6
Maximum desig	gn envelope for WTG quadropod jacket foundatio	ns
Table 1.5	Number of legs per foundation	4
Table 1.5	Separation of adjacent legs at seabed level (m)	40
Table 1.5	Separation of adjacent legs at Mean Sea Level (MSL) (m)	20
Table 1.5	Height of main access platform above HAT (m)	20
Table 1.5	Leg diameter (m)	3.5
Table 1.5	Embedment depth (below seabed) (m)	70
Table 1.5	Volume of drill arisings per foundation (four pin-piles) (m³)	1,400
Table 1.5	Locations requiring drilling (%)	50
Table 1.5	Locations potentially installed by driven piling (%)	100
Table 1.5	Total drill arisings (m³)	17,802
Table 1.5	Grout volume per foundation (piles) (m³)	60
Table 1.5	Grout volume per foundation (screw piles) (m³)	85
Table 1.5	Hammer energy (kJ)	2,700
Table 1.5	Piling time per foundation (four pinpiles) (assuming issues such as low blow rate, refusal etc.) (hours)	10
Maximum desig	gn envelope for suction caisson jacket WTG found	ations
Table 1.6	Number of legs	4
Table 1.6	Separation of adjacent legs at seabed level (m)	40
Table 1.6	Separation of adjacent legs at Mean Sea Level (MSL) (m)	20
Table 1.6	Height of platform above HAT (m)	20
Table 1.6	Leg diameter (m)	3.5
Table 1.6	Suction buckets per foundation	4
Table 1.6	Suction bucket diameter (m)	20
N/A	Suction bucket footprint (m²)	1,256.6



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.6	Bucket penetration depth (below seabed) (m)	20
Table 1.6	Grout volume per foundation (m³)	105
Table 1.6	Depth of seabed preparation (m)	3
Table 1.6	Area of seabed preparation per foundation (m ²)	3,200
Table 1.6	Volume per foundation for seabed preparation work (m³)	9,600
Table 1.6	Volume for seabed preparation works (for WTG foundations only) (m³)	268,800 ⁱⁱⁱ
	gn envelope for scour protection (based on suction	
	hich represent the greatest scour protection requi	<u> </u>
Table 1.7	Median rock diameter (mm)	200
Table 1.7	Scour protection depth (rock) (m)	5
Table 1.7	Total scour protection area (WTG foundations only) (m ²)	219,912
Table 1.7	Scour protection diameter	5 x pile diameter
Table 1.7	Scour protection volume per foundation (m³)	39,269.90 ^{iv}
Table 1.7	Scour protection total volume (WTG foundations only) (m³)	1,112,647.40
Paragraphs 1.4.52 to 1.4.55	Scour protection types	Rock placement, rock armour, frond mat systems
Maximum desi	gn envelope for the inter-array cables	
Table 1.8	System voltage (kV)	66
Table 1.8	External cable diameter (mm)	300
Table 1.8	Total length of inter-array cables (km)	64
Table 1.8	Maximum burial depth (m)	3
Table 1.8	Minimum burial depth (m)	0
Table 1.8	Trench width (m)	1
Paragraph 1.4.60	Pre-lay grapnel runs	Pre-Lay Grapnel Runs (PLGR) will be conducted to remove seabed surface debris along a 1 – 2 m wide area. The grapnel

iii See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1) for how this has been assessed within the application.

^{iv} See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.



Project		
Description	Parameter description	Maximum
Chapter Ref		parameters
		typically penetrates the seabed to 0.5 m depth and is selected and configured in accordance with the seabed conditions.
Maximum desig	gn envelope for inter-array cable installation	
Table 1.9	Burial technique	Jetting/ Ploughing/ Trenching/ Cutting/ Mass Flow Excavation/ Pre- sweeping (dredging)
Table 1.9	Length of inter-array cables (km)	64
Table 1.9	Maximum burial depth (m)	3
Table 1.9	Minimum burial depth (m)	0
Table 1.9	Percentage cable requiring additional protection (%)	25
Table 1.9	Length of cable requiring additional protection (m)	16,000
Table 1.9	Indicative trench width (m)	1
Table 1.9	Width of disturbance from jetting (m)	5
Table 1.9	Area of disturbance from jetting (km²)	0.3
Table 1.9	Width of disturbance from ploughing (m)	10
Table 1.9	Area of disturbance from ploughing (km²) ^v	0.064
Table 1.9	Width of rock berm protection (m)	5
Table 1.9	Area of cable protection excluding crossings (m²)	80,000
Table 1.9	Height of rock berm protection (m)	0.5
Table 1.9	Volume of surface protection per km (based on a 0.5 x 5, trapezoid) (m³ km⁻¹)	1,250
Table 1.9	Length of exposed cable approaching WTG foundation requiring rock dumping/remedial protection (m)	50

 $^{^{\}rm v}$ This was presented in the project description chapter as 0.06 km² as a rounding error. Please see corresponding clarification note (B of Appendix 1 of the Applicant's Deadline 1 submission).



Project		
Description	Parameter description	Maximum
Chapter Ref		parameters
Table 1.9	Total area of WTG foundations requiring rock dumping/ remedial protection (m²) (34 WTG and one OSS foundation)	17,500 ^{vi}
Maximum design	gn envelope for inter-array cable crossing protecti	on
Table 1.10	Crossing technique	Rock dumping/ concrete mattresses/ steel bridging/ concrete bridging
Table 1.10	Number of cable crossings	12
Table 1.10	Length of crossings (m)	100
Table 1.10	Width of crossings (m)	10
Table 1.10	Volume of post-lay rock berm protection per cable crossing (m³)	500
Table 1.10	Number of concrete mattresses (6 x 3 x 0.3 m) per crossing	24
Table 1.10	Area of post-lay rock berm protection per cable crossing (m ²)	1,000
Table 1.10	Total area of rock berm protection for crossings (m ²)	12,000
Table 1.10	Total volume of rock berm protection for crossings (m³)	6,000
Maximum desig	gn envelope for the OSS	
Table 1.11	Topside weight (tonnes)	2,500
Table 1.11	Topside length (m)	70
Table 1.11	Topside width (m)	50
Table 1.11	Topside height (excluding crane and helideck) (m)	30
Table 1.11	Topside height above HAT (excluding crane and helideck) (m)	55
Table 1.11	Topside height above HAT (including crane) (m)	80
Table 1.11	Annual O&M time (weeks)	2
Table 1.11	Diesel fuel (I)	200,000
Table 1.11	Gray water (m³)	1,000
Table 1.11	Black water (m³)	1,000
Table 1.11	Transformer coolant oil (kg)	600,000

 $^{^{\}rm vi}$ See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.11	UPS Batteries (I)	10
Table 1.11	Fire suppression systems (I)	20,000
Table 1.11	Sulphur hexafluoride (SF6) (kg)	1,500
Table 1.11	Engine oil (m³)	5
Table 1.11	HVAC coolant (glycol) (m³)	5
Maximum desig	gn envelope for the installation of the OSS using d	riven monopiles
Table 1.12	Pile diameter (m)	10
Table 1.12	Pile penetration depth (m)	50
Table 1.12	Hammer energy (kJ)	5,000
Table 1.12	Piling time per foundation (hr)	6
Table 1.12	Foundations by driven piling (%)	100
Table 1.12	Foundations installed by drilling (%)	50
Table 1.12	Drill diameter (m)	6
Table 1.12	Volume of risings per pile (m³)	1,000 ^{vii}
Table 1.12	Grout volume per foundation (m³)	160
Table 1.12	Scour protection options viii	Rock placement, rock armour, frond mat systems
Table 1.12	Scour protection depth (m)	5
Table 1.12	Scour protection area (excluding structure footprint (m²)	1,964 ^{ix}
Table 1.12	Topside indicative installation time excluding cable installation (from arrival on site) (weeks)	1
Maximum design envelope for the installation of the OSS using driven tripod jacket		
Table 1.12	Pile diameter (m)	3
Table 1.12	Pile penetration depth (m)	70
Table 1.12	Width of jacket at seabed (m)	36
Table 1.12	Width of jacket at MSL (m)	28
Table 1.12	Jacket leg spacing (m)	34

 $^{^{}vii}$ See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.

^{ix} See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.



viii In project description chapter states to be the same as WTG foundations. It has been repeated in this table for clarity.

Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.12	Hammer energy (kJ)	2,700
Table 1.12	Piling time per foundation (hr)	6
Table 1.12	Foundations by driven piling (%)	100
Table 1.12	Foundations installed by drilling (%)	100
Table 1.12	Drill diameter (m)	4
Table 1.12	Volume of risings per pile (m³)	200
Table 1.12	Volume of risings per OSS foundation (m³)	450
Table 1.12	Grout volume per foundation (m³)	100
Table 1.12	Scour protection options ^x	Rock placement, rock armour, frond mat systems
Table 1.12	Scour protection depth (m)	5
Table 1.12	Scour protection area (excluding structure footprint (m²)	2,025
Table 1.12	Topside indicative installation time excluding cable installation (from arrival on site) (weeks)	1
Maximum desig	gn envelope for the installation of the OSS using a	suction caisson jacket
Table 1.13	Suction bucket foundation leg diameter above sea surface (m)	3
Table 1.13	Suction bucket diameter (m) (Note: for tripod foundation)	20
N/A	Suction bucket footprint (m²)	942.5
Table 1.13	Bucket penetration depth (m)	15
Table 1.13	Grout volume per foundation (m³)	200
Table 1.13	Total grout volume for OSS (m³)	800
Table 1.13	Scour protection options ^x	Rock placement, rock armour, frond mat systems
Table 1.13	Scour protection depth (rock) (m)	5
Table 1.13	Scour protection area (including structure footprint (m ²)	7,854
Maximum design envelope for the offshore Meteorological Mast (Met Mast)		
Table 1.14	Maximum elevation (mHAT)	Maximum hub height of WTGs

 $^{^{\}rm x}$ In project description chapter states to be the same as WTG foundations. It has been repeated in this table for clarity.



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.14	Met Mast spacing	The Met Mast follows the minimum spacing of the 716 m x 480 m.
Table 1.14	Hazardous materials (litres)	0
Table 1.14	Indicative number of yearly O&M visits	15
Table 1.14	Indicative instruments	Anemometers and wind vanes at a minimum of three measurement heights.
Additional assu	mptions applied within the ES for the Met Mast –	Monopile foundation
	Diameter of monopile (bottom) (m)	Max 10
	Volume of drill arisings per pile (m³)	1,325 ^{xi}
Assumptions	Locations requiring drilling (%)	100
taken from monopile	Locations potentially installed by driven piling (%)	100
WTG	Hammer energy (kJ)	5,000
foundations – Table 1.6	Number of blows per foundation	8,000
	Piling time per foundation (assuming issues such as low blow rate, refusal etc.) (hours)	6
	Seabed preparation volume (m³)xii	9,600
Additional assurtion	mptions applied within the ES for the Met Mast –	Suction Caisson
	Number of legs	4
Assumptions taken from	Suction bucket diameter (m)	20
suction	Depth of seabed preparation (m)	3
caisson WTG foundations –	Area of seabed preparation per foundation (m ²)	3,200
Table 1.6	Volume per foundation for seabed preparation work (m ³)	9,600
Accumptions	Scour protection depth (rock) (m)	5
Assumptions taken from suction caisson WTG	Scour protection diameter	5 x pile diameter
	Scour protection areaxiii	7,854
	Scour protection volume per foundation (m³)	39,269.90

^{xi} See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.

xiii Not presented within the project description but used within assessments. See Table 3.



xii This has been derived based on the parameters for a suction caisson WTG foundation

Project			
Description	Parameter description	Maximum	
Chapter Ref		parameters	
foundations – Table 1.7	Scour protection types	Rock placement, rock armour, frond mat systems	
Additional assu	mptions applied within the ES for the Met Mast –	Jacket foundation	
	Number of legs per foundation	4	
	Separation of adjacent legs at seabed level (m)	40	
	Leg diameter (m)	3.5	
	Embedment depth (below seabed) (m)	70	
Assumptions	Volume of drill arisings per foundation (four pin-piles) (m³)	1,400	
taken from	Locations requiring drilling (%)	100	
jacket WTG foundations –	Locations potentially installed by driven piling (%)	100	
Table 1.5	Total drill arisings (m³)	1,400	
	Grout volume per foundation (piles) (m³)	60	
	Grout volume per foundation (screw piles) (m ³)	85	
	Hammer energy (kJ)	2,700	
	Piling time per foundation (four pinpiles) (assuming issues such as low blow rate, refusal etc.) (hours)	10	
Maximum desig	gn envelope for offshore export cables		
Table 1.15	Cable specification	3-core XLPE (Cross- linked Polyethylene) or similar.	
Table 1.15	Cable voltage (kV)	220 kV	
Table 1.15	Indicative external cable diameter (mm)	300	
Table 1.15	Length of cables (km)	30 per cable	
Table 1.15	Total length of cables (km)	120	
Table 1.15	Indicative expected duration of installation activities (days)	30 days per cable	
Table 1.15	Indicative spacing between cables if unbundled (m)	50 m within pair; 120 m between pairs	
Table 1.15	Spacing between adjacent cables if multiple cables (m)	250	
Table 1.15	Trench width per cable (jetting) (m)	10	
Maximum desig	Maximum design envelope for offshore export cable installation		



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.16	Maximum Burial depth (m)	3 below mean seabed depth
Table 1.16	Minimum Burial depth (m)	0
Table 1.16	Indicative trench width from jetting (m)	10
Table 1.16	Width of disturbance from jetting (m)	10
Table 1.16	Total area of disturbance from jetting (km²)	1.2 (0.3 km² per cable)
Table 1.16	Width of disturbance from ploughing (m)	12
Table 1.16	Area of disturbance from ploughing (km²)	1.4
Table 1.16	Pre-sweeping length (dredging) (km)	24 (6 km per cable)
Table 1.16	Pre-sweeping width of dredging corridor (m)	20
Table 1.16	Pre-sweeping area of dredging corridor (km²)	0.48
Table 1.16	Pre-sweeping volume of dredging corridor (m ³)	1,440,000
Table 1.16	Pre-lay grapnel run width (m)	20
Table 1.16	Pre-lay grapnel run area (km²)	2.4
Table 1.16	Width of cable protection per cable (m)	7
Table 1.16	Percentage of each cable requiring protection (%)	25
Table 1.16	Length of cable protection (m)	7,500
Table 1.16	Area of cable protection per export cable (m²)	52,500
Table 1.16	Total area of cable protection (excluding cable crossings) (m ²)	210,000
Maximum desig	gn envelope for cable crossings for the offshore ex	port cables
Table 1.17	Number of crossing	20
Table 1.17	Total number of crossings Assuming a four- cable scenario	80
Table 1.17	Length of crossings (m)	100
Table 1.17	Width of crossings (m)	10
Table 1.17	Post-lay berm height (m)	0.5
Table 1.17	Volume of post-lay rock berm protection per crossing (m³)	500
Table 1.17	Number of concrete mattresses (6.0 x 3.0 x 0.3 m) per crossing	50
Table 1.17	Area of post-lay rock berm protection per cable crossing (m ²)	1000
Not presented in the project	Total area of protection from export cable crossings (m ²)	80,000



Project		
Description	Parameter description	Maximum
Chapter Ref		parameters
description as		
a total but		
calculated		
from the		
parameters		
outlined		
above from Table 1.17.		
	gn envelope for open trenching within the intertion	I
Table 1.18	Open trench length per cable circuit (km)	2
Table 1.18	Open trench depth (m)	3
Paragraph	Trench separation and associated temporary	5
1.4.95 and	route tracks (m)	
Figure 1.16		_
T-1-1- 4 40	Width of cable route (based on 4 cable circuits,	40
Table 1.18	temporary route tracks and sediment storage)	
T-bl- 4 40	(m) Area of disturbance (m²) for four cable circuits	80,000
Table 1.18	<u> </u>	80,000
	gn envelope for HDD landfall option	T
Table 1.19	Temporary works compound area (m)	60 x 50
Table 1.19	Onshore cofferdam area (m²)	704
Table 1.19	Excavated material from landfall/ TJBs (HDD) (m³)	1,408
Table 1.19		1,600 (20 m x 20 m
	Offshore cofferdam area (m²)	per cable with a
		maximum of 4 cables)
Table 1.19	Minimum punch out distance from sea wall (m)	100
Table 1.19		(All drilling mud to be
	Volume of drilling mud volume to be released	captured within
	to environment (m³)	cofferdam or other
Table 1.19	Manual diseasting (see settle)	structure)
	Works duration (months)	
	erdam and over ground cable installation design p	
Table 1.20	Width of cofferdam (m)	165
Table 1.20	Depth of cofferdam (m)	25
Table 1.20	Temporary works compound area (m)	40 x 30
Table 1.20	Construction space required in saltmarsh (m ²)	3,872
Table 1.20	Piling Noise level (dBA)	132



Project		
Description	Parameter description	Maximum
Chapter Ref		parameters
Table 1.20	Duration of piling (days)	33
Table 1.20	Depth of sea wall extension (m)	18.5
Table 1.20	Max width of sea wall extension (m)	155
Table 1.20	Area of permanent seaward extension (m²)	1398.9 ^{xiv}
Table 1.20	% loss of saltmarsh in the Thanet Coast and Sandwich Bay SAC	0.13
Table 1.20	TJB and cable route bund slope (other than for crossings)	1:5
Table 1.20	Bund height of onshore cable route (m)	1.2
Table 1.20	Bund height of TJBs (m)	2.3
Table 1.20	Bund width of TJBs (m)	45
Paragraph 1.4.109	Maximum distance of TJBs from the existing sea wall (m)	350
UXO assumptio	ns	
Table 1.21	Number of UXO	30
Table 1.21	Clearance/ Removal date (dependent on final construction programme)	2020
Table 1.21	Days to clear (based on 4 per day)	8
Table 1.21	Detonations per 24 hr period	8
Table 1.21	Minimum charge weight anticipated (kg)	0.5
Table 1.21	Maximum charge weight anticipated (kg)	130
Maximum cons	truction vessel quantities on-site at the same time	2
Table 1.22	Seabed preparation vessels	3
Table 1.22	Foundation spreads per project	1
Table 1.22	Number of vessels per foundation spread (includes tugs and feeders)	5
Table 1.22	Transition piece installation vessels	2
Table 1.22	Scour Installation Vessels	6
Table 1.22	Number of vessels engaged in foundations	5
Table 1.22	Wind turbine installation spreads	3
Table 1.22	Max vessels per WTG installation spread	3
Table 1.22	Total WTG installation vessels	6

xiv See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application.



Project		
Description	Parameter description	Maximum parameters
Chapter Ref		parameters
Table 1.22	Commissioning vessels	7
Table 1.22	Accommodation vessels	1
Table 1.22	Total IA cable vessels	4
Table 1.22	Number of Export Cable spreads per Project	3
Table 1.22	Number of vessels per Export Cable spread	2
Table 1.22	Total export cable vessels	6
Table 1.22	Landfall cable installation vessels	2
Table 1.22	Substation/ collector IV	3
Table 1.22	Other vessels	3
Table 1.22	Total	48
Construction pe	eriod I&O Vessels Round Trips to Port for Project o	over 3 years
Table 1.23	Seabed Preparation Vessel	15
Table 1.23	Foundation Installation Spread	60
Table 1.23	Transition Piece Installation	30
Table 1.23	Scour Vessel	30
Table 1.23	WTG Installation Spread	23
Table 1.23	Commissioning Vessels	480
Table 1.23	IA Cable Vessels	60
Table 1.23	Export Cable Vessels	300
Table 1.23	Landfall Cable Installation Vessels	30
Table 1.23	Substation Installation Vessels	12
Table 1.23	Other Vessels	120
Table 1.23	Total	1,160
Construction pe	eriod I&O Vessels Round Trips to Port for Project o	over 3 years
Table 1.24	Foundation Delivery	30
Table 1.24	Turbine Delivery	15
Table 1.24	Cable Delivery	30
Table 1.24	Scour Delivery	30
Table 1.24	Substation Delivery	3
Table 1.24	Total	108
Jack-up Vessels		



Project Description Chapter Ref	Parameter description	Maximum parameters
Construction		
Table 1.25	Individual leg diameter (m)	10
Table 1.25	Individual leg footprint area (m²)	78.54
Table 1.25	Number of legs	6
Table 1.25	Combined leg area (m²)	471.24
Table 1.25	Leg penetration range	15
Table 1.25	Jacking Operations per	2
Table 1.25	Turbine sites	34
Table 1.25	Total JUV visits	68
O&M		,
Table 1.25	Individual leg diameter (m)	6
Table 1.25	Individual leg footprint area (m²)	28.27
Table 1.25	Number of legs	6 ^{xv}
Table 1.25	Combined leg area (m²)	169.65xv
Table 1.25	Leg penetration range	15
Table 1.25	Jacking Operations per Turbine	10
Table 1.25	Turbine sites	34
Table 1.25	Total JUV visits	340
Decommission	ning	
Table 1.25	Individual leg diameter (m)	6
Table 1.25	Individual leg footprint area (m²)	28.27
Table 1.25	Number of legs	4
Table 1.25	Combined leg area (m²)	113.1
Table 1.25	Leg penetration range	15
Table 1.25	Jacking Operations per Turbine	1
Table 1.25	Turbine sites	34
Table 1.25	Total JUV visits	34
Anchor footpr	ints for construction of Thanet Extension	
Installation of foundations		

^{xv} The values were incorrectly presented within the project description chapter for Table 1.25. The values presented in Table 1.34 were however presented correctly. Please see accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission).



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.26	Number of anchors for assumed construction vessel	6
Table 1.26	Individual anchor footprint area for one deployment and recovery (m²)	25
Table 1.26	Indicative anchor penetration depth (m)	3
Table 1.26	Impacted anchor area for one deployment (m ²)	150
Table 1.26	Assumed number of anchoring operations per installation	1
Table 1.26	Total impacted area (m²)	150
Table 1.26	Total impacted volume (m³)	450
Installation of t	opside (WTG and tower)	
Table 1.26	Number of anchors for assumed construction vessel	4
Assumptions	Individual anchor footprint area for one deployment and recovery (m²)	25
applied in the	Indicative anchor penetration depth (m)	3
ES based upon	Impacted anchor area for one deployment (m ²)	150
the installation of foundations in	Assumed number of anchoring operations per installation	1
Table 1.26.	Total impacted area (m²)	150
	Total impacted volume (m³)	450
Installation of t	opside (OSS)	
Table 1.26	Number of anchors for assumed construction vessel	6
Table 1.26	Individual anchor footprint area for one deployment and recovery (m²)	25
Table 1.26	Indicative anchor penetration depth (m)	3
Table 1.26	Impacted anchor area for one deployment (m ²)	150
Table 1.26	Assumed number of anchoring operations per installation	1
Table 1.26	Total impacted area (m²)	150
Table 1.26	Total impacted volume (m³)	450
Installation of export cables		
Table 1.26	Number of anchors for assumed construction vessel	6
Table 1.26	Individual anchor footprint area for one deployment and recovery (m ²)	10



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.26	Indicative anchor penetration depth (m)	3
Table 1.26	Impacted anchor area for one deployment (m²)	60
Table 1.26	Assumed number of anchoring operations per cable installation	120
Table 1.26	Anchor deployments per asset crossing (per cable)	4
Table 1.26	Total anchor deployments for asset crossings (per cable)	20
Table 1.26	Anchor deployments per cable and foundation interface (per cable)	4
Table 1.26	Total anchor deployments per cable installation	144
Table 1.26	Impacted area per cable (m²)	8,640
Table 1.26	Impacted volume per cable (m³)	25,920
Table 1.26	Total impacted area (m²)	34,560
Table 1.26	Total impacted volume per cable (m³)	103,680
Installation of a	array cables	
Table 1.26	Number of anchors for assumed construction vessel	6
Table 1.26	Individual anchor footprint area for one deployment and recovery (m²)	10
Table 1.26	Indicative anchor penetration depth (m)	3
Table 1.26	Impacted anchor area for one deployment (m ²)	60
Table 1.26	Assumed number of anchoring operations per installation	15
Table 1.26	Number of installations	34
Table 1.26	Total anchor deployments for inter-array installation	510
Table 1.26	Impacted area per cable (m²)	900
Table 1.26	Impacted volume per cable (m³)	2,700
Table 1.26	Total impacted area (m²)xvi	30,600
Table 1.26	Total impacted volume (m³)	91,800
Permanent vessel moorings ^{xvii}		
Table 1.27	Number of installations in total	2

xvi Discrepancies in this value within the ES are accounted for in the accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission).

xvii See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission)



Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.27	Possible foundation types	Concrete Gravity Base or Standard Ground Tackle
Table 1.27	Surface structure	A floating mooring buoy up to 3 m in diameter, and 3 m above sea level.
Table 1.27	Marking & Lighting	Marked and lit as required (assume high-viz yellow colouration, radar reflector, navigation light). AIS beacon may be considered judged valuable (and acceptable to THLS).
Indicative const	truction programme (assuming no breaks to work)
Table 1.28	Foundation installation	6 (includes 1 month weather downtime)
Table 1.28	Cable installation (inter-array and export)	6 (includes 1 month weather downtime)
Table 1.28	OSS (if required)	2.5 (includes 2 weeks for foundation installation and weather downtime)
Table 1.28	Met Mast (if required)	2.5 (includes 2 weeks for foundation installation and weather downtime)
Table 1.28	WTG installation	6 (includes 1 month weather downtime)
Table 1.28	Scour protection installation	1 (includes 2 weeks weather downtime)
Table 1.28	Total duration	28
Maximum O&M vessel quantities per year		
Table 1.29	Small CTV O&M vessel	2
Table 1.29	Large O&M Vessel	1
Table 1.29	Lift vessels	1
Table 1.29	Cable maintenance vessel	1
Table 1.29	Auxiliary vessels	1



Project Description	Parameter description	Maximum parameters	
Chapter Ref		parameters	
O&M Vessel Ro	O&M Vessel Round Trips to Port per year, per vesselxviii		
Table 1.30	Small CTV O&M vessel	300	
Table 1.30	Large O&M Vessel	2	
Table 1.30	Lift vessels	1	
Table 1.30	Cable maintenance vessel	1	
Table 1.30	Auxiliary vessels	3	
Table 1.30	Accommodation O&M	0	
Table 1.30	Total (including all vessels)	307	
O&M estimation	ns – inter-array cables replacement worst-case es	timates ^{xix}	
Table 1.31	Number of inter-array cable failure during lifetime of wind farm	7	
Table 1.31	Length of replacement (longest inter-array cable) (m)	2,000	
Table 1.31	Width of seabed being disrupted for replacement of inter-array cable (m)	10	
Table 1.31	Overall impact area (cable and JUV) per repair (m²)xx	20,000	
Table 1.31	Total repair area (m²) ^{xxi}	140,000	
O&M estimation	ns – inter-array cables repair worst-case estimate	S .	
Table 1.32	Cable re-burial - Reburial (total inter-array length) (m)	64,000	
Table 1.32	Cable re-burial - Frequency (once every 5 years)	6	
Table 1.32	Cable repair - Total width of disturbance (m)	10	
Table 1.32	Cable repair - Total area (cable alone) (m²)	640,000	
Table 1.32	Overall cumulative impact area (cable +JUV) per repair (m²)	3,840,000	
Export cable repairs/ reburial worst-case estimates xix			
Table 1.33	Cable inspection- One failure per cable per 5 years (total repairs in lifetime of project)	24	

xviii Please See accompanying clarification note (Ref Annex B of Appendix 1 of the Applicant's Deadline 1 submission) with respect to O&M vessels quantities assessed within the ES.

xxi This value was incorrectly presented in the project description chapter as 980,000. Please see accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission).



xix Please See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) with respect to O&M cable activities assessed within the ES.

xx This value was incorrectly presented in the project description chapter as 140,000. Please see accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission).

Project Description Chapter Ref	Parameter description	Maximum parameters
Table 1.33	Cable inspection- Assumed repair length (through removal) (m)	300
Table 1.33	Cable burial using surface protection- Total width of disturbance (same method as installation but decreased from 30 to 10 m) (m)	10
Table 1.33	Cable re-burial Total area (cable alone) (m²)	3,000
Table 1.33	Additional cable laying- Overall cumulative impact area (cable +JUV) per repair (m²)	72,000
WTGs O&M w	orst-case estimates	
Table 1.34	Individual leg diameter (m)	6
Table 1.34	Individual leg footprint area (m²)	28.27
Table 1.34	Number of legs	6
Table 1.34	Combined leg area (m²)	169.65
Table 1.34	Leg penetration range	15.00
Table 1.34	Jacking Operations per Turbine (1 visit every 3 years)	10
Table 1.34	Turbine sites	34
Table 1.34	Total operations	340
Table 1.34	Total footprint during operational period (m²)	57,680
OSS O&M wor	st-case estimates	
Table 1.35	Individual leg diameter (m)	6
Table 1.35	Individual leg footprint area (m²)	28.27
Table 1.35	Number of legs	6
Table 1.35	Combined leg area (m²)	169.65
Table 1.35	Leg penetration range	15
Table 1.35	Jacking Operations (total) (1 visit every 2 years)	12.5
Table 1.35	OSS sites	1
Table 1.35	Total operations	13
Table 1.35	Total footprint during operational period (m ²)	2,121



Table 2: Maximum Disposal Volumes for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Volume (m³)
Transmission	Table 1.16 and assumptions of WTGs foundations were applied for the OSS (Table 1.6)	Pre-sweeping OECC and seabed preparation for OSS suction caisson foundation	1,440,000 + 9,600 = 1,449,600
Generation	Table 1.6 and assumptions of WTGs foundations were applied for the met mast (Table 1.6)	Seabed preparation for suction caisson foundations (28 WTGs and a met mast)	29 x 9,600 = 278,400
Total	,		1,728,000

Table 3: Maximum scour protection area for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area (m²)
Transmission	Table 1.13	Scour protection for the OSS	7,854
Generation	Table 1.7 and assumptions of WTGs foundations were applied for the met mast (Table 1.7)	Scour protection for WTGs and the met mast	219,912 + 7,854 = 227,766
Total			235,620

Table 4: Maximum scour protection volume for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Volume (m³)
Transmission	The assumptions of WTGs foundations were applied for the OSS (Table 1.7)	Scour protection for OSS	39,269.9
Generation	Table 1.7 and assumptions of WTGs foundations were applied for the met mast (Table 1.7)	Scour protection for the WTGs and the met mast	1,112,647.4 + 39,269.9 = 1,151,917.3
Total			1,191,187.2



Table 5: Maximum cable protection area for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area (m²)
	Table 1.16	Export Cable	210,000
Transmission	Table 1.17	Export Cable crossings	80 crossings x 1000 = 80,000
Transmission	Not presented as a total in the project description	Total for Export Cable	290,000
	Table 1.9	Inter-array cables	80,000
	Table 1.10	Inter-array cables crossings	12,000
Generation	Table 1.9	Total area of WTG foundations requiring rock dumping/ remedial protection (m ₂)	17,500 – 500 =17,000
	Not presented as a total in the project description	Total for inter-array cables	109,000
Total			399,000



Table 6: Maximum cable protection volume for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area (m³)
	Table 1.16	Export Cable	210,000 m ² x 0.5 m = 105,000 m ³
Transmission	Table 1.17	Export Cable crossings	80 crossings x 500m ^{3 =} 40,000 m ³
	Not presented as a total in the project description	Total for Export Cable	145,000 m ³
	Table 1.9	Total area of WTG foundations requiring rock dumping/ remedial protection (m ₂)	17,500 m ² x 0.5 m = 8,750 m ³
Generation	Table 1.9	Inter-array cables	16 km x 1,250 m ³ km ⁻¹ = 20,000 m ³
	Table 1.10	Inter-array cables crossings	6,000
	Not presented as a total in the project description	Total for inter-array cables	34,750
Total			179,750

Table 7: Maximum drill arising volume for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Volume (m²)
Transmission	Table 1.12	Maximum volume for to drill OSS	1,000
Generation	Table 1.4	Maximum volume to drill 50% of WTG foundations and one met mast (assuming 10MW)	19,627 + 1,155 = 20,782
Total			21,782 ^{xxii}

^{xxii} See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application. This value was not presented as total within the project description chapter.



Table 8: Maximum disturbance sediment volume for installation of cabling for Thanet Extension (excluding pre-sweeping)

Infrastructure	Project Description Chapter Ref	Activity	Maximum Volume (m³)
Transmission	Table 1.16	Jetting of export cables (assuming a v-shaped trench and 50% of sediment is liquidised)	10 m x 3 m x 120 km x 0.5 x 50% = 900,000 ^{xxiii}
Generation	Table 1.9	Jetting of inter-array cables (assuming a v-shaped trench and 50% of sediment is liquidised)	1 m x 3 m x 64 km x 0.5 x 50% = 48,000 ^{xxiv}
Total			948,000

Table 9: Maximum disturbance sediment volume for pre-sweeping for cable corridors for Thanet Extension

Infrastructure	Project Description Chapter Ref	Activity	Maximum Volume (m³)
Transmission	Table 1.16	Pre-sweeping (/ sandwave clearance) of export cable corridor	20% of export cable route (24 km) x 20 m x 60 m ³ /m = 1,440,000 m ³
Generation	N/A	N/A	N/A
Total			1,440,000 m ³

xxiv See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application. This value was not presented as total within the project description chapter.



xxiii See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application. This value was not presented as total within the project description chapter.

Table 10: Maximum infrastructure footprint for Thanet Extension Construction activities

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area (m²)
Transmission	Based on parameters from Table 1.13	One OSS (based on a tripod suction bucket diameter of 20 m)	942.5 ^{xxv}
Generation	Based on parameters from Table 1.6	28 x 12 MW WTGs and one met mast with a diameter of 20 m (assuming the same parameters as WTGs)	1,256.6 x 29 = 36,442.5
Total			37,385 ^{xxvi}

xxvi Based on the discrepancy between the footprint for the OSS, this has been assessed as 37,680 m² within the ES. Please see accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission).



 $^{^{}xxv}$ This is based on a tripod OSS as within the project description chapter, however this has been assessed as 1,256 m 2 within the ES.

Table 11: Maximum disturbance area for Thanet Extension O&M activities

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area (m²)
	Table 1.33	Export Cable O&M works	72,000
Transmission	Table 1.35	JUVs for OSS	2,121
	N/A	Transmission Total	74,121
	Tables 1.31 & 1.32	Inter-array cable O&M	140,000 +
		replacement and reburial	3,840,000 =
			3,980,000
Generation	Table 1.25	JUVs for WTGs	169.65 x 340 =
			57,680
	N/A	Generation Total	4,037,860
Total			4,111,801 ^{xxvii}

Table 12: Maximum disturbance volume for Thanet Extension O&M activities

Infrastructure	Project Description Chapter Ref	Activity	Maximum Area(m²)
Transmission	Table 1.33	Export Cable O&M works	72,000 m ² x 3m x
11 01151111551011			0.5 x 50% = 54,000
	Tables 1.31 & 1.32	Inter-array cable O&M	3,980,000 m ² x 3m x
Generation		replacement and reburial	0.5 x 50% =
			2,985,000
Total			3,039,000 ^{xxviii}

xxviii See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application. This value was not presented as total within the project description chapter.



xxvii See accompanying clarification note (Annex B of Appendix 1 of the Applicant's Deadline 1 submission) for how this has been assessed within the application. This value was not presented as total within the project description chapter.