

Vattenfall Wind Power Ltd

Thanet Extension Offshore Wind Farm

Annex E to Appendix 8 to Deadline 8 Submission:
Plan of Plans

Relevant Examination Deadline: 8

Submitted by Vattenfall Wind Power Ltd

Date: June 2019

Revision B

| | |
|-------------------|---------------------------|
| Drafted By: | Vattenfall Wind Power Ltd |
| Approved By: | Daniel Bates |
| Date of Approval: | June 2019 |
| Revision: | B |

| | |
|------------|--|
| Revision A | Original document submitted to the Examining Authority |
| Revision B | Revised document submitted to the Examining Authority |
| | |
| | |
| | |
| | |
| | |
| | |

Copyright © 2019 Vattenfall Wind Power Ltd

All pre-existing rights retained

Offshore Pre-Commencement Requirements/ Conditions

Draft DCO June 2019

Draft DCO Schedule
1, Part 3

DML Schedule 11
Part 2 & Schedule 12
Part 4

Detailed design
parameters
offshore
Requirement 2 - 6

Aviation safety
Requirement 7

Pre-construction Plans and documentation

Schedule 11, Condition 13, 14 & 15
Schedule 12, Condition 11, 12, 13 & 14

Design Plan

Schedule 11, Condition 13(1)(a)
Schedule 12, Condition 11(1)(b)

Construction programme & Monitoring Plan

Schedule 11, Condition 13(1)(b)
Schedule 12, Condition 11(1)(c)

Construction Method Statement

Schedule 11, Condition 13(1)(c)
Schedule 12, Condition 11(1)(d)

Project Environmental Management Plan

Schedule 11, Condition 13(1)(d)
Schedule 12, Condition 11(1)(e)

Marine Pollution Contingency Plan

Scour Protection Management & Cable Protection Plan

Schedule 11, Condition 13(1)(e)
Schedule 12, Condition 11(1)(f)

Draft Marine Mammal Mitigation Protocol

Schedule 11, Condition 13(1)(f)
Schedule 12, Condition 11(1)(g)

Draft Marine Mammal Mitigation Protocol (UXO) *Licence not sought at this time*

Cable Specification, Installation & Monitoring Plan

Schedule 11, Condition 13(1)(g)
Schedule 12, Condition 11(1)(h)

Written Scheme of Archaeological Investigation

Schedule 11, Condition 13(1)(h)
Schedule 12, Condition 11(1)(i)

Offshore Operations & Maintenance Plan

Schedule 11, Condition 13(1)(i)
Schedule 12, Condition 11(1)(j)

Aids to Navigation Management Plan

Schedule 11, Condition 13(1)(j)
Schedule 12, Condition 11(1)(k)

Site Integrity Plan

Schedule 11, Condition 13(1)(k)(i)
Schedule 12, Condition 11(1)(l)

Ringed Plover Mitigation Plan

Schedule 12, Condition 11(1)(m)

Emergency Response Co-operation Plan (ERCoP)

Schedule 11, Condition 15(7)
Schedule 12, Condition 13(7)

Contamination Prevention Plan

Schedule 12, Condition 11(1)(a)

Shipping & Navigation Liaison Plan

Schedule 11, Condition 25(2)
Schedule 12, Condition 28(2)

Notifications & Inspections

Schedule 11, Condition 7 & 22
Schedule 12, Condition 6, 20 & 23

Notification to the MMO

Schedule 11, Condition 7(13) & 22(1)
Schedule 12, Condition 6(6), 6(13), 20 & 24(1)

Kingfisher Information Service Notification

Schedule 11, Condition 7(7)
Schedule 12, Condition 6(7)

Notice to Mariners

Schedule 11, Condition 7(8 & 9)
Schedule 12, Condition 6(8 & 9)

Notification to UK Hydrographic Office

Schedule 11, Condition 7(10 & 11)
Schedule 12, Condition 6(10 & 11)

Aids to Navigation

Schedule 11, Condition 8 & 9
Schedule 12, Condition 7 & 8

Aviation Safety

Schedule 11, Condition 10

Fisheries Liaison and Co-existence Plan

Schedule 11, Condition 20
Schedule 12, Condition 22

Pre-construction Monitoring & Surveys

Schedule 11, Condition 16
Schedule 12, Condition 15

Biogenic Reef Monitoring Plan

Schedule 11, Condition 16(2)(a)
Schedule 12, Condition 15(2)(a)

Swath-bathymetry Survey & Side Scan Sonar Plan

Schedule 11, Condition 16(2)(b)
Schedule 12, Condition 15(2)(d)

Saltmarsh Mitigation, Reinstatement & Monitoring Plan

Schedule 12, Condition 15(2)(c) and 17(2)(c)

Seabed Preparation and clearance

Schedule 11, Condition 21
Schedule 12, Condition 23

Offshore Ornithology Monitoring Plan

Schedule 11, Condition 13(1)(k)(ii)

Construction Monitoring

Schedule 11, Condition 17
Schedule 12, Condition 16

Reporting of impact pile driving

Schedule 11, Condition 19(1)

Construction Traffic Monitoring Plan

Schedule 11, Condition 17(4)

Reporting of Impact Pile Driving

Schedule 11, Condition 19
Schedule 12, Condition 19

Chemicals, drilling and debris

Schedule 11, Condition 11
Schedule 12, Condition 9

Outline documents submitted in the
examination

Outline documents submitted with the
application

Document submitted with the application

Post-consent requirement

Post-consent document

Design Plan

S.11, C.13(1)(a) / S.12, C.11(1)(b)

Individual plans required for the Generation and Export Cable System Marine Licences

Information Required

Foundations

Dimensions of foundations

Proposed location of WTG and
foundation type

Exclusions zones and
micrositing requirements

Foundations
WTGs
Met mast
Offshore substation/
platforms

Plan showing indicative layout
of all structures

Rotor diameters and spacing
of WTGs

Dimensions of structures

Inter-array cable &
export cable
(as informed by layouts)

Lengths and arrangements of
cables

All packages

Programme of construction

Detail

A design plan at a scale of between 1:25,000 and 1:50,000, including detailed representation on the most suitably scaled admiralty chart.

Proposed layout of WTG in accordance with the recommendations contained in MGN543.

Links to:

Schedule 1, Part 3, Requirement 2-5: Detailed Design Parameters

Approval Requirements

Discharging Authority

Others


MMO

In consultation with Trinity
House, the MCA and Natural
England

Construction programme & Monitoring Plan

S.11, C.13(1)(b) / S.12, C.11(1)(c)

Information Required



Detail

Details to be submitted to the MMO in accordance with the following:

- At least four months prior to the first survey, detail of the pre-construction surveys and an outline of all proposed monitoring;
- At least four months prior to construction, detail on construction monitoring;
- At least four months prior to commissioning, detail of post-construction (and operational) monitoring.


Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | |

Construction Method Statement

S.11, C.13(1)(c) / S.12, C.11(1)(d)

Information Required



Detail

- foundation installation methodology, including drilling methods and disposal of drill arisings and having regard to the Biogenic Reef Mitigation Plan;
- soft start procedures with specified duration periods;
- cable installation;
- contractors;
- associated and ancillary works.

Approval Requirements

Discharging Authority


Others

MMO

Project Environmental Monitoring Plan

S.11, C.13(1)(d) / S.12, C.11(1)(e)

Information Required



Detail

Marine pollution contingency plan addresses:

- Risks; and
- Methods and procedures for spills and collision incidents.

Chemical risk assessment details:

- How and when chemicals are to be used, stored and transported; and
- How accordance with recognised best practice guidance is met.


Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | |

Scour & Cable Protection Plan

S.11, C.13(1)(e) / S.12, C.11(1)(f)

Information Required



Detail

Details:

- Type;
- Sources;
- Quantity; and
- Installation methods

Must be updated for and resubmitted for approval if changes to it are proposed following cable laying operations.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | |

Draft Marine Mammal Mitigation Protocol

S.11, C.13(1)(f) / S.12, C.11(1)(g)

Information Required

Only required if

Driven or part driven pile foundations are proposed to be used

Detail

Details:

- Follows current best practice as advised by the relevant statutory nature conservation bodies.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | |

Cable Specification, Installation & Monitoring Plan

S.11, C.13(1)(g) / S.12, C.11(1)(h)

Information Required

Technical specifications

Offshore cables below
MHWS

Cable laying plan

Covering order limits and
risk assessments

Monitoring

Proposals for monitoring
during the operational
lifetime

Detail

Technical specification includes:

- Desked based assessment of attenuation of electro-magnetic fields strengths, shielding and cable burial depth following industry good practice.

Cable laying plan risk assessments of:

- Burial to ascertain suitable burial depths and cable laying techniques, including protection.

Monitoring:

- Includes a risk based approach to the management of unburied or shallow cables.

Approval Requirements

Discharging Authority


Others

MMO

Written Scheme of Archaeological Investigation

S.11, C.13(1)(h) / S.12, C.11(1)(i)

Information Required



Approval Requirements

| Discharging Authority | Others |
|-----------------------|--|
| MMO | In consultation with the statutory historic body |

Detail

Scheme includes:

- Details of undertaker, archaeological consultant and contractor responsibilities;
- Methodology including geophysical, geotechnical and diver or ROV;
- Analysis of survey data and timetable for reporting – submitted within four months of survey completion;
- Mitigation including exclusion zones;
- Monitoring of exclusion zones during and post-construction;
- Copy of any agreed report is submitted to the National Record of the Historic Environment;
- Reporting and recording protocol during construction, operation and decommissioning; and
- Timetable of all further site investigations.

Links to

- S.11, C13(1) and S.12, C10(2) pre-construction/ pre-commencement intrusive seabed works must accord with specific written scheme and be approved by MMO.
- S.11, C14 and S.12 C11 which includes the ERCoP and follows recommendations within MGN543.

Offshore Operations & Maintenance Plan

S.11, C.13(1)(i) / S.12, C.11(1)(j)

Information Required

Submission deadline

At least four months prior to commencement

Accords with

Outline offshore operations and maintenance plan

Detail

- submitted to the MMO at least six months prior to commencement of operation of the licensed activities; and
- Review of plan to be resubmitted every three years during the operational phase.

Approval Requirements

Discharging Authority


Others

MMO

Aids to Navigation Management Plan

S.11, C.13(1)(j) / S.12, C.11(1)(k)

Information Required



Detail

Complies with relevant conditions for the lifetime of the authorised scheme.

Links to S.1, P3, Req 6.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|------------------------------------|
| MMO | In consultation with Trinity House |

Site Integrity Plan

S.11, C.13(1)(k)(i) / S.12, C.11(1)(l)

Information Required

Submission deadline

At least four months prior to commencement

Accords with

Outline Site Integrity Plan

Detail

- submitted to the MMO at least six months prior to commencement of operation of the licensed activities.

Approval Requirements

Discharging Authority

MMO

Others

In consultation with Natural England

Offshore Ornithology Monitoring Plan

S.11, C.13(1)(k)(ii)

Information Required

Submission deadline

At least four months prior to commencement

Accords with

In-principle Offshore Ornithology Monitoring Plan

Detail

- submitted to the MMO at least six months prior to commencement of operation of the licensed activities.

Approval Requirements

Discharging Authority

Others

MMO

In consultation with Natural England

Ringed Plover Mitigation Plan

S.12, C.11(1)(m)

Information Required

Submission deadline

At least four months prior to commencement

Detail

- submitted to the MMO prior to commencement of operation of the licensed activities.


Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | N/A |

Emergency Response Co-operation Plan (ERCoP)

S.11, C.15(7) / S.12, C.13(7)

Information Required



Detail

No part of the authorised scheme may commence until the MMO, in consultation with the MCA, has given written approval of an Emergency Response Co-operation Plan (ERCoP) which includes full details of the plan for emergency, response and co-operation for the construction, operation and decommissioning phases.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| MMO | MCA |

Contamination Prevention Plan

S.12, C.11(1)(a)

Information Required

Work No.

3B

Detail

A contamination prevention plan which must contain details of necessary measures in order to ensure that construction works undertaken within Work No. 3B do not release any contaminants into the marine environment.

Approval Requirements

Discharging Authority

Others

MMO

N/A

Shipping and Navigation Liaison Plan

S.11, C.25(2)/ S.12, C28(2)

Information Required

Submission deadline

At least four months prior to commencement

Accords with

Outline Shipping and Navigation Liaison Plan

Detail

- submitted to the MMO at least six months prior to commencement of operation of the licensed activities.

Approval Requirements

Discharging Authority

Others

MMO

Notifications & Inspections

S.11, C.7 & 22 / S.12, C.6, 20 & 23

Information Required

MMO

Notify MMO Coastal Office at least 5 days prior to work commencement

Kingfisher Information Service

Notify 14 days prior to commencement and on completion.

Notice to Mariners

Issued at least 10 days prior to commencement. Weekly updates in construction/ 5 days before O&M

UK Hydrographic Office

Notified within 10 days of commencement and within 10 days of completion of construction

Damage/ destruction

Any damage, destruction or decay of authorised scheme seaward of MHWS notified to MMO, MCA, Trinity House and UKHO within 24 hrs

Detail

All agents and contractors notified to the MMO. Only persons and vessels notified to the MMO are permitted to carry out the licensed activities.

Confirmation of Kingfisher notifications must be provided to the MMO within five days.

Copies of all Notice to Mariners provided to MMO and UKHO within 5 days

Approval Requirements

Discharging Authority

Others

MMO

Notification (not consultation) provided to Kingfisher Information Services/ UKHO/ MCA

Aids to Navigation

S.11, C.8 & 9 / S.12, C.7 & 8

Information Required

Notification

Trinity House and MMO

Plans

[Aids to Navigation
Management Plan](#)

Colour Schemes

Yellow (colour code RAL
1023)
Light Grey (colour code RAL
7035)

Detail

Notifications:

Within 24 hrs of commencement of construction occurring;
Within 24 hours of any aids to navigation being established;
Within five days of completion of construction;
Within 24 hrs notify of any failure of the aids to navigation during the whole life cycle of the project.

Plans:

Reports on availability of aids to navigation in accordance with the frequency set out in the Aids to Navigation Management Plan.

In the event of a failure to aids of navigation the undertaker must lay down buoys, exhibit lights and take other steps to prevent danger to navigation as directed by Trinity House.

Approval Requirements

Discharging Authority

Others

Trinity House and MMO

N/A

Aviation Safety

S.11, C.10

Information Required

Notification

Notify Defence Infrastructure Organisation Safeguarding 14 days prior

Reporting

Date of commencement and commissioning of any wind turbine

Max height of any construction equipment and infrastructure installed

Latitude and longitude of all infrastructure installed

MMO

MMO require a copy of any notifications

Detail

Defence Infrastructure Organisation Safeguarding are to be notified of any changes and on completion of works.

Approval Requirements

Discharging Authority

Others


Defence Infrastructure Organisation Safeguarding

N/A

Fisheries Liaison and Co-Existence Plan

S.11, C.20 / S.12, C.22

Information Required



Detail


N/A

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--|
| MMO | Consultation with Thanet Fisherman's Association |

Pre-construction Monitoring & Surveys

S.11, C.16 / S.12, C.15



Detail

Survey proposals must detail:

- Objectives;
- Explain how comparisons to post-construction will be drawn.

Baseline Survey reports must detail:

- Valid statement of pre-construction position;
- Clearly define post-construction comparison that is intended.

Survey proposals/ details:

- Biogenic Reef Mitigation Plan
- Saltmarsh Mitigation, Reinstatement and Monitoring Plan.
- Swath bathymetric and Side Scan Sonar surveys must provide full coverage within the order limits including 500 m buffer.

Timings of reporting to be agreed with the MMO.

| Approval Requirements | |
|-----------------------|--------|
| Discharging Authority | Others |
| MMO | N/A |

Construction Monitoring

S.11, C.17 / S.12, C.16

Information Required

Monitoring Plans

Piling noise monitoring
Construction traffic noise

Consultation

Natural England

Detail

Must be submitted in discharging condition 12(b) (Sch 11) and condition 9(d) (Sch 12).

Monitoring of noise generated by the installation of the first four piled foundations. Results to be provided to the MMO within six weeks of the installation of the first four piled foundations.

Approval Requirements

Discharging Authority

MMO


Others

In consultation with Natural England

Reporting of Impact Pile Driving

S.11, C.19 / S.12, C.19

Information Required



Detail

Only when driven or part driven pile foundations are proposed.

UK Marine Noise Registry to be provided with:

- Prior to commencement expected locations and start/ end dates;
- Six month Interval locations and dates of impact pile driving; and
- Locations and dates of impact piling within 12 weeks of completion.

MMO to be notified of successful submission to UK Marine Noise Registry within 7 days of submission.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--|
| MMO | Provide specific information to UK Marine Noise Registry |

Chemicals, drilling and debris

S.11, C.11 / S.12, C.9

Information Required

Approved chemicals

Offshore Chemicals
Regulations 2002 (as
amended)

Reporting

Any oil fuel or chemical spill
in the marine environment
is reported to the MMO

Any loss of rock material
below MHWS reported to
District Marine Office within
48 hrs

All dropped objects are to
be reported within 24 hours
to the MMO.

Disposal

Only inert material of
natural origin produced
during drilling or seabed
preparation.
Location and quantity
recorded monthly

Detail

Coatings and treatments are suitable for the marine environment and used in accordance with HSE and EA Pollution Prevention Control Guidelines.

Storage, handling, transport and use of fuels, lubricants, chemicals and other substances must be undertaken so as to prevent release into the marine environment; including bunding of 110% of the total volume of all reservoirs and containers.

Undertaken must ensure that any rock material used in construction is from a recognised source; free from contaminants and contains minimal fines.

The undertaker must inform the MMO of the location and quantities of material disposed of each month by submission of a disposal return.

Approval Requirements

Discharging Authority

Others

MMO

N/A

Onshore Pre-Commencement Requirements

June 2019

Draft DCO
Schedule 1, Part 3

Ctrl + Click to go to slide

Detailed design
parameters
onshore
Requirement 11

Landfall Method
Notification
Requirement 12

Saltmarsh
mitigation,
reinstatement
and monitoring
plan
Requirement 13

Access
Management
Strategy
Requirement 14

Onshore
Substation
Landscaping
Requirement 15

Highway accesses
Requirement 17

Construction
Environmental
Management
Plan (CEMP)
Requirement 18

Outline Access
Management
Strategy

Temporary
fencing and other
means of
enclosure
Requirement 19

Onshore
substation
surface water and
drainage
management plan
Requirement 20

Contaminated
land and
groundwater plan
(CLGWP)
Requirement 21

Construction
noise and
vibration
management plan
(CNVMP)
Requirement 22

Construction
traffic
management plan
(CTMP)
Requirement 23

Onshore
archaeological
written scheme of
investigation
Requirement 24

Landscape and
ecological
management plan
(LEMP)
Requirement 25

Control of noise
during
operational phase
Requirement 28

Outline LEMP

Operational noise
management plan

Outline documents submitted with the application

Documents submitted with the application

Post-consent requirements

Post-consent documents

Detailed Design Parameters Onshore (Req 11)

Information Required

Onshore substation station

Details of the layout, scale and external appearance of the substation

Onshore cable corridor

Height of corridor

Kiosks

Maximum size

Detail

The total number of buildings housing principle electrical equipment for the onshore substation must not exceed 1.

Buildings must not exceed a height of 14 m above existing ground level.

External electrical equipment must not exceed a height of 12.5 m above existing ground level.

The artificial berm associated with Pegwell Bay must not exceed a height of 1.3 m above existing ground level for the cables and a height of 2.3 m for the TJBs.

Approval Requirements

Discharging Authority


Others

Relevant Planning Authority

N/A

Landfall Method Notification (Req 12)

Information Required



Detail

No part of Work No. 3B may commence until written notification is provided to the relevant planning authority confirming which one option of Work No. 3B(a), 3B(b) or 3B(c) will be constructed. The method statement must include:

- The anticipated timing of the proposed works being undertaken; and
- Where applicable, measures for long horizontal directional drilling below the coastal shore platform and cliff base at the landfall.

Approval Requirements

| Discharging Authority | Others |
|-----------------------|--------|
| None | N/A |

Saltmarsh Mitigation, Reinstatement and Monitoring plan (Req 13)

Information Required

Submission deadline

Certified document does not require resubmission

Accords with

Saltmarsh mitigation, reinstatement and monitoring plan

Detail

- undertake appropriate surveys at the locations for Works No. 3A and 3B in order to monitor the impact of development authorised by the Order within any areas of saltmarsh, as provided for within the saltmarsh mitigation, reinstatement and monitoring plan.

Approval Requirements

Discharging Authority

Others

Relevant Planning Authority

N/A

Access Management Strategy (Req 14)

Information Required

Accords with

Outline Access Management Strategy.

Detail

No stage of the connection works may commence until for that stage an access management strategy (which must accord with the outline access management strategy) has been submitted to and approved by the relevant planning authority.

Approval Requirements

Discharging Authority

Others

Relevant Planning Authority

N/A

Onshore Substation Landscaping (*Req 15*)

Information Required

Accords with

Outline Landscape and
ecological management plan

Types of planting

Hard and soft landscaping

Approval Requirements

Discharging Authority

Others

Relevant Planning Authority

N/A

Detail


Written landscaping management scheme and associated work programme must accord with the outline landscape and ecological management plan (LEMP).

Details of hard and soft landscaping includes:

- Location, number, species, size and planting density of any proposed planting, including any trees;
- Cultivation, importing of materials and other operations to ensure plant establishment;
- Proposed finished ground levels;
- Hard surfacing materials;
- Vehicular and pedestrian access, parking and circulation areas;
- Minor structures, such as furniture, refuse or other storage units, signs and lighting;
- Proposed and existing functional services above and below, ground, including drainage, power and communications cables and pipelines, manholes and supports;
- Details of existing trees to be retained with measures for their protection during the construction period;
- Retained historic landscape features and proposals for restoration, where relevant;
- Implementation timetables for all landscaping works;
- Maintenance of the landscaping, including irrigation arrangements; and
- Soil retention, handling and protection.

Highways Accesses (Req 17)

Information Required



Detail

- Written details (in accordance with the Outline Access Management Plan) of:
- Siting, design, layout and any access management measures for any new, permanent or temporary means of access used by vehicular traffic; or
 - Any alteration to an existing means of access to a highway used by vehicular traffic.

Approval Requirements

| Discharging Authority | Others |
|----------------------------|--------|
| Relevant Highway Authority | N/A |

Construction Environmental Management Plan (CEMP) (Req 18)

Information Required

Accords with

Code of Construction Practice

Detail

The CEMP must contain details of:

- relevant health, safety and environmental legislation and compliance;
- local community liaison responsibilities;
- site security;
- biosecurity measures;
- lighting;
- soil management;
- dust control measures;
- flood risk management; and
- waste management.

Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--------|
| Relevant Planning Authority | n/a |

Temporary fencing and other means of enclosure (*Req 19*)

Information Required

Fencing

Details on proposed temporary fences

Enclosure

Details on all temporary enclosures

Detail

All construction sites must remain securely fenced at all times during construction.

Any temporary fencing must be removed on completion of the relevant works.

Approval Requirements

Discharging Authority


Others

Relevant Planning Authority

N/A

Onshore substation surface Water and Drainage Management Plan (Req 20)

Information Required



Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--|
| Relevant Planning Authority | In consultation with relevant drainage authority |


Detail

Must include:

- Sustainable drainage principles; and
- Assessment of the hydrological and hydrogeological context of the development.

Contaminated Land and Groundwater Plan (CLGWP) (Req 21)

Information Required



Detail

Must include:


- Mitigation measures against the potential release of contaminants within the Order limits.

Approval Requirements

| Discharging Authority | Others |
|-----------------------------|---|
| Relevant Planning Authority | In consultation with the Environment Agency |

Construction Noise and Vibration Management Plan (CNVMP) (Req 22)

Information Required



Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--------|
| Relevant Planning Authority | N/A |

Detail

Must set out:

- The construction works, and the method used;
- The noise attenuation measures to be taken to minimise noise resulting from the construction works, including any noise limits; and
- A scheme for monitoring for noise during construction to ensure compliance with noise limits and attenuation measures.

Construction Traffic Management Plan (CTMP) (Req 23)

Information Required

Method

Timings, traffic control and routing.

Accord

Must accord to the CTMP principles within the CoCP.

Detail

Must set out:

- Scheduling and timing of movements, in particular abnormal load movements;
- Temporary warning signs and traffic control; and
- Construction vehicle routing.

Approval Requirements

Discharging Authority


Others

Relevant Highway Authority

N/A

Onshore Archaeological Written Scheme of Investigation (Req 24)

Information Required



Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--|
| Relevant Planning Authority | Consultation with Historic England and Kent County Council |

Detail


If a site investigation is required the scheme must include details on:

- Research questions;
- Methodology of investigation and recording;
- Post investigation assessment;
- Analysis and recording provisions;
- Publication and dissemination provisions of the analysis and records;
- Archive deposition provisions for analysis and records; and
- Nomination of a competent person or persons/organisation to undertake the works.

Site investigations must complete investigation and post investigation assessments.

Landscape and Ecological Management Plan (LEMP) (Req 25)

Information Required



Detail

Surveys include any habitat and species specific surveys e.g. badgers, newts, birds, bats, etc...

Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--------------------------------------|
| Relevant Planning Authority | In consultation with Natural England |

Control of Noise during Operational Phase (*Req 28*)

Information Required

Operational Noise
Management Plan



Methods of noise monitoring

Detail

Includes:

- Monitoring, attenuation and any applicable noise limits with reference to the onshore substation

Approval Requirements

| Discharging Authority | Others |
|-----------------------------|--------|
| Relevant Planning Authority | NA |