
# **Riverside Energy Park**

# **Draft DCO Schedule of Changes**



Planning Act 2008 | Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009



#### RIVERSIDE ENERGY PARK

### SCHEDULE OF CHANGES MADE TO THE DRAFT DEVELOPMENT CONSENT ORDER – REVISION 3 (DEADLINE 5)

In this document, where reference is made to an Article or Requirement, that reference is to the corresponding Article or Reference in the dDCO (3.1, Rev 3) submitted at Deadline 5.

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
Article 2 Date of final commissioning	Insertion of the words "as the context requires" and reference to Requirement 16 changed to Requirement 24 of Schedule 2.	Amendment made to make it clear that the term applies to the authorised development or to part of the authorised development, as the particular provision requires. Therefore the words "as the
commonities	In addition, the cross referencing has been updated to refer to Requirement 24 of Schedule 2, which is the Requirement	context requires" have been inserted.
	providing notice of the date of final commissioning.	Cross referencing to Schedule 2 updated.
Article 2	This is a new definition that has been added.	This plan shows the area of Metropolitan Open Land where no buildings will be erected
MOL plan		(hatched in orange).
Article 2	"Operational" has been inserted in the definition.	This is to correct a typographical error.
Outline operational worker travel plan		
Article 2	This is a new definition that has been added.	The term "pre-commencement works" has been narrowed to restrict where the works can take
Pre-commencement land		place to just certain areas of existing hardstanding in the REP site. The " <i>pre-commencement land</i> " is defined by reference to the " <i>pre-commencement plan</i> ."

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		This is in response to a concern raised by LBB in relation to Requirement 4 (pre- commencement biodiversity mitigation scheme).
Article 2 Pre-commencement plan	This is a new definition that has been added.	This has been added as a new plan is to be certified by the Secretary of State showing where the " <i>pre-commencement works</i> " can take place. The plan links into the new definition of " <i>pre-commencement land</i> ." This is in response to a concern raised by LBB in relation to Requirement 4 (pre- commencement biodiversity mitigation scheme).
Article 2 Pre-commencement works	This definition has been amended by the insertion of the words "on the pre-commencement land only". The definition now reads: ""pre-commencement works" means operations on the pre- commencement land only consisting of…"	narrowed to restrict where the works can take place to just certain areas of existing
Article 2 REP and RRRF Application Boundaries	This is a new definition that has been added.	This plan shows the overlap of the main elements of REP with the existing RRRF planning application boundary. The plan is to be certified by the Secretary of State and shows the

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
Plan		area of land that is to be removed from the "section 36 consent" and the "RRRF planning permission" by virtue of Article 6. New Schedule 14 is relevant to this definition.
		The new definitions have been inserted to deal with a concern of LBB regarding the breadth of Article 6.
Article 2 RRRF	This is a new definition that has been added.	This new term is required to assist with the interpretation of new definition " <i>RRRF planning permission</i> ". The new definitions have been inserted to deal with a concern of LBB regarding the breadth of Article 6.
		The definition describes the existing facility known as " <i>RRRF</i> ".
Article 2 RRRF condition	This is a new definition that has been added.	This term is required to ensure the drafting in Article 6 is clear and precise. The new definitions referring to " <i>RRRF</i> " have been inserted to deal with a concern of LBB regarding the breadth of Article 6. New Schedule 14 is relevant to this definition.
Article 2 RRRF planning permission	This is a new definition that has been added.	This has been added to ensure that Article 6 is clear and precise as Article 6 modifies the " <i>RRRF planning permission</i> ." This definition links into the term " <i>RRRF condition</i> ", the latter being a condition on the " <i>RRRF planning</i> <i>permission</i> ". New Schedule 14 is relevant to this

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		definition.
		The new definitions have been inserted to deal with a concern of LBB regarding the breadth of Article 6.
Article 2 Section 36 consent	This is a new definition that has been added.	This has been added to ensure that Article 6 is clear and precise as Article 6 modifies the "section 36 consent." New Schedule 14 is relevant to this definition.
		The new definition has been inserted to deal with a concern of LBB regarding the breadth of Article 6.
Article 2	The definition of undertaker to be amended to read:	This is to clarify that both companies can take the benefit of the dDCO independently of each
Undertaker	<i>""undertaker" means Cory Environmental Holdings Limited (company number 05360864) <u>or</u> Riverside Energy Park Limited (company number 11536739) or any other person who"</i>	other.
Article 6	Article 6(3) has been inserted to implement new Schedule 14, where the modifications to the section 36 consent and RRRF	The amendments to Article 6 are in response to LBB's concerns submitted at Deadline 4 in their
Disapplication of legislative provisions	planning permission are set out.	comments on the revised dDCO submitted at Deadline 3.
and modifications to section 36 consent and RRRF planning permission	Article 6(4) has been amended to remove reference to condition 7 and 23 of the RRRF conditions and to provide added clarity regarding the extent of the disapplication.	Article 6 modifies the section 36 consent by removing land from that consent (the land that is surplus to RRRF) and on which the main elements of REP are to be constructed. This ensures that there is no conflict between the

Riverside Energy Park Draft DCO Schedule of Changes

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		dDCO and the section 36 consent. In addition, the section 36 consent is modified by inserting reference to the dDCO on the face of the section 36 consent.
		Article 6 also modifies the RRRF planning permission by removing the same land from that permission so as to provide clarity to LBB over the land on which enforcement action can be taken in respect of the RRRF planning permission. Article 6 then modifies the RRRF planning permission by (1) inserting reference to the dDCO on the face of the RRRF planning permission, (2) inserting words into condition 7 so that the jetty can be used for both REP and RRRF, which LBB agrees to, and (3) deleting the current condition 23 and replacing it with an updated condition that obliges RRRF to only store bottom ash in the bunker. This provides the clarity to LBB as they have requested.
		As a consequence of the above, Article 6(4) has been updated to refer to conditions 1 and 22 only and to make it clear that the conditions are disapplied in respect of any inconsistency between the RRRF planning permission and the dDCO, again as requested by LBB. Schedule 14 applies to Article 6.

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
Article 42(3)	The words "Subject to any other provision in this Order" have been inserted to clarify that the arbitration provisions are subject	This is amended to reflect the wording agreed with Network Rail.
(Arbitration)	to any other provisions in the Order.	
Schedule 1		
Work No 8	Amendment of "compound" to "compounds"	Correcting a typographical error and to accurately reflect the Works Plans.
Schedule 2		
Requirement 3, Table 1 (Parameters of authorised development)	The minimum height for the anaerobic digestion plant emission stack (work 1B(vi)) has been amended from 4 metres to 8 metres.	This is to ensure that the dDCO reflects the assessments undertaken as part of the Environmental Statement and Environmental Permit (as set out in the Paragraph 3.4.1 of the Anaerobic Digestion Facility Emissions Mitigation Note (8.02.42, REP4-021) submitted at Deadline 4).
Requirement 4 (Pre-commencement biodiversity mitigation strategy)	This has been amended to require the submission of a pre- commencement biodiversity mitigation strategy to the relevant planning authority for approval, setting out details of mitigation measures required to protect protected habitats and species.	This is a consequence of the amendment to the definition of " <i>pre-commencement works</i> " to only those works on areas where there is existing hard standing and is in current use by the Applicant and the Cory Group. As a result of the " <i>pre-commencement works</i> " only taking place on existing hardstanding and the removal of land and vegetation clearance, no off-setting will be required and land will not need to be restored, which was the purpose of Requirement 4(2)(b) and Requirement 4(2)(c) which have therefore

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		been deleted.
Requirement 7	Requirement 7(2)(c) has been amended and now reads:	This is amended to reflect the wording agreed with Kent County Council.
(Archaeology)	"identify any within the administrative area of Kent County Council drilling or boring locations where a phased"	
Requirement 12 (Construction hours)	Work No. 6 has been added.	This is in response to Thames Water Utilities Limited's comment submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.
Requirement 13	A comma was inserted instead of a full stop. This now reads:	This is to correct a typographical error.
(Construction traffic management plan(s))	"submitted to and approved by the relevant planning authority (in consultation with the relevant highway authority and, for streets within the London Borough of Bexley, Transport for London)."	
Requirement 14	The following changes have been made:	The changes are in response to:
(Heavy commercial vehicle movements delivering waste)	<ol> <li>14(1) and 14(3): The number of maximum two-way movements has been clarified.</li> </ol>	in their comments on the revised dDCO submitted at Deadline 3.
	<ol> <li>14(2): Inserting a cap of 240,000 tonnes per annum of waste being delivered by road to Work No. 1A and Work No. 1B (save in the event of a jetty outage).</li> </ol>	
	<ol> <li>14(1), 14(3) and 14(5): Deletion of "from the street known as Norman Road".</li> </ol>	<ol> <li>LBB's and GLA's comments submitted at Deadline 4 in their comments on the</li> </ol>

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
	<ol> <li>14(5): Deletion of the request for records by the relevant planning authority being limited to a maximum of 4 requests per year.</li> <li>14(6): The definition of jetty outage amended to a period of 4 consecutive days, rather than 48 hours.</li> <li>14(6): Insertion of a definition of two-way vehicle movements.</li> </ol>	<ul> <li>revised dDCO submitted at Deadline 3.</li> <li>4. LBB's and GLA's comments submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.</li> <li>5. LBB's comments submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 4.</li> <li>6. LBB's comments submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.</li> </ul>
New requirement 15 (Emission limits – Work No. 1A)	New requirement inserted to limit the Applicant to an average daily emission limit value and an annual emission limit value for nitrogen oxide and nitrogen dioxide for the ERF.	This is in response to LBB's and GLA's comments submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.
New requirement 16 (Emission limits – Work No. 1B)	A new emissions Requirement has been inserted in respect of the Anaerobic Digestion plant, which restricts the average emission limit value and the annual emission limit value for nitrogen oxide and nitrogen dioxide.	This is in response to LBB's comment submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.
New requirement 17 (Ambient air quality monitoring)	This has been inserted to provide for the Applicant to prepare an air quality monitoring programme, which must also meet the requirements of any air quality monitoring condition on the Environmental Permit.	This is in response to LBB's comment submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3. The Environment Agency is the discharging body to ensure that there is no contradiction between the dDCO and the Environmental Permit. Furthermore, the intention is for there to be

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		single monitoring and not monitoring under the dDCO and the Environmental Permit - the monitoring to be undertaken should comply with both the dDCO and the Environmental Permit.
New requirement 18	This has been inserted to require the Applicant to prepare a scheme setting out arrangements for maintenance of the waste	
(Waste hierarchy scheme)	hierarchy.	dDCO submitted at Deadline 3.
Requirement 19	The insertion of "operational" to read:	This is to correct a typographical error.
Operational worker travel plan	"The <b>operational</b> worker travel plan must be in substantial accordance with the outline operational worker travel plan."	
New requirement 21	This has been inserted to commit the Applicant to prepare a noise monitoring scheme to be approved by the relevant	
(Control of operational noise)	planning authority.	dDCO submitted at Deadline 3 and is very similar to the additional requirement LBB suggested to be inserted in the track change dDCO submitted at Deadline 2.
Requirement 22	The river wall condition survey must be submitted to the Environment Agency. This has been amended to also require	This requirement is now agreed with the Environment Agency and has been amended to
(River Wall)	consultation with the relevant planning authority.	reflect the agreed wording.
	The remedial works must be carried out within 2 years instead of 3.	
Requirement 25	This has been inserted to commit the Applicant to set out the phasing on the construction and commissioning of Work No. 1.	This is in response to GLA's comment submitted at Deadline 4 in their comments on the revised

## Riverside Energy Park Draft DCO Schedule of Changes

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
(Phasing of construction and commissioning of Work Number 1)		dDCO submitted at Deadline 3.
Requirement 26	The following changes have been made:	The changes are in response to:
(Combined heat and power)	<ol> <li>26(2): Inserting that commissioning may not start for Work No. 1A until a working group has been established.</li> <li>26(2): The inclusion of what the working group must do (i.e. engage with the Department for Business, Energy &amp; Industrial Strategy and the Heat Network Investment Programme to identify funding for any financial shortfall identified by any CHP review).</li> <li>26(3): Deletion of the word "reasonably".</li> <li>26(3): Replacing "sufficient details are known" with "sufficient certainty"</li> <li>26(3): Requiring the CHP review to be undertaken by a competent CHP consultant.</li> <li>26(3) and 26(4): Insertion that the actions that the undertaker is required to take must be technically feasible and commercially viable.</li> </ol>	<ol> <li>This is in response to GLA's comment submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.</li> <li>This is in response to LBB's comment submitted at Deadline 4 in their comments on their revised dDCO submitted at Deadline 4 in their comments on their revised dDCO submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 3.</li> <li>This is in response to GLA's comment submitted at Deadline 3.</li> </ol>

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
		6. This is to clarify that the undertaker is only required to include and take such actions which are technically feasible and commercially viable, otherwise the dDCO will not be bankable.
Requirement 27 (Use of compost material and gas from Work Number 1B)	This has been inserted to commit the Applicant to submit an Anaerobic Digestion review, looking at the feasibility and commercial viability of connection to the gas grid network and for export of the compost material produced. The Applicant is only required to consider the opportunities for gas grid network connection in the first Anaerobic Digestion review. However, should the export of the compost material not be feasible or commercially viable at the first review, the Applicant will carry out a review every 5 years, until it is demonstrated that the export of compost material produced from Work Number 1B is technically feasible and commercially viable.	at Deadline 4 in their comments on the revised dDCO submitted at Deadline 3.
Requirement 28	Work Nos. 2, 3, 4 and 5 have been inserted in relation to details on the restoration and management of the site following cessation of operation.	
Requirement 30	This has been amended to reflect that no buildings shall be erected, and no materials stored, within the area on the FRAPA drawing.	
Requirement 32	This has been inserted to ensure no buildings will be erected on any part of the Metropolitan Open Land, as shown on the MOL plan submitted at Deadline 5 (and as defined in Article 2).	
Schedule 7		

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
Schedule 7	Insertion of plots 12/06a, 12/06(b), 12/17(a) and 12/17(b).	To reflect the updated <b>Book of Reference (4.3, REP4-004)</b> and <b>Land Plans (2.1, REP4-003)</b> submitted at Deadline 4 (following creation of the new plots).
Schedule 10		
Schedule 10 Protective Provisions	Updating the protective provisions.	These have been updated in accordance with the Applicant's latest position. Please see the <b>Protective Provisions</b> <b>Summary (8.02.45)</b> for further information.
Schedule 11		
Schedule 11 (Documents and plans to be certified)	Updating the list of plans that are to be certified.	This reflects the insertion of the "MOL plan", "pre-commencement plan" and the "REP and RRRF Application Boundaries plan" as certified documents. The date of the FRAPA drawing has been corrected.
Schedule 14		
Schedule 14	This has been inserted to set out the modifications being made to the section 36 consent (Part 1) and the RRRF planning	

Riverside Energy Park Draft DCO Schedule of Changes

Article / Requirement number	Change in the Development Consent Order (Revision 3)	Reason for the change
(Modifications to the section 36 consent and the RRRF planning permission)	permission (Part 2).	