


Environmental Statement: Volume III

Appendix 11B: Supplementary Phase 1 Geo- Environmental Assessment



VPI Immingham Supplementary Phase I Geo- environmental Assessment

AECOM Environment & Infrastructure

VPI Immingham

Project Reference: 60547702

10th October 2018

Quality information

Prepared by

Guy Brumfield
Assistant Environmental
Consultant

Daniel Maher
Senior Consultant

Checked by

Dr Alex Freeman
Associate Director

Approved by

David Cragg
Technical Director

Revision History

Revision	Revision date	Details	Authorized	Name	Position
DRAFT	10/10/18		AJF	Alex Freeman	Associate Director

Distribution List

# Hard Copies	PDF Required	Association / Company Name

Prepared for:

VPI Immingham
Rosper Road
South Killingholme
Immingham
DN40 3DZ

Prepared by:

Daniel Maher
Senior Consultant
T: 0113-204-5051
M: 0788-754-1213
E: alex.freeman@aecom.com

AECOM Infrastructure & Environment UK Limited
2 City Walk
Leeds
West Yorkshire
LS11 9AR

© This Report is the copyright of AECOM Infrastructure & Environment UK Limited. Any unauthorised reproduction or usage by any person other than the addressee is strictly prohibited.

AECOM Infrastructure & Environment UK Limited ("AECOM") has prepared this Report for the sole use of VPI Immingham ("Client") in accordance with the Agreement under which our services were performed. No other warranty, expressed or implied, is made as to the professional advice included in this Report or any other services provided by AECOM. This Report is confidential and may not be disclosed by the Client nor relied upon by any other party without the prior and express written agreement of AECOM.

The conclusions and recommendations contained in this Report are based upon information provided by others and upon the assumption that all relevant information has been provided by those parties from whom it has been requested and that such information is accurate. Information obtained by AECOM has not been independently verified by AECOM, unless otherwise stated in the Report.

The methodology adopted and the sources of information used by AECOM in providing its services are outlined in this Report. The work described in this Report was undertaken in May and June 2018 and is based on the conditions encountered and the information available during the said period of time. The scope of this Report and the services are accordingly factually limited by these circumstances.

Where assessments of works or costs identified in this Report are made, such assessments are based upon the information available at the time and where appropriate are subject to further investigations or information which may become available.

AECOM disclaim any undertaking or obligation to advise any person of any change in any matter affecting the Report, which may come or be brought to AECOM's attention after the date of the Report.

Certain statements made in the Report that are not historical facts may constitute estimates, projections or other forward-looking statements and even though they are based on reasonable assumptions as of the date of the Report, such forward-looking statements by their nature involve risks and uncertainties that could cause actual results to differ materially from the results predicted. AECOM specifically does not guarantee or warrant any estimate or projections contained in this Report.

Table of Contents

1.	Introduction	5
1.1	Project Background	5
1.2	Objectives and Aims	5
1.3	Scope of Works	5
1.4	Information Sources	6
2.	Site Description.....	7
2.1	Site Location.....	7
2.2	Site Layout.....	7
2.3	Surrounding Land Use.....	7
3.	Environmental Setting.....	8
3.1	Geology	8
3.2	Hydrology	8
3.3	Hydrogeology	9
3.4	Radon.....	9
4.	Site History	10
4.1	Introduction.....	10
4.2	History of the Site and Surrounding Land Use.....	10
5.	Regulatory Database Search.....	11
5.1	Introduction.....	11
5.2	Database Review	11
6.	Previous Reports	13
6.1	Introduction.....	13
6.2	Factual Report on Ground Investigation, VPI Immingham, SOCOTEC (August, 2018).....	13
6.3	Phase 2 Geotechnical and Geo-environmental Interpretative Report, VPI Immingham Energy Park, AECOM (September 2018)	13
7.	Conceptual Site Model.....	17
7.1	Introduction.....	17
7.2	Assessment Framework	17
7.3	Potential Sources of Contamination	17
7.4	Contaminants of Concern.....	18
7.5	Potential Receptors	18
7.6	Potential Pathways	19
7.7	Summary of Potential Pollutant Linkages (CSM).....	20
8.	Conclusions and Data Gaps	23
8.1	Conclusions.....	23
8.2	Data Gaps	23
8.3	Recommendations.....	23
	Appendix A – Groundsure® Report.....	
	Appendix B – Factual Report on Ground Investigation, Report No A8015-18, August 2018.....	
	Appendix C – Photolog	
	Appendix D – Historic Maps.....	
	Appendix E – Phase 2 Geotechnical and Geo-environmental Interpretative Report, September 2018	
	Appendix F – Risk Assessment Principles	

Tables

Table 1 – Summary of Site History	10
Table 2 – Summary of Database Review	11
Table 3 – Summary of Ground Conditions Encountered	13
Table 4 – Groundwater Monitoring Results Summary	14
Table 5 – Exceedance of Stage 2 GAC for Controlled Waters: Groundwater.....	15
Table 6 – Summary of Contaminants of Concern.....	18
Table 7 – Summary of Pollutant Linkages	21

1. Introduction

AECOM Infrastructure & Environment UK Ltd (hereafter referred to as AECOM) was commissioned by Vitol Power International (VPI) Immingham to undertake a Supplementary Phase 1 Geo-environmental Site Assessment of the current VPI land, referred to hereafter as the 'site', to support the proposed development of a parcel of land to the north of the current VPI facility. The proposed development is understood to include construction of gas engines and an open cycle gas turbine (OCGT), which will be constructed on land to the north of the current VPI site.

A separate Phase 1 report has already been prepared for the additional parcel of land comprising the bulk of the proposed development, and this report has been designed to characterise the existing VPI power station site, parts of which are intended for construction laydown and connection corridors associated with the proposed development. A site location plan is provided as Figure 1.

1.1 Project Background

The current VPI Immingham combined heat and power (CHP) plant has been operational since 2004. The CHP power plant is understood to produce steam which is supplied to nearby Humber and Lindsey Oil Refineries. It is understood that the proposed development includes the addition of a series of gas engines and OCGT plant to the VPI Immingham site, to increase export from 1320 MWe to 1800 MWe.

While the development is proposed on undeveloped land to the north of the existing VPI facility, during construction the existing VPI car park (in the northeast of the site) and an area of open ground forming the southeastern boundary of the VPI site will be used for construction laydown. In addition, a connection corridor is proposed on the western and southern boundaries of the existing VPI facility.

1.2 Objectives and Aims

The objective of this Supplementary Phase 1 Environmental Desk Study was to determine the likely ground conditions beneath the site and the potential for ground contamination arising from historical or current on-site or off-site activities on the VPI facility. This risk assessment also aimed to determine the presence of contamination sources and potential pathways to sensitive receptors located both on and offsite.

1.3 Scope of Works

The scope of services for this study included:

- Commissioning and review of a Groundsure[®] report (including a regulatory database search, Coal Authority Report and historical Ordnance Survey (OS) maps);
- Review of publically available web-based sources, including the Environment Agency (EA) website and British Geological Survey (BGS);
- Review of relevant previous site investigation reports;
- Assessment of anticipated ground conditions and identification of potential development constraints; and
- Development of a preliminary Conceptual Site Model (CSM), identifying potential contaminants of concern, sources, pathways and receptors.

1.4 Information Sources

The following information sources were used in the completion of this geo-environmental assessment:

- Google Maps, accessed May 2018;
- Magic Maps Application <http://magic.defra.gov.uk/MagicMap.aspx>, accessed May 2018;
- Government Service website (<https://flood-map-for-planning-service.gov.uk/>), accessed May 2018;
- British Geological Survey (BGS) website (www.bgs.ac.uk) including the 'GeoIndex' tool, accessed May 2018;
- The Coal Authority Interactive Map Viewer (<http://mapapps2.bgs.ac.uk/coalauthority/home.html>), accessed May 2018;
- Groundsure® Reports; EnviroInsight (ref. GS-5087181), GeoInsight (ref. GS-5087182), and MapInsight (ref. GS- 5087183), dated 30th May 2018;
- UXO report, ref 502279
- The British Geological Survey (BGS) 1:50,000 solid and drift geology map No. 81;
- SOCOTEC, VPI Immingham, Draft Factual Report on Ground Investigation, Report No A8015-18, July 2018;
- AECOM Phase 2 Geotechnical and Geo-environmental Interpretative Report, VPI Immingham Energy Park, September 2018; and
- A site walkover conducted on 1st June 2018.

2. Site Description

2.1 Site Location

The site is located off Rosper Road, Immingham, North East Lincolnshire (see Figure 1), and is approximately 2 km east of South Killingholme. The site is centred on National Grid Reference (NGR) TA 16762 17168.

The site is surrounded by a mix of industrial and agricultural land use, namely the Total Lindsey Oil Refinery (TLOR) to the northwest, and the Phillips 66 Humber refinery to the southwest. Directly to the east is agricultural land and the River Humber is located approximately 1.3 km from the site. Directly south is an area of unused/waste land.

2.2 Site Layout

The site occupies a total area of approximately 18.53 ha. The site consists of the CHP plant, the site car park and a former laydown area. The site is bounded to the east by Rosper Road. Immingham Port is located approximately 2.5km to the South East and the River Humber is located approximately 1.3km to the east.

2.3 Surrounding Land Use

Based on a review of maps, the land use immediately surrounding the site was assessed and is summarised below:

- North: Immediately north of the site is an area of undeveloped vegetated land, which is largely flat with two large mounds formed from stockpiled topsoil and subsoil generated from previous construction works to the north. Immediately north the undeveloped land lies the existing TLOR car park and an access road which links the Lindsey Oil Refinery and Rosper Road:
- East: An unnamed drain and Rosper Road are directly east of the site, beyond which there are agricultural fields:
- West: a railway line separates the site from the TLOR facility to the northwest; and
- South: Immediately south of the site is some unused waste/ grass land, bounded to the southwest by the railway line with the Philips 66 Humber Refinery beyond.

3. Environmental Setting

3.1 Geology

The Groundsure[®] reports (**Appendix A**), and data from the SOCOTEC factual report relating to a recent ground investigation conducted on land to the north of the site (**Appendix B**), publically available nearby BGS borehole records, historic reports associated with the site and nearby A160 improvements, have been reviewed to identify the likely geological sequence at the site. The anticipated sequence is detailed below:

3.1.1 Made Ground

The Groundsure[®] Geo Insight report records that to the north west of the site an area of historic surface ground workings. These areas are recorded as unspecified heaps, possibly associated with material generated during previous excavations conducted on the TLOR site.

A site walkover was conducted on the site and hardstanding and tarmac was evident across much of the eastern portion of the site formerly used as construction laydown during development of the CHP. Photos taken during the site visits are attached in **Appendix C**. It is anticipated that a layer of granular sub-base will be present beneath the areas of hardstanding.

The southern portion of the site was partially vegetated with a surface cover of gravel.

Aerial imagery and topographical surveys show that to the north of the site there are located a series of stockpiles. A ground investigation conducted in this area in early 2018 confirmed that the stock piles comprised brown sandy slightly gravelly clay, consistent with these stockpiles being topsoil and subsoil removed and stockpiled during construction of the TLOR car park north of the site.

3.1.2 Glacial deposits

The Groundsure[®] Geo Insight report indicates that superficial drift deposits on the site are likely to comprise glacial deposits, comprising glacial till and glacial sands and gravels. A small pocket of Tidal flat deposits consisting of clays and silts was located in the north east of the site.

Superficial deposits north of the site were recorded in the SOCOTEC factual report as comprising firm to very stiff sandy slightly gravelly clay, with occasional interbedded bands of laminated clay and silty gravelly sand, and silt.

3.1.3 Bedrock

Published geological maps and memoirs indicate that the site is underlain by the Burnham Chalk Formation of the Upper Cretaceous period. The BGS Lexicon describes the Burnham Chalk Formation as “*White, thinly-bedded chalk with common tabular and discontinuous flint bands; sporadic marl seams*”. The upper 10m to 20m of the bedrock is frequently described as “soft chalk”, overlying “hard chalk and flints”, indicating that the upper part of the Chalk is extensively weathered.

The depth to Burnham Chalk bedrock varied from 21.5 m bgl in the northeast to 28.5m bgl in the central southern portion of the site to the north of the VPI facility.

3.2 Hydrology

A review of Ordnance Survey maps indicated that the site is located approximately 1.3km west of the River Humber, which flows north west to south east. Drains run along the northern and north eastern site boundaries, and a small water storage pond is located approximately 100m north west of the site. The Humber Estuary is a designated Ramsar site.

The site is located within an area designated as ‘Flood Risk Zone 3 whereby the Environment Agency issue flood warnings, meaning there is a high (greater than 1 in 100) annual probability of flooding. Flood defences are located along the banks of the River Humber and the area falls under the jurisdiction of North East Lindsey Internal Drainage Board.

3.3 Hydrogeology

Consultation with the Environment Agency Aquifer Maps indicates that:

- The superficial glacial deposits are classified as a 'Secondary Aquifer (undifferentiated)', defined either as 'permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers', or 'lower permeability layers which may store and yield limited amounts of groundwater due to localised features such as fissures, tin permeable horizons and weathering'.
- The bedrock, Burnham Chalk Formation, is classified as a Principal Aquifer, defined as 'highly permeable formations usually with a known or probable presence of significant fracturing. They may be highly productive and able to support large abstractions for public supply and other purposes.

Fourteen groundwater monitoring wells were installed on the development site to the north of the VPI site and during subsequent groundwater monitoring events standing groundwater levels ranged from 0.67m to 4.4m above Ordnance Datum (aOD).

3.4 Radon

Public Health England's interactive Radon map indicates that the site is not in a Radon Affected Area, as less than 1% of properties are above the Action Level.

4. Site History

4.1 Introduction

AECOM has reviewed historical Ordnance Survey (OS) maps dating from 1886 to 2014 obtained as part of the Groundsure® report in order to assess potential historical uses of the site and the surrounding land. The summary provided below identifies key historical land uses and features which are considered to have the potential to have impacted the soil and groundwater beneath the subject site. The historical maps included within the Groundsure® report are provided in **Appendix D**.

4.2 History of the Site and Surrounding Land Use

AECOM has reviewed historical Ordnance Survey (OS) maps (**Appendix D**) and aerial imagery dating from 1886 to 2014 obtained as part of the Groundsure® report in order to assess potential historical uses of the site and the surrounding land. **Table 1** identifies the key historical land uses of the site and surrounding areas some of which are considered to have had the potential to impact the soil and groundwater beneath the site.

Table 1 – Summary of Site History

Year	On Site	Offsite
1886-1887	Marsh/ Agricultural land; Rosper Road present;	Humber road – South (350m) ; Cawber Farm – north west (550m); East middle mere road - north (650m); Marsh Farm – north east (700m);
1905-1910	No significant change;	No significant change;
1929-1930	No significant change;	Ulceby-Immingham railway line present south (adjacent); School present – south east (350m);
1947	No significant change;	No significant change;
1951	No significant change;	No significant change;
1968	No significant change;	No significant change;
1974	No significant change;	Oil refineries and associated buildings and tanks have been constructed and extend beyond 750m away from the site to the west/ north west and south; Railway line has been constructed running adjacent to the south west of the site ; Cawber farm is no longer there;
1983	No significant change;	No significant change;
2002	A pipeline now runs through the middle of the site and one borders the north western boundary of the site;	No significant change;
2010	Buildings constructed on site most likely associated with the VPI facility, with the pipeline being redirected around the facility;	Immingham West Fire Station – south east (400m);
2014	Roads associated with the VPI facility are now shown on the map.	No significant change.

5. Regulatory Database Search

5.1 Introduction

AECOM commissioned Groundsure® Limited to conduct a database search of available regulatory agency records to evaluate whether activities on or near the subject site have the potential to create a significant adverse impact. Groundsure® reviews databases compiled by national and local governmental agencies. The Groundsure® Report essentially relates to operational activities for which licences or authorisations are required and have been obtained pursuant to environmental laws. It is therefore possible that there are unauthorised activities being carried out in the vicinity of the subject site that are not detailed. It is noted that the database is not updated regularly and more recent unlisted or otherwise unregistered activities may therefore be present in the surrounding area.

It should be noted that this information is reported as AECOM received it from Groundsure®, which in turn reports information as it is provided in various government databases. It is not possible for either AECOM or Groundsure® to verify the accuracy or completeness of information contained in these databases. However, the use of this information is a generally accepted practice in the conduct of Phase 1 environmental assessments.

Sites identified within the study radius are evaluated to assess if they are likely to have had an adverse impact on the subject property or could be adversely affected by the subject property. The criteria used to evaluate sites within the study radius include distance from the subject property, expected depth and direction of groundwater and surface water flow, likely storm water flow direction and the presence / absence of documented contaminant releases at the identified sites.

The approximate distances to features described in this section have been estimated from the closest boundary of the site and may be subject to error.

5.2 Database Review

Key information from the Groundsure® Report that is considered pertinent to the subject site (within a radius of 500m), is summarised in **Table 2** below:

Table 2 – Summary of Database Review

CATEGORY	SUMMARY OF INFORMATION (<500m)
Part A(1) and IPPC Authorised Activities	1 effective: on site; and 8 superseded: on site;
List 1 Dangerous Substances Inventory Sites	1 inactive: 75m south west for Mercury and Cadmium relating to the Phillips 66 Humber Refinery site;
List 2 Dangerous Substance Inventory Sites	1 active: 75m south west for arsenic, chromium, copper, lead, nickel and zinc relating to the Phillips 66 Humber Refinery site;
Part A(2) and Part B Activities and Enforcements	2 current part B permits 245m south east both for coal and coke, one for Phillips 66 and one for P.D Port Services Ltd; 1 current part A2 permit 450m south west for coal and coke for Longs Steel (UK) Limited.1 historic part B permit 260m south east for coal and coke for P.D. Port Services Ltd; 1 historical part B permit 320m south east for coal and coke for P.D. Port Services Ltd;
Licensed Discharge Consents	4 revoked: one 40m north west (relating to The Lindsey Oil Refinery), two 75m south west (relating to the Humber Refinery) and one 410m south east (relating to the common pump station); and 2 effective: one 250m north west (relating to the Humber Refinery) and one 450m south east (relating to the Fire Station);

CATEGORY	SUMMARY OF INFORMATION (<500m)
Planning Hazardous Substance Consents and Enforcements	1 approved active consents: 130m south relating to VPI Immingham – Consent to store 3050 tonnes of petroleum gas oil;
Dangerous or Hazardous Sites	1 on site current COMAH site (lower tier) relating to VPI Immingham CHP; 3 off site current COMAH sites (all upper tier) relating to the Total Lindsey Oil Refinery (30m north west), Phillips 66 Humber refinery (40m south) and Associated British Ports (410m south east); 2 off site historic NIHHS sites for Conoco Manufacturing Ltd (90m south) and Humbersea Sea and Land Services Limited (120m south) 1 off site historic COMAH site relating to Humber LPG terminal Ltd (310m north east)
EA Recorded Pollution Incidents List 2	2 recorded: 1 On site – minor impact to air (atmospheric pollutants and effects) 1 20m south – minor impact to land & air (Oils and Fuels);
EA Recorded Pollution Incidents List 1	1 recorded 20m south of site relating to major persistent and extensive impacts to water (East Halton Beck);
Environment Agency/Natural Resources Wales historic landfill sites	1 historic landfill licence relating to liquid sludge from the Lindsey Oil Refinery (120m north west);
Environment Agency/Natural Resources Wales licensed waste sites	1 surrendered license 260m north west of the site relating to a biological treatment facility operated by the Lindsey Oil Refinery.

No other database entries were identified within 500m of the site boundary. Database listings reviewed included: Historic IPC Authorisations, Red List Discharge Consent Register Part A(2) and Part B Activities and Enforcements, Category 3 or 4 Radioactive Substances Authorisations, Water Industry Referrals, Sites Determined as Contaminated land (Part 2a) or Petrol & fuel sites.

6. Previous Reports

6.1 Introduction

AECOM reviewed previous environmental reports for the site by various others, as listed in Section 1.6. Pertinent information considered relevant to this assessment is summarised in the following sections.

6.2 Factual Report on Ground Investigation, VPI Immingham, SOCOTEC (August, 2018)

In April 2018, SOCOTEC conducted a Phase 2 intrusive investigation on the development site to the north of the VPI site. The findings were presented in a Factual Report, dated August 2018 (**Appendix B**). The investigation comprised the following:

- Installation of six cable percussive boreholes (BH1-BH6), with rotary drilling follow on in three of the holes (BH1, BH2 & BH5);
- Advancement of eight window samples (WS01-WS08); and
- Excavation of ten trial pits (TP01-TP10) and three trial trenches (TT1-TT3).

6.2.1 Ground Conditions

Exploratory hole logs and the results of in-situ and geotechnical testing are presented in SOCOTEC's factual report enclosed in **Appendix B**. The exploratory holes encountered the following generalised succession beneath the site, summarised in **Table 3** below:

Table 3 – Summary of Ground Conditions Encountered

Material	Typical Description	Top of Strata (m bgl)	Base of Strata (m bgl)	Top of Strata (m OD)	Base of Strata (m OD)
Made Ground	Sandy gravelly clay	0.0	0.2 to 1.7	6.5 to 4.0	6.3 to 3.2
Glacial Till	Firm to stiff sandy gravelly clay	0.0 to 1.7	21.5 to 27.5	6.0 to 3.5	-16.8 to -21.5
Glacial Sands and Gravels	Medium dense clayey sand and gravel	12.9 to 13.0	15.2 to 16.0	-6.6 to 8.2	-9.3 to -10.6
Weathered Chalk	Extremely weak to very weak chalk	21.5 to 27.5	26.1 to 30.9	-17.0 to 21.5	-22.5 to -26.6
Unweathered Chalk	Medium Strong to strong chalk	26.1 to 30.9	Unproven	-22.5 to 26.5	Unproven

During the investigation, AECOM staff collected soil and groundwater samples for chemical analysis. The results of the analysis are presented in the AECOM Phase 2 Interpretative Report, summarised below.

6.3 Phase 2 Geotechnical and Geo-environmental Interpretative Report, VPI Immingham Energy Park, AECOM (September 2018)

A copy of the AECOM Phase 2 Geotechnical and Geo-Environmental Interpretative report is attached in **Appendix E**.

6.3.1 Soil Sampling and Analysis

Soil headspace analysis was undertaken in the field using a Photo Ionisation Detector (PID), and of the nine samples with measurable PID readings, eight were less than 5ppm, with one sample from TP02 yielding a higher reading of 42.4ppm.

Soil samples were collected from each exploratory location and submitted for chemical analysis at Exova Jones, an AECOM approved laboratory, with 26 samples analysed for the following contaminants:

- Volatile Organic Compounds (VOCs) including tentatively identified compounds (TICs);
- Semi-volatile organic compounds (SVOCs) including TICs;
- Total Petroleum Hydrocarbons (TPH-CWG);
- Metals (including arsenic, barium, beryllium, cadmium, chromium, copper, lead, mercury, nickel, selenium, zinc, vanadium);
- Anions (including fluoride, nitrate, chloride, sulphide, and sulphate)
- pH;
- Soil organic matter; and
- Asbestos screening.

6.3.2 Soil Results and Human Health Risk Assessment

With respect to asbestos, 25 soil samples (from made ground or reworked natural deposits) were submitted for asbestos screening, and fibre bundles of chrysotile were identified in six samples (BH1, BH2, WS01, TP01, TP02 and TP06), all located in the western portion of the site. These six samples were submitted for additional quantitative analysis, and all of the samples contained trace levels of asbestos (<0.001% w/w).

The results of the chemical analysis were screened against generic assessment criteria (GACs) derived for commercial / industrial end use, and no exceedances for any of the contaminants of concern were reported.

6.3.3 Groundwater Monitoring

Following drilling, fourteen groundwater monitoring wells were installed in the window samples (WS01-WS08) and deeper boreholes (BH1-BH6). Subsequent groundwater monitoring events were conducted in April 2018, and measured groundwater levels measured are summarised in **Table 4** below:

Table 4 – Groundwater Monitoring Results Summary

Hole ID	GL m OD	Range of groundwater levels m bgl	Range of ground water levels m OD	Response zone (m bgl)	Strata
BH01	6.36	3.70 -3.97	2.39 - 2.65	12.50-15.00	Glacial Deposits
BH02	5.43	2.66 - 2.87	2.56 - 2.77	14.00-15.30	Glacial Deposits
BH03	5.43	2.57 - 2.75	2.68 - 2.86	26.60-28.60	Burnham Chalk
BH04	4.19	1.31 - 1.56	2.63 - 2.88	28.60-34.60	Burnham Chalk
BH05	4.65	1.86 - 2.04	2.61 - 2.78	17.50-18.50	Glacial Deposits
BH06	4.71	2.19 - 2.33	2.38 - 2.51	25.50-34.50	Burnham Chalk
WS01	6.49	2.08 - 2.16	4.33 - 4.40	1.00-1.40	Made Ground
WS02	5.46	1.32 - 1.36	4.09 - 4.14	0.70-1.20	Made Ground
WS03	5.52	1.40 - 1.52	3.99 - 4.12	2.50-3.50	Glacial Deposits
WS04	5.1	0.96 - 0.99	4.11 - 4.13	1.30-2.30	Made Ground/Glacial Deposits

WS05	4.7	0.98 - 1.00	3.67 - 3.72	3.20-4.20	Glacial Deposits
WS06	5.69	1.59 - 1.64	4.05 - 4.10	3.10-3.70	Glacial Deposits
WS07	5.79	1.83 - 1.86	3.92 - 3.95	3.00-3.50	Glacial Deposits
WS08	4.53	3.33 - 3.86	0.67 - 1.19	3.60-4.10	Glacial Deposits

Measured groundwater levels range from 4.33m OD to 0.67m OD.

6.3.4 Groundwater Sampling and Analysis

During the subsequent monitoring, eight groundwater samples were collected and submitted for analysis of the following:

- Volatile Organic Compounds (VOCs) including tentatively identified compounds (TICs);
- Semi-volatile organic compounds (SVOCs) including TICs;
- Total Petroleum Hydrocarbons (TPH-CWG);
- Metals (including arsenic, barium, beryllium, boron, cadmium, chromium, copper, iron, lead, mercury, nickel, selenium, zinc, vanadium);
- Anions (including alkalinity, ammoniacal nitrogen, chloride, nitrate, phosphate, and sulphate)
- pH; and
- Dissolved organic carbon.

6.3.5 Groundwater Results and Controlled Waters Risk Assessment

The following Controlled Waters receptors were considered in the assessment:

- Superficial deposits underlying the site are classified as a Secondary Aquifer (undifferentiated);
- The Burnham Chalk Formation limestone bedrock underlying the site classified as a Principal Aquifer; and
- The Humber estuary.

Drinking Water Standards (DWS) and coastal Environmental Quality Standards (EQS) were used for screening groundwater results to assess potential risks to underlying groundwater and surface water respectively. The exceedances identified are summarised in **Table 5**, below:

Table 5 – Exceedance of Stage 2 GAC for Controlled Waters: Groundwater

Parameter	Location	Max Concentration (µg/l)	Exceedance of DWS	Exceedance of EQS
Selenium	BH03	16	X	
Zinc	BH01, BH03, WS05	12		X
Sulphate	WS03-WS06	983,900		X
Chloride	WS03-WS05	1,280,000		X

Only selenium concentrations exceeded the DWS, while concentrations of zinc, sulphates and chloride exceeded the Coastal EQS.

The exceedance of the DWS for selenium was marginal (a magnitude of 1.6) and there are no potable extractions in the vicinity of the site.

According to published Environment Agency monitoring data for surface waters within the hydrological catchment of the site, the EQS exceedances for zinc, sulphate and chloride were not replicated in surface waters.

6.3.6 Ground Gas Risk Assessment

A ground gas assessment was completed based on a three ground gas monitoring events undertaken during May and June 2018.

The results of the gas monitoring are summarised below:

- Methane was recorded at levels <0.1 – 0.7% Vol. which is below the lower explosive limit.
- Carbon dioxide was recorded at levels <0.1 – 3.9% Vol.
- Oxygen was recorded at levels between 14.4– 20.7% Vol;
- Gas flow rates were recorded between -17.0 and 7.3l/hr;

Potential risks posed by the identified ground gas regime were assessed using the methodology outlined in BS 8485:2015, and the site was classified as Characteristic Situation (CS) 2, with respect to ground gases, which equated to a low risk.

7. Conceptual Site Model

7.1 Introduction

AECOM has developed a preliminary conceptual site model (CSM) based on a qualitative “Source → Pathway → Receptor” (SPR) risk assessment. The following sections consider the identified potential sources, pathways and receptors.

7.2 Assessment Framework

The site, in terms of potential land contamination, will be regulated by the local authority (Lincolnshire County Council) under the Town and Country Planning Act 1990 (as amended), taking account of the National Planning Policy Framework 2012, with the Environment Agency, Natural England and English Heritage acting as statutory consultees.

The ‘suitable for use’ approach is adopted for the assessment of contaminated land where remedial measures are only undertaken where unacceptable risks to human health or the environment are realised taking into account the use (or proposed use) of the land in question and the environmental setting. Additional environmental liabilities can arise through provisions contained within statutory legislation including Part 2A of the EPA 1990, the Water Resources Act 1991, the Groundwater Regulations 2009 and the Water Act 2003.

Current best practice recommends that the determination of health hazards due to contaminated land is based on the principle of risk assessment, as outlined in the Statutory Guidance to Part 2A (2012) and CLR11.

The risk assessment process for environmental contaminants is based on a source-pathway-receptor analysis. These terms can be defined as follows:

- Source: hazardous substance that has the potential to cause adverse impacts;
- Pathway: route whereby a hazardous substance may come into contact with the receptor: examples include ingestion of contaminated soil and leaching of contaminants from soil into watercourses; and
- Receptor: target that may be affected by contamination: examples include human occupants / users of site, water resources (surface waters or groundwater), or structures.

For a risk to be present there must be a relevant pollutant linkage; i.e. a mechanism whereby a source impacts on a sensitive receptor via a pathway resulting in potentially significant harm.

Further details on the risk assessment process and methodology are provided in **Appendix F**.

7.3 Potential Sources of Contamination

Based upon the available information, potential sources of contamination include:

7.3.1 On Site

- Sources associated with a pipeline which was constructed between 1983 and 2002; and
- Sources from the VPI facility constructed in 2004.

7.3.2 Offsite

- Total Lindsey Oil Refinery & Phillips 66 Humber Refinery (operations and spills/leaks);
- Made ground within infilled land associated with the former sludge land farm and construction activities in the area
- Railway line and railway sidings; and,
- Surrounding agricultural land use.

7.4 Contaminants of Concern

Identified potential sources of contamination are summarised in **Table 6**, below.

Table 6 – Summary of Contaminants of Concern

Land use	Contaminant Grouping	Specific Contaminants
VPI power plant operations including pipeline (on site)	Organic	- Hydrocarbons e.g. crude oil, motor oils, petrol, diesel, kerosene, lubricants, waxes, bitumen, aviation fuel - Other organics e.g. alcohols, PCBs, MTBE, TAME, solvents, aliphatic and aromatic compounds
	Inorganic	- Mineral acids, alkalis, cyanides, sulphur and sulphide - Metals e.g. aluminium, cobalt, copper, iron, lead, molybdenum, nickel and vanadium
	Other	- Asbestos
Agricultural land (on site)	Organic	- Insecticides/pesticides/ herbicides including organophosphates, Diazinon, Alphacypermethrin, Oxfendazole, Ivermectin, Glyphosate
Made ground within land farm and infilled land/ stockpiles (off site)	Organic	- Hydrocarbons e.g. diesel, lubricating oils, petrol - Polychlorinated Biphenyls (PCBs) - Polycyclic Aromatic Hydrocarbons (PAHs)
	Inorganic	- Metals including arsenic, zinc, lead, copper, manganese and cadmium
	Other	- Ground gases including carbon dioxide, methane and hydrogen sulphide. - Asbestos
Railway line and former railway sidings (off site)	Organic	- Hydrocarbons e.g. diesel, lubricating oils, paraffin - Polychlorinated Biphenyls (PCBs) - Polycyclic Aromatic Hydrocarbons (PAHs) - Solvents - Ethylene glycol - Creosote (contains PAHs) - Herbicides (e.g. atrazine, simazine, sodium chlorate, dalapon, diuron, borax, paraquat, picloram)
	Inorganic	- Ferrous residues - Metal fines
	Other	- Asbestos - Ash and fill (possibly containing metals, phenols, sulphates and PAHs)

Information included in the above table is based upon information from the Department of Environment (DoE) 1995 Industry Profiles for “Oil refineries and bulk storage of crude oil and petroleum products” and “Railway land”, the Health and Safety Executive database on pesticides, the Veterinary Medicines Directorate Defra website as well as industry experience

Whilst **Table 6** generally reflects contaminants that are associated with the specified land uses, it is not an exhaustive list, nor should it be interpreted as a list of chemicals that are present at site. It should also be noted that unrecorded land uses (which can significantly impact ground conditions on site) may have occurred; consequently uncertainty remains as to the exact nature and extent of potential contamination on site.

7.5 Potential Receptors

7.5.1 Human Health:

- On site construction workers;
- Current and future workers at the VPI site
- Future workers at the new power station to the north; and

- Off-site workers e.g. Total Lindsey Oil Refinery.

7.5.2 Controlled Waters:

- Surface waters including the River Humber and nearby drains;
- Shallow groundwater within the superficial deposits (Secondary undifferentiated Aquifer); and,
- Groundwater within the bedrock (Principal Aquifer).

7.5.3 Infrastructure:

- Underground services e.g. buried pipes; and,
- Proposed future on-site buildings.

7.5.4 Ecology:

- Flora and Fauna; and,
- Ecological systems associated with SSSI, SAC and Ramsar designations within the Humber Estuary.

7.6 Potential Pathways

7.6.1 Human Health:

- Direct dermal contact with substances in shallow soil and/or groundwater during potential groundworks;
- Inhalation of substances from the partitioning of vapours from soil and / or shallow groundwater; and,
- Accidental ingestion and/or inhalation of substances in soil/dust and/or shallow groundwater during potential groundworks.

7.6.2 Controlled Waters:

- Vertical migration through unsurfaced areas, vegetated areas and hard-standing, and drains / pipework into Made Ground / shallow soils;
- Lateral and vertical migration within the made ground and superficial deposits (Secondary undifferentiated Aquifer), e.g. leaching from made ground vertically into shallow soil layers, including into deeper groundwater;
- Preferential lateral and vertical migration along routes of underground services, pipelines and associated trenches;
- Lateral overland flow, including via drains, to nearby surface waters; and
- Lateral and vertical migration within deeper groundwater with the chalk aquifer.

7.6.3 Ecology:

- Plant uptake and subsequent ingestion by fauna; and,
- Ecological systems designated SSSI, SAC and Ramsar within the Humber Estuary.

7.6.4 Infrastructure:

- Migration of ground gases and accumulation in confined spaces associated with the future development of the site (e.g. basements, service ducts).
- Piling foundations associated with future development of the site.

7.7 Summary of Potential Pollutant Linkages (CSM)

A summary of the potential pollutant linkages and the related initial qualitative assessment of risk is summarised in **Table 7**, below. The risk rankings assume that the current ground and groundwater conditions prevail, prior to any mitigation measures such as further intrusive investigation, quantitative risk assessment or remediation. The risk rankings for each of the pollutant linkages are derived from a combination of the magnitude of the potential consequence (i.e. severity) of the exposure of the receptor to the contaminant; and the magnitude of probability (i.e. likelihood) that the pollutant linkage is present or will occur.

Table 7 – Summary of Pollutant Linkages

SOURCE	PATHWAY	RECEPTOR	POTENTIAL SEVERITY	LIKELIHOOD OF OCCURRENCE	LEVEL OF RISK	DISCUSSION AND POSSIBLE MITIGATION
Made ground within areas of potentially infilled land/ stockpiles	Direct contact and/or ingestion of contaminated material	On site construction workers and future logistics site employees	Moderate	Possible	Medium	Direct contact and ingestion of contaminated particulates and dust is possible during site works, and as such there should be appropriate safety and mitigation measure (e.g. the use of PPE) put in place to minimise occupational risks to human health should areas of suspected contamination be encountered. Given use of the site is restricted to construction laydown, with little in the way of earthworks proposed, the risks of encountering contaminated soils is considered to be minimal.
	Inhalation of particulates/dusts/ vapours / gases	On site construction workers/ employees	Moderate	Possible	Medium	As with the direct contact/ingestion pathway there is a possibility for vapours/gases/dusts and/or particulates to be inhaled as a consequence of disturbing the ground during site work. For the proposed development, the greatest risk is associated with the construction of service and utility trenches which dependent on the depth of excavation should be considered confined spaces.
	Migration of ground gases (e.g. methane and carbon dioxide) through permeable made ground strata	Newly constructed infrastructure	Minor	Possible	Low	Due to the proximity of the site to potentially in filled land an assessment of risks from ground gases may be required. As above, these risks are only likely to be present during construction, with no buildings proposed on the site as part of the development.
	Leaching/ surface runoff of substances from any newly exposed/ excavated ground	Surface waters		Moderate	Unlikely	Low
Flora and fauna within areas designated SSSI, SAC or Ramsar			Moderate	Unlikely	Low	Mitigation measures e.g. making sure any suspected contaminated material is contained and/ or appropriately disposed of, any plant machinery is thoroughly decontaminated and intrusive works minimised to reduce the disturbance of soils and fuel spills are rapidly dealt with is likely to be required for any soils stockpiled.

Impacted shallow groundwater below site	Vertical migration of impacted groundwater from within the made ground superficial deposits	Deeper groundwater in the bedrock	Moderate	Unlikely	Low	Considering the low porosity of the superficial deposits it is unlikely that contaminants will be able to migrate to significant depths towards the bedrock. Despite this low risk it is still advised that good construction work practices are implemented.
Impacted shallow groundwater below site	Vertical migration of impacted groundwater from within the made ground and superficial deposits via enhanced pathways e.g. utility trenches	Deeper groundwater in the bedrock	Moderate	Unlikely	Low	The low permeable superficial deposits are likely acting as a protective layer above the Burnham formation chalk bedrock. It is considered unlikely that any foundations or excavations associated with utilities constructed as part of the Proposed Development will penetrate the full thickness of low permeability superficial deposits and the risk of utilities acting as a preferential pathway to deep groundwater is considered to be low.

8. Conclusions and Data Gaps

8.1 Conclusions

This Phase 1 Geo-environmental assessment comprises a review of available geo-environmental information for the VPI Immingham site in order to assess the likely ground conditions beneath the site and the potential for ground contamination arising from historical or current on-site or off-site activities.

Key findings of the assessment included:

- The geology underlying the site is anticipated to comprise variable depths of Made Ground, superficial deposits (Glacial till and Glacial sands and gravels) and weathered bedrock consisting of the Burnham Chalk Formation;
- The superficial deposits are classified as being of Secondary (undifferentiated) Aquifer potential. The Burnham Chalk Formation is classified as a Principal Aquifer;
- The largest and most proximal surface water course is the River Humber, located ~1.3km directly to the east of the site. A number of other drains and tributaries of the River Humber are also present in close proximity to the site;
- Prior to its current use as a CHP plant site has been used primarily as agricultural land with the exception of a pipeline which was constructed between 1983 and 2002. A limited number of other potential sources of contamination were identified from historical maps including a railway, oil refineries and a former sludge land farm;
- There are significant data gaps relating to the presence of potential contamination originating from the historic sludge land farm located to the north of the site; and
- The main risks identified by the CSM pertained to the direct contact and inhalation of contaminants by construction workers as well as the potential for impacted shallow groundwater to migrate into the deeper groundwater via enhanced pathways e.g. piling foundations and boreholes. Thus it is advised that appropriate PPE is worn by those likely to come into contact with site soils and particular care is taken during the design and construction if works are required to go beyond the superficial deposits.

8.2 Data Gaps

Whilst the information from secondary datasets and previous ground investigation reports are able to provide a general idea of expected ground conditions, unrecorded land uses (which can significantly impact ground conditions on site) may have occurred. Furthermore coverage from previous ground investigations is poor for the site. Consequently large uncertainty remains as to the exact nature of the ground conditions present at the site, particularly in regards to the nature of the potentially infilled land associated with the historic land farm to the north of site.

8.3 Recommendations

Based upon the above data gaps, it is recommended that intrusive ground investigations, (potentially with further phases of additional ground investigation to delineate contamination hotspots, if identified), are undertaken in order to further assess potential risks posed to the proposed development (associated with ground conditions at the site) and establish an accurate environmental baseline of the site prior to the proposed development.

The ground investigations should include the installation of gas and groundwater monitoring wells across the site and around its perimeter to allow collection of soil and groundwater samples for laboratory analysis of contaminants based on the potential sources identified in Section 7.4. A programme of periodic gas and groundwater monitoring events may also need to be undertaken in order to identify changes in site conditions in response to weather and seasonal changes.

Appendix A – Groundsure[®] Report



Aecom Infrastructure and Environment UK Ltd
AECOM LTD,2, CITY WALK,
LEEDS, LS11 9AR

Groundsure Reference: GS-5087181
Your Reference: VPI_Immingham
Report Date 30 May 2018
Report Delivery Method: Email - pdf

Enviro Insight


Address: TANKS 90M FROM V P I IMMINGHAM, ROSPER ROAD. 18M FROM UNNAMED ROAD, FOOTPATH SKIL91A, SOUTH KILLINGHOLME, DN40 3DZ

Dear Sir/ Madam,

Thank you for placing your order with Groundsure. Please find enclosed the **Groundsure Enviro Insight** as requested.

If you need any further assistance, please do not hesitate to contact our helpline on 08444 159000 quoting the above Groundsure reference number.

Yours faithfully,



Managing Director
Groundsure Limited

Enc.
Groundsure Enviroinsight

Address: TANKS 90M FROM V P I IMMINGHAM, ROSPER ROAD. 18M FROM UNNAMED ROAD, FOOTPATH SKIL91A, SOUTH KILLINGHOLME, DN40 3DZ

Date: 30 May 2018

Reference: GS-5087181

Client: Aecom Infrastructure and Environment UK Ltd

NW

N

NE

W

E



SW

S

SE

Aerial Photograph Capture date: 21-Apr-2016
Grid Reference: 516701,417117
Site Size: 18.53ha
Report Reference: GS-5087181
Client Reference: VPI_Immingham

Contents Page

Contents Page	3
Overview of Findings	6
Using this report	10
1. Historical Land Use	11
1. Historical Industrial Sites	12
1.1 Potentially Contaminative Uses identified from 1:10,000 scale Mapping	12
1.2 Additional Information – Historical Tank Database	14
1.3 Additional Information – Historical Energy Features Database	15
1.4 Additional Information – Historical Petrol and Fuel Site Database	15
1.5 Additional Information – Historical Garage and Motor Vehicle Repair Database	15
1.6 Potentially Infilled Land	16
2. Environmental Permits, Incidents and Registers Map	17
2. Environmental Permits, Incidents and Registers	18
2.1 Industrial Sites Holding Licences and/or Authorisations	18
2.1.1 Records of historic IPC Authorisations within 500m of the study site	18
2.1.2 Records of Part A(1) and IPPC Authorised Activities within 500m of the study site	18
2.1.3 Records of Red List Discharge Consents (potentially harmful discharges to controlled waters) within 500m of the study site	20
2.1.4 Records of List 1 Dangerous Substances Inventory Sites within 500m of the study site	20
2.1.5 Records of List 2 Dangerous Substance Inventory Sites within 500m of the study site	20
2.1.6 Records of Part A(2) and Part B Activities and Enforcements within 500m of the study site	20
2.1.7 Records of Category 3 or 4 Radioactive Substances Authorisations	21
2.1.8 Records of Licensed Discharge Consents within 500m of the study site	21
2.1.9 Records of Water Industry Referrals (potentially harmful discharges to the public sewer) within 500m of the study site	23
2.1.10 Records of Planning Hazardous Substance Consents and Enforcements within 500m of the study site	23
2.2 Dangerous or Hazardous Sites	23
2.3 Environment Agency/Natural Resources Wales Recorded Pollution Incidents	24
2.3.1 Records of National Incidents Recording System, List 2 within 500m of the study site	24
2.3.2 Records of National Incidents Recording System, List 1 within 500m of the study site	25
2.4 Sites Determined as Contaminated Land under Part 2A EPA 1990	25
3. Landfill and Other Waste Sites Map	26
3. Landfill and Other Waste Sites	27
3.1 Landfill Sites	27
3.1.1 Records from Environment Agency/Natural Resources Wales landfill data within 1000m of the study site	27
3.1.2 Records of Environment Agency/Natural Resources Wales historic landfill sites within 1500m of the study site	27
3.1.3 Records of BGS/DoE non-operational landfill sites within 1500m of the study site	29
3.1.4 Records of Landfills from Local Authority and Historical Mapping Records within 1500m of the study site	29
3.2 Other Waste Sites	29
3.2.1 Records of waste treatment, transfer or disposal sites within 500m of the study site	29
3.2.2 Records of Environment Agency/Natural Resources Wales licensed waste sites within 1500m of the study site	30
4. Current Land Use Map	33
4. Current Land Uses	34
4.1 Current Industrial Data	34
4.2 Petrol and Fuel Sites	34
4.3 National Grid High Voltage Underground Electricity Transmission Cables	35
4.4 National Grid High Pressure Gas Transmission Pipelines	35

5. Geology	36
5.1 Artificial Ground and Made Ground.....	36
5.2 Superficial Ground and Drift Geology	36
5.3 Bedrock and Solid Geology	36
6 Hydrogeology and Hydrology	37
6a. Aquifer Within Superficial Geology	37
6b. Aquifer Within Bedrock Geology and Abstraction Licences	38
6c. Hydrogeology – Source Protection Zones and Potable Water Abstraction Licences	39
6d. Hydrogeology – Source Protection Zones within confined aquifer	40
6e. Hydrology – Watercourse Network and River Quality	41
6.Hydrogeology and Hydrology	42
6.1 Aquifer within Superficial Deposits.....	42
6.2 Aquifer within Bedrock Deposits.....	42
6.3 Groundwater Abstraction Licences.....	43
6.4 Surface Water Abstraction Licences.....	45
6.5 Potable Water Abstraction Licences.....	45
6.6 Source Protection Zones.....	46
6.7 Source Protection Zones within Confined Aquifer.....	46
6.8 Groundwater Vulnerability and Soil Leaching Potential.....	46
6.9 River Quality.....	46
6.9.1 Biological Quality:.....	47
6.9.2 Chemical Quality:.....	47
6.10 Ordnance Survey MasterMap Water Network.....	47
6.11 Surface Water Features.....	67
7a. Environment Agency/Natural Resources Wales Flood Map for Planning (from rivers and the sea)	69
7b. Environment Agency/Natural Resources Wales Risk of Flooding from Rivers and the Sea (RoFRaS) Map	70
7 Flooding	71
7.1 River and Coastal Zone 2 Flooding.....	71
7.2 River and Coastal Zone 3 Flooding.....	71
7.3 Risk of Flooding from Rivers and the Sea (RoFRaS) Flood Rating.....	71
7.4 Flood Defences.....	72
7.5 Areas benefiting from Flood Defences.....	72
7.6 Areas benefiting from Flood Storage.....	72
7.7 Groundwater Flooding Susceptibility Areas.....	72
7.8 Groundwater Flooding Confidence Areas.....	73
8. Designated Environmentally Sensitive Sites Map	74
8. Designated Environmentally Sensitive Sites	75
8.1 Records of Sites of Special Scientific Interest (SSSI) within 2000m of the study site:.....	75
8.2 Records of National Nature Reserves (NNR) within 2000m of the study site:.....	75
8.3 Records of Special Areas of Conservation (SAC) within 2000m of the study site:.....	75
8.4 Records of Special Protection Areas (SPA) within 2000m of the study site:.....	76
8.5 Records of Ramsar sites within 2000m of the study site:.....	76
8.6 Records of Ancient Woodland within 2000m of the study site:	76
8.7 Records of Local Nature Reserves (LNR) within 2000m of the study site:.....	76
8.8 Records of World Heritage Sites within 2000m of the study site:.....	76
8.9 Records of Environmentally Sensitive Areas within 2000m of the study site:	76
8.10 Records of Areas of Outstanding Natural Beauty (AONB) within 2000m of the study site:	77
8.11 Records of National Parks (NP) within 2000m of the study site:	77
8.12 Records of Nitrate Sensitive Areas within 2000m of the study site:.....	77
8.13 Records of Nitrate Vulnerable Zones within 2000m of the study site:.....	77

8.14 Records of Green Belt land within 2000m of the study site:.....	77
9. Natural Hazards Findings	78
9.1 Detailed BGS GeoSure Data.....	78
9.1.1 Shrink Swell.....	78
9.1.2 Landslides.....	78
9.1.3 Soluble Rocks.....	78
9.1.4 Compressible Ground.....	79
9.1.5 Collapsible Rocks.....	79
9.1.6 Running Sand.....	79
9.2 Radon.....	80
9.2.1 Radon Affected Areas.....	80
9.2.2 Radon Protection.....	80
10. Mining	81
10.1 Coal Mining.....	81
10.2 Non-Coal Mining.....	81
10.3 Brine Affected Areas	81
Contact Details	82
Standard Terms and Conditions	84

Overview of Findings

For further details on each dataset, please refer to each individual section in the main report as listed. Where the database has been searched a numerical result will be recorded. Where the database has not been searched '-' will be recorded.

Section 1: Historical Industrial Sites	On-site	0-50	51-250	251-500
1.1 Potentially Contaminative Uses identified from 1:10,000 scale mapping	0	6	13	54
1.2 Additional Information – Historical Tank Database	0	0	5	40
1.3 Additional Information – Historical Energy Features Database	0	0	0	4
1.4 Additional Information – Historical Petrol and Fuel Site Database	0	0	0	0
1.5 Additional Information – Historical Garage and Motor Vehicle Repair Database	0	0	0	0
1.6 Potentially Infilled Land	0	0	9	6
Section 2: Environmental Permits, Incidents and Registers	On-site	0-50m	51-250	251-500
2.1 Industrial Sites Holding Environmental Permits and/or Authorisations				
2.1.1 Records of historic IPC Authorisations	0	0	0	0
2.1.2 Records of Part A(1) and IPPC Authorised Activities	9	0	0	0
2.1.3 Records of Red List Discharge Consents	0	0	0	0
2.1.4 Records of List 1 Dangerous Substances Inventory sites	0	0	1	0
2.1.5 Records of List 2 Dangerous Substances Inventory sites	0	0	1	0
2.1.6 Records of Part A(2) and Part B Activities and Enforcements	0	0	2	3
2.1.7 Records of Category 3 or 4 Radioactive Substances Authorisations	0	0	0	0
2.1.8 Records of Licensed Discharge Consents	0	1	3	6
2.1.9 Records of Water Industry Referrals	0	0	0	0
2.1.10 Records of Planning Hazardous Substance Consents and Enforcements within 500m of the study site	1	0	0	1
2.2 Records of COMAH and NIHHS sites	0	3	2	2
2.3 Environment Agency/Natural Resources Wales Recorded Pollution Incidents				
2.3.1 National Incidents Recording System, List 2	1	1	0	0
2.3.2 National Incidents Recording System, List 1	0	1	0	0
2.4 Sites Determined as Contaminated Land under Part 2A EPA 1990	0	0	0	0

Section 3: Landfill and Other Waste Sites	On-site	0-50m	51-250	251-500	501-1000	1000-1500
3.1 Landfill Sites						
3.1.1 Environment Agency/Natural Resources Wales Registered Landfill Sites	0	0	0	0	0	Not searched
3.1.2 Environment Agency/Natural Resources Wales Historic Landfill Sites	0	0	1	0	6	8
3.1.3 BGS/DoE Landfill Site Survey	0	0	0	0	0	0
3.1.4 Records of Landfills in Local Authority and Historical Mapping Records	0	0	0	0	0	0
3.2 Landfill and Other Waste Sites Findings						
3.2.1 Operational and Non-Operational Waste Treatment, Transfer and Disposal Sites	0	0	0	0	Not searched	Not searched
3.2.2 Environment Agency/Natural Resources Wales Licensed Waste Sites	0	0	0	1	2	8

Section 4: Current Land Use	On-site	0-50m	51-250	251-500
4.1 Current Industrial Sites Data	4	1	10	Not searched
4.2 Records of Petrol and Fuel Sites	0	0	0	0
4.3 National Grid Underground Electricity Cables	0	0	0	0
4.4 National Grid Gas Transmission Pipelines	0	0	0	0

Section 5: Geology	
5.1 Records of Artificial Ground and Made Ground present beneath the study site	None identified
5.2 Records of Superficial Ground and Drift Geology present beneath the study site	Identified
5.3 For records of Bedrock and Solid Geology beneath the study site see the detailed findings section.	

Section 6: Hydrogeology and Hydrology	On-site	0-50m	51-250	251-500	501-1000	1000-2000
0-500m						
6.1 Records of Strata Classification in the Superficial Geology within 500m of the study site				Identified		
6.2 Records of Strata Classification in the Bedrock Geology within 500m of the study site				Identified		
6.3 Groundwater Abstraction Licences (within 2000m of the study site)	0	0	0	0	10	6
6.4 Surface Water Abstraction Licences (within 2000m of the study site)	0	0	0	0	0	1
6.5 Potable Water Abstraction Licences (within 2000m of the study site)	0	0	0	0	0	0
6.6 Source Protection Zones (within 500m of the study site)	1	0	0	0	Not searched	Not searched
6.7 Source Protection Zones within Confined Aquifer	0	0	0	0	Not searched	Not searched
6.8 Groundwater Vulnerability and Soil Leaching Potential (within 500m of the study site)	1	0	0	1	Not searched	Not searched

Section 6: Hydrogeology and Hydrology

0-500m

	On-site	0-50m	51-250	251-500	501-1000	1000-1500
6.9 Environment Agency/Natural Resources Wales information on river quality within 1500m of the study site	No	No	No	No	No	No
6.10 Ordnance Survey MasterMap Water Network entries within 500m of the site	18	34	62	116	Not searched	Not searched
6.11 Surface water features within 250m of the study site	Yes	Yes	Yes	Not searched	Not searched	Not searched

Section 7: Flooding

7.1 Environment Agency Zone 2 floodplains within 250m of the study site	Identified
7.2 Environment Agency/Natural Resources Wales Zone 3 floodplains within 250m of the study site	Identified
7.3 Risk of flooding from Rivers and the Sea (RoFRaS) rating for the study site	Very Low
7.4 Flood Defences within 250m of the study site	None identified
7.5 Areas benefiting from Flood Defences within 250m of the study site	None identified
7.6 Areas used for Flood Storage within 250m of the study site	None identified
7.7 Maximum BGS Groundwater Flooding susceptibility within 50m of the study site	Potential at Surface
7.8 BGS confidence rating for the Groundwater Flooding susceptibility areas	High

Section 8: Designated Environmentally Sensitive Sites

	On-site	0-50m	51-250	251-500	501-1000	1000-2000
8.1 Records of Sites of Special Scientific Interest (SSSI)	0	0	0	0	0	4
8.2 Records of National Nature Reserves (NNR)	0	0	0	0	0	0
8.3 Records of Special Areas of Conservation (SAC)	0	0	0	0	0	1
8.4 Records of Special Protection Areas (SPA)	0	0	0	0	0	1
8.5 Records of Ramsar sites	0	0	0	0	0	1
8.6 Records of Ancient Woodlands	0	0	0	0	0	0
8.7 Records of Local Nature Reserves (LNR)	0	0	0	0	0	0
8.8 Records of World Heritage Sites	0	0	0	0	0	0
8.9 Records of Environmentally Sensitive Areas	0	0	0	0	0	0

Section 8: Designated Environmentally Sensitive Sites	On-site	0-50m	51-250	251-500	501-1000	1000-2000
8.10 Records of Areas of Outstanding Natural Beauty (AONB)	0	0	0	0	0	0
8.11 Records of National Parks	0	0	0	0	0	0
8.12 Records of Nitrate Sensitive Areas	0	0	0	0	0	0
8.13 Records of Nitrate Vulnerable Zones	1	0	1	0	0	1
8.14 Records of Green Belt land	0	0	0	0	0	0

Section 9: Natural Hazards

9.1 Maximum risk of natural ground subsidence	Moderate
9.1.1 Maximum Shrink-Swell hazard rating identified on the study site	Low
9.1.2 Maximum Landslides hazard rating identified on the study site	Very Low
9.1.3 Maximum Soluble Rocks hazard rating identified on the study site	Negligible
9.1.4 Maximum Compressible Ground hazard rating identified on the study site	Moderate
9.1.5 Maximum Collapsible Rocks hazard rating identified on the study site	Very Low
9.1.6 Maximum Running Sand hazard rating identified on the study site	Moderate
9.2 Radon	
9.2.1 Is the property in a Radon Affected Area as defined by the Health Protection Agency (HPA) and if so what percentage of homes are above the Action Level?	The site is not in a Radon Affected Area, as less than 1% of properties are above the Action Level.
9.2.2 Is the property in an area where Radon Protection are required for new properties or extensions to existing ones as described in publication BR211 by the Building Research Establishment?	No radon protective measures are necessary.

Section 10: Mining

10.1 Coal mining areas within 75m of the study site	None identified
10.2 Non-Coal Mining areas within 50m of the study site boundary	None identified
10.3 Brine affected areas within 75m of the study site	None identified

Using this report

The following report is designed by Environmental Consultants for Environmental Professionals bringing together the most up-to-date market leading environmental data. This report is provided under and subject to the Terms & Conditions agreed between Groundsure and the Client. The document contains the following sections:

1. Historical Industrial Sites

Provides information on past land uses that may pose a risk to the study site in terms of potential contamination from activities or processes. Potentially Infilled Land features are also included. This search is conducted using radii of up to 500m.

2. Environmental Permits, Incidents and Registers

Provides information on Regulated Industrial Activities and Pollution Incidents as recorded by Regulatory Authorities, and sites determined as Contaminated Land. This search is conducted using radii up to 500m.

3. Landfills and Other Waste Sites

Provides information on landfills and other waste sites that may pose a risk to the study site. This search is conducted using radii up to 1500m.

4. Current Land Uses

Provides information on current land uses that may pose a risk to the study site in terms of potential contamination from activities or processes. These searches are conducted using radii of up to 500m. This includes information on potentially contaminative industrial sites, petrol stations and fuel sites as well as high pressure gas pipelines and underground electricity transmission lines.

5. Geology

Provides information on artificial and superficial deposits and bedrock beneath the study site.

6. Hydrogeology and Hydrology

Provides information on productive strata within the bedrock and superficial geological layers, abstraction licenses, Source Protection Zones (SPZs) and river quality. These searches are conducted using radii of up to 2000m.

7. Flooding

Provides information on river and coastal flooding, flood defences, flood storage areas and groundwater flood areas. This search is conducted using radii of up to 250m.

8. Designated Environmentally Sensitive Sites

Provides information on the Sites of Special Scientific Interest (SSSI), National Nature Reserves (NNR), Special Areas of Conservation (SAC), Special Protection Areas (SPA), Ramsar sites, Local Nature Reserves (LNR), Areas of Outstanding Natural Beauty (AONB), National Parks (NP), Environmentally Sensitive Areas, Nitrate Sensitive Areas, Nitrate Vulnerable Zones and World Heritage Sites and Scheduled Ancient Woodland. These searches are conducted using radii of up to 2000m.

9. Natural Hazards

Provides information on a range of natural hazards that may pose a risk to the study site. These factors include natural ground subsidence and radon..

10. Mining

Provides information on areas of coal and non-coal mining and brine affected areas.

11. Contacts

This section of the report provides contact points for statutory bodies and data providers that may be able to provide further information on issues raised within this report. Alternatively, Groundsure provide a free Technical Helpline (08444 159000) for further information and guidance.


Note: Maps

Only certain features are placed on the maps within the report. All features represented on maps found within this search are given an identification number. This number identifies the feature on the mapping and correlates it to the additional information provided below. This identification number precedes all other information and takes the following format -Id: 1, Id: 2, etc. Where numerous features on the same map are in such close proximity that the numbers would obscure each other a letter identifier is used instead to represent the features. (e.g. Three features which overlap may be given the identifier "A" on the map and would be identified separately as features 1A, 3A, 10A on the data tables provided).

Where a feature is reported in the data tables to a distance greater than the map area, it is noted in the data table as "Not Shown".

All distances given in this report are in Metres (m). Directions are given as compass headings such as N: North, E: East, NE: North East from the nearest point of the study site boundary.

1. Historical Land Use



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



1. Historical Industrial Sites

1.1 Potentially Contaminative Uses identified from 1:10,000 scale Mapping

The systematic analysis of data extracted from standard 1:10,560 and 1:10,000 scale historical maps provides the following information:

Records of sites with a potentially contaminative past land use within 500m of the search boundary: 73

ID	Distance [m]	Direction	Use	Date
1A	23	SW	Railway Sidings	1983
2A	23	SW	Railway Sidings	1974
3B	33	S	Unspecified Commercial/Industrial	1983
4B	33	S	Unspecified Commercial/Industrial	1974
5C	47	NW	Oil Refinery	1983
6C	47	NW	Oil Refinery	1974
7D	73	SE	Unspecified Warehouses	1983
8D	73	SE	Unspecified Depot	1974
9AJ	83	W	Unspecified Heap	1983
10AK	185	W	Unspecified Heap	1983
11AC	188	NW	Unspecified Tank	1983
12E	236	SW	Cuttings	1930
13E	237	SW	Cuttings	1947
14AE	237	W	Unspecified Tanks	1983
15F	241	SW	Cuttings	1947
16F	244	SW	Cuttings	1951
17F	248	SW	Cuttings	1968
18G	248	SW	Cuttings	1983
19G	248	SW	Cuttings	1974
20AF	263	NW	Unspecified Tanks	1983
21H	266	SW	Unspecified Tank	1983
22H	266	SW	Unspecified Tank	1974
23I	267	SW	Unspecified Tank	1974
24I	267	SW	Unspecified Tank	1983
25I	282	SW	Unspecified Tank	1983
26I	282	SW	Unspecified Tank	1974
27J	310	NW	Unspecified Tanks	1983
28J	310	NW	Unspecified Tanks	1974
29AG	323	NW	Unspecified Tanks	1983
30K	331	S	Unspecified Commercial/Industrial	1983
31K	331	S	Unspecified Commercial/Industrial	1974
32L	353	SE	Unspecified Depot	1974

33L	353	SE	Unspecified Depot	1983
34M	354	NW	Unspecified Tanks	1983
35M	354	NW	Unspecified Tanks	1974
36N	363	NW	Unspecified Tanks	1974
37N	363	NW	Unspecified Tanks	1983
38O	364	S	Unspecified Tanks	1983
39O	364	S	Unspecified Tanks	1974
40P	365	NW	Unspecified Tanks	1974
41P	365	NW	Unspecified Tanks	1983
42Q	383	W	Unspecified Tanks	1974
43Q	383	W	Unspecified Tanks	1983
44R	395	S	Unspecified Tanks	1983
45R	395	S	Unspecified Tanks	1974
46AL	396	SE	Dock	1968
47V	411	SE	Docks	1951
48S	416	SE	Dock	1947
49S	416	SE	Unspecified Commercial/Industrial	1947
50S	416	SE	Dock	1947
51	416	SE	Railway Sidings	1947
52	421	SE	Railway Sidings	1968
53T	425	SW	Unspecified Tanks	1983
54T	425	SW	Unspecified Tanks	1974
55U	429	SW	Unspecified Tanks	1983
56U	429	SW	Unspecified Tanks	1974
57V	436	SE	Railway Sidings	1951
58W	436	SE	Railway Sidings	1983
59W	436	SE	Railway Sidings	1974
60	436	SE	Railway Sidings	1930
61AH	439	W	Unspecified Tanks	1983
62F	461	W	Cuttings	1974
63F	461	W	Cuttings	1983
64X	475	NW	Unspecified Tanks	1974
65X	475	NW	Unspecified Tanks	1983
66Y	475	S	Unspecified Tanks	1983
67Y	475	S	Unspecified Tanks	1974
68Z	481	NW	Unspecified Tanks	1983
69Z	482	NW	Unspecified Tank	1974
70AA	499	SW	Unspecified Tanks	1983
71AA	499	SW	Unspecified Tanks	1974
72AB	500	SW	Unspecified Tank	1983
73AB	500	SW	Unspecified Tank	1974

1.2 Additional Information – Historical Tank Database

The systematic analysis of data extracted from High Detailed 1:1,250 and 1:2,500 scale historical maps provides the following information.

Records of historical tanks within 500m of the search boundary:

45

ID	Distance (m)	Direction	Use	Date
74	117	SW	Tanks	1972
75AD	171	SW	Tanks	1972
76AC	190	NW	Unspecified Tank	1985
77AD	201	SW	Tanks	1972
78AE	237	W	Tanks	1985
79H	258	SW	Unspecified Tank	1972
80I	263	SW	Tanks	1972
81AF	263	NW	Tanks	1985
82J	308	NW	Tanks	1970
83	320	SW	Unspecified Tank	1972
84AG	324	NW	Tanks	1985
85M	352	NW	Tanks	1985
86M	353	NW	Tanks	1970
87P	362	NW	Tanks	1985
88N	363	NW	Tanks	1985
89P	363	NW	Tanks	1970
90N	364	NW	Tanks	1970
91O	367	S	Tanks	1972
92O	372	S	Tanks	1972
93Q	381	W	Tanks	1985
94Q	381	W	Tanks	1970
95R	395	S	Tanks	1972
96Q	398	W	Tanks	1970
97O	401	S	Tanks	1972
98Q	401	W	Tanks	1970
99O	405	S	Tanks	1972
100	406	SW	Unspecified Tank	1972
101Q	410	W	Tanks	1983
102Q	411	W	Tanks	1969
103R	413	S	Tanks	1972
104T	421	SW	Tanks	1972
105U	423	SW	Tanks	1972
106AH	440	W	Tanks	1983
107	441	SW	Tanks	1972
108	445	SW	Tanks	1972
109	462	S	Tanks	1972
110X	468	NW	Tanks	1985

111X	470	NW	Tanks	1970
112	472	SW	Unspecified Tank	1972
113Z	478	NW	Tanks	1985
114Y	479	S	Tanks	1972
115Z	480	NW	Tanks	1970
116AA	495	SW	Tanks	1972
117AB	496	SW	Tanks	1972
118	497	SW	Tanks	1972

1.3 Additional Information – Historical Energy Features Database

The systematic analysis of data extracted from High Detailed 1:1,250 and 1:2,500 scale historical maps provides the following information.

Records of historical energy features within 500m of the search boundary: 4

ID	Distance (m)	Direction	Use	Date
119AI	399	SE	Electricity Substation	1982
120AI	399	SE	Electricity Substation	1982
121AI	399	SE	Electricity Substation	1972
122AI	400	SE	Electricity Substation	1972

1.4 Additional Information – Historical Petrol and Fuel Site Database

The systematic analysis of data extracted from High Detailed 1:1,250 and 1:2,500 scale historical maps provides the following information.

Records of historical petrol stations and fuel sites within 500m of the search boundary: 0

Database searched and no data found.

1.5 Additional Information – Historical Garage and Motor Vehicle Repair Database

The systematic analysis of data extracted from High Detailed 1:1,250 and 1:2,500 scale historical maps provides the following information.

Records of historical garage and motor vehicle repair sites within 500m of the search boundary: 0

Database searched and no data found.


1.6 Potentially Infilled Land

Records of Potentially Infilled Features from 1:10,000 scale mapping within 500m of the study site: 15
















The following Historical Potentially Infilled Features derived from the Historical Mapping information is provided by Groundsure:

ID	Distance(m)	Direction	Use	Date
123AJ	83	W	Unspecified Heap	1983
124AK	185	W	Unspecified Heap	1983
125E	236	SW	Cuttings	1930
126E	237	SW	Cuttings	1947
127F	241	SW	Cuttings	1947
128F	244	SW	Cuttings	1951
129F	248	SW	Cuttings	1968
130G	248	SW	Cuttings	1974
131G	248	SW	Cuttings	1983
132AL	396	SE	Dock	1968
133V	411	SE	Docks	1951
134S	416	SE	Dock	1947
135S	416	SE	Dock	1947
136F	461	W	Cuttings	1974
137F	461	W	Cuttings	1983

2. Environmental Permits, Incidents and Registers Map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.

- | | | | | | |
|---|--------------------|---|-------------------------------|---|--|
|  | Site Outline |  | Recorded Pollution Incident |  | RAS 3 & 4 Authorisations |
|  | Search Buffers (m) |  | Dangerous Substances (List 1) |  | Part A(1) Authorised Processes and Historic IPC Authorisations |
|  | 250 |  | Dangerous Substances (List 2) |  | Part A(2) and Part B Authorised Processes |
|  | 500 |  | Water Industry Referrals |  | COMAH / NIHHS Sites |
| | |  | Licenced Discharge Consents |  | Sites Determined as Contaminated Land |
| | |  | Red List Discharge Consents |  | Hazardous Substance Consents and Enforcements |

2. Environmental Permits, Incidents and Registers

2.1 Industrial Sites Holding Licences and/or Authorisations

Searches of information provided by the Environment Agency/Natural Resources Wales and Local Authorities reveal the following information:

2.1.1 Records of historic IPC Authorisations within 500m of the study site:

0

Database searched and no data found.

2.1.2 Records of Part A(1) and IPPC Authorised Activities within 500m of the study site:

9

The following Part A(1) and IPPC Authorised Activities are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
39C	0	On Site	516500 417000	Operator: Vpi Immingham Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW Permit Number: YP3837GD Original Permit Number: BJ8022IZ EPR Reference: EA/EPR/BJ8022IZ/V002 Issue Date: 4/6/2009 Effective Date: 4/6/2009 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded
40C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW Permit Number: BJ8022IZ Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 16/8/2001 Effective Date: 16/8/2001 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded
41C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW Permit Number: NP3339LK Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 30/4/2007 Effective Date: 30/4/2007 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded

ID	Distance (m)	Direction	NGR	Details	
42C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: - Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: BU6140 Original Permit Number: BJ8022 EPR Reference: - Issue Date: 1-5-2003 0:00:00 Effective Date: 1-5-2003 0:00:00 Last date noted as effective: 2004-10-01 Status: Superseded By Pas
43C	0	On Site	516500 417000	Operator: Vpi Immingham Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: XP3732RA Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 29/12/2015 Effective Date: 1/1/2016 00:00:00 Last date noted as effective: 2018-03-01 Status: Effective
44C	0	On Site	516500 417000	Operator: Vpi Immingham Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: PP3432WT Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 14/11/2014 Effective Date: 14/11/2014 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded
45C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: - Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: BJ8022 Original Permit Number: BJ8022 EPR Reference: - Issue Date: 16-8-2001 0:00:00 Effective Date: 16-8-2001 0:00:00 Last date noted as effective: 2005-10-03 Status: Superseded By Variation
46C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: NP3130BP Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 28/10/2004 Effective Date: 28/10/2004 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded
47C	0	On Site	516500 417000	Operator: Immingham Chp Llp Installation Name: Immingham Chp Power Station Epr/bj8022iz Process: COMBUSTION; ANY FUEL =>50MW	Permit Number: BU6140IT Original Permit Number: BJ8022IZ EPR Reference: - Issue Date: 1/5/2003 Effective Date: 1/5/2003 00:00:00 Last date noted as effective: 2018-03-01 Status: Superseded

2.1.3 Records of Red List Discharge Consents (potentially harmful discharges to controlled waters) within 500m of the study site:

0

Database searched and no data found.

2.1.4 Records of List 1 Dangerous Substances Inventory Sites within 500m of the study site:

1

The following List 1 Dangerous Substance Inventory Site records are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
4A	75	SW	516600 416800	Name: Conoco Main O/f Killingholme Status: Not Active Receiving Water: River Humber, South Killingholme Drain, R. Humber Authorised Substances: Mercury (other), Cadmium

2.1.5 Records of List 2 Dangerous Substance Inventory Sites within 500m of the study site:

1

The following List 2 Dangerous Substance Inventory Site records are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
5A	75	SW	516600 416800	Name: Conoco Main O/f Killingholme Status: Active Receiving Water: S Kill.drn.rosper Road Authorised Substances: Arsenic, Chromium, Copper, Lead, Nickel, Zinc

2.1.6 Records of Part A(2) and Part B Activities and Enforcements within 500m of the study site:

5

The following Part A(2) and Part B Activities are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
25	245	SE	516826 416655	Address: Phillips 66 Limited, Unit 1, Humber Road, South Killingholme, DN40 3DU Process: Coal & Coke Status: Current Permit Permit Type: Part B Enforcement: No Enforcements Notified Date of Enforcement: No Enforcements Notified Comment: No Enforcements Notified

ID	Distance (m)	Direction	NGR	Details
26D	245	SE	516867 416691	Address: P. D. Port Services Ltd, Unit 2, Humber Road, Immingham, North East Lincolnshire, DN40 3DU Process: Coal & Coke Status: Current Permit Permit Type: Part B Enforcement: No Enforcements Notified Date of Enforcement: No Enforcements Notified Comment: No Enforcements Notified
27D	258	SE	516866 416671	Address: P D Port Services Limited, Unit 2, Humber Road, South Killingholme, DN40 3DU Process: Coal and Coke Status: Historical Permit Permit Type: Part B Enforcement: No Enforcements Notified Date of Enforcement: No Enforcements Notified Comment: No Enforcements Notified
28	321	SE	516947 416671	Address: P D Port Services Limited, Unit 1, Humber Road, South Killingholme, DN40 3DU Process: Coal and Coke Status: Historical Permit Permit Type: Part B Enforcement: No Enforcements Notified Date of Enforcement: No Enforcements Notified Comment: No Enforcements Notified
29	451	SW	516336 416511	Address: Longs Steel (UK) Limited, Humber Road, South Killingholme, DN40 3DY Process: Coal & Coke Status: Current Permit Permit Type: Part A2 Enforcement: No Enforcements Notified Date of Enforcement: No Enforcements Notified Comment: No Enforcements Notified

2.1.7 Records of Category 3 or 4 Radioactive Substances Authorisations:

0

Database searched and no data found.

2.1.8 Records of Licensed Discharge Consents within 500m of the study site:

10

The following Licensed Discharge Consents records are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
6	42	NW	516470 417230	Address: THE INTERCEPTOR, LINDSEY OIL REFINERY, KILLINGHOLME, GRIMSBY. Effluent Type: TRADE DISCHARGES - UNSPECIFIED Permit Number: PR3NFF1242 Permit Version: 1 Receiving Water: South Killingholme Main Drain Status: PRE NRA LEGISLATION WHERE ISSUE DATE < 01-SEP-89 (HISTORIC ONLY) Issue date: 06/11/1979 Effective Date: 06-Nov-1979 Revocation Date: 10/01/1994
7A	75	SW	516600 416800	Address: AT HUMBER REFINERY, SOUTH KILLINGHOLME, SOUTH HUMBERSIDE Effluent Type: TRADE DISCHARGES - UNSPECIFIED Permit Number: PR3NFF855B Permit Version: 2 Receiving Water: South Killingholme Main Drain Status: POST NRA LEGISLATION WHERE ISSUE DATE > 31-AUG-89 (HISTORIC ONLY) Issue date: 08/05/1991 Effective Date: 08-May-1991 Revocation Date: 24/03/1994

ID	Distance (m)	Direction	NGR	Details	
8A	75	SW	516600 416800	Address: AT HUMBER REFINERY, SOUTH KILLINGHOLME, SOUTH HUMBERSIDE Effluent Type: TRADE DISCHARGES - UNSPECIFIED Permit Number: PR3NFF855B Permit Version: 1	Receiving Water: Trib South Killingholme Drain Status: PRE NRA LEGISLATION WHERE ISSUE DATE < 01-SEP-89 (HISTORIC ONLY) Issue date: 16/11/1983 Effective Date: 16-Nov-1983 Revocation Date: 07/05/1991
9	248	NW	516576 417535	Address: LINDSEY OIL REFINERY, LINDSEY OIL REFINERY, NORTH KILLINGHOLME, IMMINGHAM, NORTH LINCOLNSHIRE, DN40 3LW Effluent Type: SEWAGE DISCHARGES - FINAL/TREATED EFFLUENT - NOT WATER COMPANY Permit Number: EPRVP3424XR Permit Version: 1	Receiving Water: TRIB OF RIVER HUMBER Status: NEW ISSUED UNDER EPR 2010 Issue date: 05/09/2012 Effective Date: 05-Sep-2012 Revocation Date: -
10	406	SE	517000 416600	Address: COMMON PUMP STATION, SOUTH KILLINGHOLME, IMMINGHAM, DN40 Effluent Type: TRADE DISCHARGES - UNSPECIFIED Permit Number: PR3NFF782 Permit Version: 1	Receiving Water: unknown Trib Status: PRE NRA LEGISLATION WHERE ISSUE DATE < 01-SEP-89 (HISTORIC ONLY) Issue date: 18/09/1969 Effective Date: 18-Sep-1969 Revocation Date: 30/09/1993
11	446	SE	517300 416750	Address: NEW IMMINGHAM WEST FIRESTATION, ROSPER ROAD, IMMINGHAM, N. LINCOLNSHIRE, DN40 3DZ Effluent Type: SEWAGE DISCHARGES - FINAL/TREATED EFFLUENT - NOT WATER COMPANY Permit Number: PRNNF12221 Permit Version: 1	Receiving Water: SOUTH KILLINGHOLME MAIN DRAIN Status: NEW CONSENT (WRA 91, S88 & SCHED 10 AS AMENDED BY ENV ACT 1995) Issue date: 24/08/1999 Effective Date: 26-Nov-1998 Revocation Date: -
12B	482	SE	517320 416720	Address: MANBY ROAD IMMINGHAM, NEW OFFICES MANBY ROAD, SOUTH KILLINGHOLME, IMMINGHAM, DN40 3EG Effluent Type: SEWAGE DISCHARGES - FINAL/TREATED EFFLUENT - NOT WATER COMPANY Permit Number: PR3NFF1093 Permit Version: 3	Receiving Water: A DRAIN Status: VARIED BY APPLICATION - (WRA 91 SCHED 10 - AS AMENDED BY ENV ACT 1995) Issue date: 27/03/2000 Effective Date: 26-Jul-2000 Revocation Date: -
13B	482	SE	517320 416720	Address: MANBY ROAD IMMINGHAM, NEW OFFICES MANBY ROAD, SOUTH KILLINGHOLME, IMMINGHAM, DN40 3EG Effluent Type: MISCELLANEOUS DISCHARGES - SURFACE WATER Permit Number: PR3NFF1095 Permit Version: 1	Receiving Water: Unknown Trib Status: PRE NRA LEGISLATION WHERE ISSUE DATE < 01-SEP-89 (HISTORIC ONLY) Issue date: 17/07/1974 Effective Date: 17-Jul-1974 Revocation Date: 11/02/1992
14B	482	SE	517320 416720	Address: MANBY ROAD IMMINGHAM, NEW OFFICES MANBY ROAD, SOUTH KILLINGHOLME, IMMINGHAM, DN40 3EG Effluent Type: SEWAGE DISCHARGES - FINAL/TREATED EFFLUENT - NOT WATER COMPANY Permit Number: PR3NFF1093 Permit Version: 1	Receiving Water: Unknown Trib Status: PRE NRA LEGISLATION WHERE ISSUE DATE < 01-SEP-89 (HISTORIC ONLY) Issue date: 17/07/1974 Effective Date: 17-Jul-1974 Revocation Date: 03/02/1992
15B	482	SE	517320 416720	Address: MANBY ROAD IMMINGHAM, NEW OFFICES MANBY ROAD, SOUTH KILLINGHOLME, IMMINGHAM, DN40 3EG Effluent Type: SEWAGE DISCHARGES - FINAL/TREATED EFFLUENT - NOT WATER COMPANY Permit Number: PR3NFF1093 Permit Version: 2	Receiving Water: into drain Status: POST NRA LEGISLATION WHERE ISSUE DATE > 31-AUG-89 (HISTORIC ONLY) Issue date: 04/02/1992 Effective Date: 04-Feb-1992 Revocation Date: 25/07/2000

2.1.9 Records of Water Industry Referrals (potentially harmful discharges to the public sewer) within 500m of the study site:

0

Database searched and no data found.

2.1.10 Records of Planning Hazardous Substance Consents and Enforcements within 500m of the study site:

2

The following records are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	Application Reference Number	NGR	Application Status	Application Date	Address	Details	Details of Enforcement Action
48E	0	On Site	PA/2008/1704	516464417147	Approved	02/03/2009	VPI Immingham LLP (PKA Immingham CHP Plant) Combined Heat & Power Plant, Rosper Road, South Killingholme, DN40 3DZ	Hazardous Substances Consent to store 3050 tonnes of petroleum gas oil.	Enforcement: No Enforcements Notified Date of Enforcement: No Enforcement Notified Comment: No Enforcement Notified
49F	280	SE	7/1992/0508	516910416690	Approved	13/08/1992	Humberside Sea & Land Services Ltd, Units 1 And 2 Humber Road, South Killingholme, DN40 3DU	Ammonium Nitrate based fertilizer. Max quantity present during established period - 35000 tonnes. Established quantity - 52,500 tonnes	Enforcement: No Enforcements Notified Date of Enforcement: No Enforcement Notified Comment: No Enforcement Notified

2.2 Dangerous or Hazardous Sites

Records of COMAH & NIHHS sites within 500m of the study site:

7

The following COMAH & NIHHS Authorisation records provided by the Health and Safety Executive are represented as polygons or buffered points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	Company	Address	Operational Status	Tier
30	6	NW	VPA Immingham LLP	VPI Immingham LLP, Immingham CHP LLP, Rosper Road, Immingham, Grimsby, North East Lincolnshire, DN40 3DZ	Current COMAH Site	COMAH Lower Tier Operator

ID	Distance (m)	Direction	Company	Address	Operational Status	Tier
31	28	NW	Total Lindsey Oil Refinery Limited	Total Lindsey Oil Refinery Limited, Lindsey Oil Refinery, HQ/Total Lindsey, Eastfield Road, Immingham, North East Lincolnshire, DN40 3LW	Current COMAH Site	COMAH Upper Tier Operator
32	37	S	Phillips 66 Limited	Phillips 66 Limited, Humber Refinery, Humber Refinery, Eastfield Road, Grimsby, North Lincolnshire, DN40 3DW	Current COMAH Site	COMAH Upper Tier Operator
33	91	S	Conoco Manufacturing Ltd	Conoco Manufacturing Ltd, South Tank Farm, South Killingholme, Immingham	Historical NIHHS Site	-
34	120	S	Humberside Sea&land Services Ltd	Humberside Sea&land Services Ltd, Units1&2, Humber Road, South KillINngholme	Historical NIHHS Site	-
35	311	NE	Humber Lpg Terminal Ltd	Humber Lpg Terminal Ltd, Marsh Lane, South Killingholme, DN40 3ED	Historical COMAH Site	-
36	409	SE	Associated British Ports	Associated British Ports, Immingham Dock, Immingham, Lincolnshire, DN40 2NS	Current COMAH Site	COMAH Upper Tier Operator

2.3 Environment Agency/Natural Resources Wales Recorded Pollution Incidents

2.3.1 Records of National Incidents Recording System, List 2 within 500m of the study site:

2

The following NIRS List 2 records are represented as points on the Environmental Permits, Incidents and Registers Map:

ID	Distance (m)	Direction	NGR	Details
1	0	On Site	516670 417170	Incident Date: 03-Oct-2002 Incident Identification: 112451 Pollutant: Atmospheric Pollutants and Effects Pollutant Description: Smoke Water Impact: Category 4 (No Impact) Land Impact: Category 4 (No Impact) Air Impact: Category 3 (Minor)
2	22	S	516579 416873	Incident Date: 13-Dec-2004 Incident Identification: 282826 Pollutant: Oils and Fuel Pollutant Description: Crude Oil Water Impact: Category 2 (Significant) Land Impact: Category 3 (Minor) Air Impact: Category 3 (Minor)

2.3.2 Records of National Incidents Recording System, List 1 within 500m of the study site:

1

The following NIRS List 1 records are represented as points on the Environmental Permits, Incidents and Registers Map:


ID	Distance(m)	Direction	NGR	Details
3	15	S		Incident Date: 29-Jul-2000 Incident Identification: 7235.0 Catchments Name: SKITTER BECK (IMMINGHAM) Water Description: RIVER STRETCH (FRESHWATER) Water Course: EAST HALTON BECK Incident Substantiated: Yes Priority Description: Immediate (2 Hours) Waste Description: Not Available Water Impact: Major (Persistent, Extensive) Impact Land Impact: Minor Impact Air Impact: No Impact Action Taken: Prosecution

2.4 Sites Determined as Contaminated Land under Part 2A EPA 1990










Records of sites determined as contaminated land under Section 78R of the Environmental Protection Act 1990 are there within 500m of the study site 0

Database searched and no data found.

3. Landfill and Other Waste Sites Map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.

- | | | | | | |
|---|------------------------|---|---------------------------|---|---|
|  | Site Outline |  | EA/NRW Active Landfill |  | Historic and Planned Waste Sites |
|  | 250 Search Buffers (m) |  | EA/NRW Historic Landfill |  | EA/NRW Licensed Waste Site |
|  | 500 Search Buffers (m) |  | BGS / DoE Survey Landfill |  | Local Authority/Historical Mapping Landfill Records |

3. Landfill and Other Waste Sites

3.1 Landfill Sites

3.1.1 Records from Environment Agency/Natural Resources Wales landfill data within 1000m of the study site:

0

Database searched and no data found.

3.1.2 Records of Environment Agency/Natural Resources Wales historic landfill sites within 1500m of the study site:

15

The following landfill records are represented as either points or polygons on the Landfill and Other Waste Sites map:

ID	Distance (m)	Direction	NGR	Details	
1	115	NW	516400 417500	Site Address: Lindsey Oil Refinery, Rosper Road Waste Licence: Yes Site Reference: 55/19/0767, 2000/5298 Waste Type: Liquid sludge Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 06-Nov-1985 Licence Surrendered: Licence Holder Address: - Operator: Lindsey Oils Licence Holder: - First Recorded: 31-Dec-1986 Last Recorded: -
2	566	SE	517600 416500	Site Address: Landfill Site - South Killingholme, Humber Road, Grimsby, Lincolnshire Waste Licence: Yes Site Reference: - Waste Type: Industrial Environmental Permitting Regulations (Waste) Reference: YP2/L/POR001	Licence Issue: 08-Oct-1991 Licence Surrendered: 06-Nov-2007 Licence Holder Address: Moody Lane, Grimsby, Lincolnshire Operator: Landfill Site - South Killingholme Licence Holder: Landfill Site - South Killingholme First Recorded: - Last Recorded: -
3	584	SE	516900 416200	Site Address: Conoco, Killingholme Waste Licence: Yes Site Reference: 55/19/0148, 1480, 2000/5296 Waste Type: Industrial, Liquid sludge Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 10-Dec-1987 Licence Surrendered: Licence Holder Address: - Operator: - Licence Holder: - First Recorded: 31-Jul-1975 Last Recorded: -

ID	Distance (m)	Direction	NGR	Details	
4	687	E	517900 417200	Site Address: Marsh Lane, South Killingholme Waste Licence: Yes Site Reference: A553, 55/19/0553 Waste Type: Inert Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 23-Oct-1984 Licence Surrendered: 31-Dec-1987 Licence Holder Address: Arundel Howe, Stakesby Road, Whitby Operator: Geostore Limited Licence Holder: Geostore Limited First Recorded: 31-Dec-1985 Last Recorded: 31-Dec-1987
5	820	SW	515700 416500	Site Address: South Killingholme Conoco, South Killingholme, North Lincolnshire Waste Licence: - Site Reference: 55/26/809 Waste Type: - Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: Licence Surrendered: Licence Holder Address: - Operator: Conoco Licence Holder: - First Recorded: - Last Recorded: -
Not shown	834	SE	517000 416000	Site Address: Conoco, Killingholme Waste Licence: Yes Site Reference: 55/19/0148, 1480, 2000/5295 Waste Type: Industrial, Liquid sludge Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 18-Dec-1987 Licence Surrendered: Licence Holder Address: - Operator: Conoco Licence Holder: - First Recorded: 30-Jun-1975 Last Recorded: -
7	880	NW	515700 417700	Site Address: Lindsey Oils Site C, North Killingholme, North Lincolnshire Waste Licence: - Site Reference: 55/26/790 Waste Type: - Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: Licence Surrendered: Licence Holder Address: - Operator: Lindsey Oils Licence Holder: - First Recorded: - Last Recorded: -
Not shown	1043	W	515100 416800	Site Address: Eastfield Road Landfill Site, Eastfield Road, South Killingholme Waste Licence: Yes Site Reference: A023, 55/17/0023 Waste Type: Inert, Industrial, Commercial, Household, Special, Liquid sludge Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 01-Dec-1980 Licence Surrendered: 19-Oct-1989 Licence Holder Address: - Operator: Humberside County Council Licence Holder: J W Stanley First Recorded: 01-Dec-1975 Last Recorded: 01-Mar-1988
Not shown	1084	NE	518100 417600	Site Address: Killigholme Haven, Immingham, South Humberside Waste Licence: Yes Site Reference: A553, 55/19/0553 Waste Type: Inert Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 23-Oct-1984 Licence Surrendered: 31-Dec-1987 Licence Holder Address: Arundel Howe, Stakesby Road, Whitby Operator: Geostore Limited Licence Holder: Geostore Limited First Recorded: 31-Dec-1985 Last Recorded: 31-Dec-1987
Not shown	1181	E	518200 417400	Site Address: Marsh Lane, Killingholme Waste Licence: - Site Reference: 55/19/0553 Waste Type: Liquid sludge Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: Licence Surrendered: Licence Holder Address: - Operator: Geostore Limited Licence Holder: - First Recorded: - Last Recorded: -
Not shown	1274	NE	518200 417600	Site Address: Tioxide, South Killingholme Waste Licence: Yes Site Reference: A105, 55/19/0105 Waste Type: Inert, Industrial, Household Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 29-Jun-1977 Licence Surrendered: 24-Feb-1992 Licence Holder Address: Billingham, Cleveland Operator: BTP Tioxide Limited Licence Holder: BTP Tioxide Limited First Recorded: 31-Dec-1961 Last Recorded: 24-Feb-1992

ID	Distance (m)	Direction	NGR	Details	
Not shown	1290	NW	515200 418000	Site Address: Lindsey Oil Refinery Site A and C, Station Road, Thurlby, Bourne Waste Licence: Yes Site Reference: A147, 55/19/0147 Waste Type: Inert, Industrial, Household, Special, Liquid sludge Environmental Permitting Regulations (Waste) Reference: AY1/L/LIN014	Licence Issue: 14-Jun-1977 Licence Surrendered: 15-Jul-1990 Licence Holder Address: - Operator: Lindsey Oil Refinery Licence Holder: Lindsey Oil Refinery Limited First Recorded: 31-Dec-1960 Last Recorded: 31-Dec-1989
Not shown	1319	E	518400 417300	Site Address: Immingham Dock, West Of South Killingholme Haven Waste Licence: Yes Site Reference: A646, 55/19/0646 Waste Type: Inert, Industrial, Commercial, Household Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 20-Jan-1978 Licence Surrendered: 26-Jan-1990 Licence Holder Address: - Operator: British Transport Docks Board Licence Holder: ABP First Recorded: 01-Feb-1978 Last Recorded: 31-Dec-1990
Not shown	1424	E	518500 417400	Site Address: Tioxide, South Killingholme Waste Licence: Yes Site Reference: 55/19/0105, A105 Waste Type: Inert, Industrial Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: 29-Jun-1977 Licence Surrendered: 24-Feb-1992 Licence Holder Address: Billingham, Cleveland Operator: BTP Tioxide Limited Licence Holder: BTP Tioxide Limited First Recorded: 31-Dec-1961 Last Recorded: 24-Feb-1992
Not shown	1445	NW	515500 418400	Site Address: Lindsey Oil Site C, Killingholme Waste Licence: - Site Reference: 55/16/0424 Waste Type: Inert Environmental Permitting Regulations (Waste) Reference: -	Licence Issue: Licence Surrendered: Licence Holder Address: - Operator: - Licence Holder: - First Recorded: - Last Recorded: -

3.1.3 Records of BGS/DoE non-operational landfill sites within 1500m of the study site:

0

Database searched and no data found.

3.1.4 Records of Landfills from Local Authority and Historical Mapping Records within 1500m of the study site:

0

Database searched and no data found.

3.2 Other Waste Sites

3.2.1 Records of waste treatment, transfer or disposal sites within 500m of the study site:

0

Database searched and no data found.

3.2.2 Records of Environment Agency/Natural Resources Wales licensed waste sites within 1500m of the study site:

11


The following waste treatment, transfer or disposal sites records are represented as points on the Landfill and Other Waste Sites map:

ID	Distance (m)	Direction	NGR	Details
16	258	NW	516500 417500	<p>Site Address: Lindsey Oil Refinery Ltd, Lindsey Oil Refinery, South Killingholme, Grimsby, N E Lincs, DN40 3LW Type: Biological Treatment Facility Size: < 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: LIN013 EPR reference: EA/EPR/YP3695NB/S002 Operator: Lindsey Oil Refinery Ltd Waste Management licence No: 70828 Annual Tonnage: 3000.0</p> <p>Issue Date: 06/11/1985 Effective Date: - Modified: - Surrendered Date: 18/10/2006 Expiry Date: - Cancelled Date: - Status: Surrendered Site Name: Licensed Facility At Lindsey Oil Refinery Correspondence Address: -</p>
17A	829	SE	517600 416500	<p>Site Address: Tioxide Europe Ltd, Humber Road, Grimsby, N E Lincs, DN31 2SW Type: Industrial Waste Landfill (Factory curtilage) Size: >= 75000 tonnes Environmental Permitting Regulations (Waste) Licence Number: TIO003 EPR reference: - Operator: Tioxide Europe Ltd Waste Management licence No: 70833 Annual Tonnage: 25000.0</p> <p>Issue Date: 08/10/1991 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued Site Name: Landfill Site - South Killingholme Correspondence Address: Tioxide Europe Ltd, Moody Lane, Grimsby, N E Lincs, DN31 2SW</p>
18A	829	SE	517600 416500	<p>Site Address: Tioxide Europe Ltd, Humber Road, Grimsby, N E Lincs Type: Industrial Waste Landfill (Factory curtilage) Size: < 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: TIO003 EPR reference: EA/EPR/JP3095NJ/A001 Operator: Tioxide Europe Ltd Waste Management licence No: 70833 Annual Tonnage: 475000.0</p> <p>Issue Date: 08/10/1991 Effective Date: - Modified: - Surrendered Date: 06/11/2007 Expiry Date: - Cancelled Date: - Status: Surrendered Site Name: Landfill Site - South Killingholme Correspondence Address: -</p>
Not shown	1076	S	516900 415800	<p>Site Address: Conoco Ltd, Humber Refinery, South Killingholme, Grimsby, North Lincs, DN40 3DW Type: Biological Treatment Facility Size: < 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CON001 EPR reference: EA/EPR/YP3995NG/V003 Operator: Phillips 66 Limited Waste Management licence No: 70818 Annual Tonnage: 0.0</p> <p>Issue Date: 18/12/1987 Effective Date: - Modified: 13/11/2014 Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Closure Site Name: Humber Refinery Correspondence Address: -</p>
Not shown	1076	S	516900 415800	<p>Site Address: Conoco Ltd, Land/ Premises At, Humber Refinery, South Killingholme, Grimsby, N E Lincs, DN40 3DW Type: Biological Treatment Facility Size: < 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: CON001 EPR reference: EA/EPR/YP3995NG/A001 Operator: Conoco Phillips Ltd Waste Management licence No: 70818 Annual Tonnage: 400.0</p> <p>Issue Date: 18/12/1987 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: Issued Site Name: Landfarm - Humber Oil Refinery Correspondence Address: -</p>

ID	Distance (m)	Direction	NGR	Details	
Not shown	1076	S	516900 415800	<p>Site Address: Conoco Ltd, Humber Refinery, South Killingholme, Grimsby, N Lincs, DN40 9DW</p> <p>Type: Biological Treatment Facility</p> <p>Size: < 25000 tonnes</p> <p>Environmental Permitting Regulations (Waste) Licence Number: CON001</p> <p>EPR reference: -</p> <p>Operator: Conoco Ltd</p> <p>Waste Management licence No: 70818</p> <p>Annual Tonnage: 400.0</p>	<p>Issue Date: 18/12/1987</p> <p>Effective Date: -</p> <p>Modified: -</p> <p>Surrendered Date: -</p> <p>Expiry Date: -</p> <p>Cancelled Date: -</p> <p>Status: Issued</p> <p>Site Name: Landfarm - Killingholme Oil Refinery</p> <p>Correspondence Address: Conoco Ltd, Conoco Ltd, Humber Refinery, South Killingholme, Grimsby, N Lincs, DN40 3DW</p>
Not shown	1076	S	516900 415800	<p>Site Address: Conoco Ltd, Humber Refinery, South Killingholme, Grimsby, North Lincs, DN40 3DW</p> <p>Type: Biological Treatment Facility</p> <p>Size: < 25000 tonnes</p> <p>Environmental Permitting Regulations (Waste) Licence Number: CON001</p> <p>EPR reference: EA/EPR/YP3995NG/V002</p> <p>Operator: Phillips 66 Ltd</p> <p>Waste Management licence No: 70818</p> <p>Annual Tonnage: 400.0</p>	<p>Issue Date: 18/12/1987</p> <p>Effective Date: -</p> <p>Modified: 21/08/2012</p> <p>Surrendered Date: -</p> <p>Expiry Date: -</p> <p>Cancelled Date: -</p> <p>Status: Modified</p> <p>Site Name: Humber Refinery</p> <p>Correspondence Address: -</p>
Not shown	1116	W	515300 417000	<p>Site Address: Wastewise Waste Man. Svcs. Ltd, Eastfield Road, South Killingholme, Grimsby, N E Lincs, DN40 3NB</p> <p>Type: Household Waste Amenity Site</p> <p>Size: < 25000 tonnes</p> <p>Environmental Permitting Regulations (Waste) Licence Number: WAS004</p> <p>EPR reference: EA/EPR/RP3394NH/S002</p> <p>Operator: Wastewise Waste Management Services Ltd</p> <p>Waste Management licence No: 72061</p> <p>Annual Tonnage: 20000.0</p>	<p>Issue Date: 07/12/1992</p> <p>Effective Date: -</p> <p>Modified: -</p> <p>Surrendered Date: 20/03/2000</p> <p>Expiry Date: -</p> <p>Cancelled Date: -</p> <p>Status: Surrendered</p> <p>Site Name: South Killingholme C A Site</p> <p>Correspondence Address: -</p>
Not shown	1248	NW	515500 418000	<p>Site Address: Lindsey Oil Refinery, North Killingholme, Immingham, N E Lincs, DN40 3LW</p> <p>Type: Industrial Waste Landfill (Factory curtilage)</p> <p>Size: < 25000 tonnes</p> <p>Environmental Permitting Regulations (Waste) Licence Number: LIN014</p> <p>EPR reference: EA/EPR/YP3095NZ/V005</p> <p>Operator: Total Lindsey Oil Refinery Ltd</p> <p>Waste Management licence No: 70817</p> <p>Annual Tonnage: 24999.0</p>	<p>Issue Date: 14/06/1977</p> <p>Effective Date: -</p> <p>Modified: 04/01/2017</p> <p>Surrendered Date: -</p> <p>Expiry Date: -</p> <p>Cancelled Date: -</p> <p>Status: Modified</p> <p>Site Name: Total Lindsey Oil Refinery</p> <p>Correspondence Address: -</p>
Not shown	1248	NW	515500 418000	<p>Site Address: Lindsey Oil Refinery, North Killingholme, Immingham, N E Lincs, DN40 3LW</p> <p>Type: Industrial Waste Landfill (Factory curtilage)</p> <p>Size: < 25000 tonnes</p> <p>Environmental Permitting Regulations (Waste) Licence Number: LIN014</p> <p>EPR reference: EA/EPR/YP3095NZ/A001</p> <p>Operator: Lindsey Oil Refinery Ltd</p> <p>Waste Management licence No: 70817</p> <p>Annual Tonnage: 25000.0</p>	<p>Issue Date: 14/06/1977</p> <p>Effective Date: -</p> <p>Modified: -</p> <p>Surrendered Date: -</p> <p>Expiry Date: -</p> <p>Cancelled Date: -</p> <p>Status: Issued</p> <p>Site Name: Total Lindsey Oil Refinery</p> <p>Correspondence Address: -</p>

ID	Distance (m)	Direction	NGR	Details	
Not shown	1248	NW	515500 418000	Site Address: Lindsey Oil Refinery, North Killingholme, N Lincolnshire, DN40 3LW Type: Household, Commercial & Industrial Waste Landfill Size: < 25000 tonnes Environmental Permitting Regulations (Waste) Licence Number: IPC024 EPR reference: EA/EPR/CP3892NB/A001 Operator: Lindsey Oil Refinery Ltd Waste Management licence No: 73223 Annual Tonnage: 250000.0	Issue Date: 14/06/1977 Effective Date: - Modified: - Surrendered Date: - Expiry Date: - Cancelled Date: - Status: To PPC Site Name: Lindsey Oil Refinery Site A & C (bw2994in) Correspondence Address: -

4. Current Land Use Map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.

- | | | | | | |
|---|--------------------|---|--------------------------|--|---------------------------------|
|  | Site Outline |  | Current Industrial Sites |  | Electricity Transmission Cables |
|  | Search Buffers (m) |  | Petrol & Fuel Sites |  | Gas Transmission Pipelines |

4. Current Land Uses

4.1 Current Industrial Data

Records of potentially contaminative industrial sites within 250m of the study site: 15

The following records are represented as points on the Current Land Uses map.

ID	Distance (m)	Direction	Company	NGR	Address	Activity	Category
1	0	On Site	Pipeline	516743 417217	DN40	Pipelines	Industrial Features
2	0	On Site	Chimney	516723 417160	DN40	Chimneys	Industrial Features
3	0	On Site	Chimney	516563 417031	DN40	Chimneys	Industrial Features
4	0	On Site	Pipeline	516608 416957	DN40	Pipelines	Industrial Features
5	14	S	Pipelines	516577 416883	DN40	Pipelines	Industrial Features
6	53	NW	Settling Tank	516489 417254	DN40	Waste Storage, Processing and Disposal	Infrastructure and Facilities
7	69	NW	Pylon	516517 417289	DN40	Electrical Features	Infrastructure and Facilities
8	91	NE	Pipeline	516939 417475	DN40	Pipelines	Industrial Features
9	155	SW	Pipeline	516341 416953	DN40	Pipelines	Industrial Features
10	160	NW	Tank	516267 417220	DN40	Tanks (Generic)	Industrial Features
11A	179	SW	Tank	516450 416760	DN40	Tanks (Generic)	Industrial Features
12	192	NW	Tank	516285 417291	DN40	Tanks (Generic)	Industrial Features
13A	195	SW	Tank	516430 416755	DN40	Tanks (Generic)	Industrial Features
14	211	NW	Tank	516243 417275	DN40	Tanks (Generic)	Industrial Features
15	221	S	Flare Stack	516613 416634	DN40	Gas Features	Infrastructure and Facilities

4.2 Petrol and Fuel Sites

Records of petrol or fuel sites within 500m of the study site: 0

Database searched and no data found.

4.3 National Grid High Voltage Underground Electricity Transmission Cables

This dataset identifies the high voltage electricity transmission lines running between generating power plants and electricity substations. The dataset does not include the electricity distribution network (smaller, lower voltage cables distributing power from substations to the local user network). This information has been extracted from databases held by National Grid and is provided for information only with no guarantee as to its completeness or accuracy. National Grid do not offer any warranty as to the accuracy of the available data and are excluded from any liability for any such inaccuracies or errors.

Records of National Grid high voltage underground electricity transmission cables within 500m of the study site: 0

Database searched and no data found.

4.4 National Grid High Pressure Gas Transmission Pipelines

This dataset identifies high-pressure, large diameter pipelines which carry gas between gas terminals, power stations, compressors and storage facilities. The dataset does not include the Local Transmission System (LTS) which supplies gas directly into homes and businesses. This information has been extracted from databases held by National Grid and is provided for information only with no guarantee as to its completeness or accuracy. National Grid do not offer any warranty as to the accuracy of the available data and are excluded from any liability for any such inaccuracies or errors.

Records of National Grid high pressure gas transmission pipelines within 500m of the study site: 0

Database searched and no data found.

5. Geology

5.1 Artificial Ground and Made Ground

Database searched and no data found.

The database has been searched on site, including a 50m buffer.

5.2 Superficial Ground and Drift Geology

The database has been searched on site, including a 50m buffer.

Lex Code	Description	Rock Type
TILLD-DMTN	TILL, DEVENSIAN	DIAMICTON
TFD-XCZ	TIDAL FLAT DEPOSITS	CLAY AND SILT

5.3 Bedrock and Solid Geology


The database has been searched on site, including a 50m buffer.

Lex Code	Description	Rock Type
BCK-CHLK	BURNHAM CHALK FORMATION	CHALK

(Derived from the BGS 1:50,000 Digital Geological Map of Great Britain)

6 Hydrogeology and Hydrology


6a. Aquifer Within Superficial Geology




6b. Aquifer Within Bedrock Geology and Abstraction Licenses




© Crown copyright and database rights 2018
Ordnance Survey license 100035207.




6c. Hydrogeology – Source Protection Zones and Potable Water Abstraction Licenses




© Crown copyright and database rights 2018
Ordnance Survey license 100035207.




6d. Hydrogeology – Source Protection Zones within confined aquifer



© Crown copyright and database rights 2018
Ordnance Survey license 100035207.



6e. Hydrology – Watercourse Network and River Quality



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6. Hydrogeology and Hydrology

6.1 Aquifer within Superficial Deposits

Records of strata classification within the superficial geology at or in proximity to the property Yes

From 1 April 2010, the Environment Agency/Natural Resources Wales's Groundwater Protection Policy has been using aquifer designations consistent with the Water Framework Directive. For further details on the designation and interpretation of this information, please refer to the Groundsure Enviro Insight User Guide.

The following aquifer records are shown on the Aquifer within Superficial Geology Map (6a):

ID	Distance (m)	Direction	Designation	Description
2	0	On Site	Secondary (undifferentiated)	Assigned where it is not possible to attribute either category A or B to a rock type. In general these layers have previously been designated as both minor and non-aquifer in different locations due to the variable characteristics of the rock type
3	0	On Site	Unproductive	These are rock layers or drift deposits with low permeability that have negligible significance for water supply or river base flow

6.2 Aquifer within Bedrock Deposits

Records of strata classification within the bedrock geology at or in proximity to the property Yes

From 1 April 2010, the Environment Agency/Natural Resources Wales's Groundwater Protection Policy has been using aquifer designations consistent with the Water Framework Directive. For further details on the designation and interpretation of this information, please refer to the Groundsure Enviro Insight User Guide.

The following aquifer records are shown on the Aquifer within Bedrock Geology Map (6b):

ID	Distance (m)	Direction	Designation	Description
1	0	On Site	Principal	Geology of high intergranular and/or fracture permeability, usually providing a high level of water storage and may support water supply/river base flow on a strategic scale. Generally principal aquifers were previously major aquifers

6.3 Groundwater Abstraction Licences

Groundwater Abstraction Licences within 2000m of the study site

Identified

The following Abstraction Licences records are represented as points, lines and regions on the Aquifer within Bedrock Geology Map (6b):

ID	Distance (m)	Direction	NGR	Details
2A	779	NE	517760 417440	Status: Active Licence No: 4/29/09/*G/0129 Details: General Use Relating To Secondary Category (Low Loss) Direct Source: Ground Water Source Of Supply Point: Inland Cavern Bore 1 Data Type: Point Name: Phillips 66 Limited Annual Volume (m ³): 14000 Max Daily Volume (m ³): 1056 Original Application No: NPS/WR/011065 Original Start Date: 8/5/1985 Expiry Date: - Issue No: 102 Version Start Date: 13/7/2012 Version End Date:
3A	788	NE	517770 417440	Status: Active Licence No: 4/29/09/*G/0129 Details: General Use Relating To Secondary Category (Low Loss) Direct Source: Ground Water Source Of Supply Point: Inland Cavern Bore 2 Data Type: Point Name: Phillips 66 Limited Annual Volume (m ³): 14000 Max Daily Volume (m ³): 1056 Original Application No: NPS/WR/011065 Original Start Date: 8/5/1985 Expiry Date: - Issue No: 102 Version Start Date: 13/7/2012 Version End Date:
Not shown	810	W	515620 416950	Status: Historical Licence No: AN/029/0009/001 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Conoco Bore2 S.killingholme Data Type: Point Name: Phillips 66 Ltd Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NPS/WR/002956 Original Start Date: 1/4/2010 Expiry Date: 31/3/2018 Issue No: 1 Version Start Date: 1/4/2010 Version End Date:
Not shown	810	W	515620 416950	Status: Historical Licence No: 4/29/09/*G/0124 Details: Process water Direct Source: Ground Water Source Of Supply Point: Conoco Bore2 S.killingholme Data Type: Point Name: CONOCO LTD Annual Volume (m ³): - Max Daily Volume (m ³): - Original Application No: - Original Start Date: 1/6/1980 Expiry Date: 31/07/2002 Issue No: 100 Version Start Date: 1/7/1997 Version End Date:
Not shown	810	W	515620 416950	Status: Historical Licence No: 4/29/09/*G/0145 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Conoco Bore2 S.killingholme Data Type: Point Name: CONOCOPHILLIPS LTD Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NA363 Original Start Date: 2/7/2002 Expiry Date: 31/3/2010 Issue No: 2 Version Start Date: 15/7/2003 Version End Date:
Not shown	810	W	515620 416950	Status: Active Licence No: AN/029/0009/001 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Borehole 2 S.killingholme Data Type: Point Name: Phillips 66 Limited Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NPS/WR/011064 Original Start Date: 1/4/2010 Expiry Date: 31/3/2018 Issue No: 2 Version Start Date: 13/7/2012 Version End Date:

ID	Distance (m)	Direction	NGR	Details	
8B	824	SW	515730 416670	Status: Historical Licence No: 4/29/09/*G/0124 Details: Process water Direct Source: Ground Water Source Of Supply Point: Conoco Bore1 S.killingholme Data Type: Point Name: CONOCO LTD	Annual Volume (m ³): - Max Daily Volume (m ³): - Original Application No: - Original Start Date: 1/6/1980 Expiry Date: 31/07/2002 Issue No: 100 Version Start Date: 1/7/1997 Version End Date:
9B	824	SW	515730 416670	Status: Historical Licence No: AN/029/0009/001 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Conoco Bore1 S.killingholme Data Type: Point Name: Phillips 66 Ltd	Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NPS/WR/002956 Original Start Date: 1/4/2010 Expiry Date: 31/3/2018 Issue No: 1 Version Start Date: 1/4/2010 Version End Date:
10B	824	SW	515730 416670	Status: Historical Licence No: 4/29/09/*G/0145 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Conoco Bore1 S.killingholme Data Type: Point Name: CONOCOPHILLIPS LTD	Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NA363 Original Start Date: 2/7/2002 Expiry Date: 31/3/2010 Issue No: 2 Version Start Date: 15/7/2003 Version End Date:
11B	824	SW	515730 416670	Status: Active Licence No: AN/029/0009/001 Details: Process Water Direct Source: Ground Water Source Of Supply Point: Borehole 1 S.killingholme Data Type: Point Name: Phillips 66 Limited	Annual Volume (m ³): 619000 Max Daily Volume (m ³): 1700 Original Application No: NPS/WR/011064 Original Start Date: 1/4/2010 Expiry Date: 31/3/2018 Issue No: 2 Version Start Date: 13/7/2012 Version End Date:
Not shown	1310	NE	518170 417800	Status: Active Licence No: 4/29/09/*G/0129 Details: General Use Relating To Secondary Category (Low Loss) Direct Source: Ground Water Source Of Supply Point: Riverside Cavern Bore 1 Data Type: Point Name: Phillips 66 Limited	Annual Volume (m ³): 14000 Max Daily Volume (m ³): 1056 Original Application No: NPS/WR/011065 Original Start Date: 8/5/1985 Expiry Date: - Issue No: 102 Version Start Date: 13/7/2012 Version End Date:
Not shown	1319	NE	518180 417800	Status: Active Licence No: 4/29/09/*G/0129 Details: General Use Relating To Secondary Category (Low Loss) Direct Source: Ground Water Source Of Supply Point: Riverside Cavern Bore 2 Data Type: Point Name: Phillips 66 Limited	Annual Volume (m ³): 14000 Max Daily Volume (m ³): 1056 Original Application No: NPS/WR/011065 Original Start Date: 8/5/1985 Expiry Date: - Issue No: 102 Version Start Date: 13/7/2012 Version End Date:
Not shown	1598	E	518578 416651	Status: Active Licence No: 4/29/09/*G/0045 Details: Raw Water Supply Direct Source: Ground Water Source Of Supply Point: Timber Yard Bore Data Type: Point Name: ASSOCIATED BRITISH PORTS	Annual Volume (m ³): 1400000 Max Daily Volume (m ³): 5480 Original Application No: NPS/WR/002800 Original Start Date: 1/6/1966 Expiry Date: - Issue No: 101 Version Start Date: 7/12/2010 Version End Date:
Not shown	1619	SE	518197 415977	Status: Active Licence No: 4/29/09/*G/0045 Details: Raw Water Supply Direct Source: Ground Water Source Of Supply Point: Reception Bore Data Type: Point Name: ASSOCIATED BRITISH PORTS	Annual Volume (m ³): 1400000 Max Daily Volume (m ³): 5480 Original Application No: NPS/WR/002800 Original Start Date: 1/6/1966 Expiry Date: - Issue No: 101 Version Start Date: 7/12/2010 Version End Date:

ID	Distance (m)	Direction	NGR	Details	
Not shown	1635	E	518600 416600	Status: Historical Licence No: 4/29/09/*G/0045 Details: Raw Water Supply Direct Source: Ground Water Source Of Supply Point: Timber Yard Bore Data Type: Point Name: ASSOCIATED BRITISH PORTS	Annual Volume (m ³): 945588 Max Daily Volume (m ³): 2619 Original Application No: - Original Start Date: 1/6/1966 Expiry Date: - Issue No: 100 Version Start Date: 1/4/1997 Version End Date:
Not shown	1676	SE	518200 415900	Status: Historical Licence No: 4/29/09/*G/0045 Details: Raw Water Supply Direct Source: Ground Water Source Of Supply Point: Reception Bore Data Type: Point Name: ASSOCIATED BRITISH PORTS	Annual Volume (m ³): 945588 Max Daily Volume (m ³): 2619 Original Application No: - Original Start Date: 1/6/1966 Expiry Date: - Issue No: 100 Version Start Date: 1/4/1997 Version End Date:

6.4 Surface Water Abstraction Licences

Surface Water Abstraction Licences within 2000m of the study site Identified

The following Surface Water Abstraction Licences records are represented as points, lines and regions on the Aquifer within Bedrock Geology Map (6b):

ID	Distance (m)	Direction	NGR	Details	
Not shown	1819	SE	517910 415510	Status: Historical Licence No: 4/29/09/*S/0127 Details: Make-Up Or Top Up Water Direct Source: Surface Water Source Of Supply Point: Trib. Of Habrough Marsh Drain Data Type: Point Name: IMMINGHAM TOWN COUNCIL	Annual Volume (m ³): 4092 Max Daily Volume (m ³): 46 Application No: - Original Start Date: 1/1/1985 Expiry Date: - Issue No: 100 Version Start Date: 1/4/2008 Version End Date:

6.5 Potable Water Abstraction Licences

Potable Water Abstraction Licences within 2000m of the study site None identified

Database searched and no data found.

6.6 Source Protection Zones

Source Protection Zones within 500m of the study site

Identified

The following Source Protection Zones records are represented on the SPZ and Potable Water Abstraction Map (6c):

ID	Distance (m)	Direction	Zone	Description
1	0	On Site	3	Total catchment

6.7 Source Protection Zones within Confined Aquifer

Source Protection Zones within the Confined Aquifer within 500m of the study site

None identified

Historically, Source Protection Zone maps have been focused on regulation of activities which occur at or near the ground surface, such as prevention of point source pollution and bacterial contamination of water supplies. Sources in confined aquifers were often considered to be protected from these surface pressures due to the presence of a low permeability confining layer (e.g. glacial till, clay). The increased interest in subsurface activities such as onshore oil and gas exploration, ground source heating and cooling requires protection zones for confined sources to be marked on SPZ maps where this has not already been done.

Database searched and no data found.

6.8 Groundwater Vulnerability and Soil Leaching Potential

Environment Agency/Natural Resources Wales information on groundwater vulnerability and soil leaching potential within 500m of the study site

Identified

Distance (m)	Direction	Classification	Soil Vulnerability Category	Description
0	On Site	Major Aquifer/Low Leaching Potential	L	Soils in which pollutants are unlikely to penetrate the soil layer because either water movement is largely horizontal, or they have the ability to attenuate diffuse pollutants.
273	E	Major Aquifer/High Leaching Potential	H1	Soils which readily transmit liquid discharges because they are shallow or susceptible to rapid flow directly to rock, gravel or groundwater.

6.9 River Quality

Environment Agency/Natural Resources Wales information on river quality within 1500m of the study site

None identified

6.9.1 Biological Quality:

Database searched and no data found.

6.9.2 Chemical Quality:

Database searched and no data found.

6.10 Ordnance Survey MasterMap Water Network

Ordnance Survey MasterMap Water Network entries within 500m of the study site

This watercourse information is provided by Ordnance Survey MasterMap Water Network. The data provides a detailed centre line following the curve of the waterway precisely, so all distances provided in the report should be understood as measurements to the centreline rather than a measurement to the nearest point of the watercourse. Underground watercourses are inferred from entry and exit points so caution is advised in using these to indicate precise locations of underground watercourses when planning site investigation and development.

The following Ordnance Survey MasterMap Water Network records are represented on the Hydrology Map (6e):

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
1	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
2	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
3	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
4	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
5	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
6	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
7	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
8	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
9	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3
14	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
15	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
16	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
17	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
18	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
19	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
20	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
21	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
22	0 On Site	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
10	3 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
23	3 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
11	6 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
24	6 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
12	10 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
25	10 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
13	12 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0
26	12 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0
14	14 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3
27	14 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3
15	15 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
16	15 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
28	15 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
29	15 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0
17	16 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
30	16 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
18	18 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
31	18 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
19	19 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
32	19 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
20	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.2
21	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
22	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
33	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.2

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
34	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
35	26 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
23	31 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
36	31 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
24	37 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
25	37 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
37	37 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
38	37 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
26	50 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
39	50 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
27	54 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
40	54 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
28	69 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
41	69 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
29	72 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0
42	72 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.0
30	77 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
31	77 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
43	77 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
44	77 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
32	78 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.7
45	78 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.7
33	79 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
46	79 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
34	80 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
47	80 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
35	120 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.2
48	120 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.2
36	126 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
49	126 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
37	143 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.9
50	143 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.9
38	151 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
51	151 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
39	152 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
52	152 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
40	154 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
53	154 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.9
41	156 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
54	156 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
42	157 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3
55	157 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.3
43	164 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
56	164 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.8
44	187 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
57	187 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
45	191 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.4
58	191 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.4

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
46	202 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
59	202 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
47	203 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.6
60	203 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.6
48	226 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
61	226 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
49	241 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.4
50	241 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.9
62	241 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.4
63	241 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.9
51	248 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
64	248 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
52	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 5.4
53	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.8
54	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.1
55	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
56	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
65	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 5.4
66	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.8
67	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.1
68	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
69	249 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
57	250 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.1
70	250 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.1

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
58	255 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
71	255 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
59	257 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
72	257 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
60	260 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
73	260 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
61	261 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
62	261 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
74	261 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
75	261 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
63	263 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
76	263 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
64	273 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
77	273 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
65	275 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.4
66	275 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
78	275 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.4
79	275 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
67	278 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
80	278 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
68	279 SE	-	Lake, loch or reservoir.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
81	279 SE	-	Lake, loch or reservoir.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
69	285 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
70	285 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.2

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
71	285 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
82	285 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
83	285 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.2
84	285 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.5
72	291 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.1
85	291 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.1
73	292 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.3
86	292 NE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.3
74	297 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
75	297 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	297 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	297 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
76	299 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
89	299 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
77	300 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
78	300 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
90	300 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
91	300 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.0
79	305 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
92	305 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
80	326 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
93	326 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
81	340 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
Not shown	340 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
82	349 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	349 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
83	360 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
96	360 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
84	366 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
85	366 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
97	366 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.1
98	366 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.4
86	367 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	367 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
87	371 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	371 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
88	374 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	374 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
89	392 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	392 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
90	393 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.8
103	393 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 1.8
91	396 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
104	396 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
92	403 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
105	403 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
93	404 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
106	404 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
94	406 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	406 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
95	412 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
96	412 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	412 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: Underground Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	412 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
97	417 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
110	417 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 2.2
98	418 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	418 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
99	419 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
112	419 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
100	435 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	435 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
101	439 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
114	439 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
102	440 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	440 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
103	442 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
116	442 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
104	449 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.6
Not shown	449 E	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 4.6
105	456 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
118	456 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
106	459 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
119	459 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
107	475 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	475 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
108	476 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
121	476 SE	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
109	481 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	481 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
110	482 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	482 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
111	486 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.5
Not shown	486 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): 3.5

ID	Distance/ Direction	Name	Type of Watercourse	Additional Details
112	487 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
113	487 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	487 SW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	487 NW	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
114	495 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	495 W	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
115	496 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided
Not shown	496 S	-	Inland river not influenced by normal tidal action.	Catchment Area: Louth Grimsby and Ancholme Relationship to Ground Level: On ground surface Permanence: Watercourse contains water year round (in normal conditions) Average Width in Watercourse Section (m): Not Provided

6.11 Surface Water Features


Surface water features within 250m of the study site

Identified

The following surface water records are not represented on mapping:

Distance (m)	Direction
0	On Site
0	On Site
6	NE
10	SE
16	NW
18	NE
18	NE
25	NE
27	NE
32	NW
37	NW
50	W
54	S
59	NW
71	NW
77	NW
79	SW
80	NW
92	NW
110	SE
114	S
117	SW
118	NW
126	NW
143	SE
145	SE
152	NW
156	W
157	NE
161	SW
172	SW
187	NW
200	E
203	SW
222	SE
226	SW
242	S
246	NW
246	NW
247	NW
249	NW
250	NW

7a. Environment Agency/Natural Resources Wales Flood Map for Planning (from rivers and the sea)




© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



7b. Environment Agency/Natural Resources Wales Risk of Flooding from Rivers and the Sea (RoFRaS) Map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



7 Flooding

7.1 River and Coastal Zone 2 Flooding

Environment Agency/Natural Resources Wales Zone 2 floodplain within 250m Identified

Environment Agency/Natural Resources Wales Zone 2 floodplains estimate the annual probability of flooding as between 1 in 1000 (0.1%) and 1 in 100 (1%) from rivers and between 1 in 1000 (0.1%) and 1 in 200 (0.5%) from the sea. Any relevant data is represented on Map 7a – Flood Map for Planning:

ID	Distance (m)	Direction	Update	Type
1	0	On Site	19-Mar-2018	Zone 2 - (Fluvial /Tidal Models)

7.2 River and Coastal Zone 3 Flooding

Environment Agency/Natural Resources Wales Zone 3 floodplain within 250m Identified

Zone 3 shows the extent of a river flood with a 1 in 100 (1%) or greater chance of occurring in any year or a sea flood with a 1 in 200 (0.5%) or greater chance of occurring in any year. Any relevant data is represented on Map 7a – Flood Map for Planning.

ID	Distance (m)	Direction	Update	Type
1	0	On Site	19-Mar-2018	Zone 3 - (Fluvial Models)

7.3 Risk of Flooding from Rivers and the Sea (RoFRaS) Flood Rating

Highest risk of flooding onsite Very Low

The Environment Agency/Natural Resources Wales RoFRaS database provides an indication of river and coastal flood risk at a national level on a 50m grid with the flood rating at the centre of the grid calculated and given above. The data considers the probability that the flood defences will overtop or breach by considering their location, type, condition and standard of protection.

RoFRaS data for the study site indicates the property is in an area with a Very Low (less than 1 in 1000) chance of flooding in any given year.

Any relevant data within 250m is represented on the RoFRaS Flood map. Data to 50m is reported in the table below.

ID	Distance (m)	Direction	RoFRaS flood Risk
1	0.0	On Site	Very Low
2	8.0	N	High

3	9.0	S	High
4	10.0	S	High
5	14.0	N	Very Low
6	22.0	SE	High
7	24.0	NE	High
8	24.0	NE	Low
9	26.0	NE	Low
10	30.0	NE	Very Low
11A	47.0	SE	High

7.4 Flood Defences

Flood Defences within 250m of the study site None identified
 Database searched and no data found.

7.5 Areas benefiting from Flood Defences

Areas benefiting from Flood Defences within 250m of the study site None identified

7.6 Areas benefiting from Flood Storage

Areas used for Flood Storage within 250m of the study site None identified

7.7 Groundwater Flooding Susceptibility Areas

7.7.1 British Geological Survey groundwater flooding susceptibility areas within 50m of the boundary of the study site Identified

Clearwater Flooding or Superficial Deposits Flooding Clearwater Flooding

Notes: Groundwater flooding may either be associated with shallow unconsolidated sedimentary aquifers which overlie unproductive aquifers (Superficial Deposits Flooding), or with unconfined aquifers (Clearwater Flooding).

7.7.2 Highest susceptibility to groundwater flooding in the search area based on the underlying geological conditions

Potential at Surface

Where potential for groundwater flooding to occur at surface is indicated, this means that given the geological conditions in the area groundwater flooding hazard should be considered in all land-use planning decisions. It is recommended that other relevant information e.g. records of previous incidence of groundwater flooding, rainfall, property type, and land drainage information be investigated in order to establish relative, but not absolute, risk of groundwater flooding.

7.8 Groundwater Flooding Confidence Areas


British Geological Survey confidence rating in this result

High

Notes: Groundwater flooding is defined as the emergence of groundwater at the ground surface or the rising of groundwater into man-made ground under conditions where the normal range of groundwater levels is exceeded.

The confidence rating is on a threefold scale - Low, Moderate and High. This provides a relative indication of the BGS confidence in the accuracy of the susceptibility result for groundwater flooding. This is based on the amount and precision of the information used in the assessment. In areas with a relatively lower level of confidence the susceptibility result should be treated with more caution. In other areas with higher levels of confidence the susceptibility result can be used with more confidence.

8. Designated Environmentally Sensitive Sites Map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



8. Designated Environmentally Sensitive Sites

Designated Environmentally Sensitive Sites within 2000m of the study site

Identified

8.1 Records of Sites of Special Scientific Interest (SSSI) within 2000m of the study site:

4

The following Site of Special Scientific Interest (SSSI) records provided by Natural England/Natural Resources Wales are represented as polygons on the Designated Environmentally Sensitive Sites Map:

ID	Distance (m)	Direction	SSSI Name	Data Source
3	1360	NE	Humber Estuary	Natural England
4	1394	NE	Humber Estuary	Natural England
5	1628	NE	Humber Estuary	Natural England
Not shown	1650	E	Humber Estuary	Natural England

8.2 Records of National Nature Reserves (NNR) within 2000m of the study site:

0

Database searched and no data found.

8.3 Records of Special Areas of Conservation (SAC) within 2000m of the study site:

1

The following Special Area of Conservation (SAC) records provided by Natural England/Natural Resources Wales are represented as polygons on the Designated Environmentally Sensitive Sites Map:

ID	Distance (m)	Direction	SAC Name	Data Source
1A	1360	NE	Humber Estuary	Natural England

8.4 Records of Special Protection Areas (SPA) within 2000m of the study site:

1

The following Special Protection Area (SPA) records provided by Natural England/Natural Resources Wales are represented as polygons on the Designated Environmentally Sensitive Sites Map:

ID	Distance (m)	Direction	SPA Name	Data Source
2A	1361	NE	Humber Estuary	Natural England

8.5 Records of Ramsar sites within 2000m of the study site:

1

The following Ramsar records provided by Natural England/Natural Resources Wales are represented as polygons on the Designated Environmentally Sensitive Sites Map:

ID	Distance (m)	Direction	Ramsar Site Name	Ramsar Site Status	Data Source
7A	1360	NE	Humber Estuary	Listed	Natural England

8.6 Records of Ancient Woodland within 2000m of the study site:

0

Database searched and no data found.

8.7 Records of Local Nature Reserves (LNR) within 2000m of the study site:

0

Database searched and no data found.

8.8 Records of World Heritage Sites within 2000m of the study site:

0

Database searched and no data found.

8.9 Records of Environmentally Sensitive Areas within 2000m of the study site:

0

Database searched and no data found.

8.10 Records of Areas of Outstanding Natural Beauty (AONB) within 2000m of the study site:

0

Database searched and no data found.

8.11 Records of National Parks (NP) within 2000m of the study site:

0

Database searched and no data found.

8.12 Records of Nitrate Sensitive Areas within 2000m of the study site:

0

Database searched and no data found.

8.13 Records of Nitrate Vulnerable Zones within 2000m of the study site:

3

The following Nitrate Vulnerable Zone records produced by DEFRA are represented as polygons on the Designated Environmentally Sensitive Sites Map:

ID	Distance (m)	Direction	NVZ Name	Data Source
8	0	On Site	Modified	DEFRA
9	214	S	Existing	DEFRA
Not shown	1780	W	Existing	DEFRA

8.14 Records of Green Belt land within 2000m of the study site:

0

Database searched and no data found.

9. Natural Hazards Findings

9.1 Detailed BGS GeoSure Data

BGS GeoSure Data has been searched to 50m. The data is included in tabular format. If you require further information on geology and ground stability, please obtain a **Groundsure Geo Insight**, available from our [website](#). The following information has been found:

9.1.1 Shrink Swell

Maximum Shrink-Swell** hazard rating identified on the study site Low

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard
Ground conditions predominantly medium plasticity. Do not plant trees with high soil moisture demands near to buildings. For new build, consideration should be given to advice published by the National House Building Council (NHBC) and the Building Research Establishment (BRE). There is a possible increase in construction cost to reduce potential shrink-swell problems. For existing property, there is a possible increase in insurance risk, especially during droughts or where vegetation with high moisture demands is present.

9.1.2 Landslides

Maximum Landslide* hazard rating identified on the study site Very Low

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard
Slope instability problems are unlikely to be present. No special actions required to avoid problems due to landslides. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with landslides.

9.1.3 Soluble Rocks

Maximum Soluble Rocks* hazard rating identified on the study site Negligible

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard
Soluble rocks are present, but unlikely to cause problems except under exceptional conditions. No special actions required to avoid problems due to soluble rocks. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with soluble rocks.

* This indicates an automatically generated 50m buffer and site.

9.1.4 Compressible Ground

Maximum Compressible Ground* hazard rating identified on the study site

Moderate

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard

Significant potential for compressibility problems. Avoid large differential loadings of ground. Do not drain or de-water ground near the property without technical advice. For new build consider possibility of compressible ground in ground investigation, construction and building design. Consider effects of groundwater changes. Extra construction costs are likely. For existing property possible increase in insurance risk from compressibility, especially if water conditions or loading of the ground change significantly.

9.1.5 Collapsible Rocks

Maximum Collapsible Rocks* hazard rating identified on the study site

Very Low

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard

Deposits with potential to collapse when loaded and saturated are unlikely to be present. No special ground investigation required or increased construction costs or increased financial risk due to potential problems with collapsible deposits.

9.1.6 Running Sand

Maximum Running Sand** hazard rating identified on the study site

Moderate

The following natural subsidence information provided by the British Geological Survey is not represented on mapping:

Hazard

Significant potential for running sand problems with relatively small changes in ground conditions. Avoid large amounts of water entering the ground (for example through pipe leakage or soak-aways). Do not dig (deep) holes into saturated ground near the property without technical advice. For new build consider the consequences of soil and groundwater conditions during and after construction. For existing property possible increase in insurance risk from running sand, for example, due to water leakage, high rainfall events or flooding.

* This indicates an automatically generated 50m buffer and site.

9.2 Radon

9.2.1 Radon Affected Areas

Is the property in a Radon Affected Area as defined by the Health Protection Agency (HPA) and if so what percentage of homes are above the Action Level? The site is not in a Radon Affected Area, as less than 1% of properties are above the Action Level.

The radon data in this report is supplied by the BGS/Public Health England and is the definitive map of Radon Affected Areas in Great Britain and Northern Ireland. The dataset was created using long-term radon measurements in over 479,000 homes across Great Britain and 23,000 homes across Northern Ireland, combined with geological data. The dataset is considered accurate to 50m to allow for the margin of error in geological lines, and the findings of this report supercede any answer given in the less accurate Indicative Atlas of Radon in Great Britain, which simplifies the data to give the highest risk within any given 1km grid square. As such, the radon atlas is considered indicative, whereas the data given in this report is considered definitive.

9.2.2 Radon Protection

Is the property in an area where Radon Protection are required for new properties or extensions to existing ones as described in publication BR211 by the Building Research Establishment? No radon protective measures are necessary.

10. Mining

10.1 Coal Mining

Coal mining areas within 75m of the study site

None identified

Database searched and no data found.

10.2 Non-Coal Mining

Non-Coal Mining areas within 50m of the study site boundary

None identified

Database searched and no data found.

10.3 Brine Affected Areas

Brine affected areas within 75m of the study site

None identified

Guidance: No Guidance Required.

Contact Details

Groundsure Helpline
Telephone: 08444 159 000
info@groundsure.com

British Geological Survey Enquiries

Kingsley Dunham Centre
Keyworth, Nottingham NG12 5GG
Tel: 0115 936 3143.
Fax: 0115 936 3276.
Email:

Web: www.bgs.ac.uk

BGS Geological Hazards Reports and general geological enquiries:
enquiries@bgs.ac.uk

Environment Agency

National Customer Contact Centre, PO Box 544
Rotherham, S60 1BY
Tel: 03708 506 506

Web: www.environment-agency.gov.uk

Email: enquiries@environment-agency.gov.uk

Public Health England

Public information access office
Public Health England, Wellington House
133-155 Waterloo Road, London, SE1 8UG
www.gov.uk/phe

Email: enquiries@phe.gov.uk
Main switchboard: 020 7654 8000

The Coal Authority

200 Lichfield Lane
Mansfield
Notts NG18 4RG
Tel: 0345 7626 848
DX 716176 Mansfield 5
www.coal.gov.uk

Ordnance Survey

Adanac Drive, Southampton
SO16 0AS
Tel: 08456 050505

Local Authority

Authority: North Lincolnshire Council
Phone: 01724 296 296

Web: <http://www.northlincs.gov.uk/>

Address: Civic Centre, Ashby Road, Scunthorpe, North Lincolns, DN16

Gemapping PLC

Virginia Villas, High Street, Hartley Witney,
Hampshire RG27 8NW
Tel: 01252 845444



Groundsure
LOCATION INTELLIGENCE



Public Health England



The Coal Authority



Acknowledgements: Site of Special Scientific Interest, National Nature Reserve, Ramsar Site, Special Protection Area, Special Area of Conservation data is provided by, and used with the permission of, Natural England/Natural Resources Wales who retain the Copyright and Intellectual Property Rights for the data.

PointX © Database Right/Copyright, Thomson Directories Limited © Copyright Link Interchange Network Limited © Database Right/Copyright and Ordnance Survey © Crown Copyright and/or Database Right. All Rights Reserved. Licence Number [03421028].

This report has been prepared in accordance with the Groundsure Ltd standard Terms and Conditions of business for work of this nature.

Standard Terms and Conditions

Groundsure's Terms and Conditions can be viewed online at this link:

<https://www.groundsure.com/terms-and-conditions-may25-2018>



Groundsure

LOCATION INTELLIGENCE

Aecom Infrastructure and Environment UK Ltd AECOM LTD,2, CITY WALK, LEEDS, LS11 9AR	Groundsure Reference: Your Reference:	GS-5087182 VPI_Immingham
	Report Date	30 May 2018
	Report Delivery Method:	Email - pdf

Geo Insight

Address: TANKS 90M FROM V P I IMMINGHAM, ROSPER ROAD. 18M FROM UNNAMED ROAD,
FOOTPATH SKIL91A, SOUTH KILLINGHOLME, DN40 3DZ

Dear Sir/ Madam,

Thank you for placing your order with Groundsure. Please find enclosed the **Groundsure Geo Insight** as requested.

If you need any further assistance, please do not hesitate to contact our helpline on 08444 159000 quoting the above Groundsure reference number.

Yours faithfully,



Managing Director
Groundsure Limited

Enc.
Groundsure Geo Insight

Address: TANKS 90M FROM V P I IMMINGHAM, ROSPER ROAD. 18M FROM UNNAMED ROAD, FOOTPATH SKIL91A, SOUTH KILLINGHOLME, DN40 3DZ

Date: 30 May 2018

Reference: GS-5087182

Client: Aecom Infrastructure and Environment UK Ltd

NW N NE



SW S SE

Aerial Photograph Capture date: 21-Apr-2016
Grid Reference: 516701,417117

Site Size: 18.53ha

Contents Page

Contents Page.....	4
Overview of Findings.....	6
1:10,000 Scale Availability.....	9
Availability of 1:10,000 Scale Geology Mapping.....	10
1 Geology (1:10,000 scale).....	11
1.1 Artificial Ground map (1:10,000 scale).....	11
1. Geology 1:10,000 scale.....	12
1.1 Artificial Ground.....	12
1.2 Superficial Deposits and Landslips map (1:10,000 scale).....	13
1.2 Superficial Deposits and Landslips.....	14
1.2.1 Superficial Deposits/ Drift Geology.....	14
1.2.2 Landslip.....	14
1.3 Bedrock and linear features map (1:10,000 scale).....	15
1.3 Bedrock and linear features.....	16
1.3.1 Bedrock/ Solid Geology.....	16
1.3.2 Linear features.....	16
2 Geology 1:50,000 Scale.....	17
2.1 Artificial Ground map.....	17
2. Geology 1:50,000 scale.....	18
2.1 Artificial Ground.....	18
2.1.1 Artificial/ Made Ground.....	18
2.1.2 Permeability of Artificial Ground.....	18
2.2 Superficial Deposits and Landslips map (1:50,000 scale).....	19
2.2 Superficial Deposits and Landslips.....	20
2.2.1 Superficial Deposits/ Drift Geology.....	20
2.2.2 Permeability of Superficial Ground.....	20
2.2.3 Landslip.....	20
2.2.4 Landslip Permeability.....	20
2.3 Bedrock and linear features map (1:50,000 scale).....	21
2.3 Bedrock, Solid Geology & linear features.....	22
2.3.1 Bedrock/Solid Geology.....	22
2.3.2 Permeability of Bedrock Ground.....	22
2.3.3 Linear features.....	22
3 Radon Data.....	23
3.1 Radon Affected Areas.....	23
3.2 Radon Protection.....	23
4 Ground Workings map.....	24
4 Ground Workings.....	25
4.1 Historical Surface Ground Working Features derived from Historical Mapping.....	25
4.2 Historical Underground Working Features derived from Historical Mapping.....	25
4.3 Current Ground Workings.....	26
5 Mining, Extraction & Natural Cavities.....	28
5.1 Historical Mining.....	28
5.2 Coal Mining.....	28
5.3 Johnson Poole and Bloomer.....	28
5.4 Non-Coal Mining.....	28
5.5 Non-Coal Mining Cavities.....	29
5.6 Natural Cavities.....	29
5.7 Brine Extraction.....	29
5.8 Gypsum Extraction.....	29
5.9 Tin Mining.....	29
5.10 Clay Mining.....	30
6 Natural Ground Subsidence.....	31
6.1 Shrink-Swell Clay map.....	31
6.2 Landslides map.....	32
6.3 Ground Dissolution of Soluble Rocks map.....	33
6.4 Compressible Deposits map.....	34
6.5 Collapsible Deposits map.....	35
6.6 Running Sand map.....	36

6 Natural Ground Subsidence.....	37
6.1 Shrink-Swell Clays.....	37
6.2 Landslides.....	37
6.3 Ground Dissolution of Soluble Rocks.....	38
6.4 Compressible Deposits.....	38
6.5 Collapsible Deposits.....	38
6.6 Running Sands.....	39
7 Borehole Records.....	41
8 Estimated Background Soil Chemistry.....	42
9 Railways and Tunnels map.....	43
9 Railways and Tunnels.....	44
9.1 Tunnels	44
9.2 Historical Railway and Tunnel Features	44
9.3 Historical Railways.....	45
9.4 Active Railways.....	45
9.5 Railway Projects.....	47

Overview of Findings

The Groundsure Geo Insight provides high quality geo-environmental information that allows geo-environmental professionals and their clients to make informed decisions and be forewarned of potential ground instability problems that may affect the ground investigation, foundation design and possibly remediation options that could lead to possible additional costs.

The report is based on the BGS 1:50,000 and 1:10,000 Digital Geological Map of Great Britain, BGS Geosure data; BRITPITS database; Non-coal mining data and Borehole Records, Coal Authority data including brine extraction areas, PBA non-coal mining and natural cavities database, Johnson Poole and Bloomer mining data and Groundsure's unique database including historical surface ground and underground workings.

For further details on each dataset, please refer to each individual section in the report as listed. Where the database has been searched a numerical result will be recorded. Where the database has not been searched '-' will be recorded.

Section 1: Geology 1:10,000 Scale		
1.1 Artificial Ground	1.1 Is there any Artificial Ground/ Made Ground present beneath the study site at 1:10,000 scale?	No
1.2 Superficial Geology and Landslips	1.2.1 Is there any Superficial Ground/Drift Geology present beneath the study site at 1:10,000 scale?*	No
	1.2.2 Are there any records of landslip within 500m of the study site boundary at 1:10,000 scale?	No
1.3 Bedrock, Solid Geology and linear features	1.3.1 For records of Bedrock and Solid Geology beneath the study site* see the detailed findings section.	
	1.3.2 Are there any records of linear features within 500m of the study site boundary at 1:10,000 scale?	No
Section 2: Geology 1:50,000 Scale		
2.1 Artificial Ground	2.1.1 Is there any Artificial Ground/ Made Ground present beneath the study site?	No
	2.1.2 Are there any records relating to permeability of artificial ground within the study site*boundary?	No
2.2 Superficial Geology and Landslips	2.2.1 Is there any Superficial Ground/Drift Geology present beneath the study site?*	Yes
	2.2.2 Are there any records of permeability of superficial ground within 500m of the study site?	Yes
	2.2.3 Are there any records of landslip within 500m of the study site boundary?	No
	2.2.4 Are there any records relating to permeability of landslips within the study site* boundary?	No

Section 2: Geology 1:50,000 Scale

2.3 Bedrock, Solid Geology and linear features

2.3.1 For records of Bedrock and Solid Geology beneath the study site* see the detailed findings section.

2.3.2 Are there any records relating to permeability of bedrock ground within the study site boundary?

Yes

2.3.3 Are there any records of linear features within 500m of the study site boundary?

No

Section 3: Radon

3. Radon

3.1 Is the property in a Radon Affected Area as defined by the Health Protection Agency (HPA) and if so what percentage of homes are above the Action Level?

The property is not in a Radon Affected Area, as less than 1% of properties are above the Action Level.

3.2 Radon Protection

No radon protective measures are necessary.

Section 4: Ground Workings


	On-site	0-50m	51-250	251-500	501-1000
4.1 Historical Surface Ground Working Features from Small Scale Mapping	0	0	8	Not Searched	Not Searched
4.2 Historical Underground Workings from Small Scale Mapping	0	0	0	0	0
4.3 Current Ground Workings	0	0	0	0	0

Section 5: Mining, Extraction & Natural Cavities

	On-site	0-50m	51-250	251-500	501-1000
5.1 Historical Mining	0	0	0	0	0
5.2 Coal Mining	0	0	0	0	0
5.3 Johnson Poole and Bloomer Mining Area	0	0	0	0	0
5.4 Non-Coal Mining*	0	0	0	0	0
5.5 Non-Coal Mining Cavities	0	0	0	0	0
5.5 Natural Cavities	0	0	0	0	0


Section 5: Mining, Extraction & Natural Cavities	On-site	0-50m	51-250	251-500	501-1000
5.6 Brine Extraction	0	0	0	0	0
5.7 Gypsum Extraction	0	0	0	0	0
5.8 Tin Mining	0	0	0	0	0
5.9 Clay Mining	0	0	0	0	0
Section 6: Natural Ground Subsidence	On-site				
6.1 Shrink-Swell Clay	Low				
6.2 Landslides	Very Low				
6.3 Ground Dissolution of Soluble Rocks	Negligible				
6.4 Compressible Deposits	Moderate				
6.5 Collapsible Deposits	Very Low				
6.5 Running Sand	Moderate				
Section 7: Borehole Records	On-site	0-50m	51-250		
7 BGS Recorded Boreholes	1	0	1		
Section 8: Estimated Background Soil Chemistry	On-site	0-50m	51-250		
8 Records of Background Soil Chemistry	11	1	0		
Section 9: Railways and Tunnels	On-site	0-50m	51-250	250-500	
9.1 Tunnels	0	0	0	Not Searched	
9.2 Historical Railway and Tunnel Features	0	2	5	Not Searched	
9.3 Historical Railways	0	0	0	Not Searched	
9.4 Active Railways	0	26	36	Not Searched	
9.5 Railway Projects	0	0	0	0	

1:10,000 Scale Availability



1_10,000 Availability Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



Availability of 1:10,000 Scale Geology Mapping

The following information represents the availability of the key components of the 1:10,000 scale geological data.

ID	Distance	Artificial Coverage	Superficial Coverage	Bedrock Coverage	Mass Movement Coverage
1	0.0	No deposits are mapped	No coverage	No coverage	No coverage


Guidance: The 1:10,000 scale geological interpretation is the most detailed generally available from BGS and is the scale at which most geological surveying is carried out in the field. The database is presented as four types of geology (artificial, mass movement, superficial and bedrock), although not all themes are mapped or available on every map sheet. Therefore a coverage layer showing the availability of the four themes is presented above.

The definitions of coverage are as follows:

Geology	Full Coverage	Partial Coverage	No Coverage
Bedrock	The whole tile has been mapped	Some but not all the tile has been mapped	No coverage
Superficial	The whole tile has been mapped	Some but not all of the tile has been mapped	No coverage
Artificial	Some deposits are mapped on this tile	-	No deposits are mapped
Mass Movement	Some deposits are mapped on this tile	-	No coverage

1 Geology (1:10,000 scale).

1.1 Artificial Ground map (1:10,000 scale)



Artificial Ground Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



1. Geology 1:10,000 scale


1.1 Artificial Ground

The following geological information represented on the mapping is derived from 1:10,000 scale BGS Geological mapping.

Are there any records of Artificial/ Made Ground within 500m of the study site boundary at 1:10,000 scale? No




Database searched and no data found.

1.2 Superficial Deposits and Landslips map (1:10,000 scale)



Artificial Ground Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.

-  Site Outline
 -  500
 -  1000
- Search Buffers (m)

1.2 Superficial Deposits and Landslips

The following geological information represented on the mapping is derived from 1:10,000 scale BGS Geological mapping

1.2.1 Superficial Deposits/ Drift Geology

Are there any records of Superficial Deposits/ Drift Geology within 500m of the study site boundary at 1:10,000 scale? No

Database searched and no data found.

1.2.2 Landslip


Are there any records of Landslip within 500m of the study site boundary at 1:10,000 scale? No

Database searched and no data found.

The geology map for the site and surrounding area are extracted from the BGS Digital Geological Map of Great Britain at 1:10,000 scale


This Geology shows the main components as discrete layers, these are: Artificial / Made Ground, Superficial / Drift Geology and Landslips. These are all displayed with the BGS Lexicon code for the rock unit and BGS sheet number. Not all of the main geological components have nationwide coverage.

1.3 Bedrock and linear features map (1:10,000 scale)



Bedrock and linear features Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



1.3 Bedrock and linear features

The following geological information represented on the mapping is derived from 1:10,000 scale BGS Geological mapping.

1.3.1 Bedrock/ Solid Geology

Records of Bedrock/Solid Geology within 500m of the study site boundary at 1:10,000 scale.

Database searched and no data found at this scale.

1.3.2 Linear features

Are there any records of linear features within 500m of the study site boundary at 1:10,000 scale? No


Database searched and no data found at this scale.

The geology map for the site and surrounding area are extracted from the BGS Digital Geological Map of great Britain at 1:10,000 scale.

This Geology shows the main components as discrete layers, these are: Bedrock/ Solid Geology and linear features such as faults. These are all displayed with the BGS Lexicon code for the rock unit and BGS sheet number. Not all of the main geological components have nationwide coverage.

2 Geology 1:50,000 Scale

2.1 Artificial Ground map



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



2. Geology 1:50,000 scale

2.1 Artificial Ground

The following geological information represented on the mapping is derived from 1:50,000 scale BGS Geological mapping, Sheet No: 081

2.1.1 Artificial/ Made Ground

Are there any records of Artificial/ Made Ground within 500m of the study site boundary? Yes


ID	Distance (m)	Direction	LEX Code	Description	Rock Description
1	441.0	SE	MGR-ARTDP	MADE GROUND (UNDIVIDED)	ARTIFICIAL DEPOSIT
2	479.0	E	MGR-ARTDP	MADE GROUND (UNDIVIDED)	ARTIFICIAL DEPOSIT

2.1.2 Permeability of Artificial Ground


Are there any records relating to permeability of artificial ground within the study site boundary? No

Database searched and no data found.

2.2 Superficial Deposits and Landslips map (1:50,000 scale)



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



2.2 Superficial Deposits and Landslips

2.2.1 Superficial Deposits/ Drift Geology

Are there any records of Superficial Deposits/ Drift Geology within 500m of the study site boundary? Yes

ID	Distance	Direction	LEX Code	Description	Rock Description
1	0.0	On Site	TILLD-DMTN	TILL, DEVENSIAN	DIAMICTON
2	0.0	On Site	TFD-XCZ	TIDAL FLAT DEPOSITS	CLAY AND SILT

2.2.2 Permeability of Superficial Ground

Are there any records relating to permeability of superficial ground within the study site boundary? Yes

Distance (m)	Direction	Flow Type	Maximum Permeability	Minimum Permeability
0.0	On Site	Intergranular	Low	Very Low
0.0	On Site	Mixed	High	Low

2.2.3 Landslip

Are there any records of Landslip within 500m of the study site boundary? No

Database searched and no data found.

The geology map for the site and surrounding area are extracted from the BGS Digital Geological Map of Great Britain at 1:50,000 scale.


This Geology shows the main components as discrete layers, there are: Artificial/ Made Ground, Superficial/ Drift Geology and Landslips. These are all displayed with the BGS Lexicon code for the rock unit and BGS sheet number. Not all of the main geological components have nationwide coverage.

2.2.4 Landslip Permeability


Are there any records relating to permeability of landslips within the study site boundary? No

Database searched and no data found.

2.3 Bedrock and linear features map (1:50,000 scale)



© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



2.3 Bedrock, Solid Geology & linear features

The following geological information represented on the mapping is derived from 1:50,000 scale BGS Geological mapping, Sheet No: 081

2.3.1 Bedrock/Solid Geology

Records of Bedrock/Solid Geology within 500m of the study site boundary:

ID	Distance	Direction	LEX Code	Rock Description	Rock Age
1	0.0	On Site	BCK-CHLK	BURNHAM CHALK FORMATION - CHALK	TURONIAN

2.3.2 Permeability of Bedrock Ground

Are there any records relating to permeability of bedrock ground within the study site boundary? Yes

Distance	Direction	Flow Type	Maximum Permeability	Minimum Permeability
0.0	On Site	Fracture	Very High	Very High

2.3.3 Linear features

Are there any records of linear features within 500m of the study site boundary? No

Database searched and no data found.

The geology map for the site and surrounding area are extracted from the BGS Digital Geological Map of Great Britain at 1:50,000 scale.

This Geology shows the main components as discrete layers, these are: Bedrock/Solid Geology and linear features such as faults. These are all displayed with the BGS Lexicon code for the rock unit and BGS sheet number. Not all of the main geological components have nation wide coverage.

3 Radon Data

3.1 Radon Affected Areas

Is the property in a Radon Affected Area as defined by the Health Protection Agency (HPA) and if so what percentage of homes are above the Action Level? The property is not in a Radon Affected Area, as less than 1% of properties are above the Action Level.

The radon data in this report is supplied by the BGS/Public Health England and is the definitive map of Radon Affected Areas in Great Britain and Northern Ireland. The dataset was created using long-term radon measurements in over 479,000 homes across Great Britain and 23,000 homes across Northern Ireland, combined with geological data. The dataset is considered accurate to 50m to allow for the margin of error in geological lines, and the findings of this report supercede any answer given in the less accurate Indicative Atlas of Radon in Great Britain, which simplifies the data to give the highest risk within any given 1km grid square. As such, the radon atlas is considered indicative, whereas the data given in this report is considered definitive.

3.2 Radon Protection






Is the property in an area where Radon Protection are required for new properties or extensions to existing ones as described in publication BR211 by the Building Research Establishment? No radon protective measures are necessary.

4 Ground Workings map



Ground Workings Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.

- | | | | |
|---|--------------------|---|----------------------------------|
|  | Site Outline |  | Historic Surface Ground Workings |
|  | Search Buffers (m) |  | Historic Underground Workings |
| | |  | Current Ground Workings |

4 Ground Workings

4.1 Historical Surface Ground Working Features derived from Historical Mapping

This dataset is based on Groundsure's unique Historical Land Use Database derived from 1:10,560 and 1:10,000 scale historical mapping

Are there any Historical Surface Ground Working Features within 250m of the study site boundary? Yes

ID	Distance (m)	Direction	NGR	Use	Date
1	83.0	W	516267 417234	Unspecified Heap	1983
2	185.0	W	516186 417187	Unspecified Heap	1983
3	236.0	SW	516021 417015	Cuttings	1930
4A	241.0	SW	516013 417033	Cuttings	1947
5A	244.0	SW	516022 417025	Cuttings	1951
6A	248.0	SW	516008 417028	Cuttings	1968
7B	248.0	SW	516190 416977	Cuttings	1974
8B	248.0	SW	516190 416977	Cuttings	1983

4.2 Historical Underground Working Features derived from Historical Mapping

This data is derived from the Groundsure unique Historical Land Use Database. It contains data derived from 1:10,000 and 1:10,560 historical Ordnance Survey Mapping and includes some natural topographical features (Shake Holes for example) as well as manmade features that may have implications for ground stability. Underground and mining features have been identified from surface features such as shafts. The distance that these extend underground is not shown.

Are there any Historical Underground Working Features within 1000m of the study site boundary? No

Database searched and no data found.


4.3 Current Ground Workings

This dataset is derived from the BGS BRITPITS database covering active; inactive mines; quarries; oil wells; gas wells and mineral wharves; and rail deposits throughout the British Isles.

Are there any BGS Current Ground Workings within 1000m of the study site boundary? No


Database searched and no data found.

5 Mining, Extraction & Natural Cavities map



Mining, Extraction and Natural Cavities Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



5 Mining, Extraction & Natural Cavities

5.1 Historical Mining

This dataset is derived from Groundsure unique Historical Land-use Database that are indicative of mining or extraction activities.

Are there any Historical Mining areas within 1000m of the study site boundary? No

Database searched and no data found.

5.2 Coal Mining

This dataset provides information as to whether the study site lies within a known coal mining affected area as defined by the coal authority.

Are there any Coal Mining areas within 1000m of the study site boundary? No

Database searched and no data found.

5.3 Johnson Poole and Bloomer

This dataset provides information as to whether the study site lies within an area where JPB hold information relating to mining.

Are there any JPB Mining areas within 1000m of the study site boundary? No

The following information provided by JPB is not represented on mapping: Database searched and no data found.

5.4 Non-Coal Mining

This dataset provides information as to whether the study site lies within an area which may have been subject to non-coal historic mining.

Are there any Non-Coal Mining areas within 1000m of the study site boundary? No

Database searched and no data found.

5.5 Non-Coal Mining Cavities

This dataset provides information from the Peter Brett Associates (PBA) mining cavities database (compiled for the national study entitled “Review of mining instability in Great Britain, 1990” PBA has also continued adding to this database) on mineral extraction by mining.

Are there any Non-Coal Mining cavities within 1000m of the study site boundary? No

Database searched and no data found.

5.6 Natural Cavities

This dataset provides information based on the Peter Brett Associates natural cavities database. The dataset is made up of points and polygons. Where polygons are used these represent an area in which it is expected the cavities could be found. It does not indicate that cavities are present everywhere within the polygon, and caution should be used in the interpretation of this data.

Are there any Natural Cavities within 1000m of the study site boundary? No

Database searched and no data found.

5.7 Brine Extraction

This data provides information from the Coal Authority issued on behalf of the Cheshire Brine Subsidence Compensation Board.

Are there any Brine Extraction areas within 1000m of the study site boundary? No

Database searched and no data found.

5.8 Gypsum Extraction

This dataset provides information on Gypsum extraction from British Gypsum records.

Are there any Gypsum Extraction areas within 1000m of the study site boundary? No

Database searched and no data found.

5.9 Tin Mining

This dataset provides information on tin mining areas and is derived from tin mining records. This search is based upon postcode information to a sector level..

Are there any Tin Mining areas within 1000m of the study site boundary? No

Database searched and no data found.

5.10 Clay Mining

This dataset provides information on Kaolin and Ball Clay mining from relevant mining records.


Are there any Clay Mining areas within 1000m of the study site boundary?

No

Database searched and no data found.

6 Natural Ground Subsidence

6.1 Shrink-Swell Clay map




Shrink Swell Clay Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6.2 Landslides map



Landslides Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6.3 Ground Dissolution of Soluble Rocks map




**Ground Dissolution
Soluble Rocks Legend**

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6.4 Compressible Deposits map




Compressible Deposits Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6.5 Collapsible Deposits map




Collapsible Deposits Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6.6 Running Sand map



Running Sand Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



6 Natural Ground Subsidence

The National Ground Subsidence rating is obtained through the 6 natural ground stability hazard datasets, which are supplied by the British Geological Survey (BGS).

The following GeoSure data represented on the mapping is derived from the BGS Digital Geological map of Great Britain at 1:50,000 scale.

What is the maximum hazard rating of natural subsidence within the study site** boundary? Moderate

6.1 Shrink-Swell Clays

The following Shrink Swell information provided by the British Geological Survey:

ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Low	Ground conditions predominantly medium plasticity. Do not plant trees with high soil moisture demands near to buildings. For new build, consideration should be given to advice published by the National House Building Council (NHBC) and the Building Research Establishment (BRE). There is a possible increase in construction cost to reduce potential shrink-swell problems. For existing property, there is a possible increase in insurance risk, especially during droughts or where vegetation with high moisture demands is present.
2	0.0	On Site	Very Low	Ground conditions predominantly low plasticity. No special actions required to avoid problems due to shrink-swell clays. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with shrink-swell clays.

6.2 Landslides

The following Landslides information provided by the British Geological Survey:

ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Very Low	Slope instability problems are unlikely to be present. No special actions required to avoid problems due to landslides. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with landslides.

* This includes an automatically generated 50m buffer zone around the site

6.3 Ground Dissolution of Soluble Rocks

The following Ground Dissolution information provided by the British Geological Survey:

ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Negligible	Soluble rocks are present, but unlikely to cause problems except under exceptional conditions. No special actions required to avoid problems due to soluble rocks. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with soluble rocks.

6.4 Compressible Deposits

The following Compressible Deposits information provided by the British Geological Survey:

ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Negligible	No indicators for compressible deposits identified. No special actions required to avoid problems due to compressible deposits. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with compressible deposits.
2	0.0	On Site	Moderate	Significant potential for compressibility problems. Avoid large differential loadings of ground. Do not drain or de-water ground near the property without technical advice. For new build - consider possibility of compressible ground in ground investigation, construction and building design. Consider effects of groundwater changes. Extra construction costs are likely. For existing property - possible increase in insurance risk from compressibility, especially if water conditions or loading of the ground change significantly.

6.5 Collapsible Deposits

The following Collapsible Rocks information provided by the British Geological Survey:


ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Very Low	Deposits with potential to collapse when loaded and saturated are unlikely to be present. No special ground investigation required or increased construction costs or increased financial risk due to potential problems with collapsible deposits.
2	0.0	On Site	Negligible	No indicators for collapsible deposits identified. No actions required to avoid problems due to collapsible deposits. No special ground investigation required, or increased construction costs or increased financial risk due to potential problems with collapsible deposits.

6.6 Running Sands

The following Running Sands information provided by the British Geological Survey:


ID	Distance (m)	Direction	Hazard Rating	Details
1	0.0	On Site	Moderate	Significant potential for running sand problems with relatively small changes in ground conditions. Avoid large amounts of water entering the ground (for example through pipe leakage or soak-aways). Do not dig (deep) holes into saturated ground near the property without technical advice. For new build - consider the consequences of soil and groundwater conditions during and after construction. For existing property - possible increase in insurance risk from running sand, for example, due to water leakage, high rainfall events or flooding.
2	0.0	On Site	Very Low	Very low potential for running sand problems if water table rises or if sandy strata are exposed to water. No special actions required, to avoid problems due to running sand. No special ground investigation required, and increased construction costs or increased financial risks are unlikely due to potential problems with running sand.

7 Borehole Records map



Borehole Records Legend

© Crown copyright and database rights 2018.
Ordnance Survey license 100035207.



7 Borehole Records

The systematic analysis of data extracted from the BGS Borehole Records database provides the following information.

Records of boreholes within 250m of the study site boundary:

2

ID	Distance (m)	Direction	NGR	BGS Reference	Drilled Length	Borehole Name
1	0.0	On Site	517020 417150	TA11NE48	27.0	ST CRISPINS CHURCH SOUTH KILLINGHOLME
2	130.0	SE	517160 417050	TA11NE9	25.0	KILLINGHOLME MARSH LINCS

The borehole records are available using the hyperlinks below: Please note that if the donor of the borehole record has requested the information be held as commercial-in-confidence, the additional data will be held separately by the BGS and a formal request must be made for its release.

#1: scans.bgs.ac.uk/sobi_scans/boreholes/461020

#2: scans.bgs.ac.uk/sobi_scans/boreholes/460967

8 Estimated Background Soil Chemistry

Records of background estimated soil chemistry within 250m of the study site boundary:


12

For further information on how this data is calculated and limitations upon its use, please see the Groundsure Geo Insight User Guide, available on request.

Distance (m)	Direction	Sample Type	Arsenic (As)	Cadmium (Cd)	Chromium (Cr)	Nickel (Ni)	Lead (Pb)
0.0	On Site	RuralSoil	15 - 25 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	15 - 25 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	15 - 25 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	15 - 25 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
0.0	On Site	RuralSoil	<15 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg
20.0	SE	RuralSoil	15 - 25 mg/kg	<1.8 mg/kg	90 - 120 mg/kg	30 - 45 mg/kg	<100 mg/kg


*As this data is based upon underlying 1:50,000 scale geological information, a 50m buffer has been added to the search radius.

9 Railways and Tunnels map



Railways and Tunnels Legend

© Crown copyright and database rights 2018.
 Ordnance Survey license 100035207.
 © OpenStreetMapContributors



9 Railways and Tunnels

9.1 Tunnels

This data is derived from OpenStreetMap and provides information on the possible locations of underground railway systems in the UK - the London Underground, the Tyne & Wear Metro and the Glasgow Subway.

Have any underground railway lines been identified within the study site boundary? No

Have any underground railway lines been identified within 250m of the study site boundary? No

Database searched and no data found.

Any records that have been identified are represented on the Railways and Tunnels map.

This data is derived from Ordnance Survey mapping and provides information on the possible locations of railway tunnels forming part of the UK overground railway network.

Have any other railway tunnels been identified within the site boundary? No

Have any other railway tunnels been identified within 250m of the site boundary? No

Database searched and no data found.

Any records that have been identified are represented on the Railways and Tunnels map.

9.2 Historical Railway and Tunnel Features

This data is derived from Groundsure's unique Historical Land-use Database and contains features relating to tunnels, railway tracks or associated works that have been identified from historical Ordnance Survey mapping.

Have any historical railway or tunnel features been identified within the study site boundary? No

Have any historical railway or tunnel features been identified within 250m of the study site boundary? Yes

ID	Distance (m)	Direction	NGR	Details	Date
1A	23	SW	515726 417603	Railway Sidings	1983
2A	23	SW	515726 417603	Railway Sidings	1974
3	60	S	516391 416738	Railway Sidings	1972
4	62	SW	516462 416927	Railway Sidings	1972
5	116	SW	516046 417031	Railway Sidings	1985
6B	162	NW	516238 417664	Railway Sidings	1985

ID	Distance (m)	Direction	NGR	Details	Date
7B	190	NW	516229 417676	Railway Sidings	1970

Any records that have been identified are represented on the Railways and Tunnels map.

9.3 Historical Railways

This data is derived from OpenStreetMap and provides information on the possible alignments of abandoned or dismantled railway lines in proximity to the study site.

Have any historical railway lines been identified within the study site boundary? No

Have any historical railway lines been identified within 250m of the study site boundary? No

Database searched and no data found.

Multiple sections of the same track may be listed in the detail above

Any records that have been identified are represented on the Railways and Tunnels map.

9.4 Active Railways

These datasets are derived from Ordnance Survey mapping and OpenStreetMap and provide information on the possible locations of active railway lines in proximity to the study site.

Have any active railway lines been identified within the study site boundary? No

Have any active railway lines been identified within 250m of the study site boundary? Yes

Distance (m)	Direction	Name	Type
14	S	Not given	Rail
14	S	Not given	Rail
14	S	Not given	Rail
14	S	Not given	Rail
16	S	Not given	Multi Track
16	S	Not given	Multi Track
19	S	Not given	Rail
19	S	Not given	Rail
34	SW	Not given	Rail
34	W	Not given	Multi Track
34	W	Not given	Multi Track
34	SW	Not given	Rail
37	S	Not given	Multi Track
37	S	Not given	Multi Track
38	W	Not given	Rail
38	W	Not given	Rail
40	NW	Not given	Multi Track
40	NW	Not given	Multi Track
41	W	Not given	Rail
41	NW	Not given	Multi Track
41	NW	Not given	Multi Track
41	W	Not given	Rail
47	SW	Not given	Rail

Distance (m)	Direction	Name	Type
47	SW	Not given	Rail
48	W	Not given	Rail
48	W	Not given	Rail
61	S	Not given	Rail
61	S	Not given	Rail
63	S	Not given	Multi Track
63	S	Not given	Multi Track
64	NW	Not given	Rail
64	NW	Not given	Rail
65	S	Not given	Rail
65	S	Not given	Rail
66	SW	Not given	Rail
66	SW	Not given	Rail
70	S	Not given	Rail
70	S	Not given	Rail
71	S	Not given	Rail
71	S	Not given	Rail
85	S	Not given	Rail
85	S	Not given	Rail
101	SW	Not given	Rail
101	SW	Not given	Rail
119	SW	Not given	Multi Track
119	SW	Not given	Multi Track
120	SW	Not given	Rail
120	SW	Not given	Rail
159	NW	Not given	Rail
159	NW	Not given	Rail
196	NW	Not given	Rail
196	NW	Not given	Rail
206	SW	Not given	Multi Track
206	SW	Not given	Multi Track
225	NW	Not given	Rail
225	NW	Not given	Rail
229	NW	Not given	Rail
229	NW	Not given	Rail
236	SW	Not given	Multi Track
236	SW	Not given	Multi Track
238	SW	Not given	Multi Track
238	SW	Not given	Multi Track

Multiple sections of the same track may be listed in the detail above
Any records that have been identified are represented on the Railways and Tunnels map.

9.5 Railway Projects

These datasets provide information on the location of large scale railway projects High Speed 2 and Crossrail 1 .

Is the study site within 5km of the route of the High Speed 2 rail project? No

Is the study site within 500m of the route of the Crossrail 1 rail project? No

*Further information on proximity to these routes, the project construction status and associated works can be obtained through the purchase of a **Groundsure HS2 and Crossrail 1 Report**.*

The route data has been digitised from publicly available maps by Groundsure. The route as provided relates to the Crossrail 1 project only, and does not include any details of the Crossrail 2 project, as final details of the route for Crossrail 2 are still under consultation.

Please note that this assessment takes account of both the original Phase 2b proposed route and the amended route proposed in 2016. As the Phase 2b route is still under consultation, Groundsure are providing information on both options until the final route is formally confirmed. Practitioners should take account of this uncertainty when advising clients.

Contact Details

Groundsure Helpline
Telephone: 08444 159 000
info@groundsure.com



British Geological Survey Enquiries

Kingsley Dunham Centre
Keyworth, Nottingham NG12 5GG
Tel: 0115 936 3143.
Fax: 0115 936 3276.
Email: enquiries@bgs.ac.uk
Web: www.bgs.ac.uk



BGS Geological Hazards Reports and general geological enquiries

British Gypsum

British Gypsum Ltd
East Leake
Loughborough
Leicestershire
LE12 6HX



The Coal Authority

200 Lichfield Lane
Mansfield
Notts NG18 4RG
Tel: 0345 7626 848
DX 716176 Mansfield 5
www.coal.gov.uk



Public Health England

Public information access office
Public Health England, Wellington House
133-155 Waterloo Road, London, SE1 8UG
<https://www.gov.uk/government/organisations/public-health-england>
Email: enquiries@phe.gov.uk
Main switchboard: 020 7654 8000



Johnson Poole & Bloomer Limited

Harris and Pearson Building, Brettel Lane
Brierley Hill, West Midlands
DY5 3LH
Tel: +44 (0) 1384 262 000
Email: enquiries.gs@jpb.co.uk
Website: www.jpb.co.uk



Ordnance Survey

Adanac Drive, Southampton
SO16 0AS
Tel: 08456 050505
Website: <http://www.ordnancesurvey.co.uk/>



Getmapping PLC

Virginia Villas, High Street, Hartley Witney,
Hampshire RG27 8NW
Tel: 01252 845444
Website: <http://www.1.getmapping.com/>



Peter Brett Associates
Caversham Bridge House
Waterman Place
Reading
Berkshire RG1 8DN
Tel: +44 (0)118 950 0761 E-mail: reading@pba.co.uk
Website: <http://www.peterbrett.com/home>



Acknowledgements: Ordnance Survey © Crown Copyright and/or Database Right. All Rights Reserved. Licence Number [03421028]. This report has been prepared in accordance with the Groundsure Ltd standard Terms and Conditions of business for work of this nature.

Standard Terms and Conditions

Groundsure's Terms and Conditions can be viewed online at this link:
<https://www.groundsure.com/terms-and-conditions-may25-2018>

Appendix B – Factual Report on Ground Investigation, Report No A8015-18, August 2018



VPI IMMINGHAM

FACTUAL REPORT ON GROUND INVESTIGATION

Report No A8015-18

August 2018







Client:
AECOM Environmental Solutions Ltd,
AECOM House,
66-77 Victoria Street,
St Albans,
AL1 3ER

SOCOTEC UK Limited

Askern Road, Carcroft
Doncaster DN6 8DG
Tel: +44 (0) 1302 723456
email: geo.doncaster@socotec.com

Report No A8015-18

August 2018

Issue No Date	Status	Prepared by	Checked by	Approved by
1 Jul 2018	Draft report	NAME and QUALIFICATIONS W Hopkins BSc (Hons)	NAME and QUALIFICATIONS T Clifford BEng FGS	NAME and QUALIFICATIONS T Clifford BEng FGS
		SIGNATURE 	SIGNATURE 	SIGNATURE 
2 Aug 2018	Final report	NAME and QUALIFICATIONS W Hopkins BSc (Hons)	NAME and QUALIFICATIONS T Clifford BEng FGS	NAME and QUALIFICATIONS T Clifford BEng FGS
		SIGNATURE 	SIGNATURE 	SIGNATURE 

This Report has been prepared by SOCOTEC UK Limited ("SOCOTEC") with all reasonable skill and care, within the terms and conditions of the contract between SOCOTEC and the Client ("Contract") and within the limitations of the resources devoted to it by agreement with the Client.

This Report shall not be used for engineering or contractual purposes unless the Report status is 'Final' and signed by the author, checker and the approver for and on behalf of SOCOTEC.

Whilst every effort has been made to ensure the accuracy of the data supplied and any analysis interpretation derived from it, the possibility exists of variations in the ground and groundwater conditions around and between the exploratory positions. SOCOTEC shall not be liable for any use of the Report for any purpose other than that for which it was originally prepared. No liability can be accepted for any such variations in these conditions. Furthermore, any recommendations are specific to the development as detailed in this Report and no liability will be accepted should they be used for the design of alternative schemes without prior consultant with SOCOTEC.

This Report is confidential between the Client and SOCOTEC. Any reliance upon the Report is subject to the Contract terms and conditions.

SOCOTEC accepts no responsibility whatsoever to third parties to whom this document, or any part thereof, is made known. Any such party relies upon the Report at their own risk. The Contracts (Rights of Third Parties) Act 1999 does not apply to this Report nor the Contract and the provisions of the said Act are hereby excluded.

Unless specifically assigned or transferred within the terms and conditions of the Contract, SOCOTEC asserts and retains all Copyright and other Intellectual Property Rights in and over the Report and its contents. The Report may not be copied or reproduced, in whole or in part, without the written authorisation from SOCOTEC.

SOCOTEC UK Limited was formerly known as Environmental Scientifics Group Limited. The Certificate of Incorporation on Change of Name was filed on 16 October 2017.

CONTENTS

	Page
1 INTRODUCTION	1
2 SITE SETTING	1
2.1 Location and Description	1
2.2 Published Geology	2
3 FIELDWORK	2
3.1 General	2
3.2 Exploratory Holes	2
3.3 Groundwater and Gas Monitoring	3
4 LABORATORY TESTING	3
REFERENCES	4

APPENDIX A FIGURES AND DRAWINGS

APPENDIX B EXPLORATORY HOLE RECORDS

APPENDIX C INSTRUMENTATION AND MONITORING

APPENDIX D GEOTECHNICAL LABORATORY TEST RESULTS

APPENDIX E PHOTOGRAPHS

1 INTRODUCTION

In March 2018 SOCOTEC UK Limited was commissioned by AECOM Environmental Solutions Ltd (AECOM) on behalf of VPI Immingham, to carry out a ground investigation at Total Lindsey Oil Refinery (TLOR). The investigation was required to obtain geotechnical information for the proposed development.

The scope of the investigation was specified by AECOM and comprised cable percussion and rotary drilled boreholes, trial pits and laboratory testing. The investigation was performed in accordance with the contract specification, and the general requirements of BS 5930 (2015), BS EN 1997-2 (2007), BS EN ISO 22475-1 (2006) and other relevant related standards identified below. The fieldwork took place between 5 and 20 April.

This report presents the factual records of the fieldwork and laboratory testing. The information is also presented as digital data as defined in AGS (2017).

2 SITE SETTING

2.1 Location and Description

The site is adjacent to the east side of Total Lindsey Oil Refinery, approximately 4 km north west of Immingham town centre, Lincolnshire. The National Grid reference is TA 167 175, see Site Location Plan in Appendix A.

The site is a L-shaped parcel of land, approximately 350 by 200 m, and generally flat and level.

The majority of the site, the southern portion (about 350 by 120 m), comprises rough grass and scrub land, which is boggy in places. There are several soil mounds, up to about 5 m in height.

The north west portion is within the perimeter fence of the adjacent car park, and comprises a compacted generally flat hardcore surface with very little vegetation.

To the north the site is bound by a carpark, belonging to TLOR, and to the west is infrastructure associated with the refinery, including access roads, railway lines, plant and equipment. To the south is VPI Immingham, a power generation facility. To the east is open farmland and the Humber Estuary beyond, approximately 500 m away.

2.2 Published Geology

The published geological map for the area, BGS Sheet 90 (1990) and the BGS Geology of Britain Viewer (2018) show the site located on Glacial Till over bedrock of the Burnham Chalk Formation.

3 FIELDWORK

3.1 General

The exploratory hole locations were selected by AECOM and set out from local features. The coordinates and reduced levels were surveyed by SOCOTEC to National Grid and Ordnance Datum and the locations are shown on the Site Plan in Appendix A

3.2 Exploratory Holes

The exploratory holes are listed in the following table.

TABLE 1: SUMMARY OF EXPLORATORY HOLES

TYPE	QUANTITY	DEPTH RANGE (m)	REMARKS
Cable Percussion Boring	3	22.34 to 28.66	BH1, BH2 and BH5
Cable Percussion Boring extended by Rotary Core Drilling/Open Hole Drilling	3	28.60 to 34.60	BH3, BH4 and BH6
Dynamic Sampling	8	3.75 to 5.45	WS1 to WS8
Trial Pits/ Trenches	13	2.50 to 4.60	TP1 to TP10 and TT1 to TT3

The exploratory hole logs are presented in Appendix B. These provide information including the equipment and methods used, samples taken, tests carried out, water observations and descriptions of the strata encountered. Explanation of the terms and abbreviations used on the logs is given in the Key to Exploratory Hole Records in Appendix B, together with other explanatory information. The logging of soil and rock materials is in accordance with BS 5930 (2015).

Standard penetration tests (SPT) in the boreholes were carried out in accordance with BS EN ISO 22476-3+A1 (2011) and the SPT hammer energy ratio certificate is included in Appendix B. The SPT results are presented on the logs as uncorrected N values.

Photographs of the trial pits and rotary drilled core are presented in Appendix E.

On completion of the fieldwork geotechnical samples were transported to the Doncaster laboratory of SOCOTEC for testing and temporary retention.

3.3 Groundwater and Gas Monitoring

Instrumentation installed in the exploratory holes for groundwater and gas monitoring are shown on the logs and summarised in Appendix C. SOCOTEC were not required to undertake any post fieldwork.

4 LABORATORY TESTING

Geotechnical laboratory testing was scheduled by AECOM and was carried out in accordance with BS 1377 (1990), unless otherwise stated. The testing is summarised below and the results are presented in Appendix E.

- Moisture Content Determination
- Atterberg Limit Determination
- Particle Density
- Particle Size Distribution Analysis
- Unconsolidated Undrained Triaxial Compression Testing
- Consolidated Undrained Triaxial Compression Testing
- One Dimensional Oedometer Consolidation Testing
- Determination of Consolidation Properties Using a Hydraulic Cell
- Dry Density / Moisture Content Relationship
- California Bearing Ratio
- pH, Water Soluble Sulphate, Acid Soluble Sulphate and Total Sulphur Content of Soils Test methods are BS 1377 or others recognised in BRE Special Digest 1 (2005)
- Loss on Ignition
- Organic Matter

REFERENCES

AGS : 2017 : Electronic transfer of geotechnical and geoenvironmental data (Edition 4.0.4 February 2017). Association of Geotechnical and Geoenvironmental Specialists.

BGS England and Wales Sheet 90 : 1990 : Grimsby. 1:50,000 geological map (solid and drift). British Geological Survey.

BGS Geology of Britain Viewer : 2018. www.bgs.ac.uk. British Geological Survey.

BRE Special Digest 1 : 2005 : Concrete in aggressive ground. Building Research Establishment.

BS 1377 : 1990 : Methods of test for soils for civil engineering purposes. British Standards Institution.

BS 5930 : 2015 : Code of practice for ground investigations. British Standards Institution.

BS EN 1997-2 : 2007 : Eurocode 7 - Geotechnical design - Part 2 Ground investigation and testing. British Standards Institution.

BS EN ISO 14688-1:2002+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil - Part 1 Identification and description. British Standards Institution.

BS EN ISO 14688-2:2004+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil - Part 2 Principles for a classification. British Standards Institution.

BS EN ISO 14689-1 : 2003 : Geotechnical investigation and testing - Identification and classification of rock - Part 1 Identification and description. British Standards Institution.

BS EN ISO 22475-1 : 2006 : Geotechnical investigation and testing – Sampling methods and groundwater measurements - Part 1 Technical principles for execution. British Standards Institution.

BS EN ISO 22476-3:2005+A1 : 2011 : Geotechnical investigation and testing - Field testing - Part 3 Standard penetration test. British Standards Institution.

APPENDIX A
FIGURES AND DRAWINGS

Site Location Plan
Site Plan

A1
A2

Site Location Plan



**THE
SITE**

Reproduced from the 2006 Ordnance Survey 1:50 000 scale Landranger map No 113 by permission of Ordnance Survey on behalf of The Controller of Her Majesty's Stationery Office, © Crown copyright, Environmental Services Group Limited. All rights reserved. Licence Number 100006060

Notes:
Scale 1:50 000

Project **VPI IMMINGHAM**
Project No. **A8015-18**
Carried out for **AECOM**

Figure




A1



GENERAL NOTES

1. Reproduced from VPI Immingham's Drawing No. VP11-IMMB-CIV-CI01-0001.
2. Hole Locations to National Grid Co-ordinate Reference System.

LEGEND TO SYMBOLS

-  Borehole
-  Window Sample
-  Trial Pit

Scale: 1:1200



x	x	x	x	x	x
Rev	Drawn	Date	Approv.	Date	Modification Details

AMENDMENTS


Title	SITE PLAN				
-------	-----------	--	--	--	--

Project	VPI IMMINGHAM				
---------	---------------	--	--	--	--

Client	AECOM Environmental Solution Ltd				
--------	-------------------------------------	--	--	--	--



Date	04/06/2018	Drawn By	BS	Approv. By	WH
Sheet Size	A3	Scale	1:1200	Project No	A8015-18
Drawing No	A2			Rev	0



APPENDIX B
EXPLORATORY HOLE RECORDS

Key to Exploratory Hole Records	Key
SPT Hammer Energy Ratio Report	SPT Hammer Reference: SW15470 AR2068 DART235
Borehole Logs	BH1 to BH6
Borehole Logs (Dynamic Sampling)	WS1 to WS8
Trial Pit and Trench Logs	TP1 to TP10 and TT1 to TT3

Key to Exploratory Hole Records

SAMPLES

Undisturbed

U	Driven tube sample	} nominally 100 mm diameter and full recovery unless otherwise stated
UT	Driven thin wall tube sample	
TW	Pushed thin wall tube sample	
P	Pushed piston sample	
L	Liner sample from dynamic (windowless) sampling. Full recovery unless otherwise stated	
CBR	CBR mould sample	
BLK	Block sample	
C / CS	Core sample (from rotary core) taken for laboratory testing.	
AMAL	Amalgamated sample	

Disturbed

D	Small sample
B	Bulk sample

Other

W	Water sample
G	Gas sample

ES	Environmental chemistry samples (in more than one container where appropriate)
EW	Soil sample
	Water sample

Comments

Sample reference numbers are assigned to every sample taken. A sample reference of 'NR' indicates that, while an attempt was made to take a tube sample, there was no recovery.

Samples taken from borehole installations (ie water or gas) after hole construction are not shown on the exploratory hole logs.

Specimens for point load testing undertaken on site (or other non-lab location) are not shown on the log.

IN SITU TESTS

SPT S or SPT C Standard Penetration Test, open shoe (S) or solid cone (C)

The Standard Penetration Test is defined in BS EN ISO 22476-3:2005+A1:2011. The incremental blow counts are given in the Field Records column; each increment is 75 mm unless stated otherwise and any penetration under self-weight in mm (SW) is noted. Where the full 300 mm test drive is achieved the total number of blows for the test drive is presented as N = ** in the Test column. Where the test drive blows reach 50 the total blow count beyond the seating drive is given (without the N = prefix).

IV	<i>in situ</i> vane shear strength, peak (p) and remoulded (r)
HV	Hand vane shear strength, peak (p) and remoulded (r)
PP	Pocket penetrometer test, converted to shear strength
KFH, KRH, KPI	Permeability tests (KFH = falling head, KRH = rising head; KPI = packer inflow); results provided in Field Records column (one value per stage for packer tests)

DRILLING RECORDS

The mechanical indices (TCR/SCR/RQD & If) are defined in BS 5930:2015

TCR	Total Core Recovery, %
SCR	Solid Core Recovery, %
RQD	Rock Quality Designation, %
If	Fracture spacing, mm. Minimum, typical and maximum spacing measurements are presented.
NI	The term non-intact (NI) is used where the core is fragmented.
NA	Used where a measurement is not applicable (eg. If, SCR and RQD in non-rock materials).

Flush returns, estimated percentage with colour where relevant, are given in the Records column

CRF	Core recovered (length in m) in the following run
AZCL	Assessed zone of core loss

GROUNDWATER

▼	Groundwater entry
▽	Depth to groundwater after standing period

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
Project No. A8015-18
Carried out for AECOM Environmental Solutions Ltd

Key

Sheet 1 of 3

Key to Exploratory Hole Records

INSTALLATION

Details of standpipe/piezometer installations are given on the Record. Legend column shows installed instrument depths including slotted pipe section or tip depth, response zone filter material type and layers of backfill.

**Standpipe/
piezometer**

The type of instrument installed is indicated by a code in the Legend column at the depth of the response zone:

SP	Standpipe			
SPIE	Standpipe piezometer	Plain Pipe		
PPIE	Pneumatic piezometer			Slotted Pipe
EPIE	Electronic piezometer			
				Piezometer Tip

**Inclinometer or
Slip Indicator**

The installation of vertical profiling instruments is indicated on the Record. The base of tubing is shown in the Legend column.

	The type of instrument installed is indicated by a code in the Legend column at the base of the tubing:
ICE	Biaxial inclinometer
ICM	Inclinometer tubing for use with probe
SLIP	Slip indicator

**Settlement
Points or
Pressure Cells**

The installation of single point instruments is indicated on the Record. The location of the measuring device is shown in the Legend column.

	The type of instrument installed is indicated by a code in the Legend column:
ESET	Electronic settlement cell/gauge
ETM	Magnetic extensometer settlement point
EPCE	Electronic embedment pressure cell
PPCE	Electronic push in pressure cell

**INSTALLATION /
BACKFILL
LEGENDS**

A legend describing the installation is shown in the rightmost column. Legend symbols used to describe the backfill materials are indicated below.

Macadam	Concrete	Grout	Bentonite	Sand	Gravel	Arisings

**STRATUM
LEGENDS**

The legend symbols used for graphical representation of soils, rocks and other materials on the borehole logs are shown below. For soils with significant proportions of secondary soil types, a combination of two or more symbols may be used.

Macadam	Concrete	Topsoil	Made Ground / Fill	Peat	Void or No Information	
Clay	Silt	Sand	Gravel	Cobbles	Boulders	Coal
Mudstone	Siltstone	Sandstone	Conglomerate	Breccia	Limestone	Chalk
Igneous (Fine)	Igneous (Med)	Igneous (Coarse)	Metamorphic (Fine)	Metamorphic (Med)	Metamorphic (Coarse)	Tuff

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
Project No. A8015-18
Carried out for AECOM Environmental Solutions Ltd

Key

Sheet 2 of 3

Key to Exploratory Hole Records

NOTES

- 1 Soils and rocks are described in accordance with BS EN ISO 14688-1:2002+A1:2013 and 14689-1:2003 respectively as amplified by BS 5930:2015.
- 2 For fine soils, consistency determined during description is reported for those strata where undisturbed samples are available. Where the logger considers that the sample may not be representative of the condition in situ, for whatever reason, the reported consistency is given in brackets. The reliability of the sample is indicated by Probably or Possibly as appropriate. Hence (Probably firm) indicates the logger is reasonably confident of the assessment, but (Possibly firm) means less certainty. Where the samples available are too disturbed to allow a reasonable assessment of the in situ condition, no consistency is given.
- 3 Evidence of the occurrence of very coarse particles (cobbles and boulders) is presented on the logs. However, because of their size in relation to the exploratory hole these records may not be fully representative of their size and frequency in the ground mass.
- 4 The declination of bedding and joints is given with respect to the normal to the core axis. Thus in a vertical borehole this will be the dip.
- 5 The assessment of SCR, RQD and Fracture Spacing excludes artificial fractures.
- 6 Observations of discernible groundwater entries during the advancement of the exploratory hole are given at the foot of the log and in the Legend column. The absence of a recorded groundwater entry should not, however, be interpreted as a groundwater level below the base of the borehole. Under certain conditions groundwater entry may not be observed, for instance, drilling with water flush or overwater, or boring at a rate faster than water can accumulate in the borehole. Similarly, where water entry observations do exist, groundwater may also be present at higher elevations in the ground than where recorded in the borehole. In addition, where appropriate, water levels in the hole at the time of recovering individual samples or carrying out in situ tests and at shift changes are given in the Records column.
- 7 The borehole logs present the results of Standard Penetration Tests recorded in the field without correction or interpretation. However, in certain ground conditions (eg high hydraulic head or where very coarse particles are present) some judgement may be necessary in considering whether the results are representative of in situ mass conditions.

REFERENCES

- 1 BS EN ISO 14688-1:2002+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil. Part 1 Identification and description. British Standards Institution
- 2 BS EN ISO 14689-1 : 2003 : Geotechnical investigation and testing - Identification and classification of rock. Part 1 Identification and description. British Standards Institution
- 3 BS EN ISO 22476-3:2005+A1 : 2011 : Geotechnical investigation and testing - Field testing. Part 3 Standard penetration test. British Standards Institution
- 4 BS 5930 : 2015 : Code of practice for ground investigations. British Standards Institution

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
Project No. A8015-18
Carried out for AECOM Environmental Solutions Ltd

Key

Sheet 3 of 3

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX5 9JP

SPT Hammer Ref: AR1940
Test Date: 21/09/2017
Report Date: 21/09/2017
File Name: AR1940.spt
Test Operator: SH

Instrumented Rod Data





Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 200
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm²): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 332

Energy Ratio E_r (%): **70**

Signed: M.GARDNER

Title: FITTER

The recommended calibration interval is 12 months

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX5 9JP

SPT Hammer Ref: AR2068
Test Date: 15/12/2017
Report Date: 15/12/2017
File Name: AR2068.spt
Test Operator: SH

Instrumented Rod Data





Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 200
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm^2): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 296

Energy Ratio E_r (%): **63**

Signed: M.GARDNER
Title: FITTER

The recommended calibration interval is 12 months

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX59JP

SPT Hammer Ref: DART235
Test Date: 13/04/2017
Report Date: 13/04/2017
File Name: DART235.spt
Test Operator: SH

Instrumented Rod Data




Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 208
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm²): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 276

Energy Ratio E_r (%): **58**

[Redacted Signature]

Signed: S. HOWARTH
Title: FITTER

The recommended calibration interval is 12 months

Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516528.04
Checked	TC	End		14.00	14.00	200	14.00	National Grid	N 417415.39
Approved	TC	11/04/2018			28.50	150	28.50		

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	(Thickness)			
0.10	D 1	0.00-1.20 Hand excavated inspection pit.			Brown sandy clayey GRAVEL. Gravel is angular to subangular fine to coarse of chalk and limestone.		0.10 (0.10) +6.26			
0.20 - 0.40	B 2				(MADE GROUND)		(0.35)			
0.45	D 3				Brown, locally greyish brown, slightly sandy gravelly CLAY. Gravel is angular fine to coarse of chalk and mudstone. Strong hydrocarbon odour.		0.45 +5.91			
0.50 - 0.70	B 4				(MADE GROUND)		(0.65)			
1.00 - 1.20	B 5		05/04/18	1800 Dry	Greyish brown, locally dark grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to coarse of slag, mudstone, sandstone and chalk. Strong hydrocarbon odour.	1.10-1.20 locally dark grey, occasional rootlets	1.10 +5.26			
1.20 - 1.65	UT 6	52 blows 100% rec	06/04/18	0800 Dry	(MADE GROUND)					
1.65 - 1.80	D 7				Stiff brown, locally mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of quartz, mudstone, sandstone and chalk.					
2.00 - 2.45	SPTS D 8	N=25 (3,4/5,6,7,7)	1.70	Dry						
2.50 - 3.00	B 9						(2.70)			
3.00 - 3.45	UT 10	56 blows 100% rec	2.80	Dry						
3.45 - 3.60	D 11									
3.80	W 14				Thinly laminated brown, locally light grey, CLAY with frequent gravel size pockets of fine to coarse sand.		3.80 +2.56			
4.00 - 4.45	SPTS D 12	N=14 (2,2/3,3,4,4)	3.90	Dry			(0.20)			
4.00 - 4.45	B 13				Stiff, becoming very stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, sandstone, mudstone and quartz.		4.00 +2.36			
5.00 - 5.45	UT 15	50 blows 100% rec	4.70	Dry						
5.45 - 5.60	D 16									
6.50 - 6.95	SPTS D 17	N=14 (2,2/3,3,4,4)	4.70	Dry						
7.00 - 7.50	B 18									
7.20	D 19					7.10-8.40 locally sandy				
8.00 - 8.45	UT 20	38 blows 100% rec	4.70	Dry						
8.45	B 21						(9.00)			
8.50	W 21A									
9.50 - 9.95	SPTS D 22	N=14 (2,3/3,3,4,4)	9.20	Dry						
9.50 - 10.00	B 23									

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	3.80		Rose to 2.30 m after 20 minutes. Medium inflow	4.00						
2	8.50		Rose to 6.30 m after 20 minutes. Medium inflow	9.00						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:20				Sheet 1 of 3

Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring.	1.20	14.00	200	14.00	Coordinates (m)	E 516528.04
Checked	TC	End	SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	14.00	28.50	150	28.50	National Grid	N 417415.39
Approved	TC	11/04/2018							

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
11.00 - 11.45	UT 24	40 blows 100% rec	9.20	Dry	Stiff, becoming very stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, sandstone, mudstone and quartz.				
11.45 - 11.60	D 25								
12.50 - 12.95 12.50 - 12.95	SPTS D 26	N=31 (5,5/6,7,8,10)	9.20	Dry	Medium dense brown gravelly very silty fine to coarse SAND. Gravel is angular to subrounded fine to coarse of chalk and flint.		13.00 -6.64		
13.00 13.00 - 13.50	D 28 B 27						(1.80)		
13.50	W 30								
14.00 - 14.45 14.00 - 14.45	SPTS D 29	N=10 (3,3/2,3,2,3)	9.20	10.00	Medium dense brown sandy slightly clayey GRAVEL. Gravel is angular to subangular fine to coarse of flint and chalk.				
			06/04/18 9.20	1800 10.00					
14.80	D 31		09/04/18 9.20	0800 3.80			14.80 -8.44		
15.00 - 15.50	B 32				Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and rare flint.				
15.50 - 15.95 15.50 - 15.95	SPTS D 33	N=28 (3,3/5,5,8,10)	15.00	10.00				(0.90)	
16.00 - 17.00	B 34						15.70 -9.34		
17.00 - 17.45	UT 35	78 blows 100% rec	16.50	15.00		17.10 becoming greyish brown			
17.45 - 17.60	D 36								
18.50 - 18.77 18.50 - 18.77 18.50 - 19.00	SPTS D 37 B 38	50 (15,10 for 50mm/23,27 for 70mm)	18.00	17.00			(5.80)		

Groundwater Entries				Depth Related Remarks				Hard Boring			
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
3	13.50		Rose to 9.00 m after 20 minutes. Fast inflow				14.50 - 14.80	60	Chisel		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:20				Sheet 2 of 3

Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring.	1.20	14.00	200	14.00	Coordinates (m)	E 516528.04
Checked	TC	End	SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	14.00	28.50	150	28.50	National Grid	N 417415.39
Approved	TC	11/04/2018							

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
20.00 - 20.40	UT 39	100 blows 56% rec	19.50	19.50	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and rare flint.					
20.40 - 20.50	D 40									
21.00 - 21.50	B 41				Very stiff light grey slightly sandy gravelly silty CLAY. Gravel is subangular to subrounded fine to coarse of chalk.					
21.50 - 21.79 21.50 - 21.79	SPTS D 42	50 (10,15 for 60mm/22,25,3 for 5mm)	19.50	20.00						
22.50 - 22.70 22.50 22.50 - 22.70	SPTS UT NR D 43	50 (25 for 75mm/28,22 for 55mm) 100 blows No Recovery	09/04/18 19.50	1800 20.00						
23.00 - 24.00	B 44		10/04/18 19.50	0800 9.00						
24.00 - 24.28 24.00 - 24.28	SPTS D 45	50 (15,10 for 45mm/20,27,3 for 5mm)	23.50	10.00						
25.00 - 25.22 25.00 - 25.22	SPTS D 46	50 (20,5 for 15mm/25,25 for 60mm)	24.90	8.00						
26.00 - 26.22 26.00 - 26.22 26.00 - 27.00	SPTS D 47 B 48	50 (25 for 75mm/27,23 for 65mm)	25.90 10/04/18 25.90	8.00 1700 8.00						
27.50 - 27.78 27.50 - 27.78 27.50 - 28.50	SPTS D 49 B 50	50 (15,10 for 50mm/22,24,4 for 5mm)	27.50	7.00						
28.50 - 28.66 28.50 - 28.66	SPTS D 51	50 (25 for 60mm/38,12 for 20mm)	11/04/18 28.50	1500 9.00						
					END OF EXPLORATORY HOLE					

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
4	21.00		Rose to 19.80 m after 20 minutes. Medium inflow		24.50 - 26.00		24.50 - 26.00	180	Chisel	
					26.50 - 27.50		26.50 - 27.50	120	Chisel	

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:20				Sheet 3 of 3

Borehole Log



Drilled	GC	Start	11/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	14.50	Diameter (mm)	200	Casing Depth (m)	14.50	Ground Level	5.43 mOD
Logged	WH	End	16/04/2018				14.50		22.20		150		22.20	Coordinates (m)	E 516588.10
Checked	TC													National Grid	N 417353.62
Approved	TC														

Samples and Tests

Samples and Tests				Strata Description					
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.20 0.30 - 0.50	D 1 B 2	0.00-1.20 Hand excavated inspection pit.			Dark brown sandy very gravelly CLAY with high cobble content. Gravel is subrounded fine to coarse of various lithologies including chalk, macadam and sandstone. Cobbles are subrounded of chalk.		(0.50)		
0.60 0.60 - 1.00	D 3 B 4				(MADE GROUND)		0.50 +4.93		
1.00 1.00 - 1.20 1.20 - 1.65	D 5 B 6 UT 7	30 blows 100% rec		Dry	Dark brown and black very gravelly very silty fine to coarse SAND. Gravel is subangular fine to coarse of chalk and sandstone. Strong hydrocarbon odour.		1.00 +4.43		
1.65 - 1.80	D 8				(MADE GROUND)				
1.80 - 2.25	SPTS D 9 B 10	N=13 (2,2/3,4,4)	11/04/18	1800	Firm dark greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular medium of flint and chalk.				
1.80 - 2.25				1.50					
2.20 - 2.70	B 13								
2.25 - 2.70	UT NR	28 blows No Recovery	12/04/18	0800					
				2.00			(3.20)		
2.70 - 2.80	D 12								
2.80 - 3.25	SPTS D 14	N=15 (1,2/3,3,4,5)	1.70	Dry					
2.80 - 3.25									
3.30 - 3.75	UT 15	45 blows 100% rec	1.70	Dry					
3.75 - 3.90	D 16								
3.90 - 4.35	SPTS D 17 B 18	N=15 (6,7/4,3,3,5)	2.90	Dry					
3.90 - 4.35			3.90	Dry					
4.00 - 4.45	UT NR	36 blows No Recovery							
4.45 - 4.60	D 20				Brown mottled grey CLAY.	4.45 slightly gravelly sandy, gravel is subangular fine of chalk and mudstone	(0.50)		
4.60 - 5.05	SPTS D 21 B 27	N=17 (2,2/3,4,4,6)	4.50	4.00			4.70 +0.73		
4.60 - 5.05					Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular fine to medium of sandstone and chalk.				
5.10 - 5.55	UT 28	38 blows 100% rec	5.00	4.80					
5.55 - 5.70	D 29								
5.70 - 6.15	SPTS D 30 B 31	N=25 (3,4/5,6,7,7)	5.60	Dry					
5.70 - 6.15									
6.50 - 6.95	UT NR B 33	48 blows No Recovery	6.00	Dry					
6.50 - 7.00									
7.10 - 7.55	SPTS D 34 B 35	N=22 (3,4/4,5,6,7)	6.00	Dry					
7.10 - 7.55									
8.00 - 8.45	UT 36	60 blows 100% rec	6.00	Dry					
8.45 - 8.60	D 37								
8.60 - 9.05	SPTS D 38 B 39	N=27 (3,4/5,7,7,8)	6.00	Dry					
8.60 - 9.05									
9.50 - 9.95	UT 40	62 blows 100% rec	6.00	Dry			(9.40)		
9.95 - 10.10	D 41								

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth (m)	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
1	1.80		Rose to 1.50 m after 20 minutes. Slow inflow									
2	4.20		Rose to 3.80 m after 20 minutes. Slow inflow	5.00								

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:21				Sheet 1 of 3

Borehole Log



Drilled	GC	Start	11/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	14.50	Diameter (mm)	200	Casing Depth (m)	14.50	Ground Level	5.43 mOD
Logged	WH	End	16/04/2018				14.50		22.20		150		22.20	Coordinates (m)	E 516588.10
Checked	TC													National Grid	N 417353.62
Approved	TC														

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.10 - 10.55	SPTS D 42	N=22 (3,4,4,5,6,7)	6.00	Dry	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular fine to medium of sandstone and chalk.				
10.10 - 10.55	B 43								
10.10 - 10.55									
11.00 - 11.45	UT 44	64 blows 100% rec	6.00	Dry					
11.45 - 11.60	D 45								
11.60 - 12.05	SPTS D 46	N=23 (3,4/4,5,6,8)	6.00	Dry					
11.60 - 12.05	B 47								
12.50 - 12.95	UT 48	70 blows 100% rec	6.00	Dry					
12.95 - 13.10	D 49								
13.10 - 13.55	SPTS D 50	N=30 (4,6/6,7,8,9)	6.00	Dry					
13.10 - 13.55	B 51								
14.00 - 14.45	UT NR B 53	80 blows No Recovery	6.00	Dry	Firm light brown sandy very gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and mudstone.		14.10 -8.67		
14.00 - 14.60	W 59						14.40 -8.97		
14.60 - 15.05	SPTS D 54	N=39 (7,8/10,10,9,10)	14.50	10.00	Firm to stiff light brown sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and flint. Occasional gravel size pockets of fine to medium sand.				
14.60 - 15.05							(2.00)		
15.20	D 55								
15.50 - 15.95	UT 56	70 blows 33% rec	14.50	10.00					
16.20 - 16.65	SPTS D 57	N=37 (6,8/8,9,10,10)	15.50	7.00	Stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to medium of chalk.		16.40 -10.97		
16.20 - 16.65	B 58								
16.40 - 17.00									
17.00 - 17.45	UT 60	55 blows 56% rec	12/04/18 16.50	1800 7.00					
17.45 - 17.60	D 61								
17.60 - 18.05	SPTS D 62	N=35 (3,5/7,8,10,10)	16.50	5.00	17.45-18.05 light grey silty fine to coarse sand		(3.10)		
17.60 - 18.05									
18.50 - 18.95	UT NR B 63	60 blows No Recovery	18.40	9.00					
18.50 - 19.00									
19.10 - 19.55	SPTS D 64	N=35 (4,6/7,8,9,11)	18.40	9.00					
19.10 - 19.55									
19.50	D 65				Stiff to very stiff brownish grey slightly sandy CLAY with occasional gravel. Gravel is subangular fine to medium of chalk.		19.50 -14.07		

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
3	14.10		Rose to 10.00 m after 20 minutes. Medium inflow									

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:21				Sheet 2 of 3

Borehole Log



Drilled	GC	Start	11/04/2018	Equipment, Methods and Remarks Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	WH	End	16/04/2018		(m)	(m)	(mm)	(m)	Coordinates (m)	E 516588.10
Checked	TC				1.20	14.50	200	14.50	National Grid	N 417353.62
Approved	TC				14.50	22.20	150	22.20		

Samples and Tests

Samples and Tests					Strata Description					
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill	
20.00 - 20.45	UT 66	100 blows 56% rec	20.00	11.00	Stiff to very stiff brownish grey slightly sandy CLAY with occasional gravel. Gravel is subangular fine to medium of chalk.					
20.60 - 20.93 20.60 - 20.93 20.60 - 21.00	SPTS D 67 B 68	50 (12,13 for 65mm/17,21,12 for 40mm)	20.00	11.00				(2.84)		
21.50 - 21.64 21.50 - 21.64	SPTS D 69	50 (25 for 50mm/42,8 for 10mm)	21.00	11.00						
22.20 - 22.34 22.20 - 22.34	SPTS D 70	50 (25 for 50mm/39,11 for 15mm)	13/04/18 21.50 11.00 16/04/18 0800 21.50 6.00 16/04/18 1000 22.20 8.00							
					END OF EXPLORATORY HOLE					

Groundwater Entries				Depth Related Remarks				Hard Boring			
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
							21.90 - 21.90	180	Chisel		
							21.90 - 22.20	60	Chisel		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:21				Sheet 3 of 3

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.00	200	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018				146			

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	(Thickness)			
0.40 - 1.20	B 1	0.00-1.20 Hand excavated inspection pit.			Firm brown, locally mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of quartz, sandstone, chalk and mudstone.	0.00-1.20 occasional rootlets				
1.20 - 1.65	SPTS D 2	N=16 (3,4/4,4,4,4)	1.20	Dry			(3.00)			
1.65 - 2.00	B 3									
2.00 - 2.45	SPTS D 4	N=13 (3,3/3,4,3,3)	1.50	Dry						
2.50 - 3.00	B 5									
3.00 - 3.45	SPTS D 6	N=8 (1,2/2,2,2,2)	1.50	1.10	Firm thinly laminated brown CLAY with frequent partings of fine to medium sand.		3.00	+2.43		
3.50 - 4.00	B 7						(0.70)			
4.00 - 4.45	SPTS D 8	N=13 (2,2/3,3,3,4)	4.00	Dry	Medium dense brown slightly gravelly very silty fine to medium SAND. Gravel is angular to subrounded fine to medium of various lithologies.		3.70	+1.73		
4.50 - 5.00	B 9						(0.80)			
5.00 - 5.45	UT 10	39 blows 100% rec	4.50	Dry	Stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, quartz and sandstone.		4.50	-0.93		
5.45 - 5.65	D 11									
5.65 - 6.00	B 12									
6.00 - 6.45	SPTS D 13	N=22 (3,3/4,6,6,6)	6.00	Dry						
6.50 - 7.10	B 14									
7.50 - 7.95	UT 15	49 blows 100% rec	7.50	Dry		7.10-7.40 foreman reports reddish brown sand 7.40 becoming greyish brown				
7.95 - 8.15	D 16									
8.15 - 8.60	SPTS D 17	N=23 (3,3/4,5,6,8)	7.50	Dry						
8.60 - 9.00	B 18									
9.00 - 9.45	UT 19	59 blows 100% rec	9.00	Dry			(8.80)			
9.45 - 9.65	D 20									
9.65 - 10.10	SPTS D 21	N=29 (3,5/7,7,8,7)	9.50	Dry						

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	3.00		Rose to 1.10 m after 20 minutes.	3.60						
2	7.10		Rose to 4.15 m after 20 minutes.	7.40						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH3
Scale 1:50	Project No.	A8015-18		Sheet 1 of 3
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.60	200	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018				146			

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	(Thickness)			
10.00 - 10.50	B 22				Stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, quartz and sandstone.					
10.50 - 10.95	UT 23	76 blows 100% rec	10.50	Dry						
10.95 - 11.15 11.00 - 12.00 11.15 - 11.60 11.15 - 11.60	D 24 B 26 SPTS D 25	N=36 (4,6/7,9,11,9)	11.00	Dry						
12.00 - 12.45	UT 27	69 blows 100% rec	12.00	Dry						
12.45 - 12.65 12.65 - 13.10 12.65 - 13.10 12.80 - 13.30	D 28 SPTS D 29 B 30	N=30 (3,5/5,7,9,9)	12.00	Dry						
13.50 - 13.95 13.50 13.50 - 13.95	SPTS D 31 D 32	N=11 (1,2/2,3,3,3)	12.00	7.90	Medium dense greenish brown gravelly clayey fine to medium SAND. Gravel is angular to subrounded fine to coarse of various lithologies. Occasional gravel size pockets of clay.		13.30 (0.80)	-7.87	3	
14.10 - 15.00	B 33				Stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, quartz, sandstone and mudstone.					
15.00 - 15.45 15.00 - 15.45	SPTS D 34	N=11 (2,3/2,2,3,4)	11/04/18 15.00	1700 7.00						
			12/04/18 15.00	0800 3.30	Medium dense yellowish brown gravelly fine to medium SAND. Gravel is angular to subrounded fine to coarse of various lithologies. Occasional gravel size pockets of clay.					
16.00 - 16.50	B 35				Grey slightly sandy clayey SILT. Rare subangular fine to medium gravel of chalk.					
16.50 - 16.77 16.50 - 16.80	SPTS D 36	57 (10,15 for 60mm/28,29 for 60mm)	16.50	5.10						
17.00 - 18.00	B 37									
18.00 - 18.20 18.00 - 18.30	SPTS D 38	50 (15,10 for 50mm/50 for 70mm)	18.00	Dry						
18.60 - 19.50	B 39									
19.50 - 19.75 19.50 - 19.80	SPTS D 40	50 (11,14 for 50mm/22,28 for 50mm)	19.50	Dry	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
3	13.30		Rose to 6.10 m after 20 minutes.	14.10						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH3
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:22				Sheet 2 of 3

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	1.20	28.00	200	28.00	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.60	146	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018							

Samples and Tests

Samples and Tests				Strata Description					
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
20.00 - 21.00	B 41				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.				
21.00 - 21.20 21.00 - 21.30	SPTS D 42	50 (19,6 for 10mm/31,19 for 40mm)	21.00	Dry					
22.00 - 22.50	B 43								
22.50 - 22.62 22.50 - 22.70	SPTS D 44	50 (25 for 75mm/50 for 40mm)	22.50	Dry				(8.10)	
23.00 - 24.00	B 45								
24.00 - 24.14 24.00 - 24.10	SPTS D 46		12/04/18 24.00	1700 Dry			24.00 becoming locally gravelly		
25.00 - 25.50	B 47								
25.50 - 25.62 25.50 - 25.62	SPTS D 48	50 (25 for 75mm/50 for 50mm)	25.50	Dry					
26.00 - 26.50	B 49								
26.80 - 27.02 26.80 - 27.02 27.00 - 27.50	SPTS D 50 B 51	50 (18,7 for 10mm/28,22 for 60mm)	26.50	8.70		Extremely weak white CHALK. Recovered as gravelly clay. Gravel is angular to subangular fine to coarse of chalk with rare flint.	27.00 becoming recovered as clayey angular fine to coarse gravel	26.80 -21.37 (1.20)	
28.00 - 28.10		50 (25 for 60mm/50 for 40mm)	13/04/18 28.00	1630 4.10	Medium strong white CHALK. Recovered as subangular to subrounded fine to coarse gravel.				
28.00 - 28.60	42 0 0	NI -	16/04/18 28.00	1300 0.70				28.00 -22.57 (0.60)	
		Flush: 28.00 - 28.60 Air/mist 100%	16/04/18 28.00	1700 0.70					
					END OF EXPLORATORY HOLE			28.60 -23.17	

Depth	TCR	SCR	RQD	If	Records	Date Casing	Time Water	Groundwater Entries		Depth Related Remarks		Hard Boring				
								No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
								4	26.80	Rose to 8.70 m after 20 minutes.				27.60 - 28.00	60	Chisel

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175/Beretta T44. Cable percussion boring /Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516726.70
Checked	TC	End		24.00	24.00	200	16.50	National Grid	N 417410.38
Approved	TC	20/04/2018			34.60	146	28.60		

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date	Time	Main	Detail	(Thickness)			
			Casing	Water						
0.50 - 1.20	B 1	0.00-1.20 Hand excavated inspection pit.			Light brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone with frequent rootlets. (TOPSOIL)		(0.30)			
1.20 - 1.65	SPTS D 2	N=16 (2,3/4,4,4,4)	1.20	Dry	Firm brown, mottled grey and light brown, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, flint and sandstone.		+3.89			
1.65 - 2.00	B 3						(2.90)			
2.00 - 2.45	UT 4	59 blows 100% rec	1.50	Dry						
2.45 - 2.65	D 5									
2.65 - 3.10	SPTS D 6	N=15 (2,3/3.4,3.5)	1.50	Dry						
3.10 - 3.55	UT 7	51 blows 100% rec	3.00	Dry	Soft brown very sandy CLAY.		+0.99			
3.75 - 4.20	SPTS D 8	N=6 (1,2/1,2,1,2)	3.00	1.00		3.55 brown clayey sand	(0.95)			
4.00 - 4.50	B 9									
4.50 - 4.95	UT 10	47 blows 100% rec	4.50	Dry	Stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk and sandstone.		+0.04			
4.95 - 5.15	D 11									
5.15 - 5.60	SPTS D 12	N=22 (2,3/4,6,6,6)	4.50	Dry						
5.50 - 6.00	B 13						(2.95)			
6.00 - 6.45	UT 14	42 blows 100% rec	6.00	Dry						
6.45 - 6.65	D 15									
6.65 - 7.10	SPTS D 16	N=24 (2,3/4,6,6,8)	6.00	Dry						
7.20 - 7.50	B 17		16/04/18 6.00	1700 2.10		7.10-7.20 fine sand and gravel	7.10	-2.91		
7.50 - 7.95	UT 18	51 blows 100% rec	7.50	Dry	Stiff to very stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.					
7.95 - 8.15	D 19									
8.15 - 8.60	SPTS D 20	N=25 (4,4/5,6,7,7)	7.50	Dry						
8.50 - 9.00	B 21									
9.00 - 9.45	UT 22	42 blows 100% rec	9.00	Dry						
9.65 - 10.10	SPTS D 23	N=23 (3,4/5,5,7,6)	9.00	Damp			(4.90)			

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	3.20		Rose to 1.00 m after 20 minutes.	4.15						
2	7.40		Rose to 2.10 m after 20 minutes.	7.20						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		Sheet 1 of 4
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush.	1.20	24.00	200	16.50	Coordinates (m)	E 516726.70
Checked	TC	End	SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	24.00	34.60	146	28.60	National Grid	N 417410.38
Approved	TC	20/04/2018							

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.00 - 10.50	B 24				Stiff to very stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.				
10.50 - 10.95	UT 25	40 blows 100% rec	10.50	Dry					
10.95 - 11.15	D 26								
11.15 - 11.60	SPTS D 27	N=24 (3,4/5,6,6,7)	10.50	Dry					
11.50 - 12.00	B 28								
12.00 - 12.45	SPTS D 29	N=33 (4,4/6,7,9,11)	10.50	7.20	Brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk, sandstone and flint.	12.00-12.30 driller notes reddish brown fine sand	12.00 -7.81		3
12.50 - 13.00	B 30					12.50 becomes light brown sandy	(1.40)		
13.50 - 13.95	SPTS D 31	N=37 (5,5/7,10,9,11)	13.50	2.10	Stiff to very stiff light yellowish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, sandstone and flint.		13.40 -9.21		4
14.00 - 15.00	B 32					14.00-15.00 becoming slightly gravelly clayey sand			
15.00 - 15.45	SPTS D 33	N=16 (3,3/4,3,4,5)	15.00	1.10			(3.70)		5
15.50 - 16.00	B 34					15.50-16.00 sandy clayey gravel			
16.50 - 16.95	SPTS	N=44 (6,8/7,11,13,13)	16.50	1.30					
			17/04/18	1700					
			16.50	1.30					
17.10 - 17.50	B 36		18/04/18	0800	Dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		17.10 -12.91		
			16.50	1.30			(0.70)		
18.00 - 18.45	SPTS D 37	N=13 (2,3/2,3,3,5)			Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		17.80 -13.61		5
18.00 - 18.45	B 38						(1.30)		
18.00 - 19.00									
19.50 - 19.74	SPTS D 39				Very stiff greyish brown slightly sandy slightly gravelly CLAY with pockets of coarse gravel size extremely weak weathered chalk. Gravel is subrounded fine to coarse of chalk.		19.10 -14.91		
19.50 - 19.70									

Groundwater Entries			Depth Related Remarks			Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
3	12.00	Rose to 6.95 m after 20 minutes.	12.30	13.50 - 16.50	Water added to assist boring.			
4	13.40	Rose to 4.10 m after 20 minutes.						
5	17.80	Rose to 15.10 m after 20 minutes.						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:23				Sheet 2 of 4

Borehole Log



Drilled	SS/MB	Start	16/04/2018	Equipment, Methods and Remarks	Dando 175/Beretta T44. Cable percussion boring /Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	24.00	Diameter (mm)	200	Casing Depth (m)	16.50	Ground Level	4.19 mOD
Logged	WH/PC	End	20/04/2018				24.00		34.60		146		28.60	Coordinates (m)	E 516726.70
Checked	TC													National Grid	N 417410.38
Approved	TC														

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
20.00 - 21.00	B 40				Very stiff greyish brown slightly sandy slightly gravelly CLAY with pockets of coarse gravel size extremely weak weathered chalk. Gravel is subrounded fine to coarse of chalk.		(2.30)		
21.00 - 21.22 21.00 - 21.25	SPTS D 41				Very stiff dark greyish brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk.	21.00-21.25 white chalk, possible cobble	21.40 -17.21		
22.00 - 22.50	B 42						(2.00)		
22.50 - 22.64 22.50 - 22.60	SPTS D 43	50 (18,7 for 10mm/50 for 60mm)							
23.00 - 24.00	B 44						23.40 -19.21		
24.00 - 24.15 24.00 - 24.15	SPTS D 45	50 (25/50 for 60mm)	18/04/18 16.50	1700	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and flint.	24.00-24.15 light grey clayey silt	(0.60) 24.00 -19.81		
			19/04/18 18/04/18 16.50	0800 0800 0.85	Stiff grey clay. (Rotary open hole drilling) (Drillers description)		(4.50)		
28.50 - 30.00	90 6 0	NI NI 80			Medium strong to strong white CHALK. Fractures are: 1) subhorizontal, very closely spaced, undulating, rough with occasional grey staining. 2) subvertical, undulating, rough with occasional grey staining.	28.60-28.72 recovered as subangular gravel with rare angular flint 28.86-28.96 grey flint nodule 29.30-30.00 recovered as gravel 29.44-29.47 soft cream mottled greyish green clay with frequent angular fine gravel	28.50 -24.31 (2.15)		
						of chalk 30.00-30.27 AZCL			

Groundwater Entries				Depth Related Remarks				Hard Boring			
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
6	24.00	Rose to 9.60 m after 20 minutes.				21.40 - 21.90 23.40 - 24.00	40 60				

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:23				Sheet 3 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175. Beretta T44. Cable percussion boring. Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516726.70
Checked	TC	End	SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	24.00	34.60	200	28.60	National Grid	N 417410.38
Approved	TC	20/04/2018							

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	(Thickness)		
30.00 - 31.50	82 35 11			19/04/18 28.60	1700 0.85	Medium strong to strong white CHALK. Fractures are: 1) subhorizontal, very closely spaced, undulating, rough with occasional grey staining. 2) subvertical, undulating, rough with occasional grey staining.	30.27-30.37 recovered as subangular coarse gravel	30.65	-26.46	
			Flush: 28.50 - 34.60 Air/ mist 100%	20/04/18 28.60	0800 1.00	Strong white CHALK. Fractures are subhorizontal, very closely spaced, undulating, rough with brownish grey staining and rare infill of very soft greyish brown CLAY.	30.51-30.57 recovered as subangular coarse gravel			
31.50 - 32.10	47 12 0						31.50-31.81 AZCL			
32.10 - 33.10	100 46 19	NI 60 180					32.42-32.46 recovered as subangular coarse gravel	(3.95)		
33.10 - 34.10	100 44 15						32.64-32.75 recovered as subangular medium to coarse gravel including flint			
34.10 - 34.60	100 66 30			20/04/18 28.60	1700 1.00		32.77-33.00 subvertical undulating smooth fracture with clay infill 33.00-33.02 recovered as grey angular to subangular gravel of flint			
						END OF EXPLORATORY HOLE	33.40-33.42 rare subangular coarse gravel of flint 33.80-33.82 recovered as grey angular fine to medium gravel of flint	34.60	-30.41	

Groundwater Entries				Depth Related Remarks				Chiselling Details				
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:24				Sheet 4 of 4

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	13.00	Diameter (mm)	200	Casing Depth (m)	13.00	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018				13.00		26.10		150		26.00	Coordinates (m)	E 516748.31
Checked	TC													National Grid	N 417439.50
Approved	TC														

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
0.10 - 0.40	D 1 B 2	0.00-1.20 Hand excavated inspection pit.			Dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.		(0.40)			
0.50 - 0.80	D 3 B 4				(TOPSOIL) Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to medium of flint.		0.40 +4.25 (0.50)			
1.00 - 1.20 1.20 - 1.65	D 5 B 6 UT 7	35 blows 89% rec		Dry	Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk, flint and mudstone.		0.90 +3.75			
1.65 - 1.80 1.80 - 2.25 1.80 - 2.25 1.80 - 2.25	D 8 SPTS D 9 B 10	N=16 (2,3/3,4,4,5)		Dry						
2.30 - 2.75	UT 11	38 blows 100% rec	1.70	Dry						
2.75 - 2.90 2.90 - 3.35 2.90 - 3.35 2.90 - 3.35	D 12 SPTS D 13 B 14	N=19 (3,4/4,5,5,5)	1.70	Dry		2.90-4.45 gravel is subangular to subrounded	(3.60)			
3.40 - 3.85	UT 15	32 blows 100% rec	3.00	Dry						
3.85 - 3.90 4.00 - 4.45 4.00 - 4.45 4.00 - 4.45	D 16 SPTS D 17 B 18	N=17 (2,3/4,4,4,5)	3.00	Dry						
4.50 - 4.95 4.50	UT 20 D 19	40 blows 100% rec	4.40	Dry	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine of chalk, sandstone and mudstone.		4.50 +0.15			
4.95 - 5.10 5.10 - 5.55 5.10 - 5.55 5.10 - 5.55	D 21 SPTS D 22 B 22A	N=13 (2,2/3,3,3,4)	4.40	Dry						
6.50 - 6.95	UT 23	46 blows 100% rec	4.60	Dry						
6.95 - 7.10 7.10 - 7.55 7.10 - 7.55 7.10 - 7.55	D 24 SPTS D 25 B 26	N=15 (2,3/3,4,4,4)	4.60	Dry						
8.00 - 8.45	UT 27	60 blows 100% rec	4.60	Dry						
8.45 - 8.60 8.60 - 9.05 8.60 - 9.05 8.60 - 9.05	D 28 SPTS D 29 B 30	N=29 (3,5/6,7,8,8)	4.60	Dry			(7.90)			
9.50 - 9.95	UT 31	50 blows 100% rec	4.60	Dry						
9.95 - 10.10	D 32									

Groundwater Entries			Depth Related Remarks		Hard Boring			
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 3
14/08/2018 13:42:24				

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	13.00	Diameter (mm)	200	Casing Depth (m)	13.00	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018				13.00		26.10		150		26.00	Coordinates (m)	E 516748.31
Checked	TC													National Grid	N 417439.50
Approved	TC														

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.10 - 10.55 10.10 - 10.55 10.10 - 10.55	SPTS D 33 B 34	N=30 (2,4/7,7,8,8)	4.60	Dry	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine of chalk, sandstone and mudstone.				
11.00 - 11.45	UT 35	60 blows 100% rec	4.60	Dry					
11.45 - 11.60 11.60 - 12.05 11.60 - 12.05 11.60 - 12.05	D 36 SPTS D 37 B 38	N=31 (4,6/7,7,8,9)	4.60	Dry		11.45-12.05 dark brown, gravel is fine to medium			
12.40 12.50 - 12.95 12.50 - 12.95 12.50 - 12.95	W 41 SPTS D 39 B 40	N=32 (4,6/7,7,8,10)	4.60	Dry	Stiff light brown slightly sandy gravelly CLAY. Gravel is subrounded fine to medium of chalk, sandstone and mudstone.		12.40 -7.75		
13.00	D 42		17/04/18 4.60	1800 12.10					
14.00 - 14.45	UT 43	70 blows 100% rec	13.50				(2.10)		
14.45 - 14.60 14.60 - 15.05 14.60 - 15.05 14.60 - 15.05	D 44 SPTS D 45 B 46	N=46 (7,8/9,10,13,14)	13.50		Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and mudstone.		14.50 -9.85		
15.50 - 15.95	UT 47	100 blows 100% rec	15.00						
15.95 - 16.10 16.10 - 16.48 16.10 - 16.48 16.10 - 16.48	D 48 SPTS D 49 B 50	50 (8,10/13,18,19 for 75mm)	15.00	Dry		16.10 becoming light grey	(3.10)		
17.00 - 17.36 17.00 - 17.36 17.00 - 17.36	SPTS D 51 B 52	50 (10,12/14,17,19 for 65mm)	15.00	Dry					
17.70 17.70 - 18.50	D 53 B 54				Very stiff light grey slightly sandy slightly gravelly CLAY with coarse gravel size pockets of extremely weak chalk. Gravel is subrounded fine to medium of chalk.		17.60 -12.95		
18.50 - 18.86 18.50 - 18.86 18.50 - 18.86	SPTS D 55 B 56	50 (11,13/15,18,17 for 65mm)	18.00	18.00	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk.		18.50 -13.85		

Groundwater Entries				Depth Related Remarks				Hard Boring			
No.	Depth (m)	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
1	12.40		Rose to 12.10 m after 20 minutes. Slow inflow								
2	17.60		Rose to 16.70 m after 20 minutes. Medium inflow	18.00							

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:24				Sheet 2 of 3

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from	to	Diameter	Casing Depth	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018		(m)	(m)	(mm)	(m)	Coordinates (m)	E 516748.31
Checked	TC	End	19/04/2018		13.00	26.10	200	13.00	National Grid	N 417439.50
Approved	TC	End	19/04/2018		13.00	26.10	150	26.00		

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
20.00 - 20.28 20.00 - 20.28 20.00 - 20.28	SPTS D 57 B 58	50 (12,13 for 55mm/20,30 for 75mm)	19.50	19.50	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk.				
21.50 - 21.74 21.50 - 21.74 21.50 - 21.74	SPTS D 59 B 60	50 (20,5 for 15mm/26,24 for 70mm)	21.00	21.00				(7.65)	
23.00 - 23.21 23.00 - 23.21 23.00 - 23.21	SPTS D 61 B 62	50 (18,2 for 20mm/30,20 for 40mm)	22.50	22.00			23.00-23.30 including gravel of sandstone		
24.50 - 24.62 24.50 - 24.62 24.50 - 24.62	SPTS D 63 B 64	45 (25 for 20mm/33,12 for 25mm)	23.50	24.00					
25.60 - 25.72 25.60 - 25.72	SPTS D 65	50 (25 for 50mm/50 for 70mm)	18/04/18 25.00	1800 24.00					
26.10 - 26.15	SPTC	50 (25 for 20mm/50 for 30mm)	19/04/18 26.00	0800 21.00 1530 23.00	END OF EXPLORATORY HOLE		26.15 -21.50		

Groundwater Entries			Depth Related Remarks			Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
						25.40 - 25.60	60	Chisel
						25.70 - 26.10	180	Chisel

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 3 of 3
14/08/2018 13:42:24				

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	34.50	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018				146			

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date	Time	Main	Detail	(Thickness)			
			Casing	Water						
0.00 - 0.30	B 1	0.00-1.20 Hand excavated inspection pit.			Greyish brown very sandy clayey GRAVEL. Gravel is angular to subrounded fine to coarse of mudstone, sandstone, chalk and brick. (MADE GROUND)		(0.30)			
0.30 - 0.55	B 2						0.30 +4.41			
0.55 - 1.20	B 3				Firm brown, locally greyish brown, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and sandstone.		(0.30)			
1.20 - 1.65	SPTS D 4	N=14 (1,2/2,4,4,4)	1.20	Dry	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of predominantly chalk, mudstone, quartz and sandstone and rare coal.		0.60 +4.11			
1.65 - 2.00	B 5									
2.00 - 2.45	UT 6	71 blows 100% rec	1.50							
2.45 - 2.65	D 7						(4.05)			
3.00 - 3.45	SPTS D 8	N=16 (3,4/3,4,4,5)	3.00	Dry						
3.00 - 3.45										
3.50 - 4.00	B 9									
4.00 - 4.45	UT 10	60 blows 100% rec	4.00							
4.45 - 4.65	D 11		05/04/18	1700						
			4.00	2.50						
5.00 - 5.45	SPTS D 12	N=10 (1,1/1,2,3,4)	06/04/18	0800	Firm thinly laminated CLAY with occasional partings of fine sand. Frequent gravel size pockets of fine to coarse sand.		4.65 +0.06			
5.00 - 5.45			4.00	2.00			(0.65)			
5.45 - 5.50			4.60	2.90						
5.50 - 6.00	B 13				Stiff to very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk, mudstone and sandstone.		5.30 -0.59			
6.00 - 6.45	UT 14	71 blows 100% rec	6.00							
6.45 - 6.65	D 15									
7.00 - 7.50	B 16									
7.50 - 7.95	SPTS D 17	N=18 (3,3/4,4,5,5)	7.50	Dry						
7.50 - 7.95										
8.00 - 9.00	B 18									
9.00 - 9.45	UT 19	61 blows 100% rec	9.00				(7.60)			
9.45 - 9.65	D 20									

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	4.65		Rose to 2.50 m after 20 minutes.	5.30						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 1 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	1.20	24.60	200	24.60	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	34.50	146	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018							

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
10.00 - 10.50	B 21				Stiff to very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk, mudstone and sandstone.					
10.50 - 10.95	SPTS D 22	N=18 (3,3/4,5,4,5)	10.50	Dry						
11.00 - 11.80	B 23				Brown gravelly clayey fine to coarse SAND. Gravel is subangular to subrounded fine to coarse of chalk and flint.					
12.00 - 12.45	SPTS D 24	N=21 (3,4/5,4,6,6)	12.00	4.10			11.80-12.00 occasional gravel size pockets of gravelly fine to coarse sand. Gravel is angular to subangular fine to coarse of chalk			
13.00 - 13.50	B 25				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.					
13.50 - 13.95	SPTS D 26	N=4 (1,0/1,1,1,1)	13.50	9.10			13.50 SPT may be affected by groundwater disturbance at base of hole (piping)			
14.00 - 15.00	B 27									
15.00 - 15.45	SPTS D 28	N=34 (6,6/7,9,10,8)	06/04/18 15.00	1630 9.10						
15.00 - 15.45			09/04/18 15.00	0800 10.40						
15.50 - 16.50	B 29									
16.50 - 16.95	SPTS D 30	N=28 (7,7/7,7,7,7)	16.50	14.10						
17.50 - 18.00	B 31									
18.00 - 18.45	SPTS D 32	N=28 (6,7/6,7,7,8)	18.00	Dry						
18.50 - 19.50	B 33									
19.50 - 19.95	SPTS D 34	N=39 (7,8/9,10,10,10)	19.50	Dry						
19.50 - 19.95	B 35									
19.50 - 21.00										

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
2	11.80	Rose to 3.10 m after 20 minutes.								
3	18.60	Rose to 16.60 m after 20 minutes.	18.70							

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 2 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	24.60	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018							

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
21.00 - 21.45 21.00 - 21.45	SPTS D 36	N=33 (4,5/5,9,9,10)	21.00	Dry	Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
21.50 - 22.50	B 37				Extremely weak cream CHALK. Recovered as gravelly clay.		21.50 -16.79	4	
22.50 - 22.95 22.50 - 22.95	SPTS D 38	N=44 (7,8/9,10,13,12)	22.00	13.00	Very weak white, locally orangish brown, CHALK. Recovered as subangular fine to coarse gravel to cobbles.		22.50 -17.79		
23.00 - 23.80	B 39		09/04/18 22.00	1700 13.00					
23.80 - 23.91	SPTC	50 (25 for 60mm/50 for 50mm)	22.50	4.00			23.80 -19.89		
24.25 - 24.30	SPTC	50 (25 for 30mm/50 for 20mm)	10/04/18 22.50	1010 4.00					
24.60 - 25.60	95 46 30		13/04/18 22.50	0800 2.60	Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, undulating, rough with dark brown staining. 2. Subvertical, planar, smooth with yellowish brown staining. 3. Incipient fractures are very closely spaced, stepped, striated.		24.60 -19.89		
25.60 - 27.10	95 49 37	NI 100 196				26.85-26.98 1No. subangular cobble of flint 27.02-27.30 AZCL	(2.95)		
27.10 - 28.40	80 21 8	NI NI 90			Weak cream, occasionally speckled black, CHALK. Recovered as slightly silty subangular fine to coarse gravel. Fractures are subhorizontal, closely spaced, undulating, rough with yellowish brown staining.		27.55 -22.84		
28.40 - 29.90	77 30 17	NI 120 170			Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, planar, rough with dark greyish brown staining. 2. Occasionally subvertical, planar, smooth. 3. Incipient fractures are subhorizontal, extremely closely spaced, stepped, rough with occasional dark grey staining.	28.34-28.60 AZCL 28.55 rare subangular coarse gravel of flint 29.59-30.66 1No. cobble of flint 29.75-29.95 AZCL	28.70 -23.99		
		Flush: 24.60 - 34.50 Air/mist 100%					(2.20)		

Depth	TCR	SCR	RQD	If	Records	Date Casing	Time Water	Groundwater Entries	Depth Related Remarks	Hard Boring	Tool used
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
4	21.50		Rose to 16.10 m after 20 minutes.				23.80 - 24.25	60	Chisel		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 3 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175. Beretta T44. Cable percussion boring. Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	24.60	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018			34.50	146			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
29.90 - 31.40	97 63 40					Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, planar, rough with dark greyish brown staining. 2. Occasionally subvertical, planar, smooth. 3. Incipient fractures are subhorizontal, extremely closely spaced, stepped, rough with occasional dark grey staining.	30.90-33.80 dark grey staining is possible mudstone partings (<5mm thick)	30.90 -26.19		
31.40 - 32.90	100 83 67			13/04/18 24.60	1630 2.60	Weak to medium strong cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, undulating, rough and planar, rough with dark grey staining. 2. Rare 45 degree, undulating, rough with dark grey staining. 3. Incipient fractures are subhorizontal, very closely to closely spaced, undulating, striated, stepped, rough.	32.90-34.50 rare angular to subangular fine to coarse gravel of flint, rare incipient fractures are closely spaced	(3.60)		
32.90 - 34.50	94 82 73	NI 150 310		16/04/18 24.60	1100 2.60		33.80-33.89 1No. cobble of chalk and flint conglomerate			
				16/04/18 24.60	1300 0.70	END OF EXPLORATORY HOLE		34.50 -29.79		

Groundwater Entries				Depth Related Remarks				Chiselling Details		
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 4 of 4

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	6.49 mOD
Logged IH	06/04/2018	Archway Dart Dynamic sampling SPT Hammer ID: DART235, Rod type: quick thread.	1.20	3.60	87		Coordinates (m)	E 516506.21
Checked TC	End		3.60	4.60	55		National Grid	N 417414.94
Approved TC	06/04/2018							

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail			
0.00 - 0.50	D 2					Dark brown slightly sandy slightly gravelly CLAY with low cobble content. Gravel is subangular to rounded fine to medium, rarely coarse, of chalk and mudstone with occasional concrete, quartz and flint. Cobbles are subangular of chalk. (MADE GROUND)	0.50 rare rootlets	(0.50)		
0.00 - 0.50	B 1		p 120kPa, r N/A							
0.50	HV					Dark brown, locally mottled black, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk, mudstone and rare flint. Strong hydrocarbon odour. (MADE GROUND)		0.50	+5.99	
0.50 - 1.20	D 4		p 120kPa, r N/A							
0.50 - 1.20	B 3					Firm reddish brown, occasionally mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.		(0.90)		
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS					Firm grey, mottled brown, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.		1.40	+5.09	
1.20 - 1.65	D 5		N=10 (2,2/2,2,3,3)							
1.20 - 1.70	B 7					Firm to stiff indistinctly laminated reddish brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.		(0.35)		
1.20 - 2.00	L		100% rec, diameter 87mm							
1.30 - 1.50	D 6					Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of chalk.		1.75	+4.74	
1.80 - 2.00	D 8									
2.00 - 2.45	SPTS					Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of chalk.		2.00	+4.49	
2.00 - 2.20	D 10		N=26 (3,5/4,5,8,9)							
2.00 - 2.45	D 9					Brown fine to medium SAND.		(0.25)		
2.00 - 2.80	B 12		100% rec, diameter 87mm							
2.00 - 2.80	L					Firm dark brown slightly gravelly sandy CLAY. Gravel is subangular to rounded fine to medium of chalk.		2.40		
2.30 - 2.50	D 11									
2.80 - 3.25	SPTS					END OF EXPLORATORY HOLE		(1.60)		
2.80 - 3.25	D 13		N=20 (4,4/4,4,5,7)							
2.80 - 3.60	L		100% rec, diameter 87mm			4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		3.60	+2.89	
3.00 - 3.20	D 14			06/04/18	1200					
3.40 - 3.60	D 15					4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		(0.60)		
3.60 - 4.05	SPTS		N=20 (4,5/4,4,5,7)							
3.60 - 3.80	D 16					4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		4.20	+2.29	
3.60 - 4.05	D 17		75% rec, diameter 55mm							
3.60 - 4.60	L					4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		(0.40)		
4.20 - 4.40	D 18									
4.50 - 4.60	D 19					4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		4.60	+1.89	
4.60 - 5.05	SPTS		N=16 (3,3/3,4,4,5)							
4.60 - 5.05	D 20					4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		(0.45)		
						4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz		5.05	+1.44	

Groundwater Entries			Depth Related Remarks			Chiselling Details		
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	4.20			0.00 - 1.20	Hand excavated inspection pit.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:47:31				Sheet 1 of 1

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.46 mOD
Logged IH	10/04/2018	Archway Dart. Dynamic sampling.	1.20	1.70	87		Coordinates (m)	E 516529.35
Checked TC	End	SPT Hammer ID: DART235, Rod type: quick thread.	1.70	2.50	77		National Grid	N 417368.31
Approved TC	10/04/2018		2.50	3.30	67			

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail			
0.00 - 0.50	D 2					Brown, mottled orange and grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of mudstone and sandstone. Strong oil/hydrocarbon odour. (MADE GROUND)	0.50 rare angular to subrounded fine to medium gravel of flint and sandstone with rare chalk	(1.20)	+4.26	
0.00 - 0.50	B 1		p 120kPa, r N/A							
0.25	HV									
0.50	HV		p 120kPa, r N/A							
0.50 - 1.20	D 4									
0.50 - 1.20	B 3									
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS		N=16 (2,2/3,3,5,5)							
1.20 - 1.40	D 5									
1.20 - 1.65	D 6									
1.20 - 1.70	B 8									
1.20 - 1.70	L		100% rec, diameter 87mm							
1.50 - 1.70	D 7									
1.70 - 2.15	SPTS		N=28 (3,3/5,8,7,8)							
1.70 - 2.15	D 9									
1.70 - 2.50	B 11									
1.70 - 2.50	L		100% rec, diameter 77mm							
2.20 - 2.40	D 10									
2.40 - 2.50	D 12									
2.50 - 2.95	SPTS		N=22 (2,4/4,5,6,7)							
2.50 - 2.95	D 13									
2.50 - 3.10	B 16									
2.50 - 3.30	L		100% rec, diameter 67mm							
2.85 - 3.10	D 14									
3.10 - 3.30	D 15									
3.30 - 3.75	SPTS		N=26 (3,5/5,5,8,8)							
3.30 - 3.75	D 17									
				10/04/18	1100	Firm indistinctly laminated dark brown, mottled grey, CLAY.	1.50-2.50 indistinctly laminated	(1.30)	+2.96	
						Firm yellowish dark brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to medium of chalk, flint and sandstone.	2.30 gravel size pocket of dark grey fine sand	(0.60)	+2.36	
						Firm dark brown slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.	2.85-3.10 gravel size pockets of fine sand	(0.20)	+2.16	
								(0.45)	+1.71	
						END OF EXPLORATORY HOLE				

Groundwater Entries				Depth Related Remarks				Chiselling Details		
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
					0.00 - 1.20	Hand excavated inspection pit.				
					0.00 - 3.75	No groundwater encountered during drilling.				

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 1
14/08/2018 13:47:32				

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.10 mOD
Logged IH	06/04/2018	Archway Dart Dynamic sampling SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516586.01
Checked TC	End		2.00	3.00	77		National Grid	N 417401.62
Approved TC	06/04/2018		3.00	3.60	57			

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail			
0.00 - 0.50	D 2					Brown, occasionally mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and mudstone with rare flint and occasional rootlets. (MADE GROUND)				
0.00 - 0.50	B 1		p 120kPa, r N/A				0.50 dark brown	(1.40)		
0.25	HV									
0.50	HV		p 120kPa, r N/A							
0.50 - 1.20	D 4									
0.50 - 1.20	B 3									
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS		N=19 (2,3/4,5,5,5)							
1.20 - 1.40	D 5						1.35-1.40 layer of brick, recovered as subangular medium to coarse gravel	1.40	+3.70	
1.20 - 1.65	D 6						1.60 pocket of sandy clay (30mm diameter)			
1.20 - 2.00	B 8		100% rec, diameter 87mm				2.00-2.40 sandy	(1.60)		
1.20 - 2.00	L						2.40 indistinctly laminated			
1.60 - 1.80	D 7					2.70 thinly laminated				
2.00 - 2.45	SPTS		N=22 (3,4/5,5,6,6)			Medium dense orangish brown fine to coarse SAND.	3.00	+2.10		
2.00 - 2.20	D 10									
2.00 - 2.45	D 9									
2.00 - 3.00	L		75% rec, diameter 77mm							
2.40 - 2.60	D 11									
2.80 - 3.00	D 12									
3.00 - 3.45	SPTS		N=20 (2,3/4,5,5,6)							
3.00 - 3.20	D 13									
3.00 - 3.45	D 14									
3.00 - 3.50	B 16									
3.00 - 3.60	L		83% rec, diameter 57mm							
3.50 - 3.60	D 15									
3.60 - 4.05	SPTS		N=15 (3,3/3,4,4,4)	06/04/18	1500	Firm dark brown slightly gravelly sandy CLAY. Gravel is subangular to rounded fine to medium of chalk and mudstone.	3.60	+1.50		
3.60 - 4.05	D 17						3.50-3.60 brown slightly clayey fine to medium sand	(0.45)		
						END OF EXPLORATORY HOLE	4.05	+1.05		

Groundwater Entries			Depth Related Remarks			Chiselling Details		
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	3.00			0.00 - 1.20	Hand excavated inspection pit.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 1
14/08/2018 13:47:32				

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.70 mOD
Logged IH	10/04/2018	Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516626.81
Checked TC	End		2.00	3.00	77		National Grid	N 417337.47
Approved TC	10/04/2018		3.00	5.00	67			

Samples and Tests Strata Description

Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	D 2					Firm dark brown, mottled grey and black, slightly sandy slightly gravelly CLAY with low cobble content and occasional rootlets. Gravel is subangular to subrounded fine to coarse of mudstone, chalk, sandstone and occasional brick fragments. Cobble is subangular of chalk. (MADE GROUND) Firm, becoming stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to well rounded fine to coarse of mudstone with occasional sandstone and flint.				
0.00 - 1.20	B 1									
0.25	HV		p 110kPa, r N/A							
0.50	HV		p 100kPa, r N/A						(1.25)	
1.00	HV		p 100kPa, r N/A							
1.20 - 1.65	SPTS		N=9 (1,2/2,2,3)					1.20 soft	1.25	+3.45
1.20 - 1.25	D 3									
1.20 - 1.65	D 4									
1.20 - 2.00	L		100% rec, diameter 87mm							
1.25 - 1.80	B 7							1.80 brown mottled grey. Gravel is chalk and occasional mudstone		
1.50 - 1.70	D 5									
1.80 - 2.00	D 6							2.35-5.45 indistinctly laminated		
2.00 - 2.45	SPTS		N=20 (3,4/5,4,5,6)					2.65-5.45 rare gravel		
2.00 - 2.45	D 8									
2.00 - 3.00	B 11		88% rec, diameter 77mm							
2.00 - 3.00	L									
2.20 - 2.40	D 9									
2.80 - 3.00	D 10									
3.00 - 3.45	SPTS		N=24 (3,4/5,6,6,7)							
3.00 - 3.20	D 12									
3.00 - 3.45	D 13									
3.00 - 4.00	L		85% rec, diameter 67mm					(4.20)		
3.75 - 3.85	D 14						3.35-5.45 soft, gravelly. Gravel is subangular to subrounded fine to medium of chalk and mudstone with rare sandstone and flint			
4.00 - 4.45	SPTS		N=23 (4,4/4,5,6,8)							
4.00 - 4.45	D 15									
4.00 - 5.00	L		Diameter 67mm				3.40 dark brown 3.75 firm 4.00-4.45 occasional gravel size pockets of sand			
5.00 - 5.45	SPTS		N=19 (4,4/4,4,5,6)							
5.00 - 5.45	D 16			10/04/18	1300					
						END OF EXPLORATORY HOLE		5.45	-0.75	

Groundwater Entries				Depth Related Remarks				Chiselling Details		
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
					0.00 - 1.20	Hand excavated inspection pit.				
					0.00 - 5.45	No groundwater encountered during drilling.				

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 1
14/08/2018 13:47:33				

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.69 mOD
Logged WH	11/04/2018	Archway Dart Dynamic sampling SPT Hammer ID: DART235, Rod type: quick thread.	1.20	3.00	87		Coordinates (m)	E 516668.52
Checked TC	End		3.00	4.00	77		National Grid	N 417414.78
Approved TC	11/04/2018		4.00	5.00	67			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	B 1					Brown sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and sandstone. (MADE GROUND)				
0.25	HV		p 90kPa, r N/A							
0.50	HV		p 90kPa, r N/A							
0.60	D 2									
1.00	HV		p 90kPa, r N/A					(1.70)		
1.20 - 1.65	SPTS		N=8 (1,1/3,1,1,3)							
1.20 - 1.65	D 3									
1.20 - 2.00	L		94% rec, diameter 87mm							
1.30 - 1.70	B 5									
1.50	D 4									
1.70 - 2.00	B 7									
1.80	D 6									
2.00 - 2.45	SPTS		N=22 (3,3/4,6,5,7)			Firm to stiff brown, occasionally mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subangular fine to coarse of chalk, flint and sandstone.				
2.00 - 2.45	D 8									
2.00 - 3.00	B 10									
2.00 - 3.00	L		100% rec, diameter 87mm							
2.50	D 9									
2.80 - 3.25	SPTS		N=21 (4,4/5,4,6,6)			Soft brown CLAY				
2.80 - 3.25	D 11									
3.00 - 3.60	B 13									
3.00 - 4.00	L		100% rec, diameter 77mm							
3.50	D 12									
3.80 - 4.25	SPTS		N=29 (5,8/8,7,7,7)			Medium dense light brown gravelly slightly clayey fine to coarse SAND with rare pockets of gravelly clay. Gravel is subangular coarse of sandstone.				
3.80	D 14									
3.80 - 4.25	D 15									
4.00 - 5.00	L		70% rec, diameter 67mm							
4.30 - 5.00	B 17									
4.50	D 16									
5.00 - 5.45	SPTS		N=19 (4,4/5,4,5,5)	11/04/18	1100					
						END OF EXPLORATORY HOLE				

Groundwater Entries				Depth Related Remarks				Chiselling Details				
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
1	4.00				0.00 - 1.20	Hand excavated inspection pit.						

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.79 mOD
Logged WH	11/04/2018	Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	1.20	3.00	87		Coordinates (m)	E 516708.48
Checked TC	End		3.00	4.00	77		National Grid	N 417492.50
Approved TC	11/04/2018		4.00	5.00	67			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 0.30	B 1					Brown slightly gravelly sandy CLAY with rootlets and low cobble content. Gravel is subangular fine to coarse of chalk and sandstone. Cobbles are subrounded of chalk.		(0.30)		
0.20	D 2									
0.30 - 0.80	B 3							0.30	+5.49	
0.50	D 4					(TOPSOIL)	0.50-0.70 pockets of dark greyish brown clay			
0.80 - 1.20	B 5					Light brown sandy gravelly CLAY with low cobble content. Gravel is subangular fine to coarse of sandstone. Cobbles are subrounded of chalk.		(0.90)		
0.90	D 6					(MADE GROUND)				
1.20 - 1.65	SPTS D 7		N=6 (3,3/2,2,1,1)					1.20	+4.59	
1.20 - 1.80	B 9					Soft greyish brown slightly sandy CLAY with rare subrounded fine to medium gravel of chalk.		(0.60)		
1.20 - 2.00	L D 8		100% rec, diameter 87mm							
1.50										
1.80 - 2.00	B 11							1.80	+3.99	
1.90	D 10									
2.00 - 2.45	SPTS D 12		N=19 (3,4/4,4,5,6)							
2.00 - 2.45	L		80% rec, diameter 87mm							
2.00 - 3.00										
2.40 - 3.00	B 14									
2.80	D 13									
3.00 - 3.45	SPTS D 15		N=23 (4,5/5,6,6,6)							
3.00 - 3.45	L		40% rec, diameter 77mm					(3.20)		
3.00 - 4.00										
3.60 - 4.00	B 17									
3.80	D 16									
4.00 - 4.45	SPTS D 18		N=23 (5,5/5,6,6,6)							
4.00 - 4.45	L		90% rec, diameter 67mm							
4.00 - 5.00										
4.60 - 5.00	B 20									
4.90	D 19									
5.00 - 5.45	SPTS D 21		N=18 (5,5/5,4,5,4)					5.00	+0.79	
5.00 - 5.45				11/04/18	1300	Medium dense light brown gravelly fine to coarse SAND. Gravel is subrounded coarse of igneous rock and chalk.	4.80-4.85 soft brown clay	(0.45)		
								5.45	-0.34	
						END OF EXPLORATORY HOLE				

Groundwater Entries			Depth Related Remarks		Chiselling Details			
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	5.00			0.00 - 1.20	Hand excavated inspection pit.			
				0.00 - 1.00	Material too granular for hand vane testing.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS7
Scale 1:50	Project No.	A8015-18		Sheet 1 of 1
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:47:33				

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.53 mOD
Logged WH	11/04/2018	Archway Dart. Dynamic sampling.	1.20	2.00	87		Coordinates (m)	E 516813.22
Checked TC	End	SPT Hammer ID: DART235, Rod type: quick thread.	2.00	3.00	77		National Grid	N 417461.78
Approved TC	11/04/2018		3.00	4.00	67			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	B 1					Brown slightly sandy slightly gravelly CLAY with rootlets. Gravel is subangular fine to medium of sandstone. (MADE GROUND)		(1.35)		
0.25	HV		p 120kPa, r N/A							
0.50	HV		p 120kPa, r N/A							
0.60	D 2									
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS D 3		N=12 (1,1/3,3,3,3)					1.35	+3.18	
1.20 - 2.00	L		100% rec, diameter 87mm			Firm brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and sandstone.		(0.35)		
1.35 - 1.70	B 5							1.70	+2.83	
1.50	D 4									
1.70	D 6									
1.70 - 2.00	B 7					Firm brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.				
2.00 - 2.45	SPTS D 8		N=18 (3,4/4,4,5,5)							
2.00 - 2.45	L		40% rec, diameter 77mm							
2.00 - 3.00										
2.70	D 9							(2.00)		
2.70 - 3.00	B 10									
3.00 - 3.45	SPTS D 11		N=12 (3,3/3,2,3,4)							
3.00 - 3.45	L		30% rec, diameter 67mm							
3.00 - 4.00										
3.70	D 12					Soft brown CLAY.		3.70	+0.83	
4.00 - 4.45	SPTS D 13		N=14 (3,3/3,3,4,4)					(0.75)		
4.00 - 4.45				11/04/18	1500					
						END OF EXPLORATORY HOLE		4.45	+0.08	

Groundwater Entries			Depth Related Remarks			Chiselling Details			
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
					0.00 - 1.20	Hand excavated inspection pit.			
					0.00 - 4.45	No groundwater encountered during drilling.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS8
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 1
14/08/2018 13:47:34				

Trial Pit Log



Logged WH Checked TC Approved TC	Start 11/04/2018 End 11/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 6.33 mOD Coordinates (m) E 516544.31 National Grid N 417427.12
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Dark brown sandy clayey subangular to subrounded fine to coarse GRAVEL of sandstone, chalk, clinker, macadam and slag with low cobble content. Cobbles are subrounded to subangular of concrete and chalk. (MADE GROUND)		(0.50)		
0.70 0.70 - 0.90	D3 B4		Firm dark greyish brown, mottled black, slightly sandy gravelly CLAY. Gravel is subangular to subrounded of brick, clinker, sandstone, flint and chalk. Strong oil/hydrocarbon odour. (MADE GROUND)		0.50 +5.83 (0.60)		
1.20 1.20 1.20 - 1.50	HV D5 B6	p 120kPa, r N/A	Stiff brown, mottled grey, slightly sandy gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		1.10 +5.23 (1.40)		
2.00 2.00 2.00 - 2.20	HV D7 B8	p 120kPa, r N/A	Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone.		2.50 +3.83 (1.40)		
3.40 - 3.60 3.50	B10 D9	11/04/18 Dry			3.90 +2.43		
			END OF EXPLORATORY HOLE				

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 3.90 No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h1>TP1</h1> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 11/04/2018 End 11/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.70 mOD Coordinates (m) E 516559.56 National Grid N 417394.29
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 - 0.30	B2		Soft dark brown slightly gravelly sandy CLAY with low cobble content and rootlets. Gravel is subangular to subrounded fine to coarse of chalk, flint, sandstone and debris including metal bolts, wood and concrete. Cobbles are subrounded of chalk.		(0.30)		
0.20	D1		(MADE GROUND)		0.30 +5.40		
0.30	D3		Firm dark brown, mottled black, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, sandstone and flint. Strong oil/hydrocarbon odour.		(0.30)		
0.30 - 0.50	B4		(MADE GROUND)		0.60 +5.10		
			Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY with low cobble content. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone and flint. Cobbles are subrounded of chalk.	0.60-0.90 firm light brown slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, sandstone and flint			
1.30	HV	p 120kPa, r N/A					
1.30	D5						
1.30 - 1.50	B6						
					(2.90)		
2.30 - 2.50	B8						
2.50	D7						
3.10	HV	p 120kPa, r N/A					
3.40	D9						
3.40 - 3.50	B10						
				3.20-3.50 becoming grey with less gravel			
			Light brown clayey, locally very clayey, fine to medium SAND.		3.50 +2.20		
					(0.90)		
4.00	D11						
4.00 - 4.20	B12						
		11/04/18	Dry				
4.40	HV	p 120kPa, r N/A			4.40 +1.30		
4.40	D13				(0.10)		
4.40 - 4.50	B14		Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk.		4.50 +1.20		
			END OF EXPLORATORY HOLE				

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation. 0.00 - 3.50 Material too friable for hand vane testing.	Stability Stable Shoring None Weather Overcast
---	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center;">TP2</div> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.41 mOD Coordinates (m) E 516568.48 National Grid N 417297.43
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2		Soft dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)	0.20-0.40 light brown, mottled orangish brown	(0.20) 0.20 +4.21		
0.50 0.50 - 0.80	HV D3 B4	p 120kPa, r N/A	Firm light brown, mottled grey, slightly sandy gravelly CLAY with low cobble content. Gravel is subrounded fine to medium of predominantly chalk with sandstone and mudstone. Cobbles are subrounded of flint and chalk.		(2.30)		
1.80 1.80 - 2.00	D5 B6						
2.50 2.50 - 2.80	HV D7 B8	p 120kPa, r N/A	Firm brown CLAY.		2.50 +1.91 (0.30)		
			Dark brown slightly clayey fine to coarse SAND.		2.80 +1.61 (0.80)		
3.40 3.40 - 3.60	D9 B10						
			Soft dark brown very sandy CLAY with occasional gravel size pockets of sand.		3.60 +0.81 (0.90)		
4.00 4.00 - 4.20	D11 B12						
		10/04/18 Dry					
			END OF EXPLORATORY HOLE		4.50 -0.09		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation.	Stability Face A and E collapsed from 2.80m Shoring None Weather Overcast
---	--	--

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:24	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center;">TP3</div> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 09/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator Machine excavated pit	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.47 mOD Coordinates (m) E 516556.55 National Grid N 417325.06
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2	09/04/18	Dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)		(0.30)		
			Firm brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone, mudstone and flint.		0.30 +4.17		
0.80 0.80 - 1.00	D3 B4			1.10 land drain	(1.10)		1
1.40 1.40 1.40 - 1.60	HV D5 B6	p 120kPa, r N/A	Firm brown, mottled light grey, CLAY.		1.40 +3.07		
				2.60-3.00 grey mottled brown	(2.00)		
3.00 3.00 - 3.20	D7 B8			3.00-3.40 brown slightly gravelly clayey sand. Gravel is subangular fine to coarse of chalk			
3.40 3.50	B10 D9		Firm brown slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk, flint and sandstone.		3.40 +1.07		
4.00 4.00 - 4.30	D11 B12	10/04/18			(1.10)		
			END OF EXPLORATORY HOLE		4.50 -0.03		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.10 Seepage	Remarks Depth (m) Remarks	Stability Stable Shoring None Weather overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:24	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h2 style="text-align: center;">TP4</h2> Sheet 1 of 1
---	---	--



Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.31 mOD Coordinates (m) E 516595.86 National Grid N 417316.85
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2	p 120kPa, r N/A	Soft dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)	0.60-0.90 soft light yellowish brown slightly sandy clay	(0.30)		
0.50 0.50 - 0.70	HV D3 B4		Firm brown, mottled grey, gravelly slightly sandy CLAY with low cobble content. Gravel is subrounded fine to medium of chalk, flint and mudstone. Cobbles are subangular of chalk.		1.20 land drain		
1.50 1.50 - 1.70	HV D5 B6	p 120kPa, r N/A	Stiff bluish grey, mottled brown, CLAY.		(1.40)		
2.00 2.00 - 2.20	D7 B8				1.70 +2.61		
2.50 2.50 - 2.70	D9 B10		Light brown slightly clayey to clayey fine to medium SAND. Rare angular fine gravel of mudstone.		(0.80)		
		10/04/18			2.50 +1.81		
			END OF EXPLORATORY HOLE		(0.50)		
					3.00 +1.31		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.20 Seepage	Remarks Depth (m) Remarks	Stability Faces A and C collapsed Shoring None Weather Overcast
--	--	--

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP5</h3> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 240 (Deg)	Ground Level 5.43 mOD Coordinates (m) E 516601.66 National Grid N 417379.51
---	--	---	--	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Dark brown slightly gravelly clayey SAND with medium cobble content. Gravel is subangular fine to coarse of clinker, chalk and macadam. Cobbles are subrounded of chalk. (MADE GROUND)		(0.30)		
0.40 - 0.60 0.50	B4 D3		Firm dark brown, mottled orangish brown, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and flint. (MADE GROUND)		0.30 +5.13 (0.30)		
1.00 1.00 - 1.20	D5 B6		Firm light brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of flint, chalk, mudstone and sandstone.	0.60-1.20 brown mottled grey gravelly clay	0.60 +4.83		
1.50	HV	p 120kPa, r N/A		1.20 land drain			
2.00	HV	p 120kPa, r N/A			(3.50)		1 ∞
2.50 2.50 - 3.00	D7 B8						
4.10 4.10 - 4.30	D9 B10		Firm dark brown sandy CLAY with occasional gravel size pockets of sand.		4.10 +1.33 (0.50)		
		10/04/18					
			END OF EXPLORATORY HOLE		4.60 +0.83		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.90 Seepage	Remarks Depth (m) Remarks	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP6</h3> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 35 (Deg)	Ground Level 4.60 mOD Coordinates (m) E 516678.60 National Grid N 556494.03
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20 0.20 0.20 0.20 - 0.50	D1 B2 HV D3 B4	p 120kPa, r N/A	Soft dark brown silty CLAY with rootlets. (TOPSOIL)		(0.20) +4.40		
			Light orangish brown slightly sandy gravelly CLAY. Gravel is subrounded fine to coarse of sandstone and chalk. (MADE GROUND)		(0.30) +4.10		
			Firm brown, mottled light grey, slightly sandy gravelly CLAY with low cobble content. Gravel is subrounded to rounded fine to coarse of chalk and sandstone. Cobbles are subrounded of chalk.		(2.50)		
0.80 0.80 0.80 - 1.00	HV D5 B6	p 120kPa, r N/A					
2.00 2.00 - 2.20	D7 B8						
3.10 3.10 - 3.30	D9 B10		Soft light grey, mottled brown, CLAY with rare subrounded fine to medium gravel of chalk.	3.20-3.90 firm dark brown clay	(0.30) +1.60		
			Dark brown clayey fine to medium SAND with occasional gravel size pockets of sandy clay.		(0.60) +1.30		
3.70 - 3.90 3.80	B12 D11						
4.00 4.00 4.00 - 4.50	HV D13 B14	p 100kPa, r N/A	Firm brown slightly sandy silty CLAY.		(0.60) -0.70		
		10/04/18 Dry					
			END OF EXPLORATORY HOLE		4.50 -0.10		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP8</h3> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.71 mOD Coordinates (m) E 516677.98 National Grid N 417410.00
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2		Soft dark brown slightly gravelly slightly silty CLAY with frequent rootlets. Gravel is angular to subrounded fine to medium of sandstone and flint. (TOPSOIL)		(0.20)		
0.30 0.30 - 0.40	D3 B4		Light yellowish brown very sandy clayey angular to subangular fine to coarse GRAVEL of limestone and sandstone. (MADE GROUND)		0.20 +5.51		
0.80 0.80 - 1.00	D5 B6				(1.40)		
1.60 1.60 1.60 - 1.80	HV D7 B8	p 120kPa, r N/A	Stiff dark orangish brown, mottled dark brown, CLAY with rare subangular fine gravel of flint.		1.60 +4.11		
2.00 2.00 - 2.20	D9 B10		Stiff light brown, mottled grey, slightly gravelly sandy CLAY. Gravel is subangular fine to coarse of chalk.		(0.40) 2.00 +3.71		
3.20 3.20 - 3.40	D11 B12				(2.20)		
		10/04/18					
			END OF EXPLORATORY HOLE		4.20 +1.51		

Groundwater Entries <table border="1"> <thead> <tr> <th>No.</th> <th>Depth (m)</th> <th>Strike (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>0.70</td> <td></td> <td>Seepage</td> </tr> </tbody> </table>	No.	Depth (m)	Strike (m)	Remarks	1	0.70		Seepage	Remarks <table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>	Depth (m)	Remarks			Stability Faces A and C collapsed from 0.20 to 4.20m Shoring None Weather Overcast
No.	Depth (m)	Strike (m)	Remarks											
1	0.70		Seepage											
Depth (m)	Remarks													

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h2>TP9</h2> Sheet 1 of 1
---	---	--

Trial Pit Log



Logged WH Checked TC Approved TC	Start 06/04/2018 End 06/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 3.00 m 	Ground Level 4.70 mOD Coordinates (m) E 516725.56 National Grid N 417441.68
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 - 0.40	B2		Soft light brown, mottled greyish brown, slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to rounded of chalk and mudstone. (TOPSOIL)		(0.40)		
0.30	D1						
0.40	HV	p 120kPa, r N/A	Firm dark greyish brown, mottled dark grey, slightly sandy CLAY with frequent wood and plant material.		0.40 +4.30		
0.40	D3						
0.40 - 0.60	B4				(0.40)		
0.80	HV	p 120kPa, r N/A	Firm light orangish brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded of predominantly chalk with mudstone and flint.		0.80 +3.90		
0.90	D5						
0.90 - 1.20	B6			1.00-1.20 light yellowish brown sand pockets	(2.20)		1 \approx
2.20	D7						
2.20 - 2.70	B8						
3.00	D9		Firm dark brown CLAY with rare subrounded fine to medium gravel of mudstone.		3.00 +1.70		
3.20 - 3.70	B10				(1.00)		
4.20	D11		Greyish brown slightly gravelly clayey fine to coarse SAND. Gravel is subrounded fine to medium of mudstone.		4.00 +0.70		
4.20 - 4.50	B12	06/04/18			(0.50)		
			END OF EXPLORATORY HOLE		4.50 +0.20		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.00 Seepage	Remarks Depth (m) Remarks	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:26	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP10</h3> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 09/04/2018 End 09/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 6.44 mOD Coordinates (m) E 516698.32 National Grid N 417407.31
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Soft brown slightly sandy slightly gravelly CLAY. Gravel is angular to rounded fine to coarse of chalk, brick, sandstone and concrete. (MADE GROUND)		(0.50)		
0.50 0.50 - 0.70	HV D3 B4	p 120kPa, r N/A	Firm brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, flint and sandstone.	0.50 concrete block wider than trench on Face D	0.50 +5.94		
1.70 1.70	D5 D6			1.40 low cobble content. Cobbles are subrounded of chalk	(1.60)		1 M
2.20 2.20 - 2.30	HV D7 B8	p 100kPa, r N/A	Firm dark greyish brown, mottled dark grey, slightly gravelly slightly sandy to sandy CLAY. Gravel is subrounded fine to coarse of sandstone.		2.10 +4.34 (0.30)		
2.50 2.50 - 2.70	D9 B10		Firm light brown, mottled light grey, locally light orange brown, slightly gravelly CLAY. Gravel is subrounded to rounded fine to coarse of chalk.		2.40 +4.04 (1.00)		
3.40 3.50 - 3.70	D11 B12		Stiff light brown, mottled grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of sandstone and chalk.		3.40 +3.04 (1.10)		
		09/04/18		4.10 locally slightly sandy gravelly clay			
			END OF EXPLORATORY HOLE		4.50 +1.94		

Groundwater Entries <table border="1"> <thead> <tr> <th>No.</th> <th>Depth</th> <th>Strike (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>1.50</td> <td></td> <td>Seepage</td> </tr> </tbody> </table>	No.	Depth	Strike (m)	Remarks	1	1.50		Seepage	Remarks <table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>	Depth (m)	Remarks			Stability Stable Shoring None Weather Overcast
No.	Depth	Strike (m)	Remarks											
1	1.50		Seepage											
Depth (m)	Remarks													

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit TT1 Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 06/04/2018 End 06/04/2018	Equipment, Methods and Remarks Wheeled 360 excavator. Machine excavated. Top strata too friable to do hand vane.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.22 mOD Coordinates (m) E 516764.39 National Grid N 417439.42
---	--	--	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 0.25	B2		Soft light brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded of flint and sandstone. Occasional rootlets. (MADE GROUND)				
0.25	D1						
1.00 1.00 - 1.25	D3 B4				(3.00)		
2.00 2.00 2.00 - 2.15	HV D5 B6	p 70kPa, r N/A					
3.00 3.00 3.00 - 3.20	HV D7 B8	p 120kPa, r N/A	Dark greyish brown, mottled light brown, CLAY with rare angular to subrounded fine to medium gravel of various lithologies including flint and quartzite.		3.00 +2.22 (0.25)		
3.25 3.25 3.25 - 3.50	HV D9 B10	p 120kPa, r N/A 06/04/18	Dry Firm light brown slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to medium of flint and mudstone.		3.25 +1.97 (0.25)		
			END OF EXPLORATORY HOLE		3.50 +1.72		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 3.50 No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit TT2 Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 05/04/2018 End 06/04/2018	Equipment, Methods and Remarks Tracked 360 excavator Machine excavated pit	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.40 mOD Coordinates (m) E 516764.82 National Grid N 417461.85
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.30 0.30 - 0.60	D1 B2	05/04/18	Brown, locally light brown, slightly sandy CLAY with low cobble content. Cobbles are subrounded of flint and sandstone.		(1.40)		
1.30 1.30 - 1.60	D3 B4		Dark greyish brown silty CLAY with occasional wood fragments. Slight organic odour.		1.40 +4.00 (0.60)		
2.10 2.10 2.10 - 2.50	HV D5 B6	p 120kPa, r N/A 06/04/18	Firm light brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of sandstone, chalk and quartzite.		2.00 +3.40 (0.50)		
			END OF EXPLORATORY HOLE		2.50 +2.90		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 2.00 Material too friable for hand vane testing. 0.00 - 2.50 No groundwater encountered during excavation.	Stability Stable Shoring None Weather overcast
---	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:51:54	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit TT3 Sheet 1 of 1
---	---	--

APPENDIX C
INSTRUMENTATION AND MONITORING

Installation Details

Table C1



SOCOTEC

Installation Details

Instrument Reference	Instrument Type (See Notes)	Installation Date, dd/mm/yyyy	Pipe Diameter, mm	Instrument Base, mbgl	Response Zone Range, mbgl	Pipe Top Details	Headworks	Remarks
BH1 (1)	SP	11/04/2018	50	14.80	12.60 to 15.00	Gas tap	Raised cover	
BH2 (1)	SP	16/04/2018	50	15.10	14.00 to 15.20	Gas tap	Flush cover	
BH3 (1)	SP	18/04/2018	50	28.60	26.60 to 28.60	Gas tap	Flush cover	
BH4 (1)	SP	20/04/2018	50	34.60	28.60 to 34.60	Gas tap	Flush cover	
BH5 (1)	SP	19/04/2018	50	18.50	17.50 to 18.50	Gas tap	Flush cover	
BH6 (1)	SP	16/04/2018	50	34.50	25.50 to 34.50	Gas tap	Raised cover	
WS1 (1)	SP	06/04/2018	50	1.40	1.00 to 1.40	Gas tap	Raised covers	
WS2 (1)	SP	10/04/2018	50	1.20	0.70 to 1.20	Gas tap	Raised cover	
WS3 (1)	SP	10/04/2018	50	3.50	2.50 to 3.50	Gas tap	Raised cover	
WS4 (1)	SP	06/04/2018	50	2.30	1.30 to 2.30	Gas tap	Raised cover	
WS5 (1)	SP	10/04/2018	50	4.30	3.30 to 4.30	Gas tap	Raised cover	
WS6 (1)	SP	11/04/2018	50	3.70	3.10 to 3.70	Gas tap	Raised cover	
WS7 (1)	SP	11/04/2018	50	3.60	3.10 to 3.60	Gas tap	Raised cover	
WS8 (1)	SP	11/04/2018	50	4.10	3.60 to 4.10	Gas tap	Raised cover	

Notes: Type: SP - Standpipe, SPIE - Standpipe Piezometer, HPIE - Hydraulic Piezometer, PPIE - Pneumatic Piezometer, EPIE - Vibrating Wire Piezometer, PWEL - Pumping Well



Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Table

C1

APPENDIX D
GEOTECHNICAL LABORATORY TEST RESULTS

Index Properties – Summary of Results	INDX 1 to 3
Particle Size Distribution Analyses	PSD 1 to 24
Unconsolidated Undrained Triaxial Compression Tests – Summary of Results	UUSUM
Consolidated Undrained Triaxial Compression Tests with Measurement of Pore Water Pressure	CUM 1 to 6 (3 sheets per test)
One Dimensional Consolidation Test	OED 1 to 8
Determination of Consolidation Properties Using a Hydraulic Cell	HC 1 and 3 (2 sheets per test)
Dry Density / Moisture Content Relationship (Light)	COMPL 1 to 7
Dry Density / Moisture Content Relationship (Heavy)	COMPH 1 to 9
California Bearing Ratio	CBR 1 to 11
Chemical Tests	EFS/187041 EFS/187043 EFS/187204 EFS/187902

INDEX PROPERTIES - SUMMARY OF RESULTS

Hole No.	Sample			Soil Description	ρ	ρ_d	W	< 425 μ m sieve	W _L	W _P	I _p	ρ_s	Remarks	
	No.	Depth (m)												type
		from	to											
					Mg/m ³	%	%	%	%		Mg/m ³			
BH1	4	0.50	0.70	B	Greyish brown slightly sandy slightly gravelly silty CLAY.		27	91	54 a	26	28			
BH1	8	2.00	2.45	D	Brown slightly sandy slightly gravelly CLAY.		14	92	43 a	19	24			
BH1	9	2.50	3.00	B	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.							2.71-p		
BH1	17	6.50	6.95	D	Brown slightly sandy slightly gravelly CLAY.		13	82	33 a	15	18			
BH1	22	9.50	9.95	D	Brown slightly sandy slightly gravelly CLAY.		14	88	29 a	15	14			
BH1	27	13.00	13.50	B	Brown slightly gravelly sandy silty CLAY.							2.68-p		
BH1	35	17.00	17.45	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is mainly chalk.							2.72-p		
BH1	36	17.45	17.60	D	Dark grey sandy gravelly CLAY.		13	82	30 a	15	15			
BH1	40	20.40	20.50	D	Grey slightly sandy gravelly CLAY.		22							
BH1	43	22.50	22.70	D	Grey slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.		13							
BH1	46	25.00	25.22	D	Grey slightly gravelly sandy CLAY. Gravel is chalk fragments.		13	89	27 a	15	12			
BH2	2	0.30	0.50	B	Brown slightly sandy gravelly CLAY.		20	56	44 a	22	22			
BH2	5	1.00		D	Brown slightly sandy slightly gravelly CLAY.		22							
BH2	8	1.65	1.80	D	Brown slightly sandy slightly gravelly CLAY.		24	91	42 a	19	23			
BH2	15	3.30	3.75	UT	Firm laminated brown slightly sandy CLAY.		23	100	47 a	22	25			
BH2	28	5.10	5.55	UT	Firm dark brown slightly sandy slightly gravelly CLAY.		16	83	32 a	17	15	2.70-p		
BH2	34	7.10	7.55	D	Brown slightly sandy slightly gravelly CLAY.		18	88	33 a	14	19			
BH2	40	9.50	9.95	UT	Firm brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk fragments.		14	87	32 a	13	19			
BH2	51	13.10	13.55	B	Brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk.		16	89	31 a	15	16			
BH2	63	18.50	19.00	B	Greenish grey slightly sandy SILT.		22	100	23 a	NP				
BH3	3	1.65	2.00	B	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		28	95	37 a	21	16	2.71-p		
BH3	8	4.00	4.45	D	Brown slightly gravelly very sandy silty CLAY.		21							
BH3	12	5.65	6.00	B	Brown slightly sandy slightly gravelly CLAY.		18	85	32 a	15	17	2.70-p		
BH3	19	9.00	9.45	UT	Firm greyish brown slightly sandy slightly gravelly silty CLAY. Gravel contains chalk fragments.		17							
BH3	27	12.00	12.45	UT	Firm brown slightly sandy slightly gravelly CLAY.		17							
BH3	32	13.50	13.95	D	Light brown silty SAND.		25							
BH3	45	23.00	24.00	B	Greenish grey CLAY with chalk fragments.		15							
BH4	1	0.50	1.20	B	Brown slightly sandy slightly gravelly CLAY.		24	95	43 a	21	22			
BH4	7	3.10	3.55	UT	Brown slightly sandy SILT.		21							
BH4	10	4.50	4.95	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY.							2.70-p		
BH4	14	6.00	6.45	UT	Firm brown slightly sandy slightly gravelly CLAY.		14	89	33 a	14	19			

General notes:

All above tests carried out to BS1377 : 1990 unless annotated otherwise. See Remarks for further details

Key : ρ bulk density, linear

W_L Liquid limit

W_P Plastic limit

<425 μ m preparation

ρ_s particle density

ρ_d dry density

a 4 point cone test

NP non - plastic

n from natural soil

-g = gas jar

w moisture content

b 1 point cone test

IP Plasticity Index

s sieved specimen

-p = small pyknometer

* test carried out to BS EN ISO 17892-1 2014

QA Ref
SLR 1
Rev 2.91
Mar 17



Project No A8015-18
Project Name VPI IMMINGHAM

Figure
INDX

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed: 31/07/2018 12:05

INDEX PROPERTIES - SUMMARY OF RESULTS

Hole No.	Sample			Soil Description	ρ	ρ_d	W	< 425 μ m sieve	W _L	W _P	I _p	ρ_s	Remarks	
	No.	Depth (m)												type
		from	to											
					Mg/m ³		%	%	%	%		Mg/m ³		
BH4	22	9.00	9.45	UT	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.			15	89	32 a	15	17		
BH4	27	11.15	11.60	D	Brown slightly sandy slightly gravelly CLAY.			12						
BH4	34	15.50	16.00	B	Light brown gravelly SAND.			8.6						
BH4	42	22.00	22.50	B	Grey slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.			17						
BH5	3	0.50		D	Brown slightly sandy slightly gravelly CLAY.			16	96	39 a	19	20		
BH5	11	2.30	2.75	UT	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.			16					2.71-p	
BH5	20	4.50	4.95	UT	Firm laminated brown slightly gravelly sandy CLAY.			17	88	27 a	16	11		
BH5	27	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.			16	82	30 a	14	16		
BH5	35	11.00	11.45	UT	Firm brown slightly sandy slightly gravelly CLAY.			16						
BH5	42	13.00		D	Soft brown slightly gravelly, slightly sandy CLAY.			15						
BH5	51	17.00	17.36	D	Light grey sandy gravelly CLAY.			1.7						
BH5	58	20.00	20.28	B	Greenish grey CLAY with chalk fragments.			4.9						
BH6	1	0.00	0.30	B	Brown very sandy clayey GRAVEL.			20						
BH6	6	2.00	2.45	UT	Very stiff brown mottled grey slightly sandy slightly gravelly CLAY. Gravel contains chalk.								2.71-p	
BH6	9	3.50	4.00	B	Brown slightly silty CLAY.			27						
BH6	14	6.00	6.45	UT	Firm to stiff greyish brown slightly gravelly sandy CLAY. Gravel contains chalk.			15	90	29 a	18	11		
BH6	21	10.00	10.50	B				17						
BH6	25	13.00	13.50	B	Brown slightly sandy slightly gravelly CLAY.			16					2.65-g	
BH6	28	15.00	15.45	D	Light brown sandy gravelly CLAY.			16						
BH6	35	19.50	21.00	B	Greyish brown gravelly CLAY. Gravel is chalk fragments.			17						
TP1	4	0.70	0.90	B	Brown slightly sandy CLAY with occasional chalk fragments.			26						
TP1	8	2.00	2.20	B	Brown slightly sandy slightly gravelly CLAY.			20	96	47 a	19	28	2.69-p	
TP10	8	2.20	2.70	B	Brown slightly sandy slightly gravelly CLAY.			22	95	41 a	19	22		
TP10	12	4.20	4.50	B	Brown SAND.			21						
TP2	1	0.20		D	Dark brown slightly sandy slightly gravelly CLAY.			25						
TP2	8	2.30	2.50	B	Brown slightly sandy slightly gravelly CLAY.			11	94	45 a	19	26		
TP2	12	4.00	4.20	B	Brown slightly gravelly silty SAND.			25					2.72-p	
TP2	13	4.40		D	Brownish grey slightly gravelly sandy CLAY.			16	88	32 a	17	15		
TP3	10	3.40	3.60	B	Light brown SAND.			25					2.69-p	
TP3	12	4.00	4.20	B	Brown very clayey SAND with chalk fragments.			21	92	23 a	14	9		
TP4	4	0.80	1.00	B	Brown slightly sandy CLAY with chalk fragments.			17	94	42 a	17	25		

General notes:

All above tests carried out to BS1377 : 1990 unless annotated otherwise. See Remarks for further details

Key : ρ bulk density, linear

W_L Liquid limit

W_P Plastic limit

<425 μ m preparation

ρ_s particle density

ρ_d dry density

a 4 point cone test

NP non - plastic

n from natural soil

-g = gas jar

w moisture content

b 1 point cone test

IP Plasticity Index

s sieved specimen

-p = small pyknometer

* test carried out to BS EN ISO 17892-1 2014

QA Ref
SLR 1
Rev 2.91
Mar 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
INDX

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed: 31/07/2018 12:05

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104548	Sample Depth (m BGL)	0.50 - 0.70
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	70
90	100	0.0453	68
75	100	0.0323	66
63	100	0.0231	63
50	100	0.0166	59
37.5	100	0.0089	51
28	100	0.0040	38
20	100	0.0035	34
14	100	0.0015	21
10	100		
6.3	99		
5.0	98		
3.35	97		
2.00	96		
1.18	95		
0.600	93		
0.425	91		
0.300	89		
0.212	85		
0.150	79		
0.063	70		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	12.2	

Soil description	Greyish brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		26	26
		45	45
*<60mm values to aid description only		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104626	Sample Depth (m BGL)	2.50 - 3.00
		Sample Type and No	B9
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	82
90	100	0.0446	80
75	100	0.0318	78
63	100	0.0227	75
50	100	0.0162	72
37.5	100	0.0086	62
28	100	0.0037	47
20	100	0.0032	44
14	100	0.0015	31
10	100		
6.3	100		
5.0	99		
3.35	99		
2.00	98		
1.18	97		
0.600	96		
0.425	95		
0.300	94		
0.212	92		
0.150	89		
0.063	82		
		Particle density, Mg/m3	
		2.71	measured
		Dry mass of sample, kg	
		11.1	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<math><60\text{ mm}</math>
		0	0
		2	2
		16	16
		45	45
*<math><60\text{ mm}</math> values to aid description only		36	36

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104655	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	B13
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	75
90	100	0.0463	70
75	100	0.0331	67
63	100	0.0236	65
50	100	0.0168	61
37.5	100	0.0089	54
28	100	0.0041	42
20	100	0.0035	39
14	100	0.0015	29
10	100		
6.3	98		
5.0	98		
3.35	97		
2.00	95		
1.18	94		
0.600	93		
0.425	92		
0.300	90		
0.212	87		
0.150	81		
0.063	75		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	13.1	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		5	5
		21	21
		42	42
*<60mm values to aid description only		33	33

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409105002	Sample Depth (m BGL)	13.00 - 13.50
		Sample Type and No	B27
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	38
90	100	0.0453	35
75	100	0.0328	31
63	100	0.0237	29
50	100	0.0171	26
37.5	100	0.0092	20
28	100	0.0052	17
20	100	0.0038	15
14	99	0.0008	10
10	97		
6.3	96		
5.0	95		
3.35	94		
2.00	92		
1.18	91		
0.600	89		
0.425	87		
0.300	81		
0.212	70		
0.150	54		
0.063	38		

Particle density, Mg/m3	
2.68	assumed
Dry mass of sample, kg	
8.5	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		8	8
		55	55
		25	25
*<60mm values to aid description only		13	13

Uniformity Coefficient	D60 / D10	196
------------------------	-----------	-----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011418	Sample Depth (m BGL)	0.60 - 1.00
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	44
90	100	0.0484	42
75	100	0.0346	40
63	100	0.0248	36
50	100	0.0178	33
37.5	99	0.0095	23
28	95	0.0053	16
20	93	0.0039	13
14	84	0.0009	1
10	82		
6.3	80		
5.0	79		
3.35	77		
2.00	75		
1.18	73		
0.600	70		
0.425	69		
0.300	66		
0.212	60		
0.150	54		
0.063	44		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
5.1	

Soil description	Dark brown slightly sandy slightly gravelly clayey SILT.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		25	25
		31	31
		37	37
*<60mm values to aid description only		7	7

Uniformity Coefficient	D60 / D10	73
------------------------	-----------	----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011538	Sample Depth (m BGL)	2.70 - 2.80
		Sample Type and No	D12
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	74
90	100	0.0466	71
75	100	0.0333	68
63	100	0.0238	64
50	100	0.0170	62
37.5	100	0.0090	54
28	100	0.0046	44
20	100	0.0038	39
14	100	0.0015	27
10	99		
6.3	96		
5.0	95		
3.35	94		
2.00	93		
1.18	91		
0.600	89		
0.425	88		
0.300	86		
0.212	83		
0.150	77		
0.063	74		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
0.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		19	19
		43	43
*<60mm values to aid description only		30	30

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012751	Sample Depth (m BGL)	9.50 - 9.95
		Sample Type and No	UT40
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	60
90	100	0.0473	58
75	100	0.0338	55
63	100	0.0241	53
50	100	0.0172	49
37.5	99	0.0091	44
28	99	0.0050	36
20	99	0.0037	32
14	99	0.0008	19
10	98		
6.3	97		
5.0	96		
3.35	94		
2.00	93		
1.18	91		
0.600	89		
0.425	87		
0.300	84		
0.212	80		
0.150	73		
0.063	60		
		Particle density, Mg/m3	
		2.65 assumed	
		Dry mass of sample, kg	
		7.2	

Soil description	Firm brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		32	32
		34	34
*<60mm values to aid description only		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012921	Sample Depth (m BGL)	13.10 - 13.55
		Sample Type and No	B51
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	62
90	100	0.0474	57
75	100	0.0339	54
63	100	0.0242	52
50	100	0.0172	49
37.5	100	0.0091	42
28	100	0.0040	32
20	99	0.0034	30
14	99	0.0015	22
10	99		
6.3	97		
5.0	96		
3.35	95		
2.00	93		
1.18	92		
0.600	90		
0.425	89		
0.300	86		
0.212	81		
0.150	72		
0.063	62		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
15.8	

Soil description	Brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		32	32
		37	37
		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102616	Sample Depth (m BGL)	1.65 - 2.00
		Sample Type and No	B3
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	83
90	100	0.0439	79
75	100	0.0313	77
63	100	0.0223	75
50	100	0.0160	71
37.5	100	0.0085	62
28	100	0.0037	48
20	100	0.0032	45
14	100	0.0014	33
10	100		
6.3	99		
5.0	99		
3.35	98		
2.00	97		
1.18	97		
0.600	95		
0.425	95		
0.300	93		
0.212	91		
0.150	89		
0.063	83		
		Particle density, Mg/m ³	
		2.71 measured	
		Dry mass of sample, kg	
		6.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		14	14
		45	45
*<60mm values to aid description only		38	38

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102638	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	D8
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	28
90	100	0.0537	26
75	100	0.0382	23
63	100	0.0271	21
50	100	0.0193	18
37.5	100	0.0100	16
28	100	0.0050	13
20	100	0.0041	12
14	100	0.0016	8
10	98		
6.3	98		
5.0	98		
3.35	98		
2.00	98		
1.18	98		
0.600	97		
0.425	91		
0.300	59		
0.212	48		
0.150	35		
0.063	28		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	0.4	

Soil description	Brown slightly gravelly very sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		2	2
		70	70
		19	19
		9	9

Uniformity Coefficient	D60 / D10	120
------------------------	-----------	-----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102754	Sample Depth (m BGL)	9.00 - 9.45
		Sample Type and No	UT19
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	59
90	100	0.0476	57
75	100	0.0340	55
63	100	0.0242	52
50	100	0.0173	50
37.5	100	0.0091	43
28	97	0.0040	33
20	95	0.0035	31
14	95	0.0015	22
10	94		
6.3	92		
5.0	92		
3.35	91		
2.00	89		
1.18	88		
0.600	86		
0.425	85		
0.300	82		
0.212	77		
0.150	69		
0.063	59		
		Particle density, Mg/m3	
		2.65 assumed	
		Dry mass of sample, kg	
		4.7	

Soil description	Firm greyish brown slightly sandy slightly gravelly silty CLAY. Gravel contains chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		11	11
		30	30
		34	34
*<60mm values to aid description only		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102944	Sample Depth (m BGL)	13.50 - 13.95
		Sample Type and No	D32
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	100		
2.00	100		
1.18	100		
0.600	98		
0.425	85		
0.300	49		
0.212	27		
0.150	16		
0.063	13		
		Dry mass of sample, kg	
		0.4	

Soil description	Light brown silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions *<60mm values to aid description only	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	87	87
	Silt	silt+clay =	
	Clay	13	13

Uniformity Coefficient	D60 / D10	Not applicable
-------------------------------	------------------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115116	Sample Depth (m BGL)	5.50 - 6.00
		Sample Type and No	B13
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0472	59
75	100	0.0338	56
63	100	0.0241	54
50	100	0.0172	50
37.5	100	0.0091	43
28	100	0.0039	34
20	100	0.0034	31
14	100	0.0015	25
10	99		
6.3	97		
5.0	97		
3.35	96		
2.00	94		
1.18	92		
0.600	89		
0.425	87		
0.300	84		
0.212	79		
0.150	73		
0.063	61		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
7.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		6	6
		32	32
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120720	Sample Depth (m BGL)	7.10 - 7.55
		Sample Type and No	B26
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0476	58
75	100	0.0340	56
63	100	0.0242	54
50	100	0.0174	50
37.5	100	0.0091	44
28	100	0.0041	34
20	100	0.0035	32
14	100	0.0015	24
10	100		
6.3	98		
5.0	97		
3.35	96		
2.00	94		
1.18	92		
0.600	89		
0.425	87		
0.300	84		
0.212	79		
0.150	72		
0.063	61		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	14.1	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		6	6
		33	33
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092440	Sample Depth (m BGL)	0.00 - 0.30
		Sample Type and No	B1
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	93		
28	87		
20	79		
14	74		
10	68		
6.3	57		
5.0	52		
3.35	46		
2.00	39		
1.18	33		
0.600	28		
0.425	25		
0.300	22		
0.212	19		
0.150	15		
0.063	11		

Dry mass of sample, kg	
6.4	

Soil description	Brown very sandy clayey GRAVEL.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	61	61
	Silt	28	28
	Clay	11	11

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP2
	A8015-18-20180413090532	Sample Depth (m BGL)	4.00 - 4.20
		Sample Type and No	B12
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	99		
2.00	99		
1.18	99		
0.600	98		
0.425	97		
0.300	87		
0.212	55		
0.150	22		
0.063	6		
		Dry mass of sample, kg	
		11.1	

Soil description	Brown slightly gravelly silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		1	1
		93	93
		silt+clay =	
6	6		

Uniformity Coefficient	D60 / D10	3
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP5
	A8015-18-20180410090059	Sample Depth (m BGL)	2.50 - 2.70
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	100		
2.00	100		
1.18	99		
0.600	99		
0.425	99		
0.300	85		
0.212	42		
0.150	14		
0.063	7		

Dry mass of sample, kg	
13.5	

Soil description	Brown silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	92	92
	Silt	silt+clay =	
	Clay	7	7

Uniformity Coefficient	D60 / D10	3
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074235	Sample Depth (m BGL)	0.20 - 0.50
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	73
90	100	0.0459	70
75	100	0.0329	66
63	100	0.0236	63
50	100	0.0170	57
37.5	100	0.0090	49
28	100	0.0052	42
20	100	0.0038	38
14	100	0.0008	26
10	100		
6.3	99		
5.0	99		
3.35	98		
2.00	97		
1.18	97		
0.600	95		
0.425	94		
0.300	92		
0.212	89		
0.150	81		
0.063	73		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
10.6	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		24	24
		39	39
*<60mm values to aid description only		33	33

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074504	Sample Depth (m BGL)	3.8
		Sample Type and No	D11
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	99		
2.00	98		
1.18	97		
0.600	94		
0.425	93		
0.300	58		
0.212	49		
0.150	16		
0.063	8		

Dry mass of sample, kg	
1.1	

Soil description	Brown slightly gravelly silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	2	2
	Silt	90	90
	Clay	silt+clay =	
	8	8	

Uniformity Coefficient	D60 / D10	4
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091457	Sample Depth (m BGL)	0.3
		Sample Type and No	D3
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	18
90	100	0.0457	18
75	100	0.0327	17
63	100	0.0234	16
50	100	0.0169	15
37.5	100	0.0090	12
28	90	0.0045	10
20	85	0.0037	9
14	75	0.0015	6
10	69		
6.3	61		
5.0	58		
3.35	52		
2.00	46		
1.18	40		
0.600	33	Particle density, Mg/m3	
0.425	31	2.65	assumed
0.300	28	Dry mass of sample, kg	
0.212	26	1.1	
0.150	24		
0.063	18		

Soil description	Brown slightly sandy gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		54	54
		28	28
		11	11
		7	7

Uniformity Coefficient	D60 / D10	1347
------------------------	-----------	------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091609	Sample Depth (m BGL)	2.00 - 2.20
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	59
90	100	0.0471	57
75	100	0.0338	54
63	100	0.0241	52
50	100	0.0172	49
37.5	100	0.0091	43
28	100	0.0044	37
20	100	0.0037	35
14	100	0.0015	28
10	99		
6.3	98		
5.0	98		
3.35	97		
2.00	96		
1.18	95		
0.600	93		
0.425	92		
0.300	80		
0.212	74		
0.150	64		
0.063	59		
		Particle density, Mg/m3 2.65 assumed	
		Dry mass of sample, kg 10.4	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		37	37
		29	29
		30	30

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT1
	A8015-18-20180413014845	Sample Depth (m BGL)	2.20 - 2.30
		Sample Type and No	B8
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0476	58
75	100	0.0341	54
63	100	0.0244	51
50	100	0.0174	48
37.5	100	0.0092	40
28	100	0.0049	35
20	100	0.0037	31
14	98	0.0008	21
10	98		
6.3	98		
5.0	98		
3.35	97		
2.00	97		
1.18	96		
0.600	94		
0.425	93		
0.300	90		
0.212	85		
0.150	76		
0.063	61		
		Particle density, Mg/m3 2.65 assumed	
		Dry mass of sample, kg 11.2	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		35	35
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
-------------------------------	------------------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT2
	A8015-18-20180408083410	Sample Depth (m BGL)	1.00 - 1.25
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	65
90	100	0.0473	63
75	100	0.0337	60
63	100	0.0241	57
50	100	0.0172	53
37.5	100	0.0091	47
28	100	0.0046	41
20	100	0.0038	38
14	100	0.0015	29
10	100		
6.3	100		
5.0	99		
3.35	98		
2.00	96		
1.18	95		
0.600	94		
0.425	92		
0.300	90		
0.212	85		
0.150	77		
0.063	65		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	13.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with rootlets.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		32	32
		33	33
*<60mm values to aid description only		32	32

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT2
	A8015-18-20180408083738	Sample Depth (m BGL)	3.25 - 3.50
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	46
90	100	0.0474	44
75	100	0.0338	43
63	100	0.0242	40
50	100	0.0173	37
37.5	100	0.0091	33
28	100	0.0043	29
20	100	0.0036	28
14	98	0.0015	24
10	98		
6.3	96		
5.0	95		
3.35	94		
2.00	92		
1.18	91		
0.600	89		
0.425	87		
0.300	68		
0.212	62		
0.150	51		
0.063	46		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	14.0	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		8	8
		46	46
		21	21
		25	25

Uniformity Coefficient	D60 / D10	Not applicable
-------------------------------	------------------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD



Printed: 05/07/2018 11:36

UNCONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TESTS WITHOUT MEASUREMENT OF PORE PRESSURE - SUMMARY OF RESULTS

Hole No.	Sample				Soil Description	Density		w	Test type	Dia.	ø3	At failure / end of stage				Membrane Thickness	Remarks				
	No.	Depth (m)		type		bulk	dry					Mg/m3	%	mm	kPa			Axial strain	ø1 - ø3	CU	M O D E
		from	to																		
BH1	15	5.00	5.45	UT	Stiff greyish brown slightly sandy slightly gravelly CLAY.	2.21	1.93	15	UUM	99.4 99.4 99.4	100 200 400	11.4 13.4 18.8	203 216 229	101 108 114	P	0.4					
BH1	20	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY.	2.21	1.92	15	UUM	102.6 102.6 102.6	160 320 640	7.9 10.4 19.8	110 127 163	55 64 82	P	0.4					
BH1	35	17.00	17.45	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is mainly chalk.	2.23	1.96	14	UUM	103.8	250	19.9	506	253	P	0.4	Sample reached 20% axial strain during 1st stage.				
BH1	39	20.00	20.40	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is chalk.	2.2	1.92	14	UUM UUM	103.6 103.6	250 500	18.4 19.9	524 535	262 268	P	0.4	Sample reached 20% axial strain during 2nd stage.				
BH2	7	1.20	1.65	UT	Firm stiff brown slightly sandy slightly gravelly CLAY	2.05	1.71	20	UUM	103.9 103.9 103.9	25 50 100	7.9 9.8 19.1	166 180 213	83 90 106	P	0.4					
BH2	28	5.10	5.55	UT	Firm dark brown slightly sandy slightly gravelly CLAY.	2.16	1.86	16	UUM	102.7 102.7 102.7	100 200 400	2.5 4.5 19.8	33 43 66	17 22 33	P	0.4					
BH2	44	11.00	11.45	UT	Stiff greyish brown slightly sandy slightly gravelly CLAY.	2.2	1.91	15	UUM	102.8 102.8 102.8	220 440 880	10.9 12.9 19.9	217 225 254	109 113 127	P	0.4					
BH3	19	9.00	9.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.	2.12	1.81	17	UUMR	102.9 102.9 102.9	180 360 720	5.0 6.9 19.8	81 89 113	41 45 56	P	0.4					
BH4	10	4.50	4.95	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY.	2.19	1.91	14	UUM	102.6 102.6 102.6	90 180 360	10.4 12.3 19.7	220 229 246	110 114 123	P	0.4					
BH4	22	9.00	9.45	UT	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.	2.16	1.87	15	UUM	95.9 95.9 95.9	180 360 720	5.4 6.9 19.7	100 108 148	50 54 74	P	0.4					
BH5	11	2.30	2.75	UT	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.	2.14	1.84	16	UUM	102.5 102.5 102.5	45 90 180	16.3 18.8 19.8	537 541 542	268 270 271	P	0.4					
BH5	27	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.19	1.89	16	UUM	101.9 101.9 101.9	160 320 640	4.0 5.9 18.8	69 83 115	35 41 58	P	0.4					
BH6	6	2.00	2.45	UT	Very stiff brown mottled grey slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.13	1.82	17	UUM	102.7 102.7 102.7	40 80 160	10.9 12.4 19.8	446 452 480	223 226 240	P	0.4					
BH6	14	6.00	6.45	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.2	1.91	15	UUM	102.5 102.5 102.5	120 240 480	4.0 6.4 19.3	109 134 174	54 67 87	P	0.4					

General notes: Tests carried out in accordance with BS1377: Part 7: 1990, clause 8 for single stage, clause 9 for multistage tests. Specimens nominally 2:1 height diameter ratio and tested at a rate of strain of 2%/minute, unless annotated otherwise. Latex rubber membrane used and membrane correction applied in accordance with BS1377-7 8.5.1.4 unless stated.

Legend
 UU - single stage test (may be in sets of specimens) ø3 cell pressure Mode of failure P plastic
 UUM - multistage test on a single specimen ø1 - ø3 deviator stress B brittle
 suffix R - remoulded or recompacted CU undrained shear strength C compound

QA Ref SLR 2 Rev 2.7 Apr 15	 1157	 SOCOTEC	Project No A8015-18	Figure UUSUM
			Project Name VPI IMMINGHAM	
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 05/07/2018 11:44	


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH1		
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65		
			No	6	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.24
Diameter	mm	103.57
Bulk Density	Mg/m ³	2.10
Water Content	%	19
Dry density	Mg/m ³	1.76
After test		
Bulk Density	Mg/m ³	2.08
Water Content	%	20
Dry density	Mg/m ³	1.73

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	293.8
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	312	325	350	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	12	25	50	kPa	
	Pore pressure at start of consolidation	303	308	324	kPa	
	Pore pressure at end of consolidation	301	300	300	kPa	
	Pore pressure dissipation at end of consolidation	70	95	100	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.12	1.17	1.08	m ² /year
	Coefficient of Compressibility	M _{vi}	0.67	0.48	0.32	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	4.4E-10	1.7E-10	1.1E-10	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:42

Figure

CUM


sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**


Project No	A8015-18	Sample Details:	Hole No	BH1	
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65	
		No	6	Type	UT
		ID			
		Spec Ref			

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18





Printed:20/07/2018 10:42

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH1		
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65		
			No	6	Type	UT
			ID			
		Spec Ref				




Compression stages

Stage	1	2	3	
Cell pressure	312	325	350	kPa
Initial pwp	299	300	301	kPa
Initial σ_3'	14	25	49	kPa
Rate of strain	1.51	1.51	1.51	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.54	2.47	4.60	%
$(\sigma_1' / \sigma_3')_f$	6.616	5.321	4.046	
$(\sigma_1' - \sigma_3')_f$	52.8	73.0	111.8	kPa
u_f	303	308	313	kPa
$\sigma_3'_f$	9	17	37	kPa
$\sigma_1'_f$	62	90	148	kPa
A_f	0.08	0.11	0.11	
Time to failure	1.0	1.6	3.0	hrs



Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	9.8
ϕ'	degrees	31.0
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.594 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:42

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2		
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75		
			No	15	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	202.89
Diameter	mm	103.07
Bulk Density	Mg/m ³	2.03
Water Content	%	25
Dry density	Mg/m ³	1.63
After test		
Bulk Density	Mg/m ³	2.04
Water Content	%	24
Dry density	Mg/m ³	1.64

Soil Description	Firm brown laminated slightly sandy CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	300
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	355	410	520	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	55	110	220	kPa	
	Pore pressure at start of consolidation	348	365	419	kPa	
	Pore pressure at end of consolidation	301	301	302	kPa	
	Pore pressure dissipation at end of consolidation	97	99	98	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	0.97	0.94	0.93	m ² /year
	Coefficient of Compressibility	M _{vi}	0.36	0.18	0.12	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.1E-10	5.1E-11	3.3E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2		
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75		
			No	15	Type	UT
			ID			
			Spec Ref			

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18






Printed:20/07/2018 10:43

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2	
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75	
		No	15	Type	UT
		ID			
		Spec Ref			



Compression stages

Stage	1	2	3	
Cell pressure	355	410	520	kPa
Initial pwp	301	301	302	kPa
Initial σ_3'	54	109	218	kPa
Rate of strain	0.71	0.71	0.71	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.76	3.70	6.40	%
$(\sigma_1' / \sigma_3')_f$	2.839	3.051	2.751	
$(\sigma_1' - \sigma_3')_f$	60.3	150.5	267.7	kPa
u_f	322	337	367	kPa
$\sigma_3'_f$	33	73	153	kPa
$\sigma_1'_f$	93	224	421	kPa
A_f	0.35	0.24	0.24	
Time to failure	2.5	5.2	9.0	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	3.8
ϕ'	degrees	27.4
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.594 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.48
Diameter	mm	102.37
Bulk Density	Mg/m ³	2.19
Water Content	%	20
Dry density	Mg/m ³	1.82
After test		
Bulk Density	Mg/m ³	2.26
Water Content	%	16
Dry density	Mg/m ³	1.94

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	260
Final pore water pressure	kPa	237.3
Final B Value		0.99



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	335	370	440	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	35	70	140	kPa	
	Pore pressure at start of consolidation	314	327	383	kPa	
	Pore pressure at end of consolidation	300	300	302	kPa	
	Pore pressure dissipation at end of consolidation	100	100	98	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	1.30	0.95	0.84	m ² /year
	Coefficient of Compressibility	M _{vi}	0.39	0.25	0.15	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.6E-10	7.4E-11	3.9E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

Figure

CUM


sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18






Printed:20/07/2018 10:43

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	335	370	440	kPa
Initial pwp	300	294	302	kPa
Initial σ_3'	35	76	138	kPa
Rate of strain	1.02	1.02	1.02	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	2.26	3.25	4.98	%
$(\sigma_1' / \sigma_3')_f$	3.480	3.556	3.126	
$(\sigma_1' - \sigma_3')_f$	78.1	138.0	207.3	kPa
u_f	304	316	343	kPa
σ_{3f}'	32	54	98	kPa
σ_{1f}'	110	192	305	kPa
A_f	0.04	0.16	0.20	
Time to failure	2.2	3.2	4.9	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	6.9
ϕ'	degrees	29.4
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.49
Diameter	mm	103.68
Bulk Density	Mg/m ³	2.22
Water Content	%	14
Dry density	Mg/m ³	1.95
After test		
Bulk Density	Mg/m ³	2.23
Water Content	%	13
Dry density	Mg/m ³	1.97

Soil Description	Firm brown slightly sandy slightly gravelly CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	287.6
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	365	430	560	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	65	130	260	kPa	
	Pore pressure at start of consolidation	347	374	457	kPa	
	Pore pressure at end of consolidation	303	300	302	kPa	
	Pore pressure dissipation at end of consolidation	94	100	99	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.17	2.09	1.63	m ² /year
	Coefficient of Compressibility	M _{vi}	0.24	0.12	0.07	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.6E-10	7.7E-11	3.5E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44




Figure

CUM

sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	365	430	560	kPa
Initial pwp	302	300	302	kPa
Initial σ_3'	63	130	258	kPa
Rate of strain	1.56	1.56	1.56	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	2.19	3.40	4.22	%
$(\sigma_1' / \sigma_3')_f$	3.863	3.523	3.183	
$(\sigma_1' - \sigma_3')_f$	146.9	249.6	392.0	kPa
u_f	314	331	380	kPa
$\sigma_3'_f$	51	99	180	kPa
$\sigma_1'_f$	198	348	572	kPa
A_f	0.08	0.12	0.20	
Time to failure	1.4	2.2	2.7	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	15.9
ϕ'	degrees	29.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.596 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure

CUM

sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details: Hole No	BH5		
Project Name	IMMINGHAM	Depth (m BGL)	11 - 11.45		
		No	35	Type	UT
		ID			
		Spec Ref			


Specimen Details		
Initial		
Length	mm	203.00
Diameter	mm	103.08
Bulk Density	Mg/m ³	2.16
Water Content	%	17
Dry density	Mg/m ³	1.84
After test		
Bulk Density	Mg/m ³	2.17
Water Content	%	17
Dry density	Mg/m ³	1.85

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	295
Final B Value		0.96



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	327	355	410	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	27	55	110	kPa	
	Pore pressure at start of consolidation	319	334	369	kPa	
	Pore pressure at end of consolidation	300	300	300	kPa	
	Pore pressure dissipation at end of consolidation	100	100	100	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	0.68	0.76	0.57	m ² /year
	Coefficient of Compressibility	M _{vi}	0.39	0.27	0.20	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	8.2E-11	6.3E-11	3.4E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure

CUM


sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH5		
Project Name	IMMINGHAM		Depth (m BGL)	11 - 11.45		
			No	35	Type	UT
			ID			
			Spec Ref			

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44




Figure

CUM

sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH5	
Project Name	IMMINGHAM		Depth (m BGL)	11 - 11.45	
		No	35	Type	UT
		ID			
		Spec Ref			



Compression stages

Stage	1	2	3	
Cell pressure	327	355	410	kPa
Initial pwp	302	300	302	kPa
Initial σ_3'	25	55	108	kPa
Rate of strain	0.50	0.50	0.50	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	0.87	1.60	3.46	%
$(\sigma_1' / \sigma_3')_f$	3.952	3.551	3.172	
$(\sigma_1' - \sigma_3')_f$	35.4	81.6	167.3	kPa
u_f	315	323	333	kPa
$\sigma_3'_f$	12	32	77	kPa
$\sigma_1'_f$	47	114	244	kPa
A_f	0.37	0.28	0.19	
Time to failure	1.7	3.2	6.9	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	4.0
ϕ'	degrees	30.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6		
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45		
			No	19	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.49
Diameter	mm	102.79
Bulk Density	Mg/m ³	2.14
Water Content	%	17
Dry density	Mg/m ³	1.84
After test		
Bulk Density	Mg/m ³	2.17
Water Content	%	15
Dry density	Mg/m ³	1.88

Soil Description	Soft to firm brown slightly sandy slightly gravelly CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	260
Final pore water pressure	kPa	238
Final B Value		0.96



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	355	410	520	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	55	110	220	kPa	
	Pore pressure at start of consolidation	333	371	459	kPa	
	Pore pressure at end of consolidation	300	303	300	kPa	
	Pore pressure dissipation at end of consolidation	100	96	100	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.41	1.42	1.38	m ² /year
	Coefficient of Compressibility	M _{vi}	0.36	0.17	0.09	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	2.7E-10	7.4E-11	3.8E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:45


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6		
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45		
			No	19	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:45




Figure

CUM

sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6		
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45		
			No	19	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	355	410	520	kPa
Initial pwp	300	300	300	kPa
Initial σ_3'	55	110	220	kPa
Rate of strain	1.80	1.80	1.80	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.57	3.52	6.15	%
$(\sigma_1' / \sigma_3')_f$	3.142	3.205	3.052	
$(\sigma_1' - \sigma_3')_f$	68.5	143.3	264.7	kPa
u_f	323	345	391	kPa
$\sigma_3'_f$	32	65	129	kPa
$\sigma_1'_f$	101	208	394	kPa
A_f	0.34	0.31	0.34	
Time to failure	0.9	2.0	3.4	hrs

Shear Strength Parameters

		Linear regression
c'	kPa	2.2
ϕ'	degrees	30.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18




Printed:20/07/2018 10:45

Figure
CUM
sheet 3 of 3

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104630	Sample Depth (m BGL)	3.00 - 3.45
		Sample Type and No	UT10
		Specimen Ref	



Soil description

Firm laminated brown slightly sandy slightly gravelly CLAY.

Preparation

Undisturbed

Index properties

Liquid limit %		Plastic limit %	
----------------	--	-----------------	--

(if available)

Specimen details

	Initial	Final	
Particle density	2.70	assumed	Mg/m ³
Diameter	75.08		mm
Height	19.11	18.52	mm
Voids ratio	0.581	0.533	
Moisture content	21	21	%
Bulk density	2.06	2.13	Mg/m ³
Dry density	1.71	1.76	Mg/m ³
Saturation	97	105	%
Average temperature for test	20		oC
Swelling pressure	>50		kPa

Notes :

Specimen taken 10 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t ₅₀ , log) m ² /year	cv (t ₉₀ , root) m ² /year
50	0.5806	/	/	/
100	0.5730	0.095	8.4	9
200	0.5587	0.091	16	17
400	0.5384	0.065	7.6	8.1
800	0.5102	0.046	8.6	9.2
100	0.5325	0.021	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


**Figure
OED**

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011601	Sample Depth (m BGL)	3.30 - 3.75
		Sample Type and No	UT15
		Specimen Ref	



Soil description

Firm laminated brown slightly sandy CLAY.			
Undisturbed			
Liquid limit %	47	Plastic limit %	22

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

	Initial	Final	
Particle density	2.75	assumed	Mg/m3
Diameter	75.08		mm
Height	18.94	18.04	mm
Moisture content	26	25	%
Bulk density	2.01	2.08	Mg/m3
Dry density	1.59	1.67	Mg/m3
Saturation	100	105	%
Average temperature for test	20		oC

Swelling pressure >50 kPa

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
50	0.7276			
100	0.7154	0.142	2.5	2.6
200	0.6930	0.131	1.4	1.5
400	0.6571	0.106	2	2
800	0.6032	0.081	1.5	1.6
100	0.6456	0.038	-	-

Specimen taken 10 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012711	Sample Depth (m BGL)	8.00 - 8.45
		Sample Type and No	UT36
		Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY. Gravel is chalk.		
Preparation		
Undisturbed		
Index properties		
Liquid limit %		Plastic limit %

(if available)

Specimen details

	Initial	Final	
Particle density	2.75	assumed	Mg/m ³
Diameter	75.08		mm
Height	19.10	18.20	mm
Voids ratio	0.453	0.385	
Moisture content	16	14	%
Bulk density	2.19	2.27	Mg/m ³
Dry density	1.89	1.99	Mg/m ³
Saturation	97	101	%
Average temperature for test	20		oC

Swelling pressure

not measured kPa

Notes :

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t ₅₀ , log) m ² /year	cv (t ₉₀ , root) m ² /year
0	0.4526	/	/	/
50	0.4272	0.350	1.7	1.8
100	0.4141	0.183	2.5	2.7
200	0.3955	0.131	3.2	3.3
400	0.3749	0.074	3.4	3.5
50	0.3846	0.020	-	-

Specimen taken 20 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM

Figure
OED


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:
	A8015-1820180413102646

Hole No	BH3
Sample Depth (m BGL)	5.00 - 5.45
Sample Type and No	UT10
Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY.	
Undisturbed	
Liquid limit %	Plastic limit %

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

Initial	Final	
2.70	assumed	
75.03		Mg/m ³
		mm
		mm
		%
		Mg/m ³
		Mg/m ³
		%
		oC

not measured kPa

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t ₅₀ , log) m ² /year	cv (t ₉₀ , root) m ² /year
0	0.4418	/	/	/
50	0.4229	0.263	2.8	3
100	0.4117	0.157	3.5	3.7
200	0.3943	0.123	3.6	3.8
400	0.3704	0.086	3.8	4.1
50	0.3847	0.030	-	-

Specimen taken 10 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115035	Sample Depth (m BGL)	3.10 - 3.55
		Sample Type and No	UT7
		Specimen Ref	



Soil description

Brown slightly sandy SILT.		
Undisturbed		
Liquid limit %		Plastic limit %

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

Specimen taken 20 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.6386	/	/	/
50	0.6301	0.104	1.7	1.6
100	0.6245	0.069	1.1	0.91
200	0.6197	0.029	0.55	0.61
400	0.6155	0.013	0.44	0.46
50	0.6175	0.004	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120528	Sample Depth (m BGL)	3.40 - 3.85
		Sample Type and No	UT15
		Specimen Ref	



Soil description

Firm to stiff brown slightly sandy slightly gravelly CLAY.
Gravel is chalk.

Preparation

Undisturbed

Index properties

Liquid limit %		Plastic limit %	
----------------	--	-----------------	--

(if available)

Specimen details

	Initial	Final	
Particle density	2.75	assumed	Mg/m3
Diameter	75.17		mm
Height	18.97	18.50	mm
Voids ratio	0.639	0.599	
Moisture content	23	22	%
Bulk density	2.06	2.10	Mg/m3
Dry density	1.68	1.72	Mg/m3
Saturation	99	102	%
Average temperature for test	20		oC

Swelling pressure

>50 kPa

Notes :

Specimen taken 10 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
50	0.6393	/	/	/
100	0.6313	0.098	5.7	6.1
200	0.6176	0.084	3.3	1.8
400	0.5970	0.064	2.7	2.9
800	0.5683	0.045	2.7	2.9
100	0.5989	0.028	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092542	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	UT10
		Specimen Ref	



Soil description

Soft brown slightly sandy CLAY.	
Undisturbed	
Liquid limit %	Plastic limit %

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

	Initial	Final	
Particle density	2.75	assumed	Mg/m3
Diameter	75.19		mm
Height	19.12	18.09	mm
Voids ratio	0.664	0.574	
Moisture content	24	21	%
Bulk density	2.05	2.12	Mg/m3
Dry density	1.65	1.75	Mg/m3
Saturation	99	103	%
Average temperature for test	20		oC

Swelling pressure: not measured kPa

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.6638	/	/	/
50	0.6304	0.401	0.98	1.1
100	0.6096	0.255	1	1
200	0.5815	0.175	1.1	1.1
400	0.5484	0.105	1.5	1.5
50	0.5744	0.048	-	-

Specimen taken 40 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited


Figure

OED

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092658	Sample Depth (m BGL)	9.00 - 9.45
		Sample Type and No	UT19
		Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY. Gravel is chalk.

Preparation

Undisturbed

Index properties

Liquid limit %		Plastic limit %	
----------------	--	-----------------	--

(if available)

Specimen details

	Initial	Final	
Particle density	2.65	assumed	Mg/m3
Diameter	75.04		mm
Height	18.96	18.02	mm
Voids ratio	0.446	0.374	
Moisture content	17	15	%
Bulk density	2.14	2.21	Mg/m3
Dry density	1.83	1.93	Mg/m3
Saturation	98	105	%
Average temperature for test	20		oC
Swelling pressure	not measured		kPa

Notes :

Specimen taken 10 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.4456			
50	0.4182	0.380	3.2	3.3
100	0.4053	0.182	4.5	4.8
200	0.3868	0.131	5.4	5.7
400	0.3639	0.083	5.3	5.5
50	0.3737	0.020	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM

Figure
OED


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH2				
	A8015-1820180413011428	Sample Depth (m BGL)	1.20 - 1.65				
		Sample Type and No	UT7				
		Specimen Ref					
Specimen Description	Firm brown slightly sandy slightly gravelly CLAY						
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	26/06/2018				
SPECIMEN DETAILS	Type of sample Preparation	Undisturbed					
	Height	Initial	Final				
	Diameter	19.32		mm			
	Bulk density	71.94		mm			
	Moisture content	2.08	3.52	Mg/m3			
	Dry density	18.0	23.0	%			
	Voids Ratio	1.76	2.67	Mg/m3			
	Degree of Saturation	0.502		%			
	Particle density	95		%			
		2.65		Mg/m3 Assumed			
SWELLING	Swelling pressure			kPa			
	Water taken in during swelling stage			ml			
SATURATION	Cell pressure increments	50		kPa			
Back pressure	Pressure differential	10		kPa			
	Final diaphragm pressure	460		kPa			
	Final back pressure	443		kPa			
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_o$	1.00					
	Water taken in during saturation stage	28.9		ml			
	Voids ratio at end of saturation stage	0.500					
CONSOLIDATION STAGES	Type of drainage	Radial outwards		Centre drain (if applicable)			
	Type of loading	Free strain		Diameter			
	PWP location	Centre base		mm			
				Material			
				Method of formation			
Stage number		1	2	3	4	5	
Diaphragm pressure		475	500	550	650	500	kPa
Back pressure		450	450	450	450	450	kPa
Initial Pore pressure built up		459	476	486	493	362	kPa
Final pore pressure		450	450	451	450	450	kPa
Effective stress (actual) at end of stage		25	50	99	200	50	kPa
Voids at start		0.500	0.173	0.173	0.121	0.102	
Voids at end		0.222	0.173	0.121	0.102	-0.009	
PWP dissipation		100	100	97	100	100	%
Settlement in stage		0.37	0.24	0.17	0.29	-0.12	mm
Volume change in stage	(water out = +ve)	14.5	2.6	2.7	1.0	5.8	ml
Mv		7.4	1.6	0.9	0.17	-0.671	m2/MN
Cro		400	1.5	1.4	0.53	0	0
Csec		0	0	0	0		
Cro method		Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature		20.6	20.6	21.5	21.0	19.6	oC
Remarks							

QA Ref SLD 3, 5/9 Rev 2.7	 SOCOTEC	Project No A8015-18 Project Name VPI IMMINGHAM	Figure HC
Test carried out outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited			Printed: 31/07/2018 12:23



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011428	Sample Depth (m BGL)	1.20 - 1.65
		Sample Type and No	UT7
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
 Project Name VPI IMMINGHAM

Figure

HC


Test carried out outside the scope of UKAS accreditation. © Copyright 2017
 SOCOTEC UK Limited

Printed:
 31/07/2018 12:23

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH4				
	A8015-1820180418115015	Sample Depth (m BGL)	2.00 - 2.45				
		Sample Type and No	UT4				
		Specimen Ref					
Specimen Description							
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	26/06/2018				
SPECIMEN DETAILS	Type of sample Preparation	Undisturbed					
	Height	Initial	Final				
	Diameter	18.86		mm			
	Bulk density	72.13		mm			
	Moisture content	2.04	3.32	Mg/m3			
	Dry density	22.0	25.0	%			
	Voids Ratio	1.67	2.41	Mg/m3			
	Degree of Saturation	0.585		%			
	Particle density	100		%			
		2.65		Mg/m3 Assumed			
SWELLING	Swelling pressure			kPa			
	Water taken in during swelling stage			ml			
SATURATION	Cell pressure increments	50		kPa			
Back pressure	Pressure differential	10		kPa			
	Final diaphragm pressure	310		kPa			
	Final back pressure	298		kPa			
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_\sigma$	0.99					
	Water taken in during saturation stage	27.2		ml			
	Voids ratio at end of saturation stage	0.560					
CONSOLIDATION STAGES	Type of drainage	Radial outwards					
	Type of loading	Free strain					
	PWP location	Centre base					
	Centre drain (if applicable)						
	Diameter						
	Material						
	Method of formation						
Stage number		1	2	3	4	5	
Diaphragm pressure		325	350	400	500	350	kPa
Back pressure		300	300	300	300	300	kPa
Initial Pore pressure built up		315	321	335	330	255	kPa
Final pore pressure		300	300	300	300	294	kPa
Effective stress (actual) at end of stage		25	50	100	200	56	kPa
Voids at start		0.560	0.312	0.312	0.235	0.182	
Voids at end		0.388	0.312	0.235	0.182	0.102	
PWP dissipation		100	100	100	100	86	%
Settlement in stage		0.00	0.11	0.26	0.21	-0.09	mm
Volume change in stage	(water out = +ve)	8.4	3.7	3.7	2.6	3.9	ml
Mv		4.4	2.2	1.2	0.43	-0.471	m2/MN
Cro		0	36	8.6	7	0	0
Csec			0	0	0		
Cro method		Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature		21.1	20.8	20.3	21.1	21.8	oC
Remarks							

QA Ref SLD 3, 5/9 Rev 2.7		Project No A8015-18 Project Name VPI IMMINGHAM	Figure HC
Test carried out outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited			Printed: 31/07/2018 12:23



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115015	Sample Depth (m BGL)	2.00 - 2.45
		Sample Type and No	UT4
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
 Project Name VPI IMMINGHAM

Figure
HC

Test carried out outside the scope of UKAS accreditation. © Copyright 2017
 SOCOTEC UK Limited

Printed:
31/07/2018 12:23

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH5			
	A8015-1820180418120419	Sample Depth (m BGL)	1.20 - 1.65			
		Sample Type and No	UT7			
		Specimen Ref				
Specimen Description	Soft to firm brown slightly sandy slightly gravelly CLAY.					
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	11/07/2018			
SPECIMEN DETAILS						
Type of sample	Undisturbed					
Preparation						
Height	Initial	Final				
Diameter	18.55		mm			
Bulk density	72.06		mm			
Moisture content	2.24	4.58	Mg/m3			
Dry density	15.0	20.0	%			
Voids Ratio	1.95	4.02	Mg/m3			
Degree of Saturation	0.359		%			
Particle density	111		Mg/m3			
	2.65		Assumed			
SWELLING						
Swelling pressure			kPa			
Water taken in during swelling stage			ml			
SATURATION						
Back pressure	Cell pressure increments	50	kPa			
	Pressure differential	10	kPa			
	Final diaphragm pressure	360	kPa			
	Final back pressure	341	kPa			
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_o$	0.96				
	Water taken in during saturation stage	22.3	ml			
	Voids ratio at end of saturation stage	0.290				
CONSOLIDATION STAGES						
Type of drainage	Radial outwards	Centre drain (if applicable)				
Type of loading	Free strain	Diameter				
PWP location	Centre base					
		Material				
		Method of formation				
Stage number	1	2	3	4	5	
Diaphragm pressure	375	400	450	550	400	kPa
Back pressure	350	350	350	350	350	kPa
Initial Pore pressure built up	356	369	385	422	246	kPa
Final pore pressure	350	350	350	350	350	kPa
Effective stress (actual) at end of stage	25	50	100	200	50	kPa
Voids at start	0.290	0.145	0.145	0.093	0.041	
Voids at end	0.215	0.145	0.093	0.041	-0.340	
PWP dissipation	100	100	100	100	100	%
Settlement in stage	0.01	0.19	0.22	0.22	-0.62	mm
Volume change in stage	4.2	3.9	2.9	2.9	21.2	ml
Mv	2.3	2.3	0.91	0.48	-2.44	m2/MN
Cro	1.3	29	19	2.7	0	0
Csec	0	0	0	0		
Cro method	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature	20.3	20.1	20.3	21.3	20.6	oC
Remarks						



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120419	Sample Depth (m BGL)	1.20 - 1.65
		Sample Type and No	UT7
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
HC

Test carried out outside the scope of UKAS accreditation. © Copyright 2017
 SOCOTEC UK Limited



Printed:
31/07/2018 12:23

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104626	Sample Depth (m BGL)	2.50 - 3.00
		Sample Type and No	B9
		Specimen Ref	




Soil description	Brown CLAY with chalk fragments.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.78
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	0 %	16
Particle density	2.71 measured - small pycnometer	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure	COMPL
			Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited					Printed: 02/07/2018 15:44	

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120410	Sample Depth (m BGL)	0.50 - 0.80
		Sample Type and No	B4
		Specimen Ref	




Soil description	Brown slightly sandy CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material wassingle sample tested	1.67
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	0 %	18
Particle density	2.55 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157	 SOCOTEC	Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:45

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP1
	A8015-18-20180413084026	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.87
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	4 %	14
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:45

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP3
	A8015-18-20180410084322	Sample Depth (m BGL)	0.10 - 0.20
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.6, 2.5 kg rammer in a CBR mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.72
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	8 %	16
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure COMPL
			Project Name	VPI IMMINGHAM	
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited			Printed: 05/07/2018 11:42		

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP5
	A8015-18-20180410090003	Sample Depth (m BGL)	0.10 - 0.20
		Sample Type and No	B2
		Specimen Ref	




Soil description	Greenish brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.56
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	1 %	24
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure	COMPL
			Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited					Printed: 02/07/2018 15:46	

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091510	Sample Depth (m BGL)	0.30 - 0.40
		Sample Type and No	B4
		Specimen Ref	




Soil description	Light brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.99
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	15 %	12
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:47

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TT1
	A8015-18-20180413014653	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material wassingle sample tested	1.59
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	3 %	20
Particle density	2.65 assumed	
Remarks		

QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure	COMPL
			Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited					Printed: 02/07/2018 15:47	

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104548	Sample Depth (m BGL)	0.50 - 0.70
		Sample Type and No	B4
		Specimen Ref	



Soil description Greyish brown slightly sandy slightly gravelly CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, separate specimens tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.55 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.74

Optimum moisture content, %
14

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:37

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011454	Sample Depth (m BGL)	1.80 - 2.25
		Sample Type and No	B10
		Specimen Ref	



Soil description Brown slightly gravelly CLAY. Gravel is chalk

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.70 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.82

Optimum moisture content, %
17

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:39

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102609	Sample Depth (m BGL)	0.40 - 1.20
		Sample Type and No	B1
		Specimen Ref	



Soil description Brown slightly sandy CLAY with chalk fragments.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m3
1.76

Optimum moisture content, %
16

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:40

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092443	Sample Depth (m BGL)	0.30 - 0.55
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.80 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.80

Optimum moisture content, %
19

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
05/07/2018
11:41

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP10
	A8015-18-20180408084806	Sample Depth (m BGL)	0.40 - 0.60
		Sample Type and No	B4
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.95

Optimum moisture content, %
12

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 02/07/2018
 15:40

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP2
	A8015-18-20180413090338	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Dark brown slightly gravelly silty CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 4 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m3
1.55

Optimum moisture content, %
25

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
06/07/2018
07:56

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP4
	A8015-18-20180410075427	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown silty CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.80 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.71

Optimum moisture content, %
23

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:42

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP6
	A8015-18-20180410082549	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown CLAY with chalk fragments.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 2 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.82

Optimum moisture content, %
16

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:42

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP10
	A8015-18-20180408084806	Sample Depth (m BGL)	0.40 - 0.60
		Sample Type and No	B4
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.95

Optimum moisture content, %
12

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM

Figure
COMPH


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:40

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180409104552

Hole No	BH1
Sample Depth (m)	1.00 - 1.20
Sample Type and No	B5
Specimen Ref	1



Soil description	Brown slightly sandy slightly gravelly CLAY with rare rootlets.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	27

Sample Conditions		
Initial Moisture Content	%	22.0
Bulk Density	Mg/m ³	2.02
Dry Density	Mg/m ³	1.66
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	21.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	1.9	2.0
5	1.7	1.8

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	1.9	2.0
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180413011424

Hole No	BH2
Sample Depth (m)	1.00 - 1.20
Sample Type and No	B6
Specimen Ref	1



Soil description	Brown slightly sandy CLAY.
------------------	----------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	3

Sample Conditions		
Initial Moisture Content	%	25.0
Bulk Density	Mg/m ³	1.97
Dry Density	Mg/m ³	1.58
Moisture Content - TOP	%	26.0
Moisture Content - BASE	%	24.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	2.4	3.3
5	3.2	4.1

Surcharge applied	kg	16
	kPa	10


Notes :

Accepted CBR %	3.2	4.1
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No A8015-18 Project Name VPI IMMINGHAM	Figure CBR
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited	Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102609	Sample Depth (m)	0.40 - 1.20
		Sample Type and No	B1
		Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	21.0
Bulk Density	Mg/m ³	2.03
Dry Density	Mg/m ³	1.68
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Undisturbed	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.7	3.9
5	3.5	3.5

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	3.7	3.9
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180418115011

Hole No	BH4
Sample Depth (m)	1.65 - 2.00
Sample Type and No	B3
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	19.0
Bulk Density	Mg/m ³	2.12
Dry Density	Mg/m ³	1.78
Moisture Content - TOP	%	20.0
Moisture Content - BASE	%	19.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	4.8	4.4
5	4.7	4.2

Surcharge applied	kg	16
	kPa	10


Notes :

Accepted CBR %	4.8	4.4
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:	Hole No	TP1
	A8015-18-20180413084055	Sample Depth (m)	0.70 - 0.90
		Sample Type and No	B4
		Specimen Ref	1



Soil description	Brown slightly sandy CLAY with occasional chalk fragments.
------------------	--

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	23.0
Bulk Density	Mg/m ³	1.98
Dry Density	Mg/m ³	1.61
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.9	4.6
5	3.4	4.2

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	3.9	4.6
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15		

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413084231

Hole No	TP1
Sample Depth (m)	3.40 - 3.60
Sample Type and No	B10
Specimen Ref	1



Soil description	Light brown slightly sandy CLAY.
------------------	----------------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	14.0
Bulk Density	Mg/m ³	2.19
Dry Density	Mg/m ³	1.92
Moisture Content - TOP	%	13.0
Moisture Content - BASE	%	13.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	13.0	15.0
5	13.0	15.0

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	13.0	15.0
-----------------------	-------------	-------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413090359

Hole No	TP2
Sample Depth (m)	0.30 - 0.50
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly sandy slightly gravelly CLAY.
------------------	--

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	20.0
Bulk Density	Mg/m ³	1.92
Dry Density	Mg/m ³	1.60
Moisture Content - TOP	%	21.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	6.5	5.0
5	6.0	4.4

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	6.5	5.0
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180410092425

Hole No	TP7
Sample Depth (m)	1.30 - 1.60
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	17.0
Bulk Density	Mg/m ³	2.14
Dry Density	Mg/m ³	1.83
Moisture Content - TOP	%	17.0
Moisture Content - BASE	%	17.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.4	4.0
5	3.2	4.0

Surcharge applied	kg	16
	kPa	10


Notes :

Accepted CBR %	3.4	4.0
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No A8015-18 Project Name VPI IMMINGHAM	Figure CBR
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited	Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074518	Sample Depth (m)	3.70 - 3.90
		Sample Type and No	B12
		Specimen Ref	1



Soil description	Brown SAND with occasional chalk fragments.
------------------	---

Test Conditions	
Sample Retained on 20 mm sieve	%

Sample Conditions	
Initial Moisture Content	%
Bulk Density	Mg/m ³
Dry Density	Mg/m ³
Moisture Content - TOP	%
Moisture Content - BASE	%

Preparation	Method of Compaction	
	Undisturbed	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	-	-
5.0	-	-

Surcharge applied	kg	
	kPa	0


Notes :
 Test attempted @ NMC & various dryer MC's, sample protruded from mould at NMC & dryer MC's when CBR testing equipment came into contact with sample.

Accepted CBR %	-	-
-----------------------	---	---

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413014738

Hole No	TT1
Sample Depth (m)	0.50 - 0.70
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly gravelly CLAY with occasional chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	2

Sample Conditions		
Initial Moisture Content	%	27.0
Bulk Density	Mg/m ³	2.40
Dry Density	Mg/m ³	1.90
Moisture Content - TOP	%	25.0
Moisture Content - BASE	%	26.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	0.8	0.9
5	0.7	0.8

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	0.8	0.9
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180408080446

Hole No	TT3
Sample Depth (m)	0.30 - 0.60
Sample Type and No	B2
Specimen Ref	1



Soil description	Brown slightly sandy CLAY.
------------------	----------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	25.0
Bulk Density	Mg/m ³	1.94
Dry Density	Mg/m ³	1.56
Moisture Content - TOP	%	24.0
Moisture Content - BASE	%	27.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (2.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	1.6	1.1
5	2.2	1.7

Surcharge applied	kg	16
	kPa	10

Notes :

Accepted CBR %	2.2	1.7
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

TEST REPORT

Report No. EFS/187041 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham

The 4 samples described in this report were registered for analysis by SOCOTEC UK Limited on 23-Jun-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 03-Jul-2018

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of
SOCOTEC UK
Tim Barnes




Operations Director
Energy & Waste Services

Date of Issue: 03-Jul-2018

Tests marked 'N' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Units : %																	
Method Codes : ORGMAT																	
Method Reporting Limits : 0.1																	
LAB ID Number	Client Sample Description	Sample Date	Organic Matter %														
1910777	BH4 D 2 1.20		1.4														
1910778	TP02 D 3 0.30		7.1														
1910779	BH5 D 13 2.90		1.4														
1910780	BH2 D 3 0.60		16.7														
 <p>Bretby Business Park, Ashby Road Burton-on-Trent, Staffordshire, DE15 0YZ Tel +44 (0) 1283 554400 Fax +44 (0) 1283 554422</p>		Client Name SOCOTEC UK Doncaster Contact Tim Clifford	A8015-18 VPI Immingham										Sample Analysis				
												Date Printed	03-Jul-2018				
												Report Number	EFS/187041				
												Table Number	1				

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187041

Consignment No S75653
Date Logged 23-Jun-2018
In-House Report Due 29-Jun-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClustServ	ORGMAT
		Sampled	REPORT A	Organic Matter %
CL/1910777	BH4 1.20-1.65	D	D	D
CL/1910778	TP02 0.30	D	D	D
CL/1910779	BH5 2.90-3.35	D	D	D
CL/1910780	BH2 0.60	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT



1252

Report No. EFS/187043 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham

The 12 samples described in this report were registered for analysis by SOCOTEC UK Limited on 23-Jun-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 04-Jul-2018

Tests where the accreditation is set to N or No, and any individual data items marked with a * are not UKAS accredited. Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of
SOCOTEC UK Limited
Tim Barnes




Operations Director
Energy & Waste Services

Date of Issue: 04-Jul-2018

Tests marked '^' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

		Units :	mg/kg	mg/l	%	%	pH Units										
		Method Codes :	ICPACIDS	ICPWSS	ORGMAT	TSBRE1	WSLM50										
		Method Reporting Limits :	20	10	0.1	0.005											
		UKAS Accredited :	Yes	Yes	No	No	No										
LAB ID Number	Client Sample Description	Sample Date	SO4-- (acid sol)	SO4-- (H2O sol) mg/l	Organic Matter %	Total Sulphur.	pH (BS1377)										
1910790	BH2 D 14 2.80				1.6												
1910791	BH3 D 4 2.00				1.4												
1910792	BH3 D 6 3.00		433	116		0.041	8.4										
1910793	BH6 D 26 13.70		200	23		0.029	8.7										
1910794	TP1 D 1 0.10				3.6												
1910795	TP2 D 11 4.00		276	56		0.031	8.8										
1910796	TP3 D 9 3.40				1.5												
1910797	TP5 D 1 0.10				3.6												
1910798	TP6 D 3 0.40		1420	479		0.085	7.8										
1910799	TP8 D 7 2.00				1.9												
1910800	TP9 D 5 0.80				3.1												
1910801	TT2 B 6 2.00		643	118		0.039	7.5										
 <p>Bretby Business Park, Ashby Road Burton-on-Trent, Staffordshire, DE15 0YZ Tel +44 (0) 1283 554400 Fax +44 (0) 1283 554422</p>			Client Name SOCOTEC UK Doncaster Contact Tim Clifford				A8015-18 VPI Immingham						Sample Analysis				
							Date Printed 04-Jul-2018										
							Report Number EFS/187043										
							Table Number 1										

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187043

Consignment No S75655
Date Logged 23-Jun-2018
In-House Report Due 29-Jun-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClstServ	Dep.Ord	DO Mg if SO4(W)>3000	DO NO3 if pH<5.5	DO Cl if pH>5.5	ICPACIDS	ICPBRE	ICPWSS	KONECL	KoneNO3	ORGMAT	TSBRE1	WSLMS0
		Sampled	REPORT A	DO Cl if pH<5.5				SO4-- (acid sol)	Magnesium (BRE)	SO4-- (H2O sol) mg/l	Chloride:(2:1)	Nitrate (BRE 2:1): mg/l	Organic Matter %	Total Sulphur.	pH (BS1377)
								✓		✓					
CL/1910790	BH2 2.80-3.25	D	D										D		
CL/1910791	BH3 2.00-2.45	D	D										D		
CL/1910792	BH3 3.00-3.45	D	D	D	D	D	D	D	D	D	D	D	D	D	D
CL/1910793	BH6 13.70	D	D				D	D	D	D	D	D	D	D	D
CL/1910794	TP1 0.10	D	D										D		
CL/1910795	TP2 4.00	D	D				D	D	D	D	D	D	D	D	D
CL/1910796	TP3 3.40	D	D										D		
CL/1910797	TP5 0.10	D	D										D		
CL/1910798	TP6 0.40	D	D				D	D	D	D	D	D	D	D	D
CL/1910799	TP8 2.00	D	D										D		
CL/1910800	TP9 0.80	D	D										D		
CL/1910801	TT2 2.00-2.15	D	D				D	D	D	D	D	D	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ICPACIDS	Oven Dried @ < 35°C	Determination of Total Sulphate in soil samples by Hydrochloric Acid extraction followed by ICPOES detection
Soil	ICPWSS	Oven Dried @ < 35°C	Determination of Water Soluble Sulphate in soil samples by water extraction followed by ICPOES detection
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract
Soil	TSBRE1	Oven Dried @ < 35°C	Determination of Total Carbon and/or Total Sulphur in solid samples by high temperature combustion/infrared detection
Soil	WSLM50	Oven Dried @ < 35°C	Determination of pH of 2.5:1 deionised water to soil extracts using pH probe.

Where individual results are flagged see report notes for status.

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT



Report No. EFS/187204 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham


The 11 samples described in this report were registered for analysis by SOCOTEC UK Limited on 28-Jun-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 09-Jul-2018

Tests where the accreditation is set to N or No, and any individual data items marked with a * are not UKAS accredited. Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.

The following tables are contained in this report:

- Table 1 Main Analysis Results (Page 2)
- Analytical and Deviating Sample Overview (Page 3)
- Table of Method Descriptions (Page 4)
- Table of Report Notes (Page 5)
- Table of Sample Descriptions (Appendix A Page 1 of 1)


On behalf of
SOCOTEC UK Limited 
Tim Barnes Operations Director
Energy & Waste Services

Date of Issue: 09-Jul-2018

Tests marked '^' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

		Units :	mg/kg	mg/l	%	%	pH Units											
		Method Codes :	ICPACIDS	ICPWSS	ORGMAT	TSBRE1	WSLM50											
		Method Reporting Limits :	20	10	0.1	0.005												
		UKAS Accredited :	Yes	Yes	No	No	No											
LAB ID Number	Client Sample Description	Sample Date	SO4-- (acid sol)	SO4-- (H2O sol) mg/l	Organic Matter %	Total Sulphur.	pH (BS1377)											
1911581	TT02 B 6 2.00		498	79		0.033	7.8											
1911582	TT03 B 4 1.30				2.6													
1911583	BH5 B 18 4.00		737	205		0.153	8.0											
1911584	BH6 B 1 0.00				3.2													
1911585	TP02 B 10 3.40				1.6													
1911586	TP6 B 6 1.00				1.4													
1911587	TP09 B 6 0.80		626	121		0.053	7.6											
1911588	BH1 D 3 0.45				13.7													
1911589	BH1 B 5 1.00		1260	847		0.068	7.8											
1911590	BH2 B 13 2.20		1170	530		0.075	8.1											
1911591	BH2 B 31 5.70		604	178		0.319	8.5											
 Bretby Business Park, Ashby Road Burton-on-Trent, Staffordshire, DE15 0YZ Tel +44 (0) 1283 554400 Fax +44 (0) 1283 554422			Client Name SOCOTEC UK Doncaster				Contact Tim Clifford				Sample Analysis Date Printed: 09-Jul-2018 Report Number: EFS/187204 Table Number: 1				A8015-18 VPI Immingham			

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187204

Consignment No S75795
Date Logged 28-Jun-2018
In-House Report Due 04-Jul-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClientServ	Dep. Opt	DO Mg if SO4(W)>3000	DO NO3 if pH<5.5	SO4-- (acid sol)	ICPACIDS	ICPBRE	ICPWSS	KONCL	KONNO3	ORGMAT	TSBRE1	W/S/LM50
		Sampled	REPORT A	DO Cl if pH<5.5											
								✓		✓					
CL/1911581	TT02 2.00-2.15	D	D	D	D	D	D	D	D	D	D	D		D	D
CL/1911582	TT03 1.30-1.60	D	D										D		
CL/1911583	BH5 4.00-4.45	D	D				D	D	D	D	D	D		D	D
CL/1911584	BH6 0.00-0.30	D	D										D		
CL/1911585	TP02 3.40-3.50	D	D										D		
CL/1911586	TP6 1.00-1.20	D	D										D		
CL/1911587	TP09 0.80-1.00	D	D				D	D	D	D	D	D		D	D
CL/1911588	BH1 0.45	D	D										D		
CL/1911589	BH1 1.00-1.20	D	D				D	D	D	D	D	D		D	D
CL/1911590	BH2 2.20-2.70	D	D				D	D	D	D	D	D		D	D
CL/1911591	BH2 5.70-6.15	D	D				D	D	D	D	D	D		D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ICPACIDS	Oven Dried @ < 35°C	Determination of Total Sulphate in soil samples by Hydrochloric Acid extraction followed by ICPOES detection
Soil	ICPWSS	Oven Dried @ < 35°C	Determination of Water Soluble Sulphate in soil samples by water extraction followed by ICPOES detection
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract
Soil	TSBRE1	Oven Dried @ < 35°C	Determination of Total Carbon and/or Total Sulphur in solid samples by high temperature combustion/infrared detection
Soil	WSLM50	Oven Dried @ < 35°C	Determination of pH of 2.5:1 deionised water to soil extracts using pH probe.

Where individual results are flagged see report notes for status.

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT

Report No. EFS/187902 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG


Site: A8015-18 VPI Immingham

The 1 sample described in this report were registered for analysis by SOCOTEC UK Limited on 19-Jul-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 25-Jul-2018

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of 
SOCOTEC UK Limited
Tim Barnes Operations Director
Energy & Waste Services

Date of Issue: 25-Jul-2018

Tests marked 'N' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Units :	%																	
Method Codes :	ORGMAT																	
Method Reporting Limits :	0.1																	

LAB ID Number CL/	Client Sample Description	Sample Date	Organic Matter %															
1914695	BH1 D 7 1.65		1.1															

 Bretby Business Park, Ashby Road Burton-on-Trent, Staffordshire, DE15 0YZ Tel +44 (0) 1283 554400 Fax +44 (0) 1283 554422	Client Name SOCOTEC UK Doncaster	<h2>A8015-18 VPI Immingham</h2>	Sample Analysis	
	Contact Tim Clifford		Date Printed 25-Jul-2018	Report Number EFS/187902
			Table Number 1	

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187902

Consignment No S75653
Date Logged 19-Jul-2018
In-House Report Due 25-Jul-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClientServ	ORGMAT
		Sampled	REPORT A	Organic Matter %
CL/1914695	BH1 1.65-1.80	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix


Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

APPENDIX E
PHOTOGRAPHS

Rotary Cores
Trial Pits


Plate 1 to 6
Plate 7 to 21

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 1
--------	--	---------

Photographs



Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate


2

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate <p style="text-align: center;">3</p>
--------	--	--

Photographs




Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

4

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 5
--------	---	----------------

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 6
--------	--	---------

Photographs



TP1



Notes:	<p>Project VPI IMMINGHAM</p> <p>Project No. A8015-18</p> <p>Carried out for AECOM</p>	Plate 7
--------	---	----------------



TP1 Spoil

Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 8
--------	--	---------

Photographs



TP2



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 9
--------	--	---------



TP2 Spoil

Notes:	<p>Project VPI IMMINGHAM</p> <p>Project No. A8015-18</p> <p>Carried out for AECOM</p>	Plate 10
--------	---	--------------------



TP3



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 11
--------	--	----------



TP3 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

12



TP5



Notes:	<table border="0"> <tr> <td>Project</td> <td>VPI IMMINGHAM</td> </tr> <tr> <td>Project No.</td> <td>A8015-18</td> </tr> <tr> <td>Carried out for</td> <td>AECOM</td> </tr> </table>	Project	VPI IMMINGHAM	Project No.	A8015-18	Carried out for	AECOM	Plate 13
Project	VPI IMMINGHAM							
Project No.	A8015-18							
Carried out for	AECOM							



TP6



Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

14



TP6 Spoil

Notes:	<p>Project VPI IMMINGHAM</p> <p>Project No. A8015-18</p> <p>Carried out for AECOM</p>	Plate 15
--------	---	--------------------



TP9 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

16



TP10



Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

17



TP10 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

18

Photographs



TT02



Notes:

Project VPI IMMINGHAM
 Project No. A8015-18
 Carried out for AECOM

Plate

19



TT02 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

20



TT03



Notes:	<p>Project VPI IMMINGHAM</p> <p>Project No. A8015-18</p> <p>Carried out for AECOM</p>	<p>Plate</p> <p style="text-align: center; font-size: 24pt;">21</p>
--------	---	--

Appendix C – Photolog

Survey date: 1 June 2018

**Supplementary Phase 1 Geo-environmental
Assessment
VPI Immingham**

**Project No.
60547702**



Photograph 1

Substation located in the northern corner of the site.



Photograph 2

Tarmac hardstanding looking south east.

Survey date: 1 June 2018

**Supplementary Phase 1 Geo-environmental
Assessment
VPI Immingham**

**Project No.
60547702**



Photograph 3

Tarmac hardstanding looking south east.



Photograph 4

Tarmac hardstanding looking north east.

Survey date: 1 June 2018

**Supplementary Phase 1 Geo-environmental
Assessment
VPI Immingham**

**Project No.
60547702**



Photograph 5

Tarmac and hardstanding, looking at the VPI contractor compound, looking south east.



Photograph 6

VPI outfall, looking north west.

Survey date: 1 June 2018

**Supplementary Phase 1 Geo-environmental
Assessment
VPI Immingham**

**Project No.
60547702**



Photograph 7


VPI outfall looking north east.



Photograph 8

Stockpiles of demolition rubble, looking north west.

Survey date: 1 June 2018	Supplementary Phase 1 Geo-environmental Assessment VPI Immingham	Project No. 60547702
--------------------------	---	--------------------------------



Photograph 9 | Former laydown area, looking north east.



Photograph 10 | Former laydown area, looking north east.

Survey date: 1 June 2018	Supplementary Phase 1 Geo-environmental Assessment VPI Immingham	Project No. 60547702
--------------------------	---	--------------------------------



Photograph 11 | Former laydown area, including pipe bridge, looking south west.



Photograph 12 | Former laydown area, looking north east.

Appendix D – Historic Maps

Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series


Map date: 1854

Scale: 1:10,560

Printed at: 1:10,560



Surveyed N/A
 Revised N/A
 Edition N/A
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series


Map date: 1886

Scale: 1:10,560

Printed at: 1:10,560



Surveyed N/A
 Revised N/A
 Edition N/A
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ


Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series

Map date: 1886-1887

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1886 Revised 1886 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised N/A Edition N/A Copyright N/A Levelled N/A
Surveyed 1886 Revised 1886 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised 1886 Edition N/A Copyright N/A Levelled N/A



Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf

Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series

Map date: 1905-1906

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1886 Revised 1906 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised 1906 Edition N/A Copyright N/A Levelled N/A
Surveyed 1886 Revised 1905 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised 1905 Edition N/A Copyright N/A Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series


Map date: 1910

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1853
 Revised 1910
 Edition 1910
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series


Map date: 1929-1930

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1886 Revised 1929 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised 1930 Edition N/A Copyright N/A Levelled N/A
Surveyed 1886 Revised 1929 Edition N/A Copyright N/A Levelled N/A	Surveyed 1886 Revised 1930 Edition N/A Copyright N/A Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series

Map date: 1947

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1886
 Revised 1947
 Edition N/A
 Copyright N/A
 Levelled N/A

Surveyed 1886
 Revised 1947
 Edition 1947
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ


Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: County Series

Map date: 1946-1951

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1853
 Revised 1947
 Edition N/A
 Copyright N/A
 Levelled N/A

Surveyed 1886
 Revised 1946
 Edition 1946
 Copyright N/A
 Levelled N/A

Surveyed 1886
 Revised 1947
 Edition N/A
 Copyright 1951
 Levelled 1906




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: Provisional

Map date: 1951

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1951
 Revised 1951
 Edition N/A
 Copyright N/A
 Levelled N/A



Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: Provisional

Map date: 1951

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1951
 Revised 1951
 Edition N/A
 Copyright N/A
 Levelled N/A



Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: Provisional

Map date: 1968

Scale: 1:10,560

Printed at: 1:10,560



Surveyed 1968
 Revised 1968
 Edition N/A
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: National Grid

Map date: 1974

Scale: 1:10,000

Printed at: 1:10,000



Surveyed 1974
 Revised 1974
 Edition N/A
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ

Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: National Grid

Map date: 1983

Scale: 1:10,000

Printed at: 1:10,000



Surveyed 1975
 Revised 1983
 Edition N/A
 Copyright N/A
 Levelled N/A




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ


Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: 1:10,000 Raster

Map date: 2002

Scale: 1:10,000

Printed at: 1:10,000




Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ



Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: National Grid

Map date: 2010

Scale: 1:10,000

Printed at: 1:10,000



Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Site Details:

TANKS 90M FROM V P I
 IMMINGHAM, ROSPER ROAD.
 18M FROM UNNAMED ROAD,
 FOOTPATH SKIL91A, SOUTH
 KILLINGHOLME, DN40 3DZ


Client Ref: VPI_Immingham
Report Ref: GS-5087183
Grid Ref: 516729, 417136

Map Name: National Grid

Map date: 2014

Scale: 1:10,000

Printed at: 1:10,000



Produced by
 Groundsure Insights
 T: 08444 159000
 E: info@groundsure.com
 W: www.groundsure.com

© Crown copyright and database rights 2018 Ordnance Survey 100035207

Production date: 30 May 2018

Map legend available at:
www.groundsure.com/sites/default/files/groundsure_legend.pdf



Appendix E – Phase 2 Geotechnical and Geo-environmental Interpretative Report, September 2018

VPI Immingham Energy Park

Phase 2
Geotechnical & Geo-environmental Interpretative Report

VPI Immingham LLP

Project number: 60569745

31/08/2018

Quality information

Prepared by	Checked by	Verified by	Approved by
Dan Maher/Reza Vand	David Rosenberg/ Ben Braund	Dr Lawrence Bowden /Ed Brook	David Cragg
<i>DM/RV</i>	<i>DR/BB</i>	<i>LB/EB</i>	<i>DC</i>

Revision History

Revision	Revision date	Details	Authorized	Name	Position
Rev01	24/8/18	Issue 01	DC	D Cragg	Technical Director
Rev 02	19/9/18	Issue 02	DC	D Cragg	Technical Director

Distribution List

# Hard Copies	PDF Required	Association / Company Name
-	X	Vitol Power International

Prepared for:
Vitol Power International

Prepared by:

AECOM Infrastructure & Environment UK Limited
5th Floor, 2 City Walk
Leeds LS11 9AR
United Kingdom

T: +44 (0)113 391 6800
aecom.com

Limitations

AECOM Infrastructure & Environment UK Limited ("AECOM") has prepared this Report for the sole use of **Vitol Power International** ("Client") in accordance with the terms and conditions of appointment (**Project number: 60569745**) dated **24/08/2018**. No other warranty, expressed or implied, is made as to the professional advice included in this Report or any other services provided by AECOM. This Report may not be relied upon by any other party without the prior and express written agreement of AECOM.

Where any conclusions and recommendations contained in this Report are based upon information provided by others, it has been assumed that all relevant information has been provided by those parties and that such information is accurate. Any such information obtained by AECOM has not been independently verified by AECOM, unless otherwise stated in the Report. AECOM accepts no liability for any inaccurate conclusions, assumptions or actions taken resulting from any inaccurate information supplied to AECOM from others.

The methodology adopted and the sources of information used by AECOM in providing its services are outlined in this Report. The work described in this Report was undertaken between **[10/4/18]** and **[31/8/18]** and is based on the conditions encountered and the information available during the said period of time. The scope of this Report and the services are accordingly factually limited by these circumstances. AECOM disclaim any undertaking or obligation to advise any person of any change in any matter affecting the Report, which may come or be brought to AECOM's attention after the date of the Report.

The exploratory holes carried out during the fieldwork, which investigate only a small volume of the ground in relation to the size of the site, can only provide a general indication of site conditions. The comments made and recommendations given in this Report are based on the ground conditions apparent at the site of the exploratory holes. There may be exceptional ground conditions elsewhere on the site which have not been disclosed by this investigation and which have therefore not been taken into account in this Report.

The comments made on groundwater conditions are based on observations made during site work and the limited monitoring programme. It should be noted that groundwater levels might vary owing to seasonal or other effects.

The site reconnaissance consisted of a general external inspection of the site aimed at identifying any obvious signs of geotechnical hazards and potential sources of ground contamination affecting the site.

Any risks identified in this Report are perceived risks, based on the information reviewed during the desk study and therefore partially based on conjecture from available information. The study is limited by the non-intrusive nature of the work and actual risks can only be assessed following a physical investigation of the site.

The investigation itself was designed generally to meet the objectives of an exploratory investigation, as defined by BS10175:2011 Investigation of Potentially Contaminated Sites: Code of Practice (BSI). As an exploratory, the results may not provide sufficient data to make detailed estimates of the quantities involved in any remediation work, if required.

The opinions expressed in this Report concerning any contamination found and the risks arising there from are based on current good practice simple statistical assessment and comparison with available soil guideline values, AECOM generic assessment criteria and other guidance values.

It should be noted that the effects of ground and water borne contamination on the environment are constantly under review, and authoritative guidance values are potentially subject to change. The conclusions presented herein are based on the guidance values available at the time this Report was prepared, however, no liability by AECOM can be accepted for the retrospective effects of any changes or amendments to these values.

© This Report is the copyright of AECOM. Any unauthorised reproduction or usage by any person other than the addressee is strictly prohibited.]¹

Table of Contents

1.	Introduction.....	4
1.1	Terms of Appointment.....	4
1.2	Background.....	4
1.3	Scope and objective of the report.....	4
1.4	Proposed Intrusive Investigation	4
2.	Existing Information.....	6
2.1	Site Description.....	6
2.2	Anticipated Geology	6
2.3	Hydrogeology and Hydrology.....	7
2.4	Regulatory Database Review.....	8
2.5	Sensitive Land Uses.....	9
2.6	Statutory Consultations.....	9
3.	Preliminary Conceptual Site Model	10
3.1	Assessment Framework	10
3.2	Potential Sources of Contamination	10
3.3	Contaminants of Concern	11
3.4	Potential Pathways.....	13
3.5	Potential receptors	13
3.6	Preliminary Risk Evaluation	14
3.7	Summary of Potential Pollutant Linkages	14
4.	Fieldwork.....	16
4.1	Ground investigations.....	16
4.2	Ground Investigation Factual Report.....	17
4.3	Post Ground Investigation.....	17
5.	Ground Summary.....	18
5.1	Summary of Ground Conditions.....	18
6.	Geotechnical Parameters	20
6.1	Made Ground.....	20
6.2	Glacial Till	21
6.3	Burnham Chalk Formation.....	23
6.4	Groundwater Strikes.....	24
6.5	Groundwater monitoring	25
6.6	Concrete Aggressivity.....	26
7.	Contamination Assessment	27
7.1	Sample Analysis.....	27
7.2	Stage 2 Risk Assessment	28
7.3	Revised Conceptual Site Model	34
7.4	Summary of Contaminant Linkages.....	39
8.	Geotechnical Assessment	40
8.1	Proposed Works.....	40
8.2	Engineering Assessment	40
9.	Geotechnical Risk Register	42
9.1	Assessing Geotechnical Risk.....	42
9.2	Geotechnical Hazards	42
10.	References	44
	Appendix A Site Location Plan/ Proposed site layout Plan	45
	Appendix B Risk Assessment Principles	46
	Appendix C Factual Report	47
	Appendix D Laboratory Certifications.....	48
	Appendix E Gas and Groundwater Monitoring Results	49

Appendix F Parametric Study Charts..... 50
Appendix G Contamination Assessments..... 51

Glossary of Terms

AC:	Aggressive Chemical Environmental for Concrete Class,
ACEC:	Aggressive Chemical Environmental for Concrete,
BGS:	British Geological Survey,
BH:	Borehole,
CBR:	California Bearing Ratio,
CEMP:	Construction Environmental Management Plan,
CFA:	Continuous Flight Auger,
CHP:	Combined Heat and Plant,
CS:	Characteristic Situation,
CU:	Consolidated Triaxial Test,
DOC:	Dissolved Organic Carbon,
DS:	Design Sulphate,
DWS:	Drinking Water Standard,
EQS:	Environmental Quality Standard for controlled waters
GAC:	Generic Assessment Criteria,
GQRA	Generic Quantitative Risk Assessment,
HC:	Hydraulic Cell,
INDEX:	Classification tests, including moisture content, Atterberg limits,
LPG:	Liquid Petroleum Gas,
M bgl:	Metres Below Grounds Level,
M OD:	Metre Above Ordnance Datum,
OCGT:	Open Cycle Gas Turbine,
OD:	Ordnance Datum,
OED:	Consolidation Tests,
ORP:	Oxidation-Reduction Potential,
PAH:	Polyaromatic Hydrocarbons,
PID:	Photo Ionisation Detector,
PCB,;	Polychlorinated Biphenyl
PPE:	Personal Protective Equipment,
PSD:	Particle Size Distribution,
SPT:	Standard Penetration Testing,
SVOCs	Semi Volatile Organic Compounds,
TP:	Trial Pit,
TICs:	Tentatively Identified Compounds,
TOC:	Total Organic Carbon,
TPHs:	Total Petroleum Hydrocarbons,
TPH-CWG	Total Petroleum Hydrocarbons- Criteria Working Group,
TT:	Trial Trench,
UU:	Unconsolidated undrained triaxial test,
UXO:	Unexploded Ordnance,
VOCs:	Volatile Organic Compounds,
WTV:	Water Target Value,
WS:	Window Sample Hole,

EXECUTIVE SUMMARY

	Conclusions	Recommendations
Ground Conditions	<p>The results of the 2018 ground investigation by SOCOTEC UK Ltd shows that the site consists of up to 1.7m thickness of variable cohesive and granular Made Ground, underlain by cohesive Glacial Till with occasional layers of Glacial Sands and Gravels. The cohesive Glacial Till is typically described as firm to stiff, sandy, gravelly, clay with a low to medium compressibility index. A number of boreholes encountered highly weathered chalk from the Burnham Chalk Formation between the depths of 21.5m bgl and 27.5m bgl. Without geotechnical laboratory testing information available for the chalk formation, it is not possible to provide characteristic parameters.</p> <p>Borehole records and in-situ tests for the cohesive and granular Made Ground show that the material is highly variable and conservatively classified as soft or loose.</p> <p>As a conservative assumption, the occasional Glacial Sands and Gravels layers have not been included in the parameter determination process. Borehole descriptions and geotechnical tests show that the Glacial Till is firm, becoming very stiff with depth material. Depending on the foundation solution and limiting criteria, the Glacial Till can be deemed as a relatively competent material.</p> <p>Further assessments can be undertaken at specific locations within the site to refine the engineering parameters and ground models presented in this report.</p>	<p>Caution should be taken when selecting engineering and construction solutions which interact with the Made Ground material. The performance of structures founded in made ground is difficult to predict due to its variable nature.</p> <p>Should engineering solutions, such as piles, need to penetrate the Burnham Chalk Formation, further GI information will be required to develop a safe design.</p>
Building Foundations	<p>Both spread and piled foundation solutions may be considered for the proposed structures for the site. Foundation selection will depend on proposed loadings, foundation geometry and structural tolerance to total and differential settlement. Bearing resistance and tolerance to settlement will need to be considered for any spread foundations. Spread foundations should be located within natural ground below any fill or Made Ground, and founded below the depth of effect of variations due to vegetation, seasonal and climatic change.</p> <p>Piled foundations may be considered for structures depending on proposed loadings, foundation geometry or where settlement tolerances is an issue, or where spread foundations are found to be unsuitable. Piles may derive capacity from a combination of skin friction and end bearing in the superficial soils.</p> <p>Two design approaches can be adopted for piled foundations; placing the buildings on individual pile caps/rafts or creating a piled raft to cover large sections of the site. A piled raft will require a larger quantity of construction work but will ensure a stable design which will limit differential settlements between the buildings.</p>	<p>When considering shallow foundations, any soft, loose or deleterious deposits encountered at formation level should be removed and backfilled with suitable engineered fill or mass concrete.</p> <p>Should the piles need to penetrate the Burnham Chalk Formation, further GI information will be required to develop a safe design.</p> <p>Continuous Flight Auger (CFA) would be the preferred piling method for the assessed ground conditions. However, advice should be obtained from a specialist piling contractor before confirming a final design.</p>

	<p>Individual pile caps/rafts for separate buildings will allow for more flexibility in the pile design and enable costs to be optimised.</p>										
<p>Excavations & Earthworks</p>	<p>Soft, loose or deleterious material will require to be removed from under proposed structures.</p> <p>Considering the variable groundwater levels obtained from installations within the superficial deposits, and in view of the likelihood that long term equilibrium groundwater levels have not been recorded during the brief monitoring period, provision should be made for pumping from sumps to control ingress of groundwater into excavations in the event that water bearing granular bodies are encountered.</p> <p>Excavation should be possible using conventional site plant.</p>	<p>All excavations should be battered back to a safe angle as determined on site or be provided with close/continuous support and or stabilisation measures. Any temporary excavated slopes which are likely to receive fill are to be benched prior to filling.</p> <p>If earthworks are proposed it is recommended that slope stability analyses are undertaken at detailed design stage to establish maximum permissible slope angles.</p> <p>It is recommended that provision is made for pumping from sumps to control ingress of groundwater into excavations in the event that water bearing granular bodies are encountered</p>									
<p>Retaining Walls</p>	<p>Similar to spread foundations, foundations for retaining walls should be located within natural ground below any fill and Made Ground.</p>	<p>If any soft, loose or deleterious deposits are encountered at foundation and or formation level, these should be removed and backfilled with well compacted suitable engineered fill or mass concrete.</p> <p>Due to the low permeability of the Glacial Tills, it is possible that the equilibrium water levels within the standpipes have not yet been reached, therefore a conservative approach is recommended for the selection of design groundwater levels for retaining wall design.</p> <p>Groundwater levels should continue to be monitored at monthly intervals to determine equilibrium levels and seasonal variations prior to detailed design.</p> <p>Adequate drainage measures to the rear of retaining walls should be designed to prevent the build-up of water pressure against the retaining walls.</p>									
<p>Infrastructure</p>	<p>Levels of Sulphate and pH which can aggressively attack concrete have been identified for the section.</p> <p>Potentially toxic and corrosive chemicals and elements have been encountered in both total soils testing and leachate samples taken in this section that may pose a risk to new/ diverted water supply pipes.</p>	<p>The recommended design class sulphate and ACEC Classification for various concrete structures are presented below</p> <table border="1" data-bbox="930 1512 1428 1803"> <thead> <tr> <th>Stratum</th> <th>Undisturbed ground Classification</th> <th>Disturbed ground Classification</th> </tr> </thead> <tbody> <tr> <td>Made Ground</td> <td>DS-2, AC-2</td> <td>DS-2, AC-2</td> </tr> <tr> <td>Glacial Deposits</td> <td>DS-1, AC-1</td> <td>DS-3, AC-3</td> </tr> </tbody> </table> <p>Advice should be sought from United Utilities, including completing their risk assessment process, to assist in the specification of drinking water supply pipes prior to installation.</p>	Stratum	Undisturbed ground Classification	Disturbed ground Classification	Made Ground	DS-2, AC-2	DS-2, AC-2	Glacial Deposits	DS-1, AC-1	DS-3, AC-3
Stratum	Undisturbed ground Classification	Disturbed ground Classification									
Made Ground	DS-2, AC-2	DS-2, AC-2									
Glacial Deposits	DS-1, AC-1	DS-3, AC-3									

Human Health	<p>Risk assessment based on conservative assumptions does not indicate any risk to human health for the current or proposed land use.</p> <p>An appropriate CEMP and the use of standard PPE will be sufficient to protect construction workers from contact with substances present in the soil, given the concentrations encountered during the ground investigation</p>	<p>No remedial actions are required to protect current site users or future site users from substances in the soils. The stage 2 risk assessment does not assess the specific risks to construction workers, but appropriate PPE and CEMP precautions will be sufficient to mitigate risk to construction works.</p>
Groundwater	<p>Assessment of risks to controlled waters from leachable (soluble) concentrations of potentially polluting substances in soil, when compared conservatively against DWS and EQS, show a number of exceedances. However, this is not reflected in the groundwater below the site and the distance to sensitive surface waters makes the possibility of harm to sensitive controlled waters from leachable soil substances unlikely.</p> <p>There are concentrations above the relevant screening criteria for a variety of contaminants in the soils below the site and deep foundations may create pathways through less permeable layers from the unsaturated zone to sensitive groundwater below. However the risks associated with deep foundations can be mitigated by means of risk assessment specific to the design and construction proposals.</p>	<p>No remedial measures are required on site to protect controlled waters. However any piles should be designed in accordance with the EA guidance entitled <i>Piling and Penetrative Ground Improvement Methods on Land Affected by Contamination: Guidance on Pollution Prevention (2001)</i></p>
Ground Gas	<p>A preliminary assessment of measured gas concentrations and flow rates in accordance with BS8485:20015 has determined that the overall 'Characteristic Gas Classification' for the site is Category 2.. This is a category defining a low to moderate risk which would necessitate a relatively low level of protection against the ingress of gas to confined spaces in the development.</p> <p>Bs8485 provides guidance on the design of protective measures against the ingress of ground gas based upon a system of scores related to the level of risk prevalent at the site. It is considered that in accordance with published guidance and BS8485, the majority of the proposed power generation plant and buildings on site would fall into a Type D industrial style buildings which for a CS2 will require gas protection sufficient to reach a score of 1.5.. However any smaller ancillary buildings will be classified as type C which will require measures sufficient to achieve a score of 2.5.</p> <p>However if Made Ground is removed as part of the pre-construction works the site would classify as CS1 where no protection measures are required.</p>	<p>Where required ground gas protection measures as defined in BS8485 should be incorporated in the buildings.</p> <p>Standard good health and safety practice and PPE should be specified within the Construction Phase Plan in order to protect construction workers from gas within confined spaces.</p>
Ecological Receptors	<p>The Humber Estuary and Rosper Road Pools represent ecological receptors, but the distance to the receptor is such that harm is unlikely to be caused.</p>	<p>Although it is not considered the site is a significant risk to statutory ecological receptors . a landscape architect should be provided with the chemical analysis in order to establish suitable plant species for the site.</p>
Reuse of material		<p>Material encountered during construction works that is considered to be potentially contaminated through visual or olfactory evidence, or different to that assessed in the ground investigation will require chemical testing to confirm suitability for reuse.</p>
Imported Materials		<p>Imported material (e.g. fill, etc.) will require chemical and geotechnical testing before being brought onto site to demonstrate that it is suitable for use. The testing suite and frequency, along with validation requirements, should be agreed with the Contaminated Land Officer at the Local Authority prior to importation of material.</p>

1. Introduction

1.1 Terms of Appointment

AECOM were appointed by VPI Immingham LLP to undertake works comprising a ground investigation and interpretive report as described in the Ground investigation Fee Proposal Dated 02/03/18.

1.2 Background

The current Vitol Power International (VPI) Immingham LLP Combined Heat and Power plant (CHP) has been operational since 2004. The CHP plant produces steam which is supplied to the nearby Humber and Lindsey Oil Refineries. It is understood that the CHP will be extended to the north of the site for the development of several gas fired power generation and storage projects including reciprocating engines and an Open Cycle Gas Turbine (OCGT) plant. The development land is occupied by a car park and an area of open, hummocky land occupied by several vegetated mounds and ponded water in wet periods. The site location can be found in, and the proposed development can be found in Appendix A.

1.3 Scope and objective of the report

This Phase 2 Ground Investigation is concerned with the ground conditions at the proposed construction site of a new power generation and plant and buildings adjacent to the Humber and Lindsey Oil Refineries at Immingham, Humberside.

A ground investigation was undertaken to assist with the design of the proposals, including laboratory testing to determine soil properties and the installation of monitoring instruments to determine groundwater behaviour.

AECOM was commissioned by VPI Immingham LLP to provide design, management and full time technical oversight of the ground investigation works, which were completed by Socotec in April 2018; and to provide an interpretative and advisory report on the ground conditions in relation to development proposals.

The Ground Investigation comprised cable percussion and rotary drilled boreholes, trial pits and laboratory testing. The investigation was performed in accordance with the contract specification, and the general requirements of Eurocode 7, BS5930 (5930) and BS EN ISO 22475-1 (2006).

Following receipt of Socotec's factual report and the results of the laboratory testing, AECOM prepared a draft Geo-environmental and Geotechnical Interpretative Report. This includes an initial assessment of the results of the geotechnical testing and a discussion of possible foundation solutions and highways and pavement specification. The results of contamination testing of soil and groundwater samples have been screened against Stage 2 generic assessment criteria for human health and controlled waters receptors and provides an update to the conceptual site model outlined in the AECOM report "*VPI Immingham Phase 1 Geo-environmental Assessment*" (June 2017,).

1.4 Proposed Intrusive Investigation

Based on the findings of the Phase 1 desk study report and our understanding of the objectives for the site investigation and proposed redevelopment at the site, AECOM proposed the following scope for the ground investigation;

- GPR survey to make sure that the proposed exploratory locations were free from services;
- Drilling of six cable percussion boreholes to bedrock with potential follow on rotary coring to obtain samples of soil and rock for analysis of chemical and geotechnical properties, and installation of groundwater monitoring wells;
- Drilling of up to eight windowless samples into the underlying glacial till using dynamic sampling techniques to obtain in situ data, i.e. standard penetration testing (SPT), soil samples for chemical analysis and installation of gas/ groundwater wells;

- Excavation of up to ten trial pits and three trial trenches across the site to investigate potential made ground deposits present at the site including two large stockpiles;
- Installation of up to fourteen gas / groundwater monitoring wells;
- Logging of boreholes and trial pits in accordance with Eurocode 7;
- Headspace analysis of VOCs using a portable ionisation detector (PID);
- Well development to purge water and fines entrained in the filter pack during drilling;
- Completion of three gas / groundwater monitoring events including collection of groundwater samples;
- Analysis of soil and groundwater samples for a range of determinands and potential contaminants including heavy metals, Polycyclic Aromatic Hydrocarbons (PAHs), Total Petroleum Hydrocarbons Criteria Working Group, (TPH-CWG), asbestos, Volatile Organic Compounds (VOCs) and semi-Volatile Organic Compounds (SVOCs), major anions, and organic matter;
- Provisional characterisation of soils in stockpiles to assess waste classification in the event that offsite disposal is required;
- Analysis of soil and groundwater samples for analysis of BRE suite to assess concrete classification;
- Laboratory testing of soil and rock strength parameters, likely to include plasticity limits, particle size distribution, bulk and dry density testing, compaction and triaxial compression testing, and point load testing. The exact nature of the testing will be subject to the ground conditions encountered;
- Preparation of a factual site investigation report, detailing the works completed and including logs, photos and laboratory data;

Following receipt of the Factual Report from Socotec prepare a Phase 2 interpretative report including;

- a detailed reassessment of the initial Conceptual Site Model (CSM), pollutant linkages and preliminary risk assessment, and an estimation and characterisation of the risks to a potential site development from contamination;
- outline recommendations for risk mitigation;
- identify need for additional investigation or remediation.

2. Existing Information

Existing information is discussed in the AECOM report “VPI Immingham Phase I Geo-environmental Assessment”, and is summarised here.

2.1 Site Description

The site is located off Rosper Road, Immingham, North East Lincolnshire (see Appendix A, Figure 1), and is approximately 2 km east of South Killingholme. The site is centred on National Grid Reference (NGR) TA 516641 618468.

The site is surrounded by a mix of industrial and agricultural land use, namely the Lindsey Oil Refinery to the North West, which is operated by Total Ltd. To the South West is the Phillips 66 Humber refinery. Directly to the east is agricultural land and the River Humber is located approximately 1.3km from the site. The current VPI Immingham site is located directly to the south of the proposed development site.

2.1.1 Site Layout

The site occupies a total area of approximately 5 hectares (ha). The northern area of the site is currently occupied by a car park and canteen building present in the northwest which may be removed prior to construction. The southern half of site is covered in shrubbery/ grassland and contains various stockpiles believed to be from previous development including construction on the refinery land. The site is bounded to the east by Rosper Road and to the south by the current VPI Immingham CHP plant. Immingham Port is located approximately 2.5km to the South East and the River Humber is located approximately 1.3km to the east.

2.1.2 Surrounding Land Use

Based on site reconnaissance the land use immediately surrounding the site was assessed and is summarised below:

- North: Directly north of the site there is an access road which links the Lindsey Oil Refinery and Rosper Road. Beyond this, various utility buildings belonging to the Oil Refinery as well as unoccupied parcels of land are present.
- East: An unnamed drain and Rosper Road are directly east of the site, beyond which there are agricultural fields.
- West: To the west of the site mapping shows a settling tank, pond, electricity pylon as well as a railway track linking into the Lindsey Oil Refinery
- South: A utility line containing gas and liquid hydrocarbon pipes is present to the south, separating the site and the current VPI Immingham CHP plant.

2.2 Anticipated Geology

The anticipated geology of the site was assessed through examination of Groundsure GeoInsight Report GS-3982431, publically available BGS borehole data and examination of historic reports made available to AECOM. Table 1 details existing ground investigations which have taken place on the site.

Table 1 . Previous Ground Investigations Reports

Contractor/ Consultant	Investigation Description	Date
Soil Mechanics	Interpretive Report on Ground Investigation 6 cable percussion boreholes (BH1 to 6) to a maximum depth of 25 m and 10 trial pits (TP1-3, CBR2, 3, 5, 7,9,10 &13) to a maximum depth of 2 m	2006
ABB	Surrender of Waste Management Licence 13 trial pits (TP4-16) and drilling of 3 boreholes (done by Soil Mechanics; BH3-BH5). Groundwater sampling was also taken from existing monitoring wells (BH7 & BH8) installed in 1991.	2006

Table 2 summarises the anticipated geological conditions underlying the site based on the data reviewed.

Table 2. Summary of Geological Sequence

Strata	Depth (m OD)	Thickness (m)	Comment	Source
Made Ground		Unknown	<i>“Soft to firm brown slightly sandy slightly gravelly clay with bands of soft black slightly sandy slightly gravelly clay. Gravel is subangular to subrounded fine to medium of various lithologies including chalk and pottery.”</i>	Ground Investigation by Soil Mechanics, 2006
Glacial Deposits		16-26	<i>“slightly sandy, slightly gravelly clay. The sand and gravel component comprises subangular to subrounded chalk, occasionally sandstone and shell fragments.”</i>	Ground Investigation by Soil Mechanics, 2006
Burnham Chalk		Unknown	<i>“White, thinly-bedded chalk with common tabular and discontinuous flint bands; sporadic marl seams”</i>	BGS Lexicon

2.3 Hydrogeology and Hydrology

A review of Ordnance Survey maps indicated that the site is located approximately 1.3km south west of the River Humber, which flows north west to south east. Drains run along the southern and western site boundaries, and a small water storage pond is located approximately 80m west of the site. The Humber River is a designated Ramsar site, meaning that extra precautions are needed to safeguard hydrological features.

The site is located within an area whereby the Environment Agency issue flood warnings, and flood risk zone 3, meaning there is a high (greater than 1 in 100) annual probability of flooding. Flood defences are located along the banks of the River Humber and the area falls under the jurisdiction of North East Lindsey Internal Drainage Board.

Inspection of the Environment Agency Groundwater Vulnerability Maps indicates that:

- The superficial glacial deposits are classified as a ‘Secondary Aquifer (undifferentiated)’, defined either as ‘permeable layers capable of supporting water supplies at a local rather than strategic scale, and in some cases forming an important source of base flow to rivers’, or ‘lower permeability layers which may store and yield limited amounts of groundwater due to localised features such as fissures, thin permeable horizons and weathering’.

- The bedrock, Burnham Chalk Formation, is classified as a Principal Aquifer, defined as 'highly permeable formations usually with a known or probable presence of significant fracturing. They may be highly productive and able to support large abstractions for public supply and other purposes.

2.4 Regulatory Database Review

A Groundsure EnviroInsight Report was commissioned to evaluate any regulatory activities in the surrounding area which may have the potential to adversely affect the site. An initial Unexploded Ordinance report was also commissioned. The results of these searches are summarised below in Table 3 a plan showing the location can be found in the Groundsure EnviroInsight Report 3982431.

Table 3. Summary of Regulatory Database Search

CATEGORY	SUMMARY OF INFORMATION (<500m)
Part A(1) and IPPC Authorised Activities	1 effective: 270m south east; and 8 superseded: 270m south east all relating to Immingham CHP
List 1 Dangerous Substances Inventory Sites	1 inactive: 470m south east for Mercury and Cadmium relating to the Phillips 66 Humber Refinery site;
List 2 Dangerous Substance Inventory Sites	1 active: 470m south east for arsenic, chromium, copper, lead, nickel and zinc relating to the Phillips 66 Humber Refinery site;
Licensed Discharge Consents	3 revoked: one 51m south (relating to the Lindsey oil refinery oil interceptor) and two other unspecified trade discharges 470m south; and 1 effective: 50m north east; relating to sewage discharge from Lindsey oil refinery.
Planning Hazardous Substance Consents and Enforcements	1 approved active consents: 130m south relating to VPI Immingham – Consent to store 3050 tonnes of petroleum gas oil.
Dangerous or Hazardous Sites	1 on site current COMAH site (lower tier) relating to VPI Immingham CHP 2 off site current COMAH sites (both upper tier) relating to the Total Lindsey Oil Refinery (100m north east) and Phillips 66 Humber refinery (370m south) 1 off site historic NIHHS site (430m south relating to Conoco Manufacturing Ltd) 1 off site historic COMAH site relating to Humber LPG terminal Ltd (450 m east)
EA Recorded Pollution Incidents List 2	2 recorded: 140m south east – minor impact to air (atmospheric pollutants and effects) 400m south – minor impact to land & air (Oils and Fuels).
EA Recorded Pollution Incidents List 1	1 recorded 400m south of site relating to major persistent and extensive impacts to water (East Halton Beck).
Environment Agency/Natural Resources Wales historic landfill sites	1 on-site historic landfill licence relating to liquid sludge from the Lindsey Oil Refinery.
Environment Agency/Natural Resources Wales licensed waste sites	1 surrendered license 40m north west of the site relating to a biological treatment facility operated by the Lindsey Oil Refinery

CATEGORY

SUMMARY OF INFORMATION (<500m)

Preliminary Unexploded Ordnance Risk Assessment (UXO) by Zetica

Indicative British/Allied UXO Risk: **Negligible**

Indicative German UXO Risk: **Low**

No other database entries were identified within 500m of the site boundary. Database listings reviewed included: Historic IPC Authorisations, Red List Discharge Consent Register Part A(2) and Part B Activities and Enforcements, Category 3 or 4 Radioactive Substances Authorisations, Water Industry Referrals, Sites Determined as Contaminated land (Part 2a) or Petrol & fuel sites.

2.5 Sensitive Land Uses

A Groundsure EnviroInsight Report was commissioned to evaluate the presence of environmentally sensitive sites or land uses in the surrounding area which may be affected by activity at the site. In addition, online resources such as the Natural England MAGIC database were also consulted. The results of these searches are summarised below in Table 4.

Table 4. Summary of Sensitive Land Uses (<2000m)

Land use/Site/Designation	Name	Distance
Sites of Special Scientific Interest (SSSI)	Humber Estuary	1313m NE
	N. Killingholme Haven Pits	1917m N
National Nature Reserves (NNR)	None	N/A
Special Areas of Conservation (SAC)	Humber Estuary	1313m NE
Ramsar Sites	Humber Estuary	1313m NE
Ancient Woodland	None	N/A
Local Nature Reserves (LNR)	None	N/A
World Heritage Site	None	N/A
Areas of Outstanding Natural Beauty (AONB)	None	N/A
National Parks (NP)	None	N/A

Source: Groundsure EnviroInsight Report No. GS-3982430

Rosper Road Pool approximately 600m south east of this site is labelled as a Local Nature reserve on Current Ordnance Survey Mapping although a check on the DEFRA website indicates it is not officially recognised as a Local Nature Reserve.

2.6 Statutory Consultations

No statutory consultations were required in order to undertake the ground investigation. Further consultations may be required before the construction phase.

3. Preliminary Conceptual Site Model

As part of the AECOM report “VPI Immingham Phase I Geo-environmental Assessment”, a conceptual site model was developed to identify potential source- pathways- receptor linkages that may exist on the site. These linkages informed the conceptual site model and in turn informed the design of the ground investigation. The conceptual site model from the “VPI Immingham Phase I Geo-environmental Assessment” is presented here

3.1 Assessment Framework

The site, in terms of potential land contamination, will be regulated by the local authority (North Lincolnshire County Council) under the Town and Country Planning Act 1990 (as amended), taking account of the National Planning Policy Framework 2012, with the Environment Agency, Natural England and English Heritage acting as statutory consultees.

The ‘suitable for use’ approach is adopted for the assessment of contaminated land where remedial measures are only undertaken where unacceptable risks to human health or the environment are realised taking into account the use (or proposed use) of the land in question and the environmental setting.

Additional environmental liabilities can arise through provisions contained within statutory legislation including Part 2A of the EPA 1990, the Water Resources Act 1991, the Groundwater Regulations 2009 and the Water Act 2003.

Current best practice recommends that the determination of health hazards due to contaminated land is based on the principle of risk assessment, as outlined in the Statutory Guidance to Part 2A (2012) and CLR11.

The risk assessment process for environmental contaminants is based on a source-pathway-receptor analysis. These terms can be defined as follows:

- Source: hazardous substance that has the potential to cause adverse impacts;
- Pathway: route whereby a hazardous substance may come into contact with the receptor: examples include ingestion of contaminated soil and leaching of contaminants from soil into watercourses; and
- Receptor: target that may be affected by contamination: examples include human occupants / users of site, water resources (surface waters or groundwater), or structures.

For a risk to be present there must be a relevant pollutant linkage; i.e. a mechanism whereby a source impacts on a sensitive receptor via a pathway resulting in potentially significant harm.

3.2 Potential Sources of Contamination

Based upon the available information, potential sources of contamination include:

3.2.1 On Site

- Made ground/hard standing present in the car park;
- Stockpiles and mounds (unknown material);
- Historic landfill/liquid Sludge Disposal Area.

3.2.2 Offsite

- Lindsey Crude Oil Refinery (operations and spills/leaks);
- Phillips 66 Humber Refinery;
- Historic Landfills;
- Sand/Clay pits;

- Railway line and railway sidings;
- Crushed demolition material;
- Surrounding agricultural land use

3.3 Contaminants of Concern

Identified potential sources of contamination are summarised in **Table 5**, below.

Table 5 – Summary of Contaminants of Concern

	Source	Contaminants of Concern
Onsite land use	Stockpiles/mounds/made ground	<ul style="list-style-type: none"> • Stockpiles/mounds are of unknown material, however are likely to include: • Metals e.g. Arsenic, zinc, lead, copper, manganese • Organics e.g. petroleum hydrocarbons
	Historic Landfill	<ul style="list-style-type: none"> • Metals e.g. Arsenic, Zinc, Lead, Copper, Manganese and Cadmium; • Inorganic Compounds e.g. sulphates, sulphides, cyanides and chlorides;
	Railway line and former railway sidings	<ul style="list-style-type: none"> • Metals e.g. Arsenic, Zinc, Lead, Copper, Manganese and Cadmium; • Inorganic Compounds e.g. sulphates, sulphides, cyanides and chlorides; • Organic compounds e.g. mineral oils, fuel/lubricating oils, ethylene glycol, herbicides and • asbestos.
	Sand/Clay Pits	<ul style="list-style-type: none"> • Metals e.g. arsenic, zinc, lead, copper, manganese and cadmium; • Organics e.g. polyaromatic hydrocarbons (PAHs), total petroleum hydrocarbons (TPHs); • Gases e.g. methane, carbon dioxide, carbon monoxide and hydrogen sulphide.
Offsite land use	Oil refinery operations and VPI power plant operations	<ul style="list-style-type: none"> • Hydrocarbons e.g. crude oil, motor oils, petrol, diesel, kerosene, lubricants, waxes, bitumen, aviation fuel • Other organics e.g. alcohols, PCBs, MTBE, TAME, solvents, aliphatic and aromatic compounds; • Inorganic compounds e.g. acids, alkalis, cyanides, Sulphur and sulphide; • Metals e.g. aluminium, cobalt, copper, iron, lead, molybdenum, nickel and vanadium; • Others e.g. asbestos
	Crushed demolition material	<ul style="list-style-type: none"> • Metals e.g. cadmium, mercury, lead and nickel; • Hydrocarbons e.g. polyaromatics, asphaltenes and saturates; • Others e.g. asbestos
	Current VPI Immingham CHP operations, including spills/leaks	<ul style="list-style-type: none"> • Metals, metalloids and their compounds e.g. aluminium, barium, cobalt and iron; • Polyaromatic hydrocarbons e.g. naphthalene, anthracene and phenanthrene • Other organic compounds e.g. fuel oil, degreasing solvent and PCB's; • Inorganic compounds e.g. ammonium salts, boron and hydrazine; • Acids and alkalis • Others e.g. asbestos
		<ul style="list-style-type: none"> •

3.4 Potential Pathways

Based upon the available information, the following are considered potential pathways:

3.4.1 Human Health:

- Direct dermal contact with substances in shallow soil and/or groundwater during potential groundworks;
- Inhalation of substances from the partitioning of vapours from soil and / or shallow groundwater; and,
- Accidental ingestion and/or inhalation of substances in soil/dust and/or shallow groundwater during potential groundworks;

3.4.2 Controlled Waters:

- Vertical migration through unsurfaced areas, vegetated areas and hard-standing (where there are joins / cracks) and drains/pipework into the Made Ground/shallow soil;
- Lateral and vertical migration within the made ground and superficial deposits (Secondary A Aquifer), e.g. leaching from made ground vertically into shallow soil layers, including into deeper groundwater;
- Preferential lateral and vertical migration along routes of underground services, pipelines and associated trenches;
- Lateral overland flow, including via drains, to nearby surface waters;
- Preferential lateral and vertical migration along routes of underground services, pipelines and associated trench;
- Lateral and vertical migration within deeper groundwater in the Chalk bedrock (Principal Aquifer);
- Lateral migration of groundwater into surface water courses and abstraction points;
- Direct contact of substances within shallow groundwater Migration of ground gases and accumulation in confined spaces (e.g. basements, service ducts); and,
- Direct contact with nearby buildings, including Total Lindsey Oil Refinery and Phillips 66.

3.4.3 Ecology:

- Plant uptake and subsequent ingestion by fauna.

3.5 Potential receptors

3.5.1 Human Health:

- On site construction workers;
- Off-site workers e.g. Lindsey Oil refinery; and,
- Nearby residents.

3.5.2 Controlled Waters:

- Surface waters including the River Humber (RAMSAR site) and nearby drains e.g.
- Abstraction points;
- Shallow groundwater within the superficial deposits (Secondary A Aquifer); and,
- Deep groundwater within the chalk bedrock (Principal Aquifer);

3.5.3 Infrastructure:

- Underground services e.g. buried pipes; and,

- Confined spaces within buildings e.g. basements, service ducts;

3.5.4 Ecology:

- Flora and Fauna.

3.6 Preliminary Risk Evaluation

A summary of the risk assessment principles used to evaluate potential pollutant linkages is presented as Appendix B.

3.7 Summary of Potential Pollutant Linkages

A summary of the potential pollutant linkages and the related initial qualitative assessment of risk is summarised in Table 6, below. The risk rankings assume that the current ground and groundwater conditions prevail, prior to any mitigation measures such as further intrusive investigation, quantitative risk assessment or remediation. The risk rankings for each of the pollutant linkages are derived from a combination of:

- The magnitude of the potential consequence (i.e. severity) of the exposure of the receptor to the contaminant; and
- The magnitude of probability (i.e. likelihood) that the pollutant linkage is present or will occur.

Table 6 – Summary of Pollutant Linkages

Source	Pathway	Receptor	Potential severity as defined in Appendix B	Likelihood of Occurrence as defined in Appendix B	Level of Risk as defined in Appendix B	Discussion
On site e.g. Made Ground, Hard Ground and Historic Landfill	Direct dermal contact/ingestion/inhalation;	On-site construction workers	Medium	Likely	Moderate	It is likely that future site workers will come into contact with mound/stockpile material, the contents of which are unknown, therefore potential risk is high. There should be appropriate safety and mitigation measures put in place to minimise risk to human health.
	Inhalation of vapours;	Off-site workers Neighbouring residents	Medium	Likely	Moderate	
	Direct run off into surface waters e.g. River Trent Humber and nearby drains	Controlled water courses e.g. River Humber and groundwater within superficial deposits (secondary A) and bedrock (secondary B).	Medium	Likely	Moderate	As indicated by the EA, there is a historic landfill located in the north western corner of the proposed development site. It is anticipated that any contamination present may have migrated both vertically and laterally into deeper groundwater and surface waters. Hard ground is present on site, indicating that contamination may enter surface waters via overland flow.
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer), including into deeper groundwater (Secondary B aquifer);		Medium	Likely	Moderate	
	Vertical and lateral migration of ground/surface waters along preferential pathways, including to surface waters;		Medium	Likely	Moderate	
	Direct impact to buried infrastructure;	Buried infrastructure .e.g. pipes and underground utilities	Medium	Low	Moderate/Low	The site is within close proximity to the Lindsey Oil Refinery and Phillips 66, meaning that underground services are likely to be present and may be affected during excavation works.
Plant uptake and subsequent ingestion by fauna;	Flora and fauna	Medium	Likely	Moderate	The River Humber is a designated RAMSAR and Special Protection Area (SPA), therefore any contaminated groundwater uptake is of potential risk to both flora and fauna.	
Offsite power plant and oil refinery operations, including spills and leaks	Direct dermal contact/ingestion/inhalation;	On-site construction workers Future on-site excavation and construction workers	Medium	Unlikely	Low	Risk to human health is likely to be low, as remediation procedures, as well as pollutant mitigation measures, are assumed to be enforced by the operators of nearby industry, although this is not known for certain. Therefore, the likelihood of contaminants impacting upon human receptors is low.
	Inhalation of vapours;		Medium	Unlikely	Low	
	Direct run off from on-site resources into surface waters e.g. River Humber and nearby drains;	Controlled water courses e.g. River Humber and deeper groundwater within superficial deposits (secondary A) and bedrock (secondary B);	Severe	Low	Moderate	If contaminated material migrate vertically through the made ground and into the superficial deposits, it is likely that deeper groundwater within the secondary B aquifer and surface waters will also be significantly affected. The likelihood of occurrence is however deemed to be low, as pollutant mitigation measures are assumed to be in place at nearby industrial sites. It is anticipated that groundwater abstraction wells will not be significantly affected by contamination, due to distance from site.
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer) beneath the site;		Severe	Low	Moderate	
	Vertical migration into bedrock (Secondary B aquifer);		Severe	Low	Moderate	
Vertical and lateral migration of ground/surface waters along preferential pathways;		Medium	Low	Moderate/Low		
Offsite land use inc. sand/clay pits, landfill	Direct dermal contact/ingestion/inhalation;	On-site construction workers	Medium	Unlikely	Low	The likelihood of site workers coming into contact with offsite land use contamination is unlikely due to distance from site. It is unlikely that vapours relating to offsite sources will impact human health, assuming correct PPE is worn and safety measures are followed.
	Inhalation of vapours;	Off-site workers Neighbouring residents	Medium	Low	Moderate/Low	
	Direct run off from Off-site resources into surface waters e.g. River Humber and nearby drains;	Controlled water courses e.g. River Humber and groundwater within superficial deposits (secondary A) and bedrock (secondary B)	Medium	Likely	Moderate	Much of the site is covered with hard ground, meaning that any contamination present on site is likely to enter nearby surface waters via overland flow. It is also likely that if exposed during works, contamination may migrate via shallow soils into groundwater and subsequently enter surface waters via lateral migration. .
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer), including into deeper groundwater (Secondary B aquifer) beneath the site;		Medium	Likely	Moderate	
	Vertical and lateral migration of ground/surface waters along preferential pathways;		Medium	Likely	Moderate	
Direct impact to buried infrastructure onsite;	Buried infrastructure .e.g. pipes and utilities	Medium	Low	Moderate/Low	Contaminants which enter the site from offsite land use impact upon infrastructure if exposed during works.	

4. Fieldwork

4.1 Ground investigations

4.1.1 Description of field work

A summary of the exploratory holes were proposed by AECOM and advanced by engineers from Socotec during the site works can be found in Table 7 below;

Table 7. Summary of Exploratory Locations

Type	Quantity	Depth Range (m)	Remarks
Cable Percussion Boring	3	22.34 to 28.66	BH1, BH2 and BH5
Cable Percussion Boring extended by Rotary Core Drilling/Open Hole Drilling	3	28.60 to 34.60	BH3, BH4 and BH6
Dynamic Sampling	8	3.75 to 5.45	WS01 to WS08
Trial Pits/Trenches	13	2.50 to 4.60	TT1 to TT3 and TP1 to TP10

Source: Socotec Factual Report No A805-18, contained in Appendix C

The exploratory hole logs are presented in the Socotec Factual report (Appendix C). Samples taken for geotechnical purposes were collected and transported to Socotec's laboratory in Doncaster for analysis. Samples for environmental testing were collected and transported to Exova Environmental Laboratories, Deeside, for analysis. The laboratory certificates are presented in Appendix D.

4.1.2 In situ testing

Standard penetration tests (SPT) in the boreholes were carried out in accordance with BS EN ISO 22476-3+A1 (2011) and the SPT hammer energy ratio certificate is included in the Socotec Factual report Appendix C.

4.1.3 Laboratory testing

Soil testing was undertaken on samples recovered from the boreholes. The testing regime was prescribed by AECOM, and the testing was performed by Socotec Ltd and Exova Jones Ltd. All geotechnical testing was UKAS accredited and completed in accordance with current relevant standards, as set out in the Factual Report located in Appendix C. The following geotechnical laboratory tests were undertaken;

- Classification tests, including moisture content, Atterberg limits (INDEX) and particle size distribution (PSD).
- Consolidated (CU) and Unconsolidated (UU) undrained triaxial tests.
- Recompacted California Bearing Ratio (CBR) tests
- Consolidation tests (OED)
- Hydraulic Cell (HC) tests
- Soil chemical testing suite, including pH and sulphate.

Selected soil and groundwater samples were also analysed for a range of chemicals including:

- Volatile Organic Compounds (VOCs).
- Semi Volatile Organic Compounds Including USEPA PAHs (SVOCs).
- Total Petroleum Hydrocarbons- Criteria Working Group (TPH-CWG).
- Heavy Metals;
- pH,

- soil organic matter (soils only),
- asbestos,
- ammoniacal nitrogen, chloride, fluoride, nitrate, sulphide and total sulphate. .

All geochemical tests were where available UKAS and MCERTs accredited. Copies of the tests result and laboratory certificates are presented in Appendix D.

4.2 Ground Investigation Factual Report

The results of the 2018 ground investigation, including exploratory hole logs and geotechnical laboratory testing results, are presented in Socotec's ground investigation factual report entitled "*VPI Immingham Factual Report On Ground Investigation Report No A8015-18*", dated July 2018. A copy of the report can be found in Appendix C.

4.3 Post Ground Investigation

Three rounds of post site work gas and ground water monitoring was undertake by AECOM between 11/05/18 and 7/05/18 the result of which can be found in Appendix E

Fourteen dual-purpose gas / groundwater monitoring wells were installed and subjected to 3 rounds of in-situ monitoring which were undertaken on 11th May 2018, 23rd May 2018 and 1st June 2018. Depth to water was recorded at each location on each visit, while Temperature (°C), Specific Conductivity (µS/cm), Dissolved Oxygen concentration (mg/L) and Oxidation-Reduction Potential (ORP) (mV) were recorded at all wells containing groundwater on the first visit when the single round of groundwater sampling was undertake. Gas flow rates and Oxygen, Carbon dioxide and Methane concentrations were recorded at each location on each monitoring visit. The results of this monitoring is presented in Appendix E

5. Ground Summary

5.1 Summary of Ground Conditions

Published information on geology, including geological maps, is summarised in detail in the VPI Immingham Phase I Geo-environmental Assessment and summarised in Section 2.2 of this report.

The ground conditions in the vicinity of the site comprise:

- Topsoil, overlying;
- Made Ground;
- Superficial deposits (Glacial Till and Glacial Sand and Gravel);
- Chalk of the Burnham Chalk Formation of the Upper Cretaceous period.

The following information is intended to summarise the results of the 2018 ground investigation by SOCOTEC UK Limited and refine the preliminary understanding of the likely ground conditions.

An outline ground model for the site is summarised in Table 8 and discussed in more detail in Sections 5.1.1 to 5.1.3.

Table 8. Outline Ground Model of the Site.

Material	Typical Description	Top of Strata, m bgl	Base of Strata, m bgl	Top of Strata, m OD	Base of Strata, m OD
Made Ground	Sandy gravelly clay	0.0	0.2 to 1.7	6.5 to 4.0	6.3 to 3.2
Glacial Till	Firm to stiff sandy gravelly clay	0.0 to 1.7	21.5 to 27.5	6.0 to 3.5	-16.8 to -21.5
Glacial Sands and Gravels ¹	Medium dense clayey sand and gravel	12.9 to 13.0	15.2 to 16.0	-6.6 to -8.2	-9.3 to -10.6
Weathered Chalk	Extremely weak to very weak chalk	21.5 to 27.5	26.1 to 30.9	-17.0 to -21.5	-22.5 to -26.6
Unweathered Chalk	Medium Strong to strong chalk	26.1 to 30.9	Unproven	-22.5 to -26.5	Unproven

Note: 1) Glacial Sands and Gravels encountered in three of the six boreholes.

5.1.1 Made Ground

Made Ground is found in most of the exploratory boreholes over a range of depths (approximately 0.2m to 1.7m bgl) across the site. Made Ground is predominately described as a mix of slightly sandy, slightly gravelly, clay and sandy, clayey, gravel in a few boreholes. It contains a mixture of angular to sub-angular gravel of chalk, flint and sandstone. Cobbles are described as subrounded to subangular of concrete and chalk. The layers of different materials suggest both re-worked natural material and placed fill which follow no discernible pattern and so will collectively be assigned as Made Ground.

5.1.2 Superficial Deposits – Glacial Till and Glacial Sands and Gravels

Superficial materials are found to be Glacial Deposits, comprising Glacial Till and Glacial Sands and Gravels. Glacial Till is found consistently in all of the boreholes with approximately 17.0m to 21.0m thickness. It has been described mainly as firm, becoming stiff to very stiff below 0.0m OD, brown, mottled grey, slightly sandy, slightly gravelly, clay. There is a clear trend that shows the material stiffness increasing with depth. Layers of Glacial

Sands and Gravels were encountered in a number of boreholes. The material is described as medium dense, brown, slightly sandy, slightly clayey sand and slightly gravelly, slightly clayey, gravel. A layer up to approximately 1.0m thick was encountered in around 60% of the exploratory holes, between 2.0m and 0.0 m OD. A further layer of several metres thickness, varying from 2.3m to 2.7m thick was recorded in several boreholes at between -6.5m and -10.5m OD. However it was absent in boreholes BH2, BH4 and BH5, being replaced by a clay till deposit. The sand and gravel layers at the site may be lenticular deposits and therefore cannot be guaranteed and the appropriateness of their use in design should be carefully considered.

5.1.3 Bedrock – Burnham Chalk Formation

The boreholes show the bedrock to be chalk of the Burnham Chalk Formation. This confirms what can be seen in the BGS maps of the site. The top the weathered bedrock is found approximately at -17.0m to -21.5m OD. The upper levels of the chalk are frequently described as extremely weak to very weak with clusters of sub-horizontal and sub-vertical fractures. Chalk was mostly recovered as sandy, gravelly, clay. This indicates the upper part of the chalk is highly weathered.

Less weathered chalk was recorded between the depths of -22.5m and -26.5m OD and described as weak to medium strong, cream/white chalk.

6. Geotechnical Parameters

The following assessments and summaries are based on the recent ground investigation data provided by SOCOTEC UK Limited in 2018. Parameters have been derived using a combination of in-situ test results from the Ground Investigation, geotechnical laboratory testing and in the absence of any other data, established engineering correlations.

The 'Typical Derived Values' presented in the tables below are intended to serve as a reference point for establishing characteristic values, which are defined as 'cautious estimate(s) of the value(s) affecting the occurrence of the limit state' (Section 2.4.5.2 (2), BS EN 1997-1:2004). As such, the tabulated derived values are provided as cautious estimates of a parameter, but would need to be reviewed and adjusted according for the limit state being assessed.

Charts summarising the GI results are presented in Appendix F.

6.1 Made Ground

Made Ground material recovered and tested during the recent GI has been classified as either Cohesive Made Ground (predominately soft clay) or Granular Made Ground (predominately gravel). However, the layers of granular material were found less frequently and show no specific pattern so both types of material will collectively be defined as Made Ground. Table 9 presents indicative geotechnical parameters for the Made Ground material. The effective strength parameters defined for the Made Ground can be further assessed, if necessary, on a location specific basis using the GI data.

Table 9. – Typical Material Parameters – Made Ground

Parameter	Type and No. of Tests	Range Encountered	Typical Derived Value	Remarks
Unit Weight (kN/m ³)	CBR (3)	18.8 - 19.8 (mean 19.33)	19	Derived value based on data obtained as part of recompacted CBR testing and typical published values for materials identified (BS8002:2015, Bond 2014 and Barnes 2000).
Moisture Content (%)	INDX (5)	20 - 27 (mean 22.6)	-	Data obtained primarily from Atterberg limit tests.
Liquid Limit (%)	INDX (5)	44 - 54 (mean 47.2)	-	Data obtained from Atterberg limit tests.
Plasticity Index (%)	INDX (5)	21 - 29 (mean 25.2)	28	Cautious estimate of derived value based on data obtained from Atterberg limit tests.
c _u (kPa)	HV (20)	70 - 120 (mean 110.5)	30	Cautious estimate based on borehole descriptions and guidance in BS5390:2015. Hand Shear Vane tests tend to over-estimate C _u values and have therefore only been used as an approximate guide.
E _s (MPa)	HV (20) (correlated from HV)	6MPa to 15MPa	6	E _s = (200 to 500) x C _u (Bowles. 1997).
c' (kPa)	-	0	0	No direct test data available. Cautious estimate of derived value recommended.
Phi' (degrees)	INDX (5) (correlated)	24 - 26	25 (critical state)	Cautious estimate of critical state derived value based on correlations relating critical state angle of friction and plasticity index (assuming a mean PI value of 25) from Table 2 of BS 8002:2015. Location-specific interpretation to be undertaken for design due to variable composition.

6.2 Glacial Till

Glacial Till was the predominant material found in the boreholes with sporadic and of variable thickness layers of Glacial Sands and Gravels. The Glacial Sands and Gravels layers were identified in around half of the exploratory holes, at levels between 2.0m to 0.0 m OD and -6.5m to -10.5m OD, approximately. As a conservative assumption, it is not recommended that these layers should be modelled separately. Further assessment can be done on a location specific basis if it is later considered necessary and beneficial to assign engineering parameters to the Glacial Sand and Gravel layers.

The Glacial Till was found typically as clay with secondary constituents in varying proportions of sand and gravel. The colour is mostly brown with grey mottling. The stiffness and strength of the material increases with depth. Indicative geotechnical parameters are shown in Table 10.

Table 10 Typical Material Parameters – Glacial Till

Parameter	Type and No. of Tests	Range Encountered/ Derived	Typical Derived Value	Remarks
Unit Weight (kN/m ³)	CBR (7) + UU(14) + CU(6) + OED (8) + HC (2)	19 – 23.5 (mean 20.9)	20	Derived value based on data obtained as part of recompacted CBR testing and typical published values for materials identified (BS8002:2015, Bond 2014 and Barnes 2000).
Moisture Content (%)	INDX (71) + UU(14) + CU(6) + OED(8) + HC(2) + CBR(20)	4.9 - 28 (mean 18.9)	-	Data obtained primarily from Atterberg limit tests.
Liquid Limit (%)	INDX (34)	23 - 50 (mean 36.8)	-	Data obtained from Atterberg limit tests.
Plasticity Index (%)	INDX (34)	9 - 28 (mean 19.4)	Above 0.0m OD = 25 Below 0.0m OD = 18	Cautious estimate of derived value based on data obtained from Atterberg limit tests. Refer to Appendix F Figure A.7.
SPT-N	SPT (143)	4 - 57 (mean 28.13)	Above 0.0m OD = 13.5 Below 0.0m OD = 13.5 + 1.75L	Where L is depth below 0.0m OD.
C _v	CU (6) + OED(8)	0.61 to 5.6 (mean 2.1)	2.1	Typical values from OED + CU tests at $\bar{\sigma}_{vo}$ + 150kPa pressure. C _v of 17 in BH1 omitted from calculations.
M _v	CU (6) + OED(8)	0.02 to 0.67 (mean 0.22)	0.1	Range of values from CU + OED tests at $\bar{\sigma}_{vo}$ + 150kPa pressure. Results from OED tests are considered to give a more accurate representation of M _v values than CU tests, therefore more weight has been given to the OED results when creating typical values. Results indicate that the material has a very low to medium compressibility index (Tomlinson 2001)
c _u (kPa)	SPT (143) + HV(23)	20 - 285 (mean 137.2)	Above 0.0m OD = 50 Below 0.0m OD = 50 + 9.5L	Cautious estimate of derived value based on a correlation of c _u = 4 x SPT-N (Stroud, 1974). Where L is depth below 0.0m OD. Hand Shear Vane tests tend to over-estimate C _u values and have therefore only been used as an approximate guide.

Parameter	Type and No. of Tests	Range Encountered/ Derived	Typical Derived Value	Remarks
E_s (MPa)	SPT (143) (correlated)	3.6 - 45 (mean 36.8)	Above 0.0m OD = 12 Below 0.0m OD = 12 + 1.5L	Cautious estimate of derived value based on $E_s/N = 0.9$ MPa for cohesive soils.
c' (kPa)	CU(6)	2.2 – 15.9	2	Cautious assumed values taken from CU tests.
Φ' (degrees)	CU(6)	27 to 31	Above 0.0m OD = 27 Below 0.0m OD = 29	Cautious assumed values taken from CU tests

6.3 Burnham Chalk Formation

The chalk formation encountered in the boreholes is mostly described as extremely weak to weak with closely spaced fractures (recovered as gravelly clay) overlying medium to medium strong layer of chalk. The colour is identified as white and/or cream with occasional grey or black staining.

Table 11 presents a published range of values for chalk in the literature (CIRIA 574, CIRIA Project Reports 11 and 86). As part of the 2018 GI, six (6.No) SPT tests were undertaken within the Burnham Chalk Formation, one of these is located within the unweathered material. Without geotechnical laboratory testing information available for the chalk formation, it is not possible to provide typical derived values. Should the proposed foundations terminate within, or close to, the Burnham Chalk Formation, further geotechnical information will be required at the geotechnical design stage.

Table 11 Typical Material Parameters – Chalk

Parameter	Range Encountered/ Derived	Typical Derived Value (weathered chalk)	Typical Derived Value (unweathered chalk)	Remarks
Unit Weight (kN/m ³)	13 - 24	19 ⁽¹⁾	20 ⁽²⁾	No laboratory testing information available from ground investigation. (1) Correlates to a low to medium density, weak chalk (Table 3.7 Lord et al 2002) (2) Correlates to a high density moderately weak chalk.
Moisture Content (%)	4 – 40	Unknown	Unknown	
Liquid Limit (%)	18 – 53	Unknown	Unknown	
Plasticity Index (%)	4 – 30	Unknown	Unknown	
SPT (N)	44 – 50 (6.No SPT)	50	50	
Point load Index (MPa)	0.01 – 1.15	Unknown	Unknown	No laboratory testing information available from ground investigation.
q _u (MPa)	0.7 – 40	Unknown	Unknown	Typical Range of values taken from CIRIA Guide C574.
E _s (GPa)	1 – 30	Unknown	Unknown	
c' (kPa)	0 – 320	Unknown	Unknown	
Phi' (degrees) (Peak)	29 - 42	Unknown	Unknown	
UCS (MPa)	0.7 – 40	Unknown	Unknown	

6.4 Groundwater Strikes

Groundwater strikes encountered during the investigation of 2018 are summarised in Table 12 and were recorded at a range of depths (1.0m to 28.6m bgl) throughout the site. All of the strikes were found in the Glacial Till deposits with the exception of TP9, which was recorded in Made Ground at 0.7m bgl. Refer to Table 10 and Appendix C for summary of all groundwater strikes. It is considered likely that multiple water tables are contained within the Glacial Deposits.

Table 12 Recorded Groundwater Levels (04.2018)

Borehole No.	Borehole Ground Level (m OD)	Groundwater Strike Depth (m bgl)	Groundwater level after 20 mins (m bgl)	Geology
BH1	6.36	3.8	2.3	Glacial Till
		8.5	6.3	Glacial Till
		13.5	9	Glacial Sands and Gravels
		21	19.7	Glacial Till
BH2	5.43	1.8	1.5	Glacial Till
		4.2	1.7	Glacial Till
		14.1	10	Glacial Till
BH3	5.43	3	1.2	Glacial Till
		7.1	4.2	Glacial Till
		13.3	6.1	Glacial Sands and Gravels
		26.8	8.7	Chalk
BH4	4.19	3.2	1	Glacial Till
		7.4	2.1	Glacial Till
		12	7	Glacial Till
		13.4	4.2	Glacial Till
		17.8	15.1	Glacial Till
		24	9.6	Glacial Till
BH5	4.65	12.4	12.1	Glacial Till
		17.6	16.7	Glacial Till
BH6	4.71	4.65	2.5	Glacial Till

		11.7	3.1	Glacial Till
		18.6	16.6	Glacial Till
		21.5	16.1	Chalk
WS1	6.49	4.2	-	Glacial Sands and Gravels
WS4	5.1	3	-	Glacial Sands and Gravels
WS6	5.69	4	-	Glacial Sands and Gravels
WS7	5.79	5	-	Glacial Sands and Gravels
TP5	4.31	1.2	-	Glacial Till
TP6	5.43	1.9	-	Glacial Till
TP7	5.29	1.1	-	Glacial Till
TP9	5.71	0.7	-	Granular Made Ground
TP10	4.7	1	-	Glacial Till
TT1	6.44	1.5	-	Glacial Till

Groundwater strikes were recorded at a range of depths (1m to 28.6m bgl) throughout the site during the ground investigation. The majority of the strikes were found in the Glacial Till with a few strikes recorded in the Glacial Sands and Gravels and Chalk. In many cases, the groundwater is under sub-artesian pressures and semi-confined by less permeable clay layers. Upon release of these pressures, the recorded water strike level rises quite rapidly. Refer to Table 10 and Appendix C for summary of all groundwater strikes.

6.5 Groundwater monitoring

Following the 2018 GI, 3 rounds of ground water monitoring were undertaken by AECOM, a summary of these results can be found in Table 13 below.

Table 13 Groundwater Monitoring Results Summary (04.2018)

Hole ID	GL m OD	Range of groundwater levels m bgl	Range of ground water levels m OD	Response zone (m bgl)	Strata
BH01	6.36	3.70 - 3.97	2.39 - 2.65	12.50-15.00	Glacial Deposits
BH02	5.43	2.66 - 2.87	2.56 - 2.77	14.00-15.30	Glacial Deposits
BH03	5.43	2.57 - 2.75	2.68 - 2.86	26.60-28.60	Burnham Chalk
BH04	4.19	1.31 - 1.56	2.63 - 2.88	28.60-34.60	Burnham Chalk
BH05	4.65	1.86 - 2.04	2.61 - 2.78	17.50-18.50	Glacial Deposits
BH06	4.71	2.19 - 2.33	2.38 - 2.51	25.50-34.50	Burnham Chalk
WS01	6.49	2.08 - 2.16	4.33 - 4.40	1.00-1.40	Made Ground

WS02	5.46	1.32 - 1.36	4.09 - 4.14	0.70-1.20	Made Ground
WS03	5.52	1.40 - 1.52	3.99 - 4.12	2.50-3.50	Glacial Deposits
WS04	5.1	0.96 - 0.99	4.11 - 4.13	1.30-2.30	Made Ground/Glacial Deposits
WS05	4.7	0.98 - 1.00	3.67 - 3.72	3.20-4.20	Glacial Deposits
WS06	5.69	1.59 - 1.64	4.05 - 4.10	3.10-3.70	Glacial Deposits
WS07	5.79	1.83 - 1.86	3.92 - 3.95	3.00-3.50	Glacial Deposits
WS08	4.53	3.33 - 3.86	0.67 - 1.19	3.60-4.10	Glacial Deposits

As shown in Table 13, the monitored groundwater levels range from 4.33m OD to 0.67m OD. Many of the recorded levels are shown above the selected response zones. This can indicate the groundwater in the more porous strata is under sub-artesian pressures and is confined by overlying less permeable strata, as theorised in Section 6.4.

6.6 Concrete Aggressivity

The concrete aggressivity testing was undertaken only on samples from superficial layers (6.No samples from Glacial Deposits and 5.No samples in Made Ground). Based on the limited data available, the following Design Sulphate and ACEC design classes for concrete in aggressive ground are classified in Table 14. The below results are based on brownfield conditions and are in accordance with the BRE Special Digest 1 (Concrete in Aggressive Ground). Three of the four samples taken within the Glacial Till show high value of oxidisable sulphides (>0.3%), this could suggest pyritic ground. Based on this, the classification results shown in Table 14 for the disturbed ground, assume that pyrite is present.

Table 14 Summary of Preliminary Concrete Aggressivity Classification

Stratum	Classification (undisturbed ground, eg. for buried piles)	Classification (disturbed ground, eg. for pile cap)
Made Ground	DS-2, AC-2	DS-2, AC-2
Glacial Deposits	DS-1, AC-1	DS-3, AC-3

Sulfate classes (DS) and aggressivity to concrete classes (AC) range from DS-1/AC-1 to DS-5/AC-5, with higher value classes being assigned to the more adverse ground conditions.

7. Contamination Assessment

7.1 Sample Analysis

Environmental sampling was conducted on a total of 26 soil samples and 7 groundwater samples taken during the Ground Investigation works. The full results of this testing can be found in the Ground Investigation Factual Report presented in Appendix G, but a summary of the soil and groundwater testing scheduled following the ground investigation is summarised in Tables 15 and 16.

Table 15. Summary of Geo-Environmental Soil Testing

Suite	Test Determinants	No. of Tests	Locations
CLEA Metals	As, Ba, Be, Cd, Cr, Cu, Hg, Ni, Pb, Se, V, Zn, Cr VI, Cr III	26	BH01-BH06, WS01-06, TP01-TP02, TP04-TP10, TT01-TT03
VOC+TICs	VOC target list (inc BTEX/MTBE) + TICs	10	BH01, BH02, BH05, TP01, TP02, TP06, WS01-WS03, WS05
SVOC+TICs	SVOC target list including PAHs, phenol, chlorinated phenols and phthalates (100ug/kg) plus TICs	10	BH01, BH02, BH05, TP01, TP02, TP06, WS01-WS03, WS05
TPH - CWG	TPH CWG (Aliphatics C5-6,>6-8,>8-10,>10-12,>12-16,>16-21,>21-35) (Aromatics >C5-7,>7-8,>8-10,>10-12,>12-16,>16-21,>21-35) inc BTEX/MTBE	10	BH01, BH02, BH05, TP01, TP02, TP06, WS01-WS03, WS05
Inorganics	Fluoride (soluble), Nitrate (soluble), Sulphide, Total Sulphate	10	BH01, BH02, BH05, TP01, TP02, TP06, WS01-WS03, WS05
Chloride		7	BH01, BH02, BH05, WS01-WS03, WS05
pH		26	BH01-BH06, WS01-06, TP01-TP02, TP04-TP10, TT01-TT03
Soil Organic Matter (SOM)		24	BH01-BH06, WS01-06, TP04-TP10, TT01-TT03
Ammoniacal Nitrogen		25	BH01-BH03, BH05-BH06, WS01-06, TP01-TP02, TP04-TP10, TT01-TT03
Asbestos	Fibre screen/ asbestos ID (as described in HSE document HSG 248)	26	BH01-BH06, WS01-06, TP01-TP02, TP04-TP10, TT01-TT03

Table 16. Summary of Geo-Environmental Groundwater Testing

Suite	Test Determinants	No. of Tests	Locations
VOC + TICs	VOC target list including BTEX/MTBE + TICs by GC-MS	4	WS03-WS06
SVOC	SVOC target list including PAHs, phenol and chlorinated phenols by GC-MS	4	WS03-WS06
TPH-CWG	TPH CWG (Aliphatics C5-6,>6-8,>8-10,>10-12,>12-16,>16-21,>21-35) (aromatics >C5-7,>7-8,>8-10,>10-12,>12-16,>16-21,>21-35) inc BTEX/MTBE	7	BH01-BH03, WS03-WS06
CLEA full metals + Fe(II)	CLEA Metals Full As, Cd, Cr, Cu, Pb, Hg, Ni, Se, Zn, V, Be, Ba, B, Cr VI, Cr III Fe(II)	7	BH01-BH03, WS03-WS06
Dissolved Organic Carbon (DOC)		7	BH01-BH03, WS03-WS06

Suite	Test Determinants	No. of Tests	Locations
Inorganics	pH, Ammoniacal Nitrogen as N, Total Alkalinity as CaCO ₃ , Chloride, Nitrate as N, Ortho-Phosphate as P, Sulphate	7	BH01-BH03, WS03-WS06
Total Suspended Solids (TSS)		7	BH01-BH03, WS03-WS06

7.1.1 Observations of contamination

Visual and olfactory evidence of contamination was encountered at shallow depth in the made ground at 9 locations during the ground investigation. Headspace analysis for the presence of Volatile Organic Compounds (VOCs) was undertaken on samples taken from these locations and Photo Ionisation Detector (PID) readings recorded. These observations, along with the PID readings, are summarised in Table 17. These observations albeit not quantitative were used to select samples sent for laboratory analysis.

Table 17. Summary of Observations of Contamination

Location	Depth (m bgl)	Description	PID Reading (ppm)
BH01	0.45-0.7	Made Ground, oily smell, black staining, wet	3.3
BH02	0.6-1.0	Made Ground, oily smell, black staining	0.9
WS01	0.5-1.2	Made Ground, oily smell	1.3
WS02	0.0-0.5	Made Ground, oily smell, black staining	0.8
WS03	0.0-1.2	Made Ground, oily smell, black staining	0.5
WS05	0.0-1.2	Made Ground, oily smell, black staining	0.1
TP01	0.7-0.9	Made Ground, oily smell, black staining	4.4
TP02	0.3-0.5	Made Ground, oily smell, black staining	42.4
TP06	0.4-0.6	Made Ground, oily smell, black staining	0.3

7.2 Stage 2 Risk Assessment

7.2.1 Human Health Risk Assessment Methodology

This assessment has been based on a general industrial or commercial future use of the site and neighbouring sites.

The assessment considers chronic risks only and does not assess acute risks to construction / maintenance workers during intrusive works.

Where the conceptual site model identifies one or more complete pollutant linkage(s) with respect to human health it is often necessary to clarify the risk posed by that pollutant linkage by comparison of reported concentrations with guideline values that represent acceptable concentrations. This includes assessing risks to human health at a generic level (termed 'Generic Quantitative Risk Assessment' (GQRA) or 'Stage 2' in the Environment Agency's Model Procedures for the Management of Land Contamination, Contaminated Land Report 11, 2004 (known as CLR11)).

The assessment of cumulative risk from multiple substances is not required at GQRA level, with the exception of TPH. In accordance with Environment Agency science report P5-080/TR3², a hazard index (HI) is calculated for each individual sample based on the summation of the hazard quotient (HQ) for each TPH fraction.

Stage 2 Generic Assessment Criteria (GAC) for soils have been calculated using the reported Total Organic Carbon (TOC) concentration of samples collected and analysed as part of the intrusive investigation.

Based on the exploratory records, the most appropriate soil type for the Made Ground and the superficial deposits was considered to be the worse-case 'SAND' scenario, as defined by the Environment Agency's standard default soil descriptions.

It should be noted that Stage 2 assessments tend to be relatively conservative and are therefore suitable for initial screening of the potential chronic long term risks to human health at a site only. Full details of the physical and chemical parameters used in the derivation of the GAC can be made available upon request.

7.2.1.1 Asbestos

A total of 25 samples collected were analysed for asbestos across the site. Six samples reported asbestos fibres (chrysotile) were present in the made ground, however the volume of asbestos detected was reported as being less than 0.1% mass by weight in each case. Further Gravimetric Quantification testing of the samples was conducted and a summary of the asbestos quantification is presented in Table 18. Laboratory certificates are presented in Appendix D.

Table 18. Results of asbestos analysis

Location	Depth (m bgl)	Asbestos type	Present as	Quantity (w/w%)
BH01	0.45-0.70	Chrysotile	Fibre bundles	<0.001%
BH02	0.6-1.0	Chrysotile	Fibre bundles	<0.001%
WS01	1.0-1.25	Chrysotile	Fibre bundles	<0.001%
TP01	0.7-0.9	Chrysotile	Fibre bundles	<0.001%
TP02	0.3-0.5	Chrysotile	Fibre bundles	<0.001%
TP06	0.4-0.6	Chrysotile	Fibre bundles	<0.001%

The presence of asbestos fibres presents a potential acute occupational health risk to any groundworks which may be undertaken on the site and should be considered by the contractor as part of any future intended works and any off-site disposal of soils.

7.2.1.2 Human Health Risk Assessment Results & Discussion

A comparison of the results of laboratory testing with the Stage 2 GAC selected for this site indicate that there are no exceedances of the chosen screening values in either soil or groundwater samples including those where visual olfactory impact was encountered. As such, no further assessment of chronic human health risks from soils are required. The full contamination assessment can be found in Appendix G.

7.2.2 Controlled Waters Risk Assessment Methodology

AECOM has a prescribed methodology for assessing risks to controlled waters at a generic level termed 'generic quantitative risk assessment' (GQRA) or 'Stage 2' in CLR11³.

For sites in England and Wales where the conceptual site model has identified a potentially complete contaminant linkage to controlled waters, the first step is to define a suitable water target value (WTV) for the identified point of compliance upon which the risk assessment can be based. For groundwater compliance points which may support potable abstraction, the UK Drinking Water Standard (DWS) is used in England and Wales

² *The UK Approach for Evaluating Human Health Risks from Petroleum Hydrocarbons in Soil, Report P5-080/TR3*. Bristol: Environment Agency (2005).

³ Environment Agency (2004) Model Procedures for the Management of Land Contamination, Contaminated Land Report 11. September 2004.

whilst for surface water compliance points or non-potable aquifer units, an Environmental Quality Standard (EQS) is adopted. EQS coastal has been adopted for this site due to the sites proximity to the Humber Estuary.

The following Controlled Waters receptors have been considered in the following assessment:

- Superficial deposits underlying the site are classified as a Secondary A Aquifer;
- The Burnham Chalk Formation limestone bedrock underlying the site is classified as a Principal Aquifer; and
- The Humber estuary.

7.2.2.1 Controlled Waters Risk Assessment Results & Discussion

A comparison of the results of laboratory testing with the Stage 2 GAC selected for this site indicate that there are a number of exceedances of the chosen screening values. These exceedances are detailed in Table 19 below; The full contamination assessment can be found Appendix G

Table 19. Exceedance of Stage 2 GAC for Controlled Waters: Groundwater

Parameter	Location	Max Concentration (µg/l)	Exceedance of DWS	Exceedance of EQS
Selenium	BH03	16	X	
Zinc	BH01, BH03, WS05	12		X
Sulphate	WS03-WS06	983,900		X
Chloride	WS03-WS05	1,280,000		X

Table 19 shows that analysis of groundwater beneath the site indicates that only Selenium exceeds the DWS, while zinc, sulphates and chloride exceed the Coastal EQS. The exceedance of the DWS for Selenium is marginal (a magnitude of 1.6) and there are no potable extractions in the vicinity of the site, while the EQS exceedances are not replicated in surface waters within the hydrological catchment according to published Environment Agency monitoring data.

While unacceptable risk cannot be demonstrated to controlled waters at this time, the possibility of pathways for contaminants from soils to groundwater or surface water being created by the development (e.g. along services or foundations) or during the construction phase must be considered as part of the scheme design.

7.2.3 Ground Gas Risk Assessment

The ground gas assessment is based on a three ground gas monitoring events undertaken during May and June 2018. Details of the ground gas monitoring is provided in Appendix E.

The results of the gas monitoring are summarised in Table 20 and indicate that:

- Methane was recorded at levels <0.1 – 0.7% Vol. which is below the lower explosive limit.
- Carbon dioxide was recorded at levels <0.1 – 3.9% Vol.
- Oxygen was recorded at levels between 14.4– 20.7% Vol;
- Gas flow rates were recorded between -17.0 and 7.3l/hr;

Potential risks posed by the identified ground gas regime have been considered using the methodology outlined in BS 8485:2015.

A summary of the Gas monitoring is given in Table 20 which includes the Characteristic Situation per borehole. The published guidance including BS8485 and CIRIA C665 indicates that there is a six-fold scale of Characteristic Situations for the potential emission of ground gas, mainly methane and carbon dioxide, which are related to the setting of the site and the gassing potential of the ground. The Characteristic Situation is determined from data on monitored gas concentrations and flow rates. Characteristic Situation 1 is essentially very low risk typical of natural soils with low gassing potential whereas Characteristic Situation 6 is very high risk typical of young or recent active landfills. In order to calculate the worst case characteristic situation the maximum carbon dioxide concentration of 3.9% and a worst case flow rate, assuming negatives value have the potential to be positive, of 17l/hr were used to calculate the Gas Screening Value. This is therefore calculated as 0.29. Furthermore concentrations of Carbon Dioxide and Methane are below 5% and 1% respectively which, as defined by BS8485:2015, means the site is classified as Characteristic Situation (CS) 2.

In the six-fold scale CS2 denotes a low risk from ground gas.

The Characteristic Situation is then used to define the level of protection from ground gas to be built into the development, taking account of the "Type" of building development which relates to the sensitivity of the development and its use. The range of protection measures are rated according to a scoring (points) scale in BS8485, thus the designer can assemble a range of measures which together reach the required aggregate score for the Characteristic Situation and building type being dealt with. It is considered that in accordance with the development proposals, the majority of the proposed generation plant and buildings on site would fall into a "Type D" industrial style buildings which for a CS2, where the made ground is left in place, will require 1.5 points of gas protection. This is a relatively low level of protection consistent with the CS rating. However any smaller ancillary buildings will be classified as "Type C" which will require a higher level of protection which AECOM considers would be 2.5 points of gas protection in the event that the made ground is left in place.

However the highest concentrations of Carbon Dioxide and flow were detected in shallow Made Ground. Should Made Ground be removed as part of site preparation the Gas screening value, which would be defined by the gassing potential of the natural strata, would be 0.0584 which would classify the site as CS 1, very low risk, where no gas protection measures are required.

Table 20 Summary of ground Gas Monitoring

Exploratory Hole	Stratum	Date	Barometric Pressure (mb)	Peak Flow rate (l/h)	Steady Flow	Peak CO2 (% vol)	Peak CH4 (% vol)	GSV	Characteristic Situation CO2	GSV (l/hr)	Characteristic Situation CH4	Min O2 (% vol)
WS01	Made Ground	11/05/2018	1011.0	0.0	0.0	1.0	0.7	0	1	0	1	19.6
		23/05/2018	1025.0	0.0	0.0	0.1	0.1	0	1	0	1	20.3
		07/06/2018	1018.0	0.0	0.0	0.5	0.2	0	1	0	1	20.2
WS02	Made Ground	11/05/2018	1012.0	0.0	0.0	0.4	0.1	0	1	0	1	20.1
		23/05/2018	1026.0	-17.0	0.0	3.9	0.1	-0.663	1	-0.017	1	14.4
		07/06/2018	1018.0	0.0	0.0	1.3	0.1	0	1	0	1	19.4
WS03	Glacial Deposits	11/05/2018	1012.0	0.0	0.0	0.1	0.1	0	1	0	1	20.5
		23/05/2018	1025.0	7.3	0.0	0.3	0.2	0.0219	1	0.0146	1	20.3
		07/06/2018	1018.0	5.4	0.0	0.3	0.3	0.0162	1	0.0162	1	20.4
WS04	Glacial Deposits	11/05/2018	1012.0	0.0	0.0	0.2	0.2	0	1	0	1	20.2
		23/05/2018	1026.0	0.0	0.0	0.1	0.1	0	1	0	1	20.3
		07/06/2018	1018.0	0.0	0.0	0.1	0.1	0	1	0	1	20.6
WS05	Glacial Deposits	11/05/2018	1012.0	0.0	0.0	0.0	0.0	0	1	0	1	20.7
		23/05/2018	1026.0	0.0	0.0	0.1	0.1	0	1	0	1	20.3
		07/06/2018	0.0	0.0	0.0	0.0	0.0	0	1	0	1	20.4
WS06	Glacial Deposits	11/05/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.6
		23/05/2018	1025.0	0.0	0.0	0.2	0.1	0	1	0	1	20.3
		07/06/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.7
WS07	Glacial Deposits	11/05/2018	1016.0	0.4	0.2	0.4	0.2	0.0016	1	0.0008	1	20.6
		23/05/2018	1025.0	0.0	0.0	0.4	0.1	0	1	0	1	20.2
		07/06/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.7
WS08	Glacial	11/05/2018	1017.0	4.8	0.0	0.7	0.5	0.0336	1	0.024	1	20.4

	Deposits	23/05/2018	1026.0	4.8	0.0	0.2	0.0	0.0096	1	0	1	20.4
		07/06/2018	1016.0	1.3	0.0	0.5	0.0	0.0065	1	0	1	20.7
		11/05/2018	1012.0	0.0	0.0	0.4	0.2	0	1	0	1	20.1
BH01	Glacial Deposits	23/05/2018	1026.0	5.3	0.0	0.6	0.4	0.0318	1	0.0212	1	19.8
		07/06/2018	1018.0	-1.0	0.0	0.7	0.5	-0.007	1	-0.005	1	19.9
		11/05/2018	1012.0	0.0	0.0	0.2	0.2	0	1	0	1	20.5
BH02	Glacial Deposits	23/05/2018	1025.0	0.0	0.0	0.1	0.1	0	1	0	1	20.4
		07/06/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.6
		11/05/2018	No readings possible									
BH03	Chalk	23/05/2018	1026.0	0.0	0.0	0.8	0.1	0	1	0	1	20.3
		07/06/2018	1017.0	6.0	0.0	0.1	0.1	0.006	1	0.006	1	20.4
		11/05/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.7
BH04	Chalk	23/05/2018	1025.0	0.0	0.0	0.1	0.1	0	1	0	1	20.3
		07/06/2018	1016.0	0.0	0.0	0.1	0.0	0	1	0	1	20.7
		11/05/2018	1017.0	0.0	0.0	0.4	0.1	0	1	0	1	20.1
BH05	Glacial Deposits	23/05/2018	1026.0	0.0	0.0	0.2	0.1	0	1	0	1	20.3
		07/06/2018	1016.0	0.0	0.0	0.0	0.0	0	1	0	1	20.7
		11/05/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.6
BH06	Chalk	23/05/2018	1025.0	0.0	0.0	0.1	0.1	0	1	0	1	20.4
		07/06/2018	1017.0	0.0	0.0	0.1	0.1	0	1	0	1	20.7
Worst case CS			1026.0	17.0	0.2	3.9	0.7	0.663	2	0.119	0.11271	20.7

7.2.3.1 Discussion of Risks to Ecological Receptors

The Statutory Guidance which accompanies Part 2A of the Environmental Protection Act 1990 defines ecological receptors as any ecological system, or living organism forming part of such a system, within a location which is:

- A site of special scientific interest (under section 28 of the Wildlife and Countryside Act 1981)
- A national nature reserve (under s.35 of the 1981 Act)
- A marine nature reserve (under s.36 of the 1981 Act)
- An area of special protection for birds (under s.3 of the 1981 Act)
- A “European site” within the meaning of regulation 8 of the Conservation of Habitats and Species Regulations 2010
- Any habitat or site afforded policy protection under section 176 of the National Planning Policy Framework 2018 (NPPF) on nature conservation (i.e. candidate Special Areas of Conservation, potential Special Protection Areas and listed Ramsar sites); or
- Any nature reserve established under section 21 of the National Parks and Access to the Countryside Act 1949.

Any risk assessment must consider whether significant harm is being caused or a significant possibility of significant harm exists to any given ecological receptor. Harm in this context could be defined as;

- Harm which results in an irreversible adverse change, or in some other substantial adverse change, in the functioning of the ecological system within any substantial part of that location; or
- Harm which significantly affects any species of special interest within that location and which endangers the long-term maintenance of the population of that species at that location.
- In the case of “European Sites”, harm can exist where the sites designation could be affected by the presence of a contaminant linkage.

A significant possibility of significant harm exists where significant harm is more likely than not to exist for any given linkage or where there is a reasonable possibility of significant harm of that description being caused, and if that harm were to occur, it would result in such a degree of damage to features of special interest at the location in question that they would be beyond any practicable possibility of restoration.

In the case of this site, there are a number of potentially sensitive ecological sites in the wider area, but the closest (the Humber Estuary which is a SSSI, SPA and Ramsar site) is 1.3km away and so unlikely to be affected by pollutants present on the site. Routine monitoring of the ecological receptors in the Humber Estuary does not suggest that there is currently an unacceptable risk to those receptors.

7.3 Revised Conceptual Site Model

7.3.1 Introduction

A refined conceptual site model (CSM) has been developed on the basis of the desk study and the findings of the ground investigation and contamination assessment.

To assess the potential geo-environmental impacts associated with chemicals of potential concern in the section, the conceptual model has been revised using the source pathway receptor approach, promoted by DEFRA and the Environment Agency. For there to be an identifiable risk, not only must there be contaminants present across the section (source) there must also be a receptor and a pathway which allows the source to impact on the receptor.

7.3.2 Risk Assessment Framework

The site, in terms of potential land contamination, will be regulated by the local authority (North Lincolnshire County Council) under the Town and Country Planning Act 1990 (as amended), taking account of the National Planning Policy Framework 2012, with the Environment Agency, Natural England and English Heritage acting as statutory consultees.

The 'suitable for use' approach is adopted for the assessment of contaminated land where remedial measures are only undertaken where unacceptable risks to human health or the environment are realised taking into account the use (or proposed use) of the land in question and the environmental setting.

Additional environmental liabilities can arise through provisions contained within statutory legislation including Part 2A of the EPA 1990, the Water Resources Act 1991, the Groundwater Regulations 2009 and the Water Act 2003.

Current best practice recommends that the determination of health hazards due to contaminated land is based on the principle of risk assessment, as outlined in the Statutory Guidance to Part 2A (2012) and CLR11.

The risk assessment process for environmental contaminants is based on a source-pathway-receptor analysis. These terms can be defined as follows:

- Source: hazardous substance that has the potential to cause adverse impacts;
- Pathway: route whereby a hazardous substance may come into contact with the receptor: examples include ingestion of contaminated soil and leaching of contaminants from soil into watercourses; and
- Receptor: target that may be affected by contamination: examples include human occupants / users of site, water resources (surface waters or groundwater), or structures.

For a risk to be present there must be a relevant pollutant linkage; i.e. a mechanism whereby a source impacts on a sensitive receptor via a pathway resulting in potentially significant harm.

7.3.3 Pollutant Linkages

The Potential Pollutant Linkages identified in the previous AECOM report "*VPI Immingham Phase 1 Geo-environmental Assessment*" have been revised following the completion of the ground investigation and the residual linkages are presented below in Table 21. Linkages previously assessed to be 'Low' risk in the Phase 1 Desk Study document have been removed from the table:

Table 21: Revised Conceptual Site Model

Source	Pathway	Receptor	Preliminary Level of Risk	Discussion & Mitigation	Residual Level of Risk
On site e.g. Made Ground, Hard Ground and Historic Landfill	Direct dermal contact/ingestion/inhalation;	On-site construction workers Off-site workers	Moderate	A Stage 2 Risk Assessment of the results of the ground investigation has not deemed that the soils pose an unacceptable risk to human health for the proposed end use. Low levels of asbestos fibres were found to be present in made ground at several locations on the site, but these concentrations are not sufficient to present a risk to receptors on adjacent sites during construction or to the proposed development which will be covered by hardstanding or structures. Visual and Olfactory evidence of impacted soil was encountered in several locations therefore during construction the use of correct PPE and an appropriate Construction Environmental Management Plan (CEMP) will protect construction workers from exposure pathways created by excavations and stockpiled material and make sure that migration of contaminants to more sensitive adjacent land uses is controlled.	Low
	Inhalation of vapours;		Moderate		Low
	Inhalation of asbestos fibres		Moderate		Low
	Inhalation of ground gas, i.e. methane and carbon dioxide	Neighbouring residents Future site workers	Moderate	A preliminary assessment of measured gas concentrations and flow rates in accordance with BS8485:20015 has determined that the overall 'Characteristic Gas Classification' for the site is Category 2. It is considered that in accordance the majority of the proposed power generation plant and buildings on site would fall into a Type D industrial style buildings which for a CS2 will require 1.5 points of gas protection however any smaller ancillary buildings will be classified as type C which will require 2.5 points of gas protection. However if Made Ground is removed as part of the pre construction works the site would classify as CS1 where no protection measures are required. The Construction Phase Plan should make sure that construction workers take suitable precautions if working in enclosed spaces	Low
	Direct run off into surface waters e.g. River Humber and nearby drains	Controlled water courses e.g. River Humber and	Moderate	Concentrations of various substances were found to be present in the soils at concentrations above both relevant Water Target Values for those substances. However, analysis of groundwater samples does not indicate that those concentrations in soil are leading to exceedances in the underlying groundwater.	Low
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer), including into deeper groundwater (Secondary B aquifer);	groundwater within superficial deposits (secondary A) and bedrock (secondary	Moderate	An appropriate CEMP should minimise the risk of run-off from site-won material, while further risk assessment may be required with regard foundation design to prevent the creation of additional pathways to deeper bodies of groundwater. An appropriate risk assessment will be required for any piled foundations that are required in the final design. There are concentrations above the relevant WTV of a variety of contaminants in the soils below the site and deep foundations may create pathways through	Low

	Vertical and lateral migration of ground/surface waters along preferential pathways, including to surface waters;	B).	Moderate	less permeable layers from the unsaturated zone to sensitive groundwater below	Low
	Direct impact to buried infrastructure;	Buried infrastructure .e.g. pipes and underground utilities	Moderate/ Low	Elevated concentrations of sulphates have been noted in groundwater samples, but the water table is at sufficient depth and is largely confined by less permeable clay strata, so contact with buried services is unlikely as services will be located within clean backfill, in the unsaturated zone. Consideration of sulphates in groundwater may need to be given when designing building foundations, especially piled foundations. Advice should be sought from the local water supply company to confirm the appropriate pipe specification for the identified ground conditions and a UKWIR compliant risk assessment may be required to specify pipework.	Low
	Humber Estuary Ramsar, SPA, SSSI	Ecological receptors	Moderate	The distance to the Humber makes it unlikely that there is an unacceptable risk to ecological receptors, given the small number and relatively low magnitude of the exceedances detected during groundwater monitoring.	Low
Offsite power plant and oil refinery operations, including spills and leaks	Direct run off from on-site resources into surface waters e.g. River Humber and nearby drains;	Controlled water courses e.g. River Humber and deeper groundwater within superficial deposits (secondary A) and bedrock (secondary B);	Moderate	The ground investigation gave no indication of off-site contaminant sources transiting across the site as surface run off or within shallow groundwater. If such sources were found during construction phase, care should be taken to make sure that no preferential pathways are created. If this were to occur it would be notable as a health and safety issue during construction phase rather than as an ongoing environmental concern during operational phase.	Low
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer) beneath the site;		Moderate		Low
	Vertical and lateral migration of ground/surface waters along preferential pathways;		Moderate/ Low		Low
Inhalation of vapours;		On-site construction workers Future site workers	Moderate/ Low	No contamination plume with potential to cause vapours was identified coming from the adjacent site.	Low

Offsite land use inc. sand/clay pits, landfill and petrol station	Direct run off from Off-site resources into surface waters e.g. River Humber and nearby drains;	On-site construction workers	Moderate	The ground investigation gave no indication of off-site contaminant sources transiting across the site as surface run off or within shallow groundwater. If such sources were found during construction phase, care should be taken to make sure that no preferential pathways are created. If this were to occur it would be notable as a health and safety issue during construction phase rather than as an ongoing environmental concern during operational phase.	Low
	Vertical and lateral migration in made ground/superficial deposits (Secondary A aquifer), including into deeper groundwater (Secondary B aquifer) beneath the site;	Controlled water courses e.g. River Humber and groundwater within superficial deposits (secondary A) and bedrock (secondary B)	Moderate		Low
	Vertical and lateral migration of ground/surface waters along preferential pathways;		Moderate		Low
	Direct impact to buried infrastructure onsite;	Buried infrastructure .e.g. pipes and utilities			Low

7.3.4 Residual Contaminant Linkages

Following the Stage 2 Risk Assessment and consideration of the findings of the Ground Investigation, all outstanding pollutant linkages can be regarded as having a low level of risk, assuming that an appropriate CEMP is developed for the development and that appropriate risk assessment including consideration of ground conditions is applied to the design of piled foundations.

7.4 Summary of Contaminant Linkages

Table 22. Summary of Contaminant Linkages

	Conclusions	Recommendations
Buildings (Ground Gas)	<p>A preliminary assessment of measured gas concentrations and flow rates in accordance with rates in accordance with BS8485:20015 has determined that the overall 'Characteristic Gas Classification' for the site is Category 2It is considered that in accordance the majority of the proposed power generation plant and buildings on site would fall into a Type D industrial style buildings which for a CS2 will require 1.5 points of gas protection however any smaller ancillary buildings will be classified as type C which will require 2.5 points of gas protection.</p> <p>However if Made Ground is removed as part of the pre-construction works the site would classify as CS1 where no protection measures are required.</p>	<p>Where required ground gas protection measures as defined in BS8485 should be incorporated in the buildings.</p> <p>Standard good health and safety practice and PPE should be specified within the Construction Phase Plan in order to protect construction workers from gas within confined spaces.</p>
Human Health	<p>Stage 2 Screening of laboratory samples against appropriate GAC does not indicate any risk to human health for the current or proposed land use.</p> <p>An appropriate CEMP and the use of standard PPE will be sufficient to protect construction workers from contact with substances present in the soil, given the concentrations encountered during the ground investigation.</p>	<p>No remedial actions are required to protect site users or future site users from substances in the soils. The stage 2 risk assessment does not assess the specific risks to construction workers, but appropriate PPE and CEMP precautions will be sufficient to mitigate risk to construction works.</p>
Controlled Waters	<p>Assessment of risks to controlled waters from leachable (soluble) concentrations of potentially polluting substances in soil, when compared conservatively against DWS and EQS, show a number of exceedances. However, this is not reflected in the groundwater below the site and the distance to sensitive surface waters makes the possibility of harm to sensitive controlled waters from leachable soil substances unlikely.</p> <p>There are concentrations above the relevant screening criteria for a variety of contaminants in the soils below the site and deep foundations may create pathways through less permeable layers from the unsaturated zone to sensitive groundwater below. However the risks associated with deep foundations can be mitigated by means of risk assessment specific to the design and construction proposals.</p>	<p>No remedial measures are required on site to protect controlled waters. However any piles should be designed in accordance with the EA guidance entitled <i>Piling and Penetrative Ground Improvement Methods on Land Affected by Contamination: Guidance on Pollution Prevention (2001)</i></p>
Ecological Receptors	<p>The Humber Estuary and Rosper Road Pools represents ecological receptors, but the distance to the receptor is such that harm is unlikely to be caused.</p>	<p>Although it is not considered the site is a significant risk to Statutory ecological receptors . A landscape architected should be provided with the chemical analysis in order to establish suitable plant species for the site.</p>
Subsurface infrastructure		<p>Advice should be sought from the local water supply company to confirm the appropriate pipe specification for the identified ground conditions. Concrete Aggressivity is discussed in Section 5.5</p>

8. Geotechnical Assessment

8.1 Proposed Works

As noted in Section 1, VPI Immingham LLP are exploring the development of several gas fired power generation and storage projects including reciprocating engines and an OCGT power plant. The new extension will be situated north of the current site, on land presently occupied by a car park and undeveloped land. At the time of writing this report, there is no structural loading information available so the following engineering assessment is based on general assumptions.

8.2 Engineering Assessment

With no structural loading or settlement criteria information available, it is assumed that the CHP extension will contain a number of relatively heavy and sensitive structures. The proposed site layout drawings presented in Appendix B also shows several individual buildings which are linked by connections or directly adjacent to one another. Possible foundation solutions that could be progressed for the project include:

8.2.1 Shallow Foundations

Based on the recent GI, Made Ground material typically extends up to 1.5m bgl. Due to its variable nature, the Made Ground strata could not be relied upon as a stable founding material. Should shallow foundations be used, they would need to be placed upon natural ground, such as the firm to stiff clay, Glacial Till layer. This could be in the form of a large raft foundation or individual pad foundations under the separate buildings. The 1986 version of BS8004 – Code of Practice for Foundations estimates that firm to stiff clays, like those encountered on site, could achieve typical allowable bearing resistance values between 75kN/m² to 150kN/m². Further analysis will need to be undertaken to assess the potential bearing pressures produced by the CHP extension in comparison with the soils bearing resistance.

BS8004 also notes that founding on firm to stiff clays of low to medium compressibility could lead to long-term consolidation settlement. It is therefore advised that the settlement of sensitive foundations/structures should be considered. Natural variations in the Glacial Till stiffness or composition could create differential displacements between individual pad foundations. Creating a large raft foundation to support groups of buildings could help control the differential displacement between points but would result in higher total settlements. It should be noted that, if a large raft foundation at > 2.0m depth is selected, large quantities of existing material would need to be excavated as part of the construction process. This could be both environmentally and economically expensive.

In summary, it is considered that lightly loaded structures of the appropriate structural form could be founded on shallow foundations placed in glacial till of at-least firm to stiff consistency at the site.


8.2.2 Deep Foundations

Deep foundations such as piles are often used to transfer loads through weak, compressible soils to more competent soils or rocks. In the case of the generation plant and buildings, should the applied structural loads or settlement criteria supersede the capacity of shallow foundations, as discussed in Section 7.2.1, deep piled foundations could be introduced. Based on the ground conditions summarised in Section 4 and Section 5, the piles would need to be drilled to a set depth within the Glacial Till stratum or socketed into the Burnham Chalk Formation. Without an indication of the typical pile loads, the pile lengths cannot be determined. Figure 7.2.2-1 however, gives an indication of the typical ultimate single pile resistance for a range of pile diameters. Pile resistances are produced for the more critical Design Approach 1 – Combination 2 (DA1-C2), which are based on guidance given in BS EN 1997-1:2004 – Eurocode 7 – Geotechnical Design.

The graph assumes that the piles are bored with a Continuous Flight Auger (CFA) and will terminate within the Glacial Till layer. Should the piles need to penetrate the Burnham Chalk Formation, further GI information will be required to develop a safe design.

Two design approaches can be adopted for piled foundations; placing the buildings on individual pile caps/rafts or creating a piled raft to cover large sections of the site. A piled raft will require a larger quantity of construction work but will ensure a stable design which will limit differential settlements between the buildings. Individual pile caps/rafts for separate buildings will allow for more flexibility in the pile design and enable costs to be optimised.

Both shallow and deep foundation options will need to be investigated further upon the release of more structural information.



9. Geotechnical Risk Register

9.1 Assessing Geotechnical Risk

A Geotechnical Risk Register has been compiled to show the degree of risk attached to various ground related aspects of the proposed scheme. The purpose of the register is to produce an assessment of the risk to the project posed by common ground related problems and identify suitable mitigation measures to control the risk to an acceptable level. The risk register should be developed and refined as the geotechnical design and assessment progress, such that the register will allow management of the geotechnical risks.

The inclusion of a risk in the risk register does not constitute confirmation that the problem actually exists at the site. A probability of 'very unlikely' is indicative of a condition which the available evidence suggests should not be present. For the purposes of this risk register, the magnitude of each impact and the resulting severity of risk is measured against that which would 'normally' be expected for each element.

The Geotechnical Risk Register has been developed in general accordance with the guidance presented in ICE/DETR Document 'Managing Geotechnical Risk' (2001) and the HA document HD41/03 and HD22/02. The degree of risk (R) is determined by combining an assessment of the probability (P) of the hazard with an assessment of the impact (I) the hazard and associated mitigation will cause if it occurs ($R = P \times I$).

9.2 Geotechnical Hazards

The following section describes the ground-related hazards that have been identified during the investigation.

9.2.1 Variable Ground

Based on the 2018 Socotec UK Limited GI, up to 1.7m of Made Ground has been identified across the site. Due to nature of Made Ground, its properties are likely to be highly variable across the site. It is advised that any foundation solution does not rely on this material for support.

Granular layers within the Glacial Deposits could lead to settlement occurring at varying rates where these layers are and are not present. The possibility of differential settlement caused by such behaviours should be considered in the foundation design.

Burnham Chalk Formation was recorded at the base of four boreholes during the 2018 GI. The upper layers were described as weathered, extremely weak to weak chalk. Chalk is an unusual engineering material and can degenerate into a weak soil with intense weathering or mishandling. It also has the propensity to effectively re-cement with time. The design properties of Chalk are very variable, depending on the density and structure of the material. Should the proposed foundations terminate within, or close to, the Burnham Chalk Formation, further geotechnical information will be required to progress the design.

9.2.2 Ground Water

Seepages have been noted at various levels within the site. Where granular materials are present, water could flow at a relatively rapid rate, potentially undermining excavation stability. Water flowing from granular layers and from the chalk at depth which is under significant pressure could also have a detrimental effect on pile stability during construction. Continuous Flight Auger (CFA) piling, and / or bored piling under a bentonite drilling fluid, would help mitigate this problem.

9.2.3 Buried Obstructions or Services

As noted in Section 2, the site is largely surrounded by a mix of industrial and agricultural land use. This means there is the potential for buried services to be present at the site. Without service plans available, it should be assumed that there is a high risk of underground obstructions. Prior to the commencement of any construction work, further information on the potential services or buried obstructions should be sought from the relevant providers and then identified by inspection. Deeper areas of Made Ground and buried obstructions may be present at the site.

9.2.4 Risk Register of Geotechnical Hazards

The geotechnical risks associated with the proposed works are summarised in Table 22 below

Table 23 Hazard Index for Geotechnical Risk

Risk Number	Hazard/Risk	Cause	Risk Before Mitigation			Mitigation	Risk After Mitigation		
			P	I	R		P	I	R
GEO 001	Variable properties of Made Ground.	Historical site use	5	3	15	Proposed foundation solutions should not rely upon the Made Ground material. For example, piled foundations or shallow foundations founded on competent Glacial Till.	1	2	2
GEO 002	Limited ground information on Burnham Chalk Formation. Unable to derive accurate parameters for design, if required.	Insufficient borehole depth during previous ground investigations.	3	3	9	Should the proposed foundation solution come in close proximity to the Burnham Chalk Formation, further GI will be required to help derive accurate rock parameters for design.	1	2	2
GEO 003	Unknown services and buried obstructions at the site. Proposed foundation design could clash with services.	Historic site use.	4	4	16	Service plans are to be sought from providers prior to breaking ground. Area should also be surveyed to confirm potential services at the site. Buried obstructions / deep Made Ground are to be excavated during construction.	2	2	4
GEO 04	High ground water flow within granular soils and from the chalk Collapse of excavations/ pile holes.	Natural geology of the site.	3	3	9	Deep excavations should be supported when granular soils are present. CFA piling and / or use of bentonite drilling fluid should be used to construct piles.	1	2	2




Risk = Probability x Impact (also see CIRIA SP125)

16-25	Very High Risk	Unacceptable. Re-examine activities to provide lower risk.
9-15	High risk	Further mitigation measures required and/or alter method of work. Seek approval from all stakeholders if risk cannot be reduced.
6-8	Medium Risk	Tolerable only if further mitigation is not reasonably practical and there is need to continue activity with identified controls.
1-5	Low Risk	Broadly acceptable if all reasonably practicable control measures in place.




10. References

1. Wroth, C. P. and Wood, D. M. (1978), The correlation of index properties with some basic engineering properties of soils, *Canadian Geotechnical Journal*, 15: 137-145.
2. Terzaghi, K. and Peck, R. B. (1967). *Soil mechanics in engineering practice*, 2nd edition, Wiley International, New York.
3. British Standards Institute (2015), BS 8002: 2015 Code of Practice for Earth Retaining Structures, British Standards Institute.
4. Peck, R.B., Hanson, W.E. & Thornburn, T.H., (1974) *Foundation Engineering*. John Wiley & Sons.
5. CIRIA 143 (1995) *the Standard Penetration Test (SPT): Methods and use*.
6. Look, B (2007) *Handbook of Geotechnical Investigation and Design Tables*
7. Hobbs, N.B, (1974) *Proceedings of a Conference on Settlement of Structures*
8. *ISTM Suggested Method of Point Load Strength 1974-2006*
9. *UK Specification for Ground Investigation, Second Edition (2012)*. ICE Publishing.
10. BRE Construction Division (2005), *Concrete in Aggressive Ground, Special Digest 1:2005, 3rd Edition*.
11. British Standards Institute (1990), BS 1377-2 *Methods of test for Soils for civil engineering purposes - Part 2: Classification tests*: British Standards Institute.
12. CIRIA C574 (2002) *Engineering in Chalk*
13. BS8004:2015. *Code of Practice for Foundations*
14. BS EN 1997-1:2004. *Eurocode 7: Geotechnical Design*
15. *Foundation Design and Construction*. MJ Tomlinson, 7th Edition. 2001
16. BS 8485:2015. *Code of Practice for the design of protective measures for methane and carbon dioxide ground gases for new buildings*
17. CIRIA C665:2007. *Assessing risks posed by hazardous ground gases to buildings*

Appendix A Site Location Plan/Proposed Site Layout Plan




												PROJECT IMMINGHAM 'B' PROJECT		FUNCTIONAL LOCATION ICHP		SHT/SC. A1 1:1000		STATUS IFI		REV 0			
										DRAWN S.GARTSIDE		DATE 20/10/2017		TITLE SITE LOCATION SHEET 1									
										APPROVED A.LEWIS		DATE 20/10/2017											
										0 20/10/2017 PRELIMINARY DRAWING		SRG AL -											
										DRN CHK APP NO		DATE DESCRIPTION		DRN CHK APP									
										DATE DESCRIPTION		DRN CHK APP NO		DATE DESCRIPTION		DRN CHK APP							




Combined Area = 49,420m²

												PROJECT IMMINGHAM 'B' PROJECT		FUNCTIONAL LOCATION ICHP		SHT/SC. A1	STATUS IFI	REV 0	
										DRAWN S.GARTSIDE		DATE 20/10/2017		TITLE -					
										APPROVED A.LEWIS		DATE 20/10/2017		SITE LOCATION SHEET 2		DRG No VP11-IMMB-PL0T-0001			
										0 20/10/2017 PRELIMINARY DRAWING		SRG AL -							
DATE	DESCRIPTION	DRN	CHK	APP	NO	DATE	DESCRIPTION	DRN	CHK	APP									


NOTE
FOR CLARITY, SECURITY FENCES AROUND THE GAS RECEIVING STATION AND SITE BOUNDARY ARE NOT SHOWN ON THESE ELEVATIONS




SOUTH ELEVATION
1:800




NORTH ELEVATION
1:800



WEST ELEVATION
1:800



EAST ELEVATION
1:800



NO		DATE	REVISIONS AND RECORD OF ISSUE	NO	DATE	REVISIONS AND RECORD OF ISSUE			VPI IMMINGHAM ENERGY PARK PROJECT: VPIH-OCGT LAY-001A Sht 1 of 2 SHEET NUMBER: 0
1	04/07/18	ISSUED FOR INFORMATION	101	04/07/18	ISSUED FOR INFORMATION	101	101	ELEVATION VIEWS OF PROPOSED INDUSTRY LAYOUT 1: G2-OCGT DESIGNER: M. SEAMAN DATE: 04/07/18	PROJECT: VPI IMMINGHAM ENERGY PARK SHEET NUMBER: 0

Appendix B Risk Assessment Principles

Risk Assessment Principles

Current good practice recommends that the determination of hazards due to contaminated land is based on the principle of risk assessment, as outlined in the Environment Agency guidance on Model Procedures for the Management of Land Contamination (CLR 11).

For a risk to be present, there must be a viable pollutant linkage; i.e. a mechanism whereby a source impacts on a sensitive receptor via a pathway.

Assessments of risks associated with each of these pollutant linkages are discussed in the following sections.

Using criteria broadly based on those presented in EA, Chartered Institute of Environmental Health (CIEH) and National House Building Council (NHBC) R&D Publication 66 'Guidance for the Safe Development of Housing on Land Affected by Contamination' (2008), the magnitude of the risk associated with potential contamination at the site has been assessed. To do this an estimate is made of:

- The magnitude of the potential consequence (i.e. severity); and
- The magnitude of probability (i.e. likelihood).

The severity of the risk is classified according to the criteria in **Table C1**, below:

1. Table C1: Summary of Potential Pollutant Linkages

- SEVERITY	- DEFINITION AND EXAMPLES
Severe	<ul style="list-style-type: none"> - Acute risks to human health, likely to result in "significant harm" (e.g. very high concentrations of contaminants/ground gases) - Catastrophic damage to buildings/property (e.g. by explosion, sites with high gassing potential, extensive VOC contamination) - Major pollution of controlled waters (e.g. surface watercourses or Principal aquifers/source protection zones) - Short term risk to a particular ecosystem
Medium	<ul style="list-style-type: none"> - Chronic (long-term) risk to human health likely to result in "significant harm" (e.g. elevated concentration of contaminants/ground gases) - Pollution of sensitive controlled waters (e.g. surface watercourses or Principal/Secondary aquifers) - Significant effects on sensitive ecosystems or species
Mild	<ul style="list-style-type: none"> - Pollution of non-sensitive waters (e.g. smaller surface watercourses or non-aquifers) - Significant damage to crops, buildings, structures or services (e.g. by explosion, sites with medium gassing potential, elevated concentrations of contaminants)
Minor	<ul style="list-style-type: none"> - Non-permanent human health effects (requirement for protective equipment during site works to mitigate health effects) - Damage to non-sensitive ecosystems or species - Minor (easily repairable) damage to buildings, structures or services (e.g. by explosion, sites with low gassing potential)

The probability of the risk occurring is classified according to the criteria in **Table C2**, below:

2. **Table C2: Likelihood of Risk Occurrence**

LIKELIHOOD	EXPLANATION
High	- Contaminant linkage may be present that appears very likely in the short-term and risk is almost certain to occur in the long term, or there is evidence of harm to the receptor
Likely	- Contaminant linkage may be present, and it is probable that the risk will occur over the long term
Low	- Contaminant linkage may be present and there is a possibility of the risk occurring, although there is no certainty that it will do so.
Unlikely	- Contaminant linkage may be present but the circumstances under which harm would occur even in the long-term are improbable.

An overall evaluation of the level of risk is gained from a comparison of the severity and probability, as shown in **Table C3**, below:

3. **Table C3: Risk Based on Comparison of Likelihood and Severity**

		SEVERITY			
		SEVERE	MEDIUM	MILD	MINOR
LIKELIHOOD	HIGH	Very High	High	Moderate	Moderate/Low
	LIKELY	High	Moderate	Moderate/Low	Low
	LOW	Moderate	Moderate/Low	Low	Very Low
	UNLIKELY	Moderate/Low	Low	Very Low	Very Low

Appendix C Factual Report



VPI IMMINGHAM

FACTUAL REPORT ON GROUND INVESTIGATION

Report No A8015-18

August 2018







Client:
AECOM Environmental Solutions Ltd,
AECOM House,
66-77 Victoria Street,
St Albans,
AL1 3ER

SOCOTEC UK Limited

Askern Road, Carcroft
Doncaster DN6 8DG
Tel: +44 (0) 1302 723456
email: geo.doncaster@socotec.com

Report No A8015-18

August 2018

Issue No Date	Status	Prepared by	Checked by	Approved by
1 Jul 2018	Draft report	NAME and QUALIFICATIONS W Hopkins BSc (Hons)	NAME and QUALIFICATIONS T Clifford BEng FGS	NAME and QUALIFICATIONS T Clifford BEng FGS
		SIGNATURE 	SIGNATURE 	SIGNATURE 
2 Aug 2018	Final report	NAME and QUALIFICATIONS W Hopkins BSc (Hons)	NAME and QUALIFICATIONS T Clifford BEng FGS	NAME and QUALIFICATIONS T Clifford BEng FGS
		SIGNATURE 	SIGNATURE 	SIGNATURE 

This Report has been prepared by SOCOTEC UK Limited ("SOCOTEC") with all reasonable skill and care, within the terms and conditions of the contract between SOCOTEC and the Client ("Contract") and within the limitations of the resources devoted to it by agreement with the Client.

This Report shall not be used for engineering or contractual purposes unless the Report status is 'Final' and signed by the author, checker and the approver for and on behalf of SOCOTEC.

Whilst every effort has been made to ensure the accuracy of the data supplied and any analysis interpretation derived from it, the possibility exists of variations in the ground and groundwater conditions around and between the exploratory positions. SOCOTEC shall not be liable for any use of the Report for any purpose other than that for which it was originally prepared. No liability can be accepted for any such variations in these conditions. Furthermore, any recommendations are specific to the development as detailed in this Report and no liability will be accepted should they be used for the design of alternative schemes without prior consultant with SOCOTEC.

This Report is confidential between the Client and SOCOTEC. Any reliance upon the Report is subject to the Contract terms and conditions.

SOCOTEC accepts no responsibility whatsoever to third parties to whom this document, or any part thereof, is made known. Any such party relies upon the Report at their own risk. The Contracts (Rights of Third Parties) Act 1999 does not apply to this Report nor the Contract and the provisions of the said Act are hereby excluded.

Unless specifically assigned or transferred within the terms and conditions of the Contract, SOCOTEC asserts and retains all Copyright and other Intellectual Property Rights in and over the Report and its contents. The Report may not be copied or reproduced, in whole or in part, without the written authorisation from SOCOTEC.

SOCOTEC UK Limited was formerly known as Environmental Scientifics Group Limited. The Certificate of Incorporation on Change of Name was filed on 16 October 2017.

CONTENTS

	Page
1 INTRODUCTION	1
2 SITE SETTING	1
2.1 Location and Description	1
2.2 Published Geology	2
3 FIELDWORK	2
3.1 General	2
3.2 Exploratory Holes	2
3.3 Groundwater and Gas Monitoring	3
4 LABORATORY TESTING	3
REFERENCES	4

APPENDIX A FIGURES AND DRAWINGS

APPENDIX B EXPLORATORY HOLE RECORDS

APPENDIX C INSTRUMENTATION AND MONITORING

APPENDIX D GEOTECHNICAL LABORATORY TEST RESULTS

APPENDIX E PHOTOGRAPHS

1 INTRODUCTION

In March 2018 SOCOTEC UK Limited was commissioned by AECOM Environmental Solutions Ltd (AECOM) on behalf of VPI Immingham, to carry out a ground investigation at Total Lindsey Oil Refinery (TLOR). The investigation was required to obtain geotechnical information for the proposed development.

The scope of the investigation was specified by AECOM and comprised cable percussion and rotary drilled boreholes, trial pits and laboratory testing. The investigation was performed in accordance with the contract specification, and the general requirements of BS 5930 (2015), BS EN 1997-2 (2007), BS EN ISO 22475-1 (2006) and other relevant related standards identified below. The fieldwork took place between 5 and 20 April.

This report presents the factual records of the fieldwork and laboratory testing. The information is also presented as digital data as defined in AGS (2017).

2 SITE SETTING

2.1 Location and Description

The site is adjacent to the east side of Total Lindsey Oil Refinery, approximately 4 km north west of Immingham town centre, Lincolnshire. The National Grid reference is TA 167 175, see Site Location Plan in Appendix A.

The site is a L-shaped parcel of land, approximately 350 by 200 m, and generally flat and level.

The majority of the site, the southern portion (about 350 by 120 m), comprises rough grass and scrub land, which is boggy in places. There are several soil mounds, up to about 5 m in height.

The north west portion is within the perimeter fence of the adjacent car park, and comprises a compacted generally flat hardcore surface with very little vegetation.

To the north the site is bound by a carpark, belonging to TLOR, and to the west is infrastructure associated with the refinery, including access roads, railway lines, plant and equipment. To the south is VPI Immingham, a power generation facility. To the east is open farmland and the Humber Estuary beyond, approximately 500 m away.

2.2 Published Geology

The published geological map for the area, BGS Sheet 90 (1990) and the BGS Geology of Britain Viewer (2018) show the site located on Glacial Till over bedrock of the Burnham Chalk Formation.

3 FIELDWORK

3.1 General

The exploratory hole locations were selected by AECOM and set out from local features. The coordinates and reduced levels were surveyed by SOCOTEC to National Grid and Ordnance Datum and the locations are shown on the Site Plan in Appendix A

3.2 Exploratory Holes

The exploratory holes are listed in the following table.

TABLE 1: SUMMARY OF EXPLORATORY HOLES

TYPE	QUANTITY	DEPTH RANGE (m)	REMARKS
Cable Percussion Boring	3	22.34 to 28.66	BH1, BH2 and BH5
Cable Percussion Boring extended by Rotary Core Drilling/Open Hole Drilling	3	28.60 to 34.60	BH3, BH4 and BH6
Dynamic Sampling	8	3.75 to 5.45	WS1 to WS8
Trial Pits/ Trenches	13	2.50 to 4.60	TP1 to TP10 and TT1 to TT3

The exploratory hole logs are presented in Appendix B. These provide information including the equipment and methods used, samples taken, tests carried out, water observations and descriptions of the strata encountered. Explanation of the terms and abbreviations used on the logs is given in the Key to Exploratory Hole Records in Appendix B, together with other explanatory information. The logging of soil and rock materials is in accordance with BS 5930 (2015).

Standard penetration tests (SPT) in the boreholes were carried out in accordance with BS EN ISO 22476-3+A1 (2011) and the SPT hammer energy ratio certificate is included in Appendix B. The SPT results are presented on the logs as uncorrected N values.

Photographs of the trial pits and rotary drilled core are presented in Appendix E.

On completion of the fieldwork geotechnical samples were transported to the Doncaster laboratory of SOCOTEC for testing and temporary retention.

3.3 Groundwater and Gas Monitoring

Instrumentation installed in the exploratory holes for groundwater and gas monitoring are shown on the logs and summarised in Appendix C. SOCOTEC were not required to undertake any post fieldwork.

4 LABORATORY TESTING

Geotechnical laboratory testing was scheduled by AECOM and was carried out in accordance with BS 1377 (1990), unless otherwise stated. The testing is summarised below and the results are presented in Appendix E.

- Moisture Content Determination
- Atterberg Limit Determination
- Particle Density
- Particle Size Distribution Analysis
- Unconsolidated Undrained Triaxial Compression Testing
- Consolidated Undrained Triaxial Compression Testing
- One Dimensional Oedometer Consolidation Testing
- Determination of Consolidation Properties Using a Hydraulic Cell
- Dry Density / Moisture Content Relationship
- California Bearing Ratio
- pH, Water Soluble Sulphate, Acid Soluble Sulphate and Total Sulphur Content of Soils Test methods are BS 1377 or others recognised in BRE Special Digest 1 (2005)
- Loss on Ignition
- Organic Matter

REFERENCES

AGS : 2017 : Electronic transfer of geotechnical and geoenvironmental data (Edition 4.0.4 February 2017). Association of Geotechnical and Geoenvironmental Specialists.

BGS England and Wales Sheet 90 : 1990 : Grimsby. 1:50,000 geological map (solid and drift). British Geological Survey.

BGS Geology of Britain Viewer : 2018. www.bgs.ac.uk. British Geological Survey.

BRE Special Digest 1 : 2005 : Concrete in aggressive ground. Building Research Establishment.

BS 1377 : 1990 : Methods of test for soils for civil engineering purposes. British Standards Institution.

BS 5930 : 2015 : Code of practice for ground investigations. British Standards Institution.

BS EN 1997-2 : 2007 : Eurocode 7 - Geotechnical design - Part 2 Ground investigation and testing. British Standards Institution.

BS EN ISO 14688-1:2002+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil - Part 1 Identification and description. British Standards Institution.

BS EN ISO 14688-2:2004+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil - Part 2 Principles for a classification. British Standards Institution.

BS EN ISO 14689-1 : 2003 : Geotechnical investigation and testing - Identification and classification of rock - Part 1 Identification and description. British Standards Institution.

BS EN ISO 22475-1 : 2006 : Geotechnical investigation and testing – Sampling methods and groundwater measurements - Part 1 Technical principles for execution. British Standards Institution.

BS EN ISO 22476-3:2005+A1 : 2011 : Geotechnical investigation and testing - Field testing - Part 3 Standard penetration test. British Standards Institution.

APPENDIX A
FIGURES AND DRAWINGS

Site Location Plan
Site Plan

A1
A2

Site Location Plan



**THE
SITE**

Reproduced from the 2006 Ordnance Survey 1:50 000 scale Landranger map No 113 by permission of Ordnance Survey on behalf of The Controller of Her Majesty's Stationery Office, © Crown copyright, Environmental Services Group Limited. All rights reserved. Licence Number 100006060

Notes:
Scale 1:50 000

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Figure




A1



GENERAL NOTES

1. Reproduced from VPI Immingham's Drawing No. VP11-IMMB-CIV-CI01-0001.
2. Hole Locations to National Grid Co-ordinate Reference System.

LEGEND TO SYMBOLS

-  Borehole
-  Window Sample
-  Trial Pit

Scale: 1:1200



x	x	x	x	x	x
Rev	Drawn	Date	Approv.	Date	Modification Details

AMENDMENTS

Title	SITE PLAN				
-------	------------------	--	--	--	--

Project	VPI IMMINGHAM				
---------	----------------------	--	--	--	--

Client	AECOM Environmental Solution Ltd				
--------	---	--	--	--	--



Date	04/06/2018	Drawn By	BS	Approv. By	WH
Sheet Size	A3	Scale	1:1200	Project No	A8015-18
Drawing No	A2			Rev	0



APPENDIX B
EXPLORATORY HOLE RECORDS

Key to Exploratory Hole Records	Key
SPT Hammer Energy Ratio Report	SPT Hammer Reference: SW15470 AR2068 DART235
Borehole Logs	BH1 to BH6
Borehole Logs (Dynamic Sampling)	WS1 to WS8
Trial Pit and Trench Logs	TP1 to TP10 and TT1 to TT3

Key to Exploratory Hole Records

SAMPLES

Undisturbed

U	Driven tube sample	} nominally 100 mm diameter and full recovery unless otherwise stated
UT	Driven thin wall tube sample	
TW	Pushed thin wall tube sample	
P	Pushed piston sample	
L	Liner sample from dynamic (windowless) sampling. Full recovery unless otherwise stated	
CBR	CBR mould sample	
BLK	Block sample	
C / CS	Core sample (from rotary core) taken for laboratory testing.	
AMAL	Amalgamated sample	

Disturbed

D	Small sample
B	Bulk sample

Other

W	Water sample
G	Gas sample

ES	Environmental chemistry samples (in more than one container where appropriate)
EW	Soil sample
	Water sample

Comments

Sample reference numbers are assigned to every sample taken. A sample reference of 'NR' indicates that, while an attempt was made to take a tube sample, there was no recovery.

Samples taken from borehole installations (ie water or gas) after hole construction are not shown on the exploratory hole logs.

Specimens for point load testing undertaken on site (or other non-lab location) are not shown on the log.

IN SITU TESTS

SPT S or SPT C Standard Penetration Test, open shoe (S) or solid cone (C)

The Standard Penetration Test is defined in BS EN ISO 22476-3:2005+A1:2011. The incremental blow counts are given in the Field Records column; each increment is 75 mm unless stated otherwise and any penetration under self-weight in mm (SW) is noted. Where the full 300 mm test drive is achieved the total number of blows for the test drive is presented as N = ** in the Test column. Where the test drive blows reach 50 the total blow count beyond the seating drive is given (without the N = prefix).

IV	<i>in situ</i> vane shear strength, peak (p) and remoulded (r)
HV	Hand vane shear strength, peak (p) and remoulded (r)
PP	Pocket penetrometer test, converted to shear strength
KFH, KRH, KPI	Permeability tests (KFH = falling head, KRH = rising head; KPI = packer inflow); results provided in Field Records column (one value per stage for packer tests)

DRILLING RECORDS

The mechanical indices (TCR/SCR/RQD & If) are defined in BS 5930:2015

TCR	Total Core Recovery, %
SCR	Solid Core Recovery, %
RQD	Rock Quality Designation, %
If	Fracture spacing, mm. Minimum, typical and maximum spacing measurements are presented.
NI	The term non-intact (NI) is used where the core is fragmented.
NA	Used where a measurement is not applicable (eg. If, SCR and RQD in non-rock materials).

Flush returns, estimated percentage with colour where relevant, are given in the Records column

CRF	Core recovered (length in m) in the following run
AZCL	Assessed zone of core loss

GROUNDWATER

▼	Groundwater entry
▽	Depth to groundwater after standing period

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
Project No. A8015-18
Carried out for AECOM Environmental Solutions Ltd

Key

Sheet 1 of 3



Key to Exploratory Hole Records

INSTALLATION

Details of standpipe/piezometer installations are given on the Record. Legend column shows installed instrument depths including slotted pipe section or tip depth, response zone filter material type and layers of backfill.

Standpipe/ piezometer

The type of instrument installed is indicated by a code in the Legend column at the depth of the response zone:

SP	Standpipe			
SPIE	Standpipe piezometer	Plain Pipe		
PPIE	Pneumatic piezometer			Slotted Pipe
EPIE	Electronic piezometer			Piezometer Tip

Inclinometer or Slip Indicator

The installation of vertical profiling instruments is indicated on the Record. The base of tubing is shown in the Legend column.

	The type of instrument installed is indicated by a code in the Legend column at the base of the tubing:
ICE	Biaxial inclinometer
ICM	Inclinometer tubing for use with probe
SLIP	Slip indicator

Settlement Points or Pressure Cells

The installation of single point instruments is indicated on the Record. The location of the measuring device is shown in the Legend column.

	The type of instrument installed is indicated by a code in the Legend column:
ESET	Electronic settlement cell/gauge
ETM	Magnetic extensometer settlement point
EPCE	Electronic embedment pressure cell
PPCE	Electronic push in pressure cell

INSTALLATION / BACKFILL LEGENDS

A legend describing the installation is shown in the rightmost column. Legend symbols used to describe the backfill materials are indicated below.

Macadam	Concrete	Grout	Bentonite	Sand	Gravel	Arisings

STRATUM LEGENDS

The legend symbols used for graphical representation of soils, rocks and other materials on the borehole logs are shown below. For soils with significant proportions of secondary soil types, a combination of two or more symbols may be used.

Macadam	Concrete	Topsoil	Made Ground / Fill	Peat	Void or No Information	
Clay	Silt	Sand	Gravel	Cobbles	Boulders	Coal
Mudstone	Siltstone	Sandstone	Conglomerate	Breccia	Limestone	Chalk
Igneous (Fine)	Igneous (Med)	Igneous (Coarse)	Metamorphic (Fine)	Metamorphic (Med)	Metamorphic (Coarse)	Tuff

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
 Project No. A8015-18
 Carried out for AECOM Environmental Solutions Ltd

Key

Key to Exploratory Hole Records

NOTES

- 1 Soils and rocks are described in accordance with BS EN ISO 14688-1:2002+A1:2013 and 14689-1:2003 respectively as amplified by BS 5930:2015.
- 2 For fine soils, consistency determined during description is reported for those strata where undisturbed samples are available. Where the logger considers that the sample may not be representative of the condition in situ, for whatever reason, the reported consistency is given in brackets. The reliability of the sample is indicated by Probably or Possibly as appropriate. Hence (Probably firm) indicates the logger is reasonably confident of the assessment, but (Possibly firm) means less certainty. Where the samples available are too disturbed to allow a reasonable assessment of the in situ condition, no consistency is given.
- 3 Evidence of the occurrence of very coarse particles (cobbles and boulders) is presented on the logs. However, because of their size in relation to the exploratory hole these records may not be fully representative of their size and frequency in the ground mass.
- 4 The declination of bedding and joints is given with respect to the normal to the core axis. Thus in a vertical borehole this will be the dip.
- 5 The assessment of SCR, RQD and Fracture Spacing excludes artificial fractures.
- 6 Observations of discernible groundwater entries during the advancement of the exploratory hole are given at the foot of the log and in the Legend column. The absence of a recorded groundwater entry should not, however, be interpreted as a groundwater level below the base of the borehole. Under certain conditions groundwater entry may not be observed, for instance, drilling with water flush or overwater, or boring at a rate faster than water can accumulate in the borehole. Similarly, where water entry observations do exist, groundwater may also be present at higher elevations in the ground than where recorded in the borehole. In addition, where appropriate, water levels in the hole at the time of recovering individual samples or carrying out in situ tests and at shift changes are given in the Records column.
- 7 The borehole logs present the results of Standard Penetration Tests recorded in the field without correction or interpretation. However, in certain ground conditions (eg high hydraulic head or where very coarse particles are present) some judgement may be necessary in considering whether the results are representative of in situ mass conditions.

REFERENCES

- 1 BS EN ISO 14688-1:2002+A1 : 2013 : Geotechnical investigation and testing - Identification and classification of soil. Part 1 Identification and description. British Standards Institution
- 2 BS EN ISO 14689-1 : 2003 : Geotechnical investigation and testing - Identification and classification of rock. Part 1 Identification and description. British Standards Institution
- 3 BS EN ISO 22476-3:2005+A1 : 2011 : Geotechnical investigation and testing - Field testing. Part 3 Standard penetration test. British Standards Institution
- 4 BS 5930 : 2015 : Code of practice for ground investigations. British Standards Institution

Notes:

See report text for full references of standards.

Updated October 2017

Project VPI Immingham
Project No. A8015-18
Carried out for AECOM Environmental Solutions Ltd

Key

Sheet 3 of 3

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX5 9JP

SPT Hammer Ref: AR1940
Test Date: 21/09/2017
Report Date: 21/09/2017
File Name: AR1940.spt
Test Operator: SH

Instrumented Rod Data





Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 200
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm²): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 332

Energy Ratio E_r (%): **70**

Signed: M.GARDNER

Title: FITTER

The recommended calibration interval is 12 months

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX5 9JP

SPT Hammer Ref: AR2068
Test Date: 15/12/2017
Report Date: 15/12/2017
File Name: AR2068.spt
Test Operator: SH

Instrumented Rod Data





Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 200
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm²): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 296

Energy Ratio E_r (%): **63**

Signed: M.GARDNER
Title: FITTER

The recommended calibration interval is 12 months

SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

ARCHWAY ENGINEERING
AINLEYS INDUSTRIAL ESTATE
ELLAND
WEST YORKSHIRE
HX59JP

SPT Hammer Ref: DART235
Test Date: 13/04/2017
Report Date: 13/04/2017
File Name: DART235.spt
Test Operator: SH

Instrumented Rod Data





Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.0
Assumed Modulus E_a (GPa): 208
Accelerometer No.1: 7080
Accelerometer No.2: 11609

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 10.0

Comments / Location

CALIBRATION



Calculations

Area of Rod A (mm²): 905
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 276

Energy Ratio E_r (%): **58**

The recommended calibration interval is 12 months

Signed: S. HOWARTH
Title: FITTER

Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516528.04
Checked	TC	End		14.00	14.00	200	14.00	National Grid	N 417415.39
Approved	TC	11/04/2018		14.00	28.50	150	28.50		

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	(Thickness)			
0.10	D 1	0.00-1.20 Hand excavated inspection pit.			Brown sandy clayey GRAVEL. Gravel is angular to subangular fine to coarse of chalk and limestone.		0.10 (0.10) +6.26			
0.20 - 0.40	B 2				(MADE GROUND)		(0.35)			
0.45	D 3				Brown, locally greyish brown, slightly sandy gravelly CLAY. Gravel is angular fine to coarse of chalk and mudstone. Strong hydrocarbon odour.		0.45 +5.91			
0.50 - 0.70	B 4				(MADE GROUND)		(0.65)			
1.00 - 1.20	B 5		05/04/18	1800 Dry	Greyish brown, locally dark grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to coarse of slag, mudstone, sandstone and chalk. Strong hydrocarbon odour.	1.10-1.20 locally dark grey, occasional rootlets	1.10 +5.26			
1.20 - 1.65	UT 6	52 blows 100% rec	06/04/18	0800 Dry	(MADE GROUND)					
1.65 - 1.80	D 7				Stiff brown, locally mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of quartz, mudstone, sandstone and chalk.					
2.00 - 2.45	SPTS D 8	N=25 (3,4/5,6,7,7)	1.70	Dry						
2.50 - 3.00	B 9						(2.70)			
3.00 - 3.45	UT 10	56 blows 100% rec	2.80	Dry						
3.45 - 3.60	D 11									
3.80	W 14									
4.00 - 4.45	SPTS D 12	N=14 (2,2/3,3,4,4)	3.90	Dry	Thinly laminated brown, locally light grey, CLAY with frequent gravel size pockets of fine to coarse sand.		3.80 +2.56			
4.00 - 4.45	B 13				Stiff, becoming very stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, sandstone, mudstone and quartz.		(0.20) +2.36			
5.00 - 5.45	UT 15	50 blows 100% rec	4.70	Dry						
5.45 - 5.60	D 16									
6.50 - 6.95	SPTS D 17	N=14 (2,2/3,3,4,4)	4.70	Dry						
7.00 - 7.50	B 18									
7.20	D 19					7.10-8.40 locally sandy				
8.00 - 8.45	UT 20	38 blows 100% rec	4.70	Dry						
8.45	B 21									
8.50	W 21A						(9.00)			
9.50 - 9.95	SPTS D 22	N=14 (2,3/3,3,4,4)	9.20	Dry						
9.50 - 10.00	B 23									

Groundwater Entries				Depth Related Remarks		Hard Boring			
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	3.80		Rose to 2.30 m after 20 minutes. Medium inflow	4.00					
2	8.50		Rose to 6.30 m after 20 minutes. Medium inflow	9.00					

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:20				Sheet 1 of 3

Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring.	1.20	14.00	200	14.00	Coordinates (m)	E 516528.04
Checked	TC	End	SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	14.00	28.50	150	28.50	National Grid	N 417415.39
Approved	TC	11/04/2018							

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
11.00 - 11.45	UT 24	40 blows 100% rec	9.20	Dry	Stiff, becoming very stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, sandstone, mudstone and quartz.				
11.45 - 11.60	D 25								
12.50 - 12.95 12.50 - 12.95	SPTS D 26	N=31 (5,5/6,7,8,10)	9.20	Dry	Medium dense brown gravelly very silty fine to coarse SAND. Gravel is angular to subrounded fine to coarse of chalk and flint.		13.00 -6.64		
13.00 13.00 - 13.50	D 28 B 27						(1.80)		
13.50	W 30								
14.00 - 14.45 14.00 - 14.45	SPTS D 29	N=10 (3,3/2,3,2,3)	9.20	10.00	Medium dense brown sandy slightly clayey GRAVEL. Gravel is angular to subangular fine to coarse of flint and chalk.				
			06/04/18 9.20	1800 10.00					
14.80	D 31		09/04/18 9.20	0800 3.80			14.80 -8.44		
15.00 - 15.50	B 32				Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and rare flint.				
15.50 - 15.95 15.50 - 15.95	SPTS D 33	N=28 (3,3/5,5,8,10)	15.00	10.00				(0.90)	
16.00 - 17.00	B 34						15.70 -9.34		
17.00 - 17.45	UT 35	78 blows 100% rec	16.50	15.00		17.10 becoming greyish brown			
17.45 - 17.60	D 36								
18.50 - 18.77 18.50 - 18.77 18.50 - 19.00	SPTS D 37 B 38	50 (15,10 for 50mm/23,27 for 70mm)	18.00	17.00			(5.80)		

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
3	13.50		Rose to 9.00 m after 20 minutes. Fast inflow				14.50 - 14.80	60	Chisel	

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 2 of 3



Borehole Log



Drilled	GC	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	6.36 mOD
Logged	MJS	05/04/2018	Dando 2000. Cable percussion boring.	1.20	14.00	200	14.00	Coordinates (m)	E 516528.04
Checked	TC	End	SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	14.00	28.50	150	28.50	National Grid	N 417415.39
Approved	TC	11/04/2018							

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
20.00 - 20.40	UT 39	100 blows 56% rec	19.50	19.50	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and rare flint.					
20.40 - 20.50	D 40									
21.00 - 21.50	B 41				Very stiff light grey slightly sandy gravelly silty CLAY. Gravel is subangular to subrounded fine to coarse of chalk.					
21.50 - 21.79 21.50 - 21.79	SPTS D 42	50 (10,15 for 60mm/22,25,3 for 5mm)	19.50	20.00		21.50	-15.14			
22.50 - 22.70 22.50 22.50 - 22.70	SPTS UT NR D 43	50 (25 for 75mm/28,22 for 55mm) 100 blows No Recovery	09/04/18 19.50	1800 20.00	25.50 recovered as clayey angular fine to coarse gravel					
23.00 - 24.00	B 44		10/04/18 19.50	0800 9.00						
24.00 - 24.28 24.00 - 24.28	SPTS D 45	50 (15,10 for 45mm/20,27,3 for 5mm)	23.50	10.00			(6.00)			
25.00 - 25.22 25.00 - 25.22	SPTS D 46	50 (20,5 for 15mm/25,25 for 60mm)	24.90	8.00						
26.00 - 26.22 26.00 - 26.22 26.00 - 27.00	SPTS D 47 B 48	50 (25 for 75mm/27,23 for 65mm)	25.90 10/04/18 25.90	8.00 1700 8.00						
27.50 - 27.78 27.50 - 27.78 27.50 - 28.50	SPTS D 49 B 50	50 (15,10 for 50mm/22,24,4 for 5mm)	27.50	7.00	Extremely weak to very weak white CHALK. Recovered as gravelly clay. Gravel is angular to subangular fine to coarse.					
28.50 - 28.66 28.50 - 28.66	SPTS D 51	50 (25 for 60mm/38,12 for 20mm)	11/04/18 28.50	1500 9.00						
					END OF EXPLORATORY HOLE					

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
4	21.00	Rose to 19.80 m after 20 minutes. Medium inflow				24.50 - 26.00	180	Chisel		
						26.50 - 27.50	120	Chisel		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:20				Sheet 3 of 3

Borehole Log



Drilled	GC	Start	11/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	14.50	Diameter (mm)	200	Casing Depth (m)	14.50	Ground Level	5.43 mOD
Logged	WH	End	16/04/2018				14.50		22.20		150		22.20	Coordinates (m)	E 516588.10
Checked	TC													National Grid	N 417353.62
Approved	TC														

Samples and Tests

Samples and Tests				Strata Description					
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.20 0.30 - 0.50	D 1 B 2	0.00-1.20 Hand excavated inspection pit.			Dark brown sandy very gravelly CLAY with high cobble content. Gravel is subrounded fine to coarse of various lithologies including chalk, macadam and sandstone. Cobbles are subrounded of chalk. (MADE GROUND)		(0.50)		
0.60 0.60 - 1.00	D 3 B 4						0.50 +4.93		
1.00 1.00 - 1.20 1.20 - 1.65	D 5 B 6 UT 7	30 blows 100% rec		Dry	Dark brown and black very gravelly very silty fine to coarse SAND. Gravel is subangular fine to coarse of chalk and sandstone. Strong hydrocarbon odour. (MADE GROUND)		1.00 +4.43		
1.65 - 1.80	D 8								
1.80 - 2.25 1.80 - 2.25 1.80 - 2.25	SPTS D 9 B 10	N=13 (2,2/3,4,4)	11/04/18	1800 1.50	Firm dark greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular medium of flint and chalk.				
2.20 - 2.70 2.25 - 2.70	B 13 UT NR	28 blows No Recovery	12/04/18	0800 2.00					
2.70 - 2.80 2.80 - 3.25 2.80 - 3.25	D 12 SPTS D 14	N=15 (1,2/3,3,4,5)	1.70	Dry	Brown mottled grey CLAY.		(3.20)		
3.30 - 3.75	UT 15	45 blows 100% rec	1.70	Dry					
3.75 - 3.90 3.90 - 4.35 3.90 - 4.35 3.90 - 4.35 4.00 - 4.45	D 16 SPTS D 17 B 18 UT NR	N=15 (6,7/4,3,3,5)	2.90 3.90	Dry Dry	4.45 slightly gravelly sandy, gravel is subangular fine of chalk and mudstone		4.20 +1.23		
4.45 - 4.60	D 20								
4.60 - 5.05 4.60 - 5.05 4.60 - 5.05	SPTS D 21 B 27	N=17 (2,2/3,4,4,6)	4.50	4.00	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular fine to medium of sandstone and chalk.		4.70 -0.73		
5.10 - 5.55	UT 28	38 blows 100% rec	5.00	4.80					
5.55 - 5.70 5.70 - 6.15 5.70 - 6.15 5.70 - 6.15	D 29 SPTS D 30 B 31	N=25 (3,4/5,6,7,7)	5.60	Dry					
6.50 - 6.95 6.50 - 7.00	UT NR B 33	48 blows No Recovery	6.00	Dry					
7.10 - 7.55 7.10 - 7.55 7.10 - 7.55	SPTS D 34 B 35	N=22 (3,4/4,5,6,7)	6.00	Dry					
8.00 - 8.45	UT 36	60 blows 100% rec	6.00	Dry					
8.45 - 8.60 8.60 - 9.05 8.60 - 9.05 8.60 - 9.05	D 37 SPTS D 38 B 39	N=27 (3,4/5,7,7,8)	6.00	Dry					
9.50 - 9.95	UT 40	62 blows 100% rec	6.00	Dry					
9.95 - 10.10	D 41						(9.40)		

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
1	1.80		Rose to 1.50 m after 20 minutes. Slow inflow									
2	4.20		Rose to 3.80 m after 20 minutes. Slow inflow	5.00								

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:21				Sheet 1 of 3

Borehole Log



Drilled	GC	Start	11/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	14.50	Diameter (mm)	200	Casing Depth (m)	14.50	Ground Level	5.43 mOD
Logged	WH	End	16/04/2018				14.50		22.20		150		22.20	Coordinates (m)	E 516588.10
Checked	TC													National Grid	N 417353.62
Approved	TC														

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.10 - 10.55	SPTS	N=22 (3,4,4,5,6,7)	6.00	Dry	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular fine to medium of sandstone and chalk.				
10.10 - 10.55	D 42								
10.10 - 10.55	B 43								
11.00 - 11.45	UT 44	64 blows 100% rec	6.00	Dry					
11.45 - 11.60	D 45								
11.60 - 12.05	SPTS	N=23 (3,4/4,5,6,8)	6.00	Dry					
11.60 - 12.05	D 46								
11.60 - 12.05	B 47								
12.50 - 12.95	UT 48	70 blows 100% rec	6.00	Dry					
12.95 - 13.10	D 49								
13.10 - 13.55	SPTS	N=30 (4,6/6,7,8,9)	6.00	Dry					
13.10 - 13.55	D 50								
13.10 - 13.55	B 51								
14.00 - 14.45	UT NR	80 blows No Recovery	6.00	Dry	Firm light brown sandy very gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and mudstone.		14.10	-8.67	3
14.00 - 14.60	B 53						14.40	-8.97	
14.10	W 59								
14.60 - 15.05	SPTS	N=39 (7,8/10,10,9,10)	14.50	10.00	Firm to stiff light brown sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and flint. Occasional gravel size pockets of fine to medium sand.				
14.60 - 15.05	D 54								
15.20	D 55						(2.00)		
15.50 - 15.95	UT 56	70 blows 33% rec	14.50	10.00					
16.20 - 16.65	SPTS	N=37 (6,8/8,9,10,10)	15.50	7.00	Stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to medium of chalk.				
16.20 - 16.65	D 57								
16.40 - 17.00	B 58						16.40	-10.97	
17.00 - 17.45	UT 60	55 blows 56% rec	12/04/18 16.50	1800 7.00					
17.45 - 17.60	D 61				17.45-18.05 light grey silty fine to coarse sand				
17.60 - 18.05	SPTS	N=35 (3,5/7,8,10,10)	16.50	5.00					
17.60 - 18.05	D 62								
18.50 - 18.95	UT NR	60 blows No Recovery	18.40	9.00					
18.50 - 19.00	B 63								
19.10 - 19.55	SPTS	N=35 (4,6/7,8,9,11)	18.40	9.00					
19.10 - 19.55	D 64								
19.50	D 65				Stiff to very stiff brownish grey slightly sandy CLAY with occasional gravel. Gravel is subangular fine to medium of chalk.		19.50	-14.07	

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
3	14.10		Rose to 10.00 m after 20 minutes. Medium inflow									

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:21				Sheet 2 of 3

Borehole Log



Drilled GC	Start 11/04/2018	Equipment, Methods and Remarks Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.43 mOD
Logged WH	End 16/04/2018		1.20	14.50	200	14.50	Coordinates (m)	E 516588.10
Checked TC			14.50	22.20	150	22.20	National Grid	N 417353.62
Approved TC								

Samples and Tests

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
20.00 - 20.45	UT 66	100 blows 56% rec	20.00	11.00	Stiff to very stiff brownish grey slightly sandy CLAY with occasional gravel. Gravel is subangular fine to medium of chalk.					
20.60 - 20.93 20.60 - 20.93 20.60 - 21.00	SPTS D 67 B 68	50 (12,13 for 65mm/17,21,12 for 40mm)	20.00	11.00				(2.84)		
21.50 - 21.64 21.50 - 21.64	SPTS D 69	50 (25 for 50mm/42,8 for 10mm)	21.00	11.00						
22.20 - 22.34 22.20 - 22.34	SPTS D 70	50 (25 for 50mm/39,11 for 15mm)	13/04/18 21.50 11.00 16/04/18 0800 21.50 6.00 16/04/18 1000 22.20 8.00							
					END OF EXPLORATORY HOLE		22.34	-16.91		

Groundwater Entries			Depth Related Remarks			Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
						21.90 - 21.90	180	Chisel
						21.90 - 22.20	60	Chisel

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring/Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.00	200	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018				146			

Samples and Tests Strata Description

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.40 - 1.20	B 1	0.00-1.20 Hand excavated inspection pit.			Firm brown, locally mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of quartz, sandstone, chalk and mudstone.	0.00-1.20 occasional rootlets			
1.20 - 1.65	SPTS D 2	N=16 (3,4/4,4,4,4)	1.20	Dry			(3.00)		
1.65 - 2.00	B 3								
2.00 - 2.45	SPTS D 4	N=13 (3,3/3,4,3,3)	1.50	Dry					
2.50 - 3.00	B 5								
3.00 - 3.45	SPTS D 6	N=8 (1,2/2,2,2,2)	1.50	1.10	Firm thinly laminated brown CLAY with frequent partings of fine to medium sand.		3.00 +2.43		
3.50 - 4.00	B 7						(0.70)		
4.00 - 4.45	SPTS D 8	N=13 (2,2/3,3,3,4)	4.00	Dry	Medium dense brown slightly gravelly very silty fine to medium SAND. Gravel is angular to subrounded fine to medium of various lithologies.		3.70 +1.73		
4.50 - 5.00	B 9						(0.80)		
5.00 - 5.45	UT 10	39 blows 100% rec	4.50	Dry	Stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, quartz and sandstone.		4.50 -0.93		
5.45 - 5.65	D 11								
5.65 - 6.00	B 12								
6.00 - 6.45	SPTS D 13	N=22 (3,3/4,6,6,6)	6.00	Dry					
6.50 - 7.10	B 14								
7.50 - 7.95	UT 15	49 blows 100% rec	7.50	Dry		7.10-7.40 foreman reports reddish brown sand 7.40 becoming greyish brown			
7.95 - 8.15	D 16								
8.15 - 8.60	SPTS D 17	N=23 (3,3/4,5,6,8)	7.50	Dry					
8.60 - 9.00	B 18								
9.00 - 9.45	UT 19	59 blows 100% rec	9.00	Dry			(8.80)		
9.45 - 9.65	D 20								
9.65 - 10.10	SPTS D 21	N=29 (3,5/7,7,8,7)	9.50	Dry					

Groundwater Entries				Depth Related Remarks		Hard Boring			
No.	Depth (m)	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	3.00		Rose to 1.10 m after 20 minutes.	3.60					
2	7.10		Rose to 4.15 m after 20 minutes.	7.40					

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH3
Scale 1:50	Project No.	A8015-18		Sheet 1 of 3
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.60	200	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018				146			

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date	Time	Main	Detail	(Thickness)			
			Casing	Water						
10.00 - 10.50	B 22				Stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, quartz and sandstone.					
10.50 - 10.95	UT 23	76 blows 100% rec	10.50	Dry						
10.95 - 11.15	D 24									
11.00 - 12.00	B 26									
11.15 - 11.60	SPTS D 25	N=36 (4,6/7,9,11,9)	11.00	Dry						
12.00 - 12.45	UT 27	69 blows 100% rec	12.00	Dry						
12.45 - 12.65	D 28									
12.65 - 13.10	SPTS D 29	N=30 (3,5/5,7,9,9)	12.00	Dry						
12.80 - 13.30	B 30									
13.50 - 13.95	SPTS D 31	N=11 (1,2/2,3,3,3)	12.00	7.90	Medium dense greenish brown gravelly clayey fine to medium SAND. Gravel is angular to subrounded fine to coarse of various lithologies. Occasional gravel size pockets of clay.		13.30	-7.87	3	
13.50	D 32						(0.80)			
13.50 - 13.95										
14.10 - 15.00	B 33				Stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk, quartz, sandstone and mudstone.		14.10	-8.67		
							(1.00)			
15.00 - 15.45	SPTS D 34	N=11 (2,3/2,2,3,4)	11/04/18 15.00	1700 7.00	Medium dense yellowish brown gravelly fine to medium SAND. Gravel is angular to subrounded fine to coarse of various lithologies. Occasional gravel size pockets of clay.		15.10	-9.67		
15.00 - 15.45			12/04/18 15.00	0800 3.30			(0.90)			
16.00 - 16.50	B 35				Grey slightly sandy clayey SILT. Rare subangular fine to medium gravel of chalk.		16.00	-10.57		
16.50 - 16.77	SPTS D 36	57 (10,15 for 60mm/28,29 for 60mm)	16.50	5.10						
16.50 - 16.80										
17.00 - 18.00	B 37						(2.70)			
18.00 - 18.20	SPTS D 38	50 (15,10 for 50mm/50 for 70mm)	18.00	Dry						
18.00 - 18.30										
18.60 - 19.50	B 39				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.		18.70	-13.27		
19.50 - 19.75	SPTS D 40	50 (11,14 for 50mm/22,28 for 50mm)	19.50	Dry						
19.50 - 19.80										

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
3	13.30		Rose to 6.10 m after 20 minutes.	14.10						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH3
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:22				Sheet 2 of 3

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	5.43 mOD
Logged	MJS/PC	11/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	1.20	28.00	200	28.00	Coordinates (m)	E 516635.31
Checked	TC	End		28.00	28.60	146	28.00	National Grid	N 417437.68
Approved	TC	16/04/2018							

Samples and Tests

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	(Thickness)			
20.00 - 21.00	B 41				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					
21.00 - 21.20 21.00 - 21.30	SPTS D 42	50 (19,6 for 10mm/31,19 for 40mm)	21.00	Dry						
22.00 - 22.50	B 43				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					
22.50 - 22.62 22.50 - 22.70	SPTS D 44	50 (25 for 75mm/50 for 40mm)	22.50	Dry				(8.10)		
23.00 - 24.00	B 45				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					
24.00 - 24.14 24.00 - 24.10	SPTS D 46		12/04/18 24.00	1700 Dry			24.00 becoming locally gravelly			
25.00 - 25.50	B 47				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					
25.50 - 25.62 25.50 - 25.62	SPTS D 48	50 (25 for 75mm/50 for 50mm)	25.50	Dry						
26.00 - 26.50	B 49				Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk with rare flint. Locally silty.					
26.80 - 27.02 26.80 - 27.02 27.00 - 27.50	SPTS D 50 B 51	50 (18,7 for 10mm/28,22 for 60mm)	26.50	8.70		Extremely weak white CHALK. Recovered as gravelly clay. Gravel is angular to subangular fine to coarse of chalk with rare flint.	27.00 becoming recovered as clayey angular fine to coarse gravel	26.80 -21.37 (1.20)	4	
28.00 - 28.10		50 (25 for 60mm/50 for 40mm)	13/04/18 28.00	1630 4.10	Medium strong white CHALK. Recovered as subangular to subrounded fine to coarse gravel.					
28.00 - 28.60	42 0 0	NI -	16/04/18 28.00	1300 0.70				28.00 -22.57 (0.60)		
		Flush: 28.00 - 28.60 Air/mist 100%	16/04/18 28.00	1700 0.70						
					END OF EXPLORATORY HOLE			28.60 -23.17		

Depth	TCR	SCR	RQD	If	Records	Date Casing	Time Water	Groundwater Entries	Depth Related Remarks	Hard Boring	Duration (mins)	Tools used
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks		No.	Depth	Strike (m)	Remarks	
4	26.80		Rose to 8.70 m after 20 minutes.					4	26.80		Rose to 8.70 m after 20 minutes.	
									27.60 - 28.00		60	Chisel

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175/Beretta T44. Cable percussion boring /Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516726.70
Checked	TC	End		24.00	34.60	200	16.50	National Grid	N 417410.38
Approved	TC	20/04/2018				146	28.60		

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date	Time	Main	Detail	(Thickness)			
			Casing	Water						
0.50 - 1.20	B 1	0.00-1.20 Hand excavated inspection pit.			Light brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone with frequent rootlets. (TOPSOIL)		(0.30)			
1.20 - 1.65	SPTS D 2	N=16 (2,3/4,4,4,4)	1.20	Dry	Firm brown, mottled grey and light brown, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, flint and sandstone.		+3.89			
1.65 - 2.00	B 3						(2.90)			
2.00 - 2.45	UT 4	59 blows 100% rec	1.50	Dry						
2.45 - 2.65	D 5									
2.65 - 3.10	SPTS D 6	N=15 (2,3/3,4,3,5)	1.50	Dry						
3.10 - 3.55	UT 7	51 blows 100% rec	3.00	Dry	Soft brown very sandy CLAY.		+0.99			
3.75 - 4.20	SPTS D 8	N=6 (1,2/1,2,1,2)	3.00	1.00		3.55 brown clayey sand	(0.95)			
4.00 - 4.50	B 9									
4.50 - 4.95	UT 10	47 blows 100% rec	4.50	Dry	Stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk and sandstone.		+0.04			
4.95 - 5.15	D 11									
5.15 - 5.60	SPTS D 12	N=22 (2,3/4,6,6,6)	4.50	Dry						
5.50 - 6.00	B 13						(2.95)			
6.00 - 6.45	UT 14	42 blows 100% rec	6.00	Dry						
6.45 - 6.65	D 15									
6.65 - 7.10	SPTS D 16	N=24 (2,3/4,6,6,8)	6.00	Dry						
7.20 - 7.50	B 17		16/04/18 6.00	1700 2.10		7.10-7.20 fine sand and gravel	7.10			
7.50 - 7.95	UT 18	51 blows 100% rec	7.50	Dry	Stiff to very stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.		-2.91			
7.95 - 8.15	D 19									
8.15 - 8.60	SPTS D 20	N=25 (4,4/5,6,7,7)	7.50	Dry						
8.50 - 9.00	B 21									
9.00 - 9.45	UT 22	42 blows 100% rec	9.00	Dry						
9.65 - 10.10	SPTS D 23	N=23 (3,4/5,5,7,6)	9.00	Damp			(4.90)			

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	3.20		Rose to 1.00 m after 20 minutes.	4.15						
2	7.40		Rose to 2.10 m after 20 minutes.	7.20						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:23				Sheet 1 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush.	1.20	24.00	200	16.50	Coordinates (m)	E 516726.70
Checked	TC	End	SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	24.00	34.60	146	28.60	National Grid	N 417410.38
Approved	TC	20/04/2018							

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.00 - 10.50	B 24				Stiff to very stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.				
10.50 - 10.95	UT 25	40 blows 100% rec	10.50	Dry					
10.95 - 11.15	D 26								
11.15 - 11.60	SPTS D 27	N=24 (3,4/5,6,6,7)	10.50	Dry					
11.50 - 12.00	B 28								
12.00 - 12.45	SPTS D 29	N=33 (4,4/6,7,9,11)	10.50	7.20	Brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk, sandstone and flint.	12.00-12.30 driller notes reddish brown fine sand	12.00 -7.81		3
12.50 - 13.00	B 30					12.50 becomes light brown sandy	(1.40)		
13.50 - 13.95	SPTS D 31	N=37 (5,5/7,10,9,11)	13.50	2.10	Stiff to very stiff light yellowish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, sandstone and flint.		13.40 -9.21		4
14.00 - 15.00	B 32					14.00-15.00 becoming slightly gravelly clayey sand			
15.00 - 15.45	SPTS D 33	N=16 (3,3/4,3,4,5)	15.00	1.10			(3.70)		5
15.50 - 16.00	B 34					15.50-16.00 sandy clayey gravel			
16.50 - 16.95	SPTS	N=44 (6,8/7,11,13,13)	16.50	1.30					
			17/04/18	1700					
			16.50	1.30					
17.10 - 17.50	B 36		18/04/18	0800	Dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		17.10 -12.91		
			16.50	1.30			(0.70)		
18.00 - 18.45	SPTS D 37	N=13 (2,3/2,3,3,5)			Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		17.80 -13.61		5
18.00 - 18.45	B 38						(1.30)		
18.00 - 19.00									
19.50 - 19.74	SPTS D 39				Very stiff greyish brown slightly sandy slightly gravelly CLAY with pockets of coarse gravel size extremely weak weathered chalk. Gravel is subrounded fine to coarse of chalk.		19.10 -14.91		
19.50 - 19.70									

Groundwater Entries			Depth Related Remarks			Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
3	12.00	Rose to 6.95 m after 20 minutes.	12.30	13.50 - 16.50	Water added to assist boring.			
4	13.40	Rose to 4.10 m after 20 minutes.						
5	17.80	Rose to 15.10 m after 20 minutes.						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:23				Sheet 2 of 4

Borehole Log



Drilled	SS/MB	Start	16/04/2018	Equipment, Methods and Remarks	Dando 175/Beretta T44. Cable percussion boring./Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush. SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	24.00	Diameter (mm)	200	Casing Depth (m)	16.50	Ground Level	4.19 mOD
Logged	WH/PC	End	20/04/2018				24.00		34.60		146		28.60	Coordinates (m)	E 516726.70
Checked	TC													National Grid	N 417410.38
Approved	TC														

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
20.00 - 21.00	B 40				Very stiff greyish brown slightly sandy slightly gravelly CLAY with pockets of coarse gravel size extremely weak weathered chalk. Gravel is subrounded fine to coarse of chalk.		(2.30)		
21.00 - 21.22 21.00 - 21.25	SPTS D 41				Very stiff dark greyish brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk.	21.00-21.25 white chalk, possible cobble	21.40 -17.21		
22.00 - 22.50	B 42						(2.00)		
22.50 - 22.64 22.50 - 22.60	SPTS D 43	50 (18,7 for 10mm/50 for 60mm)							
23.00 - 24.00	B 44						23.40 -19.21		
			18/04/18	1700	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and flint.		(0.60)		
24.00 - 24.15 24.00 - 24.15	SPTS D 45	50 (25/50 for 60mm)	19/04/18 18/04/18 16.50	0800 0800 0.85	Stiff grey clay. (Rotary open hole drilling) (Drillers description)	24.00-24.15 light grey clayey silt	24.00 -19.81		6
							(4.50)		
28.50 - 30.00	90 6 0	NI NI 80			Medium strong to strong white CHALK. Fractures are: 1) subhorizontal, very closely spaced, undulating, rough with occasional grey staining. 2) subvertical, undulating, rough with occasional grey staining.	28.60-28.72 recovered as subangular gravel with rare angular flint 28.86-28.96 grey flint nodule 29.30-30.00 recovered as gravel 29.44-29.47 soft cream mottled greyish green clay with frequent angular fine gravel	28.50 -24.31		
						of chalk 30.00-30.27 AZCL	(2.15)		

Groundwater Entries			Depth Related Remarks			Hard Boring		
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
6	24.00	Rose to 9.60 m after 20 minutes.		21.40 - 21.90		21.40 - 21.90	40	
				23.40 - 24.00		23.40 - 24.00	60	

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.19 mOD
Logged	WH/PC	16/04/2018	Dando 175. Beretta T44. Cable percussion boring. Rotary open hole drilling to 28.50m followed by rotary core drilling (SWF size) using air mist flush.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516726.70
Checked	TC	End	SPT Hammer ID: AR2068, Rod type: 54mm Whitworth.	24.00	34.60	200	28.60	National Grid	N 417410.38
Approved	TC	20/04/2018							

Samples and Tests				Strata Description						
Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
30.00 - 31.50	82 35 11			19/04/18 28.60	1700 0.85	Medium strong to strong white CHALK. Fractures are: 1) subhorizontal, very closely spaced, undulating, rough with occasional grey staining. 2) subvertical, undulating, rough with occasional grey staining.	30.27-30.37 recovered as subangular coarse gravel	30.65 -26.46		
			Flush: 28.50 - 34.60 Air/ mist 100%	20/04/18 28.60	0800 1.00	Strong white CHALK. Fractures are subhorizontal, very closely spaced, undulating, rough with brownish grey staining and rare infill of very soft greyish brown CLAY.	30.51-30.57 recovered as subangular coarse gravel			
31.50 - 32.10	47 12 0						31.50-31.81 AZCL			
32.10 - 33.10	100 46 19	NI 60 180					32.42-32.46 recovered as subangular coarse gravel	(3.95)		
33.10 - 34.10	100 44 15						32.64-32.75 recovered as subangular medium to coarse gravel including flint			
34.10 - 34.60	100 66 30			20/04/18 28.60	1700 1.00		32.77-33.00 subvertical undulating smooth fracture with clay infill 33.00-33.02 recovered as grey angular to subangular gravel of flint			
						END OF EXPLORATORY HOLE	33.40-33.42 rare subangular coarse gravel of flint	34.60 -30.41		
							33.80-33.82 recovered as grey angular fine to medium gravel of flint			

Groundwater Entries				Depth Related Remarks				Chiselling Details			
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH4
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:24				Sheet 4 of 4

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	13.00	Diameter (mm)	200	Casing Depth (m)	13.00	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018				13.00		26.10		150		26.00	Coordinates (m)	E 516748.31
Checked	TC													National Grid	N 417439.50
Approved	TC														

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail				
0.10 - 0.40	D 1 B 2	0.00-1.20 Hand excavated inspection pit.			Dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.		(0.40)			
0.50 - 0.80	D 3 B 4				(TOPSOIL) Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to medium of flint.		0.40 +4.25 (0.50)			
1.00 - 1.20 1.20 - 1.65	D 5 B 6 UT 7	35 blows 89% rec		Dry	Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk, flint and mudstone.		0.90 +3.75			
1.65 - 1.80 1.80 - 2.25 1.80 - 2.25 1.80 - 2.25	D 8 SPTS D 9 B 10	N=16 (2,3/3,4,4,5)		Dry						
2.30 - 2.75	UT 11	38 blows 100% rec	1.70	Dry						
2.75 - 2.90 2.90 - 3.35 2.90 - 3.35 2.90 - 3.35	D 12 SPTS D 13 B 14	N=19 (3,4/4,5,5,5)	1.70	Dry		2.90-4.45 gravel is subangular to subrounded	(3.60)			
3.40 - 3.85	UT 15	32 blows 100% rec	3.00	Dry						
3.85 - 3.90 4.00 - 4.45 4.00 - 4.45 4.00 - 4.45	D 16 SPTS D 17 B 18	N=17 (2,3/4,4,4,5)	3.00	Dry						
4.50 - 4.95 4.50	UT 20 D 19	40 blows 100% rec	4.40	Dry	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine of chalk, sandstone and mudstone.		4.50 +0.15			
4.95 - 5.10 5.10 - 5.55 5.10 - 5.55 5.10 - 5.55	D 21 SPTS D 22 B 22A	N=13 (2,2/3,3,3,4)	4.40	Dry						
6.50 - 6.95	UT 23	46 blows 100% rec	4.60	Dry						
6.95 - 7.10 7.10 - 7.55 7.10 - 7.55 7.10 - 7.55	D 24 SPTS D 25 B 26	N=15 (2,3/3,4,4,4)	4.60	Dry						
8.00 - 8.45	UT 27	60 blows 100% rec	4.60	Dry						
8.45 - 8.60 8.60 - 9.05 8.60 - 9.05 8.60 - 9.05	D 28 SPTS D 29 B 30	N=29 (3,5/6,7,8,8)	4.60	Dry			(7.90)			
9.50 - 9.95	UT 31	50 blows 100% rec	4.60	Dry						
9.95 - 10.10	D 32									

Groundwater Entries			Depth Related Remarks		Hard Boring			
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 3

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks	Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from (m)	1.20	to (m)	13.00	Diameter (mm)	200	Casing Depth (m)	13.00	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018				13.00		26.10		150		26.00	Coordinates (m)	E 516748.31
Checked	TC													National Grid	N 417439.50
Approved	TC														

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.10 - 10.55 10.10 - 10.55 10.10 - 10.55	SPTS D 33 B 34	N=30 (2,4/7,7,8,8)	4.60	Dry	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine of chalk, sandstone and mudstone.				
11.00 - 11.45	UT 35	60 blows 100% rec	4.60	Dry					
11.45 - 11.60 11.60 - 12.05 11.60 - 12.05 11.60 - 12.05	D 36 SPTS D 37 B 38	N=31 (4,6/7,7,8,9)	4.60	Dry		11.45-12.05 dark brown, gravel is fine to medium			
12.40 12.50 - 12.95 12.50 - 12.95 12.50 - 12.95	W 41 SPTS D 39 B 40	N=32 (4,6/7,7,8,10)	4.60	Dry	Stiff light brown slightly sandy gravelly CLAY. Gravel is subrounded fine to medium of chalk, sandstone and mudstone.		12.40 -7.75		
13.00	D 42		17/04/18 4.60	1800 12.10					
14.00 - 14.45	UT 43	70 blows 100% rec	13.50				(2.10)		
14.45 - 14.60 14.60 - 15.05 14.60 - 15.05 14.60 - 15.05	D 44 SPTS D 45 B 46	N=46 (7,8/9,10,13,14)	13.50		Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and mudstone.		14.50 -9.85		
15.50 - 15.95	UT 47	100 blows 100% rec	15.00						
15.95 - 16.10 16.10 - 16.48 16.10 - 16.48 16.10 - 16.48	D 48 SPTS D 49 B 50	50 (8,10/13,18,19 for 75mm)	15.00	Dry		16.10 becoming light grey	(3.10)		
17.00 - 17.36 17.00 - 17.36 17.00 - 17.36	SPTS D 51 B 52	50 (10,12/14,17,19 for 65mm)	15.00	Dry					
17.70 17.70 - 18.50	D 53 B 54				Very stiff light grey slightly sandy slightly gravelly CLAY with coarse gravel size pockets of extremely weak chalk. Gravel is subrounded fine to medium of chalk.		17.60 -12.95		
18.50 - 18.86 18.50 - 18.86 18.50 - 18.86	SPTS D 55 B 56	50 (11,13/15,18,17 for 65mm)	18.00	18.00	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk.		18.50 -13.85		

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth (m)	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
1	12.40		Rose to 12.10 m after 20 minutes. Slow inflow									
2	17.60		Rose to 16.70 m after 20 minutes. Medium inflow	18.00								

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH5
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:24				Sheet 2 of 3

Borehole Log



Drilled	GC	Start	17/04/2018	Equipment, Methods and Remarks Dando 2000. Cable percussion boring. SPT Hammer ID: AR1940, Rod type: 54mm Whitworth.	Depth from	to	Diameter	Casing Depth	Ground Level	4.65 mOD
Logged	WH	End	19/04/2018		(m)	(m)	(mm)	(m)	Coordinates (m)	E 516748.31
Checked	TC	End	19/04/2018		13.00	26.10	200	13.00	National Grid	N 417439.50
Approved	TC	End	19/04/2018		13.00	26.10	150	26.00		

Samples and Tests

Samples and Tests					Strata Description				
Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
20.00 - 20.28 20.00 - 20.28 20.00 - 20.28	SPTS D 57 B 58	50 (12,13 for 55mm/20,30 for 75mm)	19.50	19.50	Very stiff light grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk.				
21.50 - 21.74 21.50 - 21.74 21.50 - 21.74	SPTS D 59 B 60	50 (20,5 for 15mm/26,24 for 70mm)	21.00	21.00				(7.65)	
23.00 - 23.21 23.00 - 23.21 23.00 - 23.21	SPTS D 61 B 62	50 (18,2 for 20mm/30,20 for 40mm)	22.50	22.00			23.00-23.30 including gravel of sandstone		
24.50 - 24.62 24.50 - 24.62 24.50 - 24.62	SPTS D 63 B 64	45 (25 for 20mm/33,12 for 25mm)	23.50	24.00					
25.60 - 25.72 25.60 - 25.72	SPTS D 65	50 (25 for 50mm/50 for 70mm)	18/04/18 25.00	1800 24.00					
26.10 - 26.15	SPTC	50 (25 for 20mm/50 for 30mm)	19/04/18 26.00	0800 21.00 1530 23.00	END OF EXPLORATORY HOLE		26.15 -21.50		

Groundwater Entries				Depth Related Remarks				Hard Boring				
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used			
							25.40 - 25.60	60	Chisel			
							25.70 - 26.10	180	Chisel			

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	34.50	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018							

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill
Depth	Type & No.	Records	Date	Time	Main	Detail	(Thickness)			
			Casing	Water						
0.00 - 0.30	B 1	0.00-1.20 Hand excavated inspection pit.			Greyish brown very sandy clayey GRAVEL. Gravel is angular to subrounded fine to coarse of mudstone, sandstone, chalk and brick. (MADE GROUND)		(0.30)			
0.30 - 0.55	B 2						0.30 +4.41			
0.55 - 1.20	B 3				Firm brown, locally greyish brown, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and sandstone.		(0.30)			
1.20 - 1.65	SPTS D 4	N=14 (1,2/2,4,4,4)	1.20	Dry	Stiff to very stiff brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of predominantly chalk, mudstone, quartz and sandstone and rare coal.		0.60 +4.11			
1.65 - 2.00	B 5									
2.00 - 2.45	UT 6	71 blows 100% rec	1.50							
2.45 - 2.65	D 7						(4.05)			
3.00 - 3.45	SPTS D 8	N=16 (3,4/3,4,4,5)	3.00	Dry						
3.00 - 3.45										
3.50 - 4.00	B 9									
4.00 - 4.45	UT 10	60 blows 100% rec	4.00							
4.45 - 4.65	D 11		05/04/18	1700						
			4.00	2.50						
5.00 - 5.45	SPTS D 12	N=10 (1,1/1,2,3,4)	06/04/18	0800	Firm thinly laminated CLAY with occasional partings of fine sand. Frequent gravel size pockets of fine to coarse sand.		4.65 +0.06			
5.00 - 5.45			4.00	2.00			(0.65)			
5.50 - 6.00	B 13				Stiff to very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk, mudstone and sandstone.		5.30 -0.59			
6.00 - 6.45	UT 14	71 blows 100% rec	6.00							
6.45 - 6.65	D 15									
7.00 - 7.50	B 16									
7.50 - 7.95	SPTS D 17	N=18 (3,3/4,4,5,5)	7.50	Dry						
7.50 - 7.95										
8.00 - 9.00	B 18									
9.00 - 9.45	UT 19	61 blows 100% rec	9.00				(7.60)			
9.45 - 9.65	D 20									

Groundwater Entries				Depth Related Remarks				Hard Boring		
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
1	4.65		Rose to 2.50 m after 20 minutes.	5.30						

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 1 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	1.20	24.60	200	24.60	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	34.50	146	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018							

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
10.00 - 10.50	B 21				Stiff to very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk, mudstone and sandstone.				
10.50 - 10.95	SPTS D 22	N=18 (3,3/4,5,4,5)	10.50	Dry					
11.00 - 11.80	B 23				Brown gravelly clayey fine to coarse SAND. Gravel is subangular to subrounded fine to coarse of chalk and flint.				
12.00 - 12.45	SPTS D 24	N=21 (3,4/5,4,6,6)	12.00	4.10					
13.00 - 13.50	B 25				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
13.50 - 13.95	SPTS D 26	N=4 (1,0/1,1,1,1)	13.50	9.10					
13.70									
14.00 - 15.00	B 27				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
15.00 - 15.45	SPTS D 28	N=34 (6,6/7,9,10,8)	06/04/18 15.00	1630 9.10					
15.00 - 15.45			09/04/18 15.00	0800 10.40					
15.50 - 16.50	B 29				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
16.50 - 16.95	SPTS D 30	N=28 (7,7/7,7,7,7)	16.50	14.10					
16.70									
17.50 - 18.00	B 31				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
18.00 - 18.45	SPTS D 32	N=28 (6,7/6,7,7,8)	18.00	Dry					
18.00 - 18.45									
18.50 - 19.50	B 33				Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
19.50 - 19.95	SPTS D 34	N=39 (7,8/9,10,10,10)	19.50	Dry					
19.50 - 19.95	B 35								
19.50 - 21.00									

Groundwater Entries			Depth Related Remarks		Hard Boring			
No.	Depth Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
2	11.80	Rose to 3.10 m after 20 minutes.						
3	18.60	Rose to 16.60 m after 20 minutes.	18.70					

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 2 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175/Beretta T44. Cable percussion boring./Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	34.50	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018							

Samples and Tests

Depth	Type & No.	Records	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
21.00 - 21.45	SPTS D 36	N=33 (4,5/5,9,9,10)	21.00	Dry	Stiff to very stiff light grey slightly sandy gravelly CLAY. Gravel is angular to subangular fine to coarse of chalk and rare flint.				
21.50 - 22.50	B 37				Extremely weak cream CHALK. Recovered as gravelly clay.		21.50 -16.79	4	
22.50 - 22.95	SPTS D 38	N=44 (7,8/9,10,13,12)	22.00	13.00	Very weak white, locally orangish brown, CHALK. Recovered as subangular fine to coarse gravel to cobbles.		22.50 -17.79		
23.00 - 23.80	B 39		09/04/18 22.00	1700 13.00					
23.80 - 23.91	SPTC	50 (25 for 60mm/50 for 50mm)	22.50	4.00			23.80 -19.89		
24.25 - 24.30	SPTC	50 (25 for 30mm/50 for 20mm)	10/04/18 22.50	1010 4.00					
24.60 - 25.60	95 46 30		13/04/18 22.50	0800 2.60	Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, undulating, rough with dark brown staining. 2. Subvertical, planar, smooth with yellowish brown staining. 3. Incipient fractures are very closely spaced, stepped, striated.		24.60 -19.89		
25.60 - 27.10	95 49 37	NI 100 196				26.85-26.98 1No. subangular cobble of flint 27.02-27.30 AZCL	(2.95)		
27.10 - 28.40	80 21 8	NI NI 90			Weak cream, occasionally speckled black, CHALK. Recovered as slightly silty subangular fine to coarse gravel. Fractures are subhorizontal, closely spaced, undulating, rough with yellowish brown staining.		27.55 -22.84		
28.40 - 29.90	77 30 17	NI 120 170			Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, planar, rough with dark greyish brown staining. 2. Occasionally subvertical, planar, smooth. 3. Incipient fractures are subhorizontal, extremely closely spaced, stepped, rough with occasional dark grey staining.	28.34-28.60 AZCL 28.55 rare subangular coarse gravel of flint 29.59-30.66 1No. cobble of flint 29.75-29.95 AZCL	28.70 -23.99		
		Flush: 24.60 - 34.50 Air/mist 100%					(2.20)		

Depth	TCR	SCR	RQD	If	Records	Date Casing	Time Water	Groundwater Entries	Depth Related Remarks	Hard Boring	Tool used
No.	Depth	Strike (m)	Remarks	Depth Sealed (m)	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
4	21.50		Rose to 16.10 m after 20 minutes.				23.80 - 24.25	60	Chisel		

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	BH6
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:42:25				Sheet 3 of 4

Borehole Log



Drilled	SS/MB	Start	Equipment, Methods and Remarks	Depth from	to	Diameter	Casing Depth	Ground Level	4.71 mOD
Logged	MJS/IH	05/04/2018	Dando 175. Beretta T44. Cable percussion boring. Rotary core drilling (SWF size) using air mist flush. SPT Hammer ID AR2068, Rod type: 54mm Whitworth.	(m)	(m)	(mm)	(m)	Coordinates (m)	E 516781.85
Checked	TC	End		24.60	24.60	200	24.60	National Grid	N 417525.42
Approved	TC	16/04/2018			34.50	146			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
29.90 - 31.40	97 63 40					Weak cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, planar, rough with dark greyish brown staining. 2. Occasionally subvertical, planar, smooth. 3. Incipient fractures are subhorizontal, extremely closely spaced, stepped, rough with occasional dark grey staining.	30.90-33.80 dark grey staining is possible mudstone partings (<5mm thick)	30.90 -26.19		
31.40 - 32.90	100 83 67			13/04/18 24.60	1630 2.60	Weak to medium strong cream CHALK. Fractures are: 1. Subhorizontal, closely spaced, undulating, rough and planar, rough with dark grey staining. 2. Rare 45 degree, undulating, rough with dark grey staining. 3. Incipient fractures are subhorizontal, very closely to closely spaced, undulating, striated, stepped, rough.	32.90-34.50 rare angular to subangular fine to coarse gravel of flint, rare incipient fractures are closely spaced	(3.60)		
32.90 - 34.50	94 82 73	NI 150 310		16/04/18 24.60	1100 2.60		33.80-33.89 1No. cobble of chalk and flint conglomerate			
				16/04/18 24.60	1300 0.70	END OF EXPLORATORY HOLE		34.50 -29.79		

Groundwater Entries				Depth Related Remarks				Chiselling Details		
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	6.49 mOD
Logged IH	06/04/2018	Archway Dart Dynamic sampling SPT Hammer ID: DART235, Rod type: quick thread.	1.20	3.60	87		Coordinates (m)	E 516506.21
Checked TC	End		3.60	4.60	55		National Grid	N 417414.94
Approved TC	06/04/2018							

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill
Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail			
0.00 - 0.50	D 2					Dark brown slightly sandy slightly gravelly CLAY with low cobble content. Gravel is subangular to rounded fine to medium, rarely coarse, of chalk and mudstone with occasional concrete, quartz and flint. Cobbles are subangular of chalk. (MADE GROUND)	0.50 rare rootlets	(0.50)		
0.00 - 0.50	B 1		p 120kPa, r N/A							
0.50	HV					Dark brown, locally mottled black, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk, mudstone and rare flint. Strong hydrocarbon odour. (MADE GROUND)	2.10 unknown fibrous rock/material	0.50	+5.99	
0.50 - 1.20	D 4		p 120kPa, r N/A							
0.50 - 1.20	B 3					Firm reddish brown, occasionally mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.	2.40 occasional pockets of reddish pink clayey fine sand	(0.90)		
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS					Firm grey, mottled brown, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.	2.10 unknown fibrous rock/material	1.40	+5.09	
1.20 - 1.65	D 5		N=10 (2,2/2,2,3,3)							
1.20 - 1.70	B 7					Firm to stiff indistinctly laminated reddish brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of chalk and mudstone with occasional flint and rare sandstone.	2.40 occasional pockets of reddish pink clayey fine sand	(0.35)		
1.20 - 2.00	L		100% rec, diameter 87mm							
1.30 - 1.50	D 6					Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of chalk.	4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz	1.75	+4.74	
1.80 - 2.00	D 8		N=26 (3,5/4,5,8,9)							
2.00 - 2.45	SPTS					Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of chalk.	4.50-4.60 brown slightly gravelly fine to coarse sand. Gravel is subangular to well rounded fine to medium of chalk and rare quartz	(0.25)		
2.00 - 2.20	D 10		100% rec, diameter 87mm							
2.00 - 2.45	D 9					END OF EXPLORATORY HOLE		2.00	+4.49	
2.00 - 2.80	B 12		N=20 (4,4/4,4,5,7)							
2.00 - 2.80	L		100% rec, diameter 87mm			Brown fine to medium SAND.		(1.60)		
2.30 - 2.50	D 11		N=20 (4,5/4,4,5,7)							
2.80 - 3.25	SPTS					Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of chalk.		3.60	+2.89	
2.80 - 3.25	D 13		75% rec, diameter 55mm							
2.80 - 3.60	L					END OF EXPLORATORY HOLE		(0.60)		
3.00 - 3.20	D 14		N=16 (3,3/3,4,4,5)	06/04/18	1200					
3.40 - 3.60	D 15					END OF EXPLORATORY HOLE		4.20	+2.29	
3.60 - 4.05	SPTS									
3.60 - 3.80	D 16					END OF EXPLORATORY HOLE		(0.40)		
3.60 - 4.05	D 17									
3.60 - 4.60	L					END OF EXPLORATORY HOLE		4.60	+1.89	
4.20 - 4.40	D 18									
4.50 - 4.60	D 19					END OF EXPLORATORY HOLE		(0.45)		
4.60 - 5.05	SPTS									
4.60 - 5.05	D 20					END OF EXPLORATORY HOLE		5.05	+1.44	

Groundwater Entries			Depth Related Remarks			Chiselling Details		
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	4.20			0.00 - 1.20	Hand excavated inspection pit.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS1
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:47:31				Sheet 1 of 1

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.46 mOD
Logged IH	10/04/2018	Archway Dart. Dynamic sampling.	1.20	1.70	87		Coordinates (m)	E 516529.35
Checked TC	End	SPT Hammer ID: DART235, Rod type: quick thread.	1.70	2.50	77		National Grid	N 417368.31
Approved TC	10/04/2018		2.50	3.30	67			

Samples and Tests

Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill	
0.00 - 0.50	D 2					Brown, mottled orange and grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of mudstone and sandstone. Strong oil/hydrocarbon odour. (MADE GROUND)	0.50 rare angular to subrounded fine to medium gravel of flint and sandstone with rare chalk	(1.20)			
0.00 - 0.50	B 1		p 120kPa, r N/A								
0.25	HV										
0.50	HV		p 120kPa, r N/A								
0.50 - 1.20	D 4										
0.50 - 1.20	B 3										
1.00	HV		p 120kPa, r N/A								
1.20 - 1.65	SPTS		N=16 (2,2/3,3,5,5)								
1.20 - 1.40	D 5										
1.20 - 1.65	D 6										
1.20 - 1.70	B 8										
1.20 - 1.70	L		100% rec, diameter 87mm								
1.50 - 1.70	D 7										
1.70 - 2.15	SPTS		N=28 (3,3/5,8,7,8)								
1.70 - 2.15	D 9										
1.70 - 2.50	B 11										
1.70 - 2.50	L		100% rec, diameter 77mm								
2.20 - 2.40	D 10										
2.40 - 2.50	D 12										
2.50 - 2.95	SPTS		N=22 (2,4/4,5,6,7)								
2.50 - 2.95	D 13										
2.50 - 3.10	B 16										
2.50 - 3.30	L		100% rec, diameter 67mm								
2.85 - 3.10	D 14										
3.10 - 3.30	D 15										
3.30 - 3.75	SPTS		N=26 (3,5/5,5,8,8)								
3.30 - 3.75	D 17										
				10/04/18	1100	Firm indistinctly laminated dark brown, mottled grey, CLAY.	1.50-2.50 indistinctly laminated	(1.30)			
						Firm yellowish dark brown, mottled grey, slightly sandy slightly gravelly CLAY. Gravel is angular to subangular fine to medium of chalk, flint and sandstone.	2.30 gravel size pocket of dark grey fine sand	2.50	+2.96		
						Firm dark brown slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to medium of chalk and sandstone.	2.85-3.10 gravel size pockets of fine sand	(0.60)			
								3.10	+2.36		
								(0.20)			
								3.30	+2.16		
								(0.45)			
								3.75	+1.71		
						END OF EXPLORATORY HOLE					

Groundwater Entries				Depth Related Remarks		Chiselling Details			
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
					0.00 - 1.20	Hand excavated inspection pit.			
					0.00 - 3.75	No groundwater encountered during drilling.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS2
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		
14/08/2018 13:47:32				Sheet 1 of 1

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.52 mOD
Logged IH	10/04/2018	Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516555.69
Checked TC	End		2.00	3.00	77		National Grid	N 417360.77
Approved TC	10/04/2018		3.00	4.00	67			

Samples and Tests

Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	D 2					Brown, mottled black and grey and rarely orangish brown, slightly sandy slightly gravelly CLAY with frequent roots and wood fragments. Gravel is subangular to rounded fine to medium of chalk and mudstone with occasional concrete. 1No. angular cobble of chalk. (MADE GROUND)		(1.20)		
0.00 - 1.20	B 1									
1.20 - 1.65	SPTS D 3		N=11 (2,2/2,2,3,4)			Soft, becoming firm, orangish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to medium of mudstone and flint with rare chalk.		1.20 (0.10)		
1.20 - 1.30	D 4		100% rec, diameter 87mm					+4.32		
1.20 - 1.65	L					Firm to stiff brown, mottled grey and rarely black, slightly sandy slightly gravelly CLAY. Gravel is angular to rounded fine to coarse of chalk and flint with rare sandstone.		1.30 (0.10)		
1.20 - 2.00	B 6							+4.22		
1.30 - 2.00	D 5					2.05-2.55 indistinctly laminated 2.30 becoming with no gravel 2.55 becoming thinly laminated		(2.10)		
1.50 - 1.70	D 7		N=23 (3,5/6,5,6,6)							
2.00 - 2.45	D 8		100% rec, diameter 77mm			Brown fine to coarse SAND.				
2.00 - 2.20	L									
2.00 - 2.45	D 9					Firm brown, mottled grey, sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to medium of chalk.				
2.00 - 3.00	D 11		N=14 (4,5/4,3,3,4)							
2.30 - 3.00	L		40% rec, diameter 67mm			Brown fine to coarse SAND.				
2.80 - 3.00	D 12									
3.00 - 3.45	D 13					END OF EXPLORATORY HOLE				
3.00 - 4.00	L		N=20 (2,3/5,4,5,6)	10/04/18	0000					
3.40 - 3.65								3.40 +2.12		
3.65 - 3.80								(0.25)		
4.00 - 4.45								3.65 +1.87		
								(0.80)		
								4.45 +1.07		

Groundwater Entries			Depth Related Remarks		Chiselling Details			
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
				0.00 - 1.20	Hand excavated inspection pit.			
				0.00 - 1.00	Material too granular for hand vane testing.			
				0.00 - 4.45	No groundwater encountered during drilling.			

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	5.10 mOD
Logged IH	06/04/2018	Archway Dart Dynamic sampling SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516586.01
Checked TC	End		2.00	3.00	77		National Grid	N 417401.62
Approved TC	06/04/2018		3.00	3.60	57			

Samples and Tests

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 0.50	D 2		p 120kPa, r N/A			Brown, occasionally mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk and mudstone with rare flint and occasional rootlets. (MADE GROUND)	0.50 dark brown	(1.40)		
0.00 - 0.50	B 1									
0.25	HV									
0.50	HV		p 120kPa, r N/A							
0.50 - 1.20	D 4									
0.50 - 1.20	B 3									
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS		N=19 (2,3/4,5,5,5)							
1.20 - 1.40	D 5									
1.20 - 1.65	D 6									
1.20 - 2.00	B 8									
1.20 - 2.00	L		100% rec, diameter 87mm							
1.20 - 2.00	D 7									
1.60 - 1.80	D 7									
2.00 - 2.45	SPTS		N=22 (3,4/5,5,6,6)			Firm brown, occasionally mottled grey and rarely reddish brown, slightly sandy slightly gravelly CLAY. Gravel is subangular to rounded fine to coarse of chalk and mudstone with rare sandstone and flint.	1.35-1.40 layer of brick, recovered as subangular medium to coarse gravel 1.60 pocket of sandy clay (30mm diameter) 2.00-2.40 sandy	1.40 +3.70		
2.00 - 2.20	D 10									
2.00 - 2.45	D 9									
2.00 - 3.00	L		75% rec, diameter 77mm							
2.00 - 3.00	D 11									
2.40 - 2.60	D 11									
2.80 - 3.00	D 12									
3.00 - 3.45	SPTS		N=20 (2,3/4,5,5,6)							
3.00 - 3.20	D 13									
3.00 - 3.45	D 14									
3.00 - 3.50	B 16									
3.00 - 3.60	L		83% rec, diameter 57mm							
3.00 - 3.60	D 15									
3.50 - 3.60	D 15									
3.60 - 4.05	SPTS		N=15 (3,3/3,4,4,4)			Firm dark brown slightly gravelly sandy CLAY. Gravel is subangular to rounded fine to medium of chalk and mudstone.	2.40 indistinctly laminated 2.70 thinly laminated	3.00 +2.10		
3.60 - 4.05	D 17									
				06/04/18	1500					
						END OF EXPLORATORY HOLE		3.60 +1.50		
								(0.60)		
								(0.45)		
								4.05 +1.05		

Groundwater Entries			Depth Related Remarks			Chiselling Details		
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	3.00			0.00 - 1.20	Hand excavated inspection pit.			

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.70 mOD
Logged IH	10/04/2018	Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516626.81
Checked TC	End		2.00	3.00	77		National Grid	N 417337.47
Approved TC	10/04/2018		3.00	5.00	67			

Samples and Tests Strata Description

Depth	TCR SCR RQD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	D 2					Firm dark brown, mottled grey and black, slightly sandy slightly gravelly CLAY with low cobble content and occasional rootlets. Gravel is subangular to subrounded fine to coarse of mudstone, chalk, sandstone and occasional brick fragments. Cobble is subangular of chalk. (MADE GROUND)				
0.00 - 1.20	B 1		p 110kPa, r N/A							
0.25	HV									
0.50	HV		p 100kPa, r N/A					(1.25)		
1.00	HV		p 100kPa, r N/A							
1.20 - 1.65	SPTS		N=9 (1,2/2,2,2,3)			Firm, becoming stiff, greyish brown slightly sandy slightly gravelly CLAY. Gravel is subangular to well rounded fine to coarse of mudstone with occasional sandstone and flint.	1.20 soft	1.25	+3.45	
1.20 - 1.25	D 3									
1.20 - 1.65	D 4									
1.20 - 2.00	L		100% rec, diameter 87mm				1.80 brown mottled grey. Gravel is chalk and occasional mudstone			
1.25 - 1.80	B 7						2.35-5.45 indistinctly laminated			
1.50 - 1.70	D 5						2.65-5.45 rare gravel			
1.80 - 2.00	D 6									
2.00 - 2.45	SPTS		N=20 (3,4/5,4,5,6)							
2.00 - 2.45	D 8									
2.00 - 3.00	B 11									
2.00 - 3.00	L		88% rec, diameter 77mm							
2.20 - 2.40	D 9									
2.80 - 3.00	D 10									
3.00 - 3.45	SPTS		N=24 (3,4/5,6,6,7)							
3.00 - 3.20	D 12									
3.00 - 3.45	D 13									
3.00 - 4.00	L		85% rec, diameter 67mm					(4.20)		
3.75 - 3.85	D 14						3.35-5.45 soft, gravelly. Gravel is subangular to subrounded fine to medium of chalk and mudstone with rare sandstone and flint			
4.00 - 4.45	SPTS		N=23 (4,4/4,5,6,8)							
4.00 - 4.45	D 15									
4.00 - 5.00	L		Diameter 67mm				3.40 dark brown 3.75 firm 4.00-4.45 occasional gravel size pockets of sand			
5.00 - 5.45	SPTS		N=19 (4,4/4,4,5,6)							
5.00 - 5.45	D 16			10/04/18	1300					
						END OF EXPLORATORY HOLE		5.45	-0.75	

Groundwater Entries				Depth Related Remarks				Chiselling Details		
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used	
					0.00 - 1.20	Hand excavated inspection pit.				
					0.00 - 5.45	No groundwater encountered during drilling.				

Borehole Log



Drilled MB	Start 11/04/2018	Equipment, Methods and Remarks Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level 5.69 mOD
Logged WH	End 11/04/2018		1.20	3.00	87		Coordinates (m) E 516668.52
Checked TC			3.00	4.00	77		National Grid N 417414.78
Approved TC			4.00	5.00	67		

Samples and Tests				Strata Description				Depth, Level (Thickness)	Legend	Backfill	
Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill	
0.00 - 1.20	B 1					Brown sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone and sandstone. (MADE GROUND)					
0.25	HV		p 90kPa, r N/A								
0.50	HV		p 90kPa, r N/A								
0.60	D 2										
1.00	HV		p 90kPa, r N/A						(1.70)		
1.20 - 1.65	SPTS		N=8 (1,1/3,1,1,3)					1.20-1.30 1No. subrounded cobble of chalk			
1.20 - 1.65	D 3							1.40-1.50 dark greyish brown clay			
1.20 - 2.00	L		94% rec, diameter 87mm								
1.30 - 1.70	B 5										
1.50	D 4										
1.70 - 2.00	B 7										
1.80	D 6								1.70 +3.99		
2.00 - 2.45	SPTS		N=22 (3,3/4,6,5,7)				Firm to stiff brown, occasionally mottled grey, slightly sandy slightly gravelly CLAY. Gravel is subangular fine to coarse of chalk, flint and sandstone.				
2.00 - 2.45	D 8										
2.00 - 3.00	B 10										
2.00 - 3.00	L		100% rec, diameter 87mm								
2.50	D 9								(1.99)		
2.80 - 3.25	SPTS		N=21 (4,4/5,4,6,6)								
2.80 - 3.25	D 11										
3.00 - 3.60	B 13										
3.00 - 4.00	L		100% rec, diameter 77mm								
3.50	D 12										
3.80 - 4.25	SPTS		N=29 (5,8/8,7,7,7)			Soft brown CLAY	3.69-3.80 light brown fine to coarse sand pocket	3.69 +2.00			
3.80	D 14							(0.31)			
3.80 - 4.25	D 15										
4.00 - 5.00	L		70% rec, diameter 67mm			Medium dense light brown gravelly slightly clayey fine to coarse SAND with rare pockets of gravelly clay. Gravel is subangular coarse of sandstone.		4.00 +1.69			
4.30 - 5.00	B 17										
4.50	D 16							(1.45)			
5.00 - 5.45	SPTS		N=19 (4,4/5,4,5,5)	11/04/18	1100						
						END OF EXPLORATORY HOLE		5.45 +0.24			

Groundwater Entries			Depth Related Remarks			Chiselling Details		
No.	Depth Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
1	4.00			0.00 - 1.20	Hand excavated inspection pit.			

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	Depth from	to	Diameter	Casing Depth	Ground Level	5.79 mOD
Logged WH	11/04/2018		(m)	(m)	(mm)	(m)	Coordinates (m)	E 516708.48
Checked TC	End		1.20	3.00	87		National Grid	N 417492.50
Approved TC	11/04/2018		3.00	4.00	77			
			4.00	5.00	67			

Samples and Tests				Strata Description				Depth, Level	Legend	Backfill	
Depth	TCR SCR RGD	If	Records/Samples	Date Casing	Time Water	Main	Detail	(Thickness)			
0.00 - 0.30	B 1					Brown slightly gravelly sandy CLAY with rootlets and low cobble content. Gravel is subangular fine to coarse of chalk and sandstone. Cobbles are subrounded of chalk. (TOPSOIL)	0.50-0.70 pockets of dark greyish brown clay	(0.30)			
0.20	D 2										
0.30 - 0.80	B 3										
0.50	D 4										
0.80 - 1.20	B 5					Light brown sandy gravelly CLAY with low cobble content. Gravel is subangular fine to coarse of sandstone. Cobbles are subrounded of chalk. (MADE GROUND)	Soft greyish brown slightly sandy CLAY with rare subrounded fine to medium gravel of chalk.	(0.90)			
0.90	D 6										
1.20 - 1.65	SPTS		N=6 (3,3/2,2,1,1)			Firm, becoming stiff, brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk.	4.80-4.85 soft brown clay	1.20			
1.20 - 1.65	D 7										
1.20 - 1.80	B 9		100% rec, diameter 87mm								
1.20 - 2.00	L										
1.50	D 8										
1.80 - 2.00	B 11										
1.90	D 10										
2.00 - 2.45	SPTS		N=19 (3,4/4,4,5,6)								
2.00 - 2.45	D 12										
2.00 - 3.00	L		80% rec, diameter 87mm								
2.40 - 3.00	B 14										
2.80	D 13										
3.00 - 3.45	SPTS		N=23 (4,5/5,6,6,6)			Medium dense light brown gravelly fine to coarse SAND. Gravel is subrounded coarse of igneous rock and chalk.	1	(3.20)			
3.00 - 3.45	D 15										
3.00 - 4.00	L		40% rec, diameter 77mm								
3.60 - 4.00	B 17										
3.80	D 16										
4.00 - 4.45	SPTS		N=23 (5,5/5,6,6,6)								
4.00 - 4.45	D 18										
4.00 - 5.00	L		90% rec, diameter 67mm								
4.60 - 5.00	B 20										
4.90	D 19										
5.00 - 5.45	SPTS		N=18 (5,5/5,4,5,4)	11/04/18	1300			5.00	+0.79		
5.00 - 5.45	D 21							(0.45)			
								5.45	-0.34		
END OF EXPLORATORY HOLE											

Groundwater Entries				Depth Related Remarks				Chiselling Details			
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used		
1	5.00				0.00 - 1.20	Hand excavated inspection pit.					
					0.00 - 1.00	Material too granular for hand vane testing.					

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.	Project	VPI IMMINGHAM	Borehole	WS7
Scale 1:50	Project No.	A8015-18		
© Copyright SOCOTEC UK Limited	Carried out for	AECOM		Sheet 1 of 1
14/08/2018 13:47:33				

Borehole Log



Drilled MB	Start	Equipment, Methods and Remarks	Depth from (m)	to (m)	Diameter (mm)	Casing Depth (m)	Ground Level	4.53 mOD
Logged WH	11/04/2018	Archway Dart. Dynamic sampling. SPT Hammer ID: DART235, Rod type: quick thread.	1.20	2.00	87		Coordinates (m)	E 516813.22
Checked TC	End		2.00	3.00	77		National Grid	N 417461.78
Approved TC	11/04/2018		3.00	4.00	67			

Samples and Tests Strata Description

Depth	TCR SCR ROD	If	Records/Samples	Date Casing	Time Water	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 1.20	B 1									
0.25	HV		p 120kPa, r N/A			Brown slightly sandy slightly gravelly CLAY with rootlets. Gravel is subangular fine to medium of sandstone. (MADE GROUND)		(1.35)		
0.50	HV		p 120kPa, r N/A							
0.60	D 2									
1.00	HV		p 120kPa, r N/A							
1.20 - 1.65	SPTS		N=12 (1,1/3,3,3,3)			Firm brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and sandstone.		1.35	+3.18	
1.20 - 1.65	D 3							(0.35)		
1.20 - 2.00	L		100% rec, diameter 87mm							
1.35 - 1.70	B 5					Firm brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		1.70	+2.83	
1.35 - 1.70	D 4									
1.50	D 6									
1.70 - 2.00	B 7									
2.00 - 2.45	SPTS		N=18 (3,4/4,4,5,5)			Soft brown CLAY.				
2.00 - 2.45	D 8									
2.00 - 3.00	L		40% rec, diameter 77mm							
2.70	D 9									
2.70 - 3.00	B 10							(2.00)		
3.00 - 3.45	SPTS		N=12 (3,3/3,2,3,4)							
3.00 - 3.45	D 11									
3.00 - 4.00	L		30% rec, diameter 67mm							
3.70	D 12							3.70	+0.83	
4.00 - 4.45	SPTS		N=14 (3,3/3,3,4,4)							
4.00 - 4.45	D 13			11/04/18	1500			(0.75)		
						END OF EXPLORATORY HOLE		4.45	+0.08	

Groundwater Entries			Depth Related Remarks			Chiselling Details			
No.	Depth	Strike	Remarks	Depth Sealed	Depths (m)	Remarks	Depths (m)	Duration (mins)	Tools used
					0.00 - 1.20	Hand excavated inspection pit.			
					0.00 - 4.45	No groundwater encountered during drilling.			

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column.		Project VPI IMMINGHAM		Borehole	
Scale 1:50		Project No. A8015-18		WS8	
© Copyright SOCOTEC UK Limited		Carried out for AECOM			
14/08/2018 13:47:34				Sheet 1 of 1	

Trial Pit Log



Logged WH Checked TC Approved TC	Start 11/04/2018 End 11/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 6.33 mOD Coordinates (m) E 516544.31 National Grid N 417427.12
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Dark brown sandy clayey subangular to subrounded fine to coarse GRAVEL of sandstone, chalk, clinker, macadam and slag with low cobble content. Cobbles are subrounded to subangular of concrete and chalk. (MADE GROUND)		(0.50)		
0.70 0.70 - 0.90	D3 B4		Firm dark greyish brown, mottled black, slightly sandy gravelly CLAY. Gravel is subangular to subrounded of brick, clinker, sandstone, flint and chalk. Strong oil/hydrocarbon odour. (MADE GROUND)		0.50 +5.83 (0.60)		
1.20 1.20 1.20 - 1.50	HV D5 B6	p 120kPa, r N/A	Stiff brown, mottled grey, slightly sandy gravelly CLAY. Gravel is subrounded fine to medium of chalk and sandstone.		1.10 +5.23 (1.40)		
2.00 2.00 2.00 - 2.20	HV D7 B8	p 120kPa, r N/A	Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone.		2.50 +3.83 (1.40)		
3.40 - 3.60 3.50	B10 D9	11/04/18 Dry			3.90 +2.43		
			END OF EXPLORATORY HOLE				

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 3.90 No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP1</h3> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 11/04/2018 End 11/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.70 mOD Coordinates (m) E 516559.56 National Grid N 417394.29
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 - 0.30	B2		Soft dark brown slightly gravelly sandy CLAY with low cobble content and rootlets. Gravel is subangular to subrounded fine to coarse of chalk, flint, sandstone and debris including metal bolts, wood and concrete. Cobbles are subrounded of chalk. (MADE GROUND) Firm dark brown, mottled black, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, sandstone and flint. Strong oil/hydrocarbon odour. (MADE GROUND) Firm brown, mottled light grey, slightly sandy slightly gravelly CLAY with low cobble content. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone and flint. Cobbles are subrounded of chalk.		(0.30)		
0.20	D1						
0.30	D3						
0.30 - 0.50	B4						
1.30	HV	p 120kPa, r N/A		0.60-0.90 firm light brown slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, sandstone and flint	0.30 +5.40		
1.30	D5						
1.30 - 1.50	B6						
2.30 - 2.50	B8				(2.90)		
2.50	D7						
3.10	HV	p 120kPa, r N/A		3.20-3.50 becoming grey with less gravel			
3.40	D9						
3.40 - 3.50	B10		Light brown clayey, locally very clayey, fine to medium SAND.		3.50 +2.20		
4.00	D11						
4.00 - 4.20	B12						
4.40	HV	p 120kPa, r N/A			4.40 +1.30		
4.40	D13						
4.40 - 4.50	B14		Firm dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk.		4.50 +1.20		
			END OF EXPLORATORY HOLE				

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation. 0.00 - 3.50 Material too friable for hand vane testing.	Stability Stable Shoring None Weather Overcast
---	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center;">TP2</div> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.41 mOD Coordinates (m) E 516568.48 National Grid N 417297.43
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2		Soft dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)	0.20-0.40 light brown, mottled orangish brown	(0.20) 0.20 +4.21		
0.50 0.50 - 0.80	HV D3 B4	p 120kPa, r N/A	Firm light brown, mottled grey, slightly sandy gravelly CLAY with low cobble content. Gravel is subrounded fine to medium of predominantly chalk with sandstone and mudstone. Cobbles are subrounded of flint and chalk.		(2.30)		
1.80 1.80 - 2.00	D5 B6						
2.50 2.50 - 2.80	HV D7 B8	p 120kPa, r N/A	Firm brown CLAY.		2.50 +1.91 (0.30)		
			Dark brown slightly clayey fine to coarse SAND.		2.80 +1.61 (0.80)		
3.40 3.40 - 3.60	D9 B10				3.60 +0.81		
4.00 4.00 - 4.20	D11 B12		Soft dark brown very sandy CLAY with occasional gravel size pockets of sand.		(0.90)		
		10/04/18 Dry					
			END OF EXPLORATORY HOLE		4.50 -0.09		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation.	Stability Face A and E collapsed from 2.80m Shoring None Weather Overcast
---	--	--

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center;">TP3</div> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 09/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator Machine excavated pit	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.47 mOD Coordinates (m) E 516556.55 National Grid N 417325.06
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2	09/04/18	Dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)		(0.30)		
			Firm brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of predominantly chalk with sandstone, mudstone and flint.		0.30 +4.17		
0.80 0.80 - 1.00	D3 B4			1.10 land drain	(1.10)		1
1.40 1.40 1.40 - 1.60	HV D5 B6	p 120kPa, r N/A	Firm brown, mottled light grey, CLAY.		1.40 +3.07		
				2.60-3.00 grey mottled brown	(2.00)		
3.00 3.00 - 3.20	D7 B8			3.00-3.40 brown slightly gravelly clayey sand. Gravel is subangular fine to coarse of chalk			
3.40 3.50	B10 D9		Firm brown slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to medium of chalk, flint and sandstone.		3.40 +1.07		
4.00 4.00 - 4.30	D11 B12	10/04/18			(1.10)		
			END OF EXPLORATORY HOLE		4.50 -0.03		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.10 Seepage	Remarks Depth (m) Remarks	Stability Stable Shoring None Weather overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:24	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h2 style="text-align: center;">TP4</h2> Sheet 1 of 1
---	---	---



Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 4.31 mOD Coordinates (m) E 516595.86 National Grid N 417316.85
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2	p 120kPa, r N/A	Soft dark brown slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to subrounded fine to medium of sandstone, chalk and flint. (MADE GROUND)	0.60-0.90 soft light yellowish brown slightly sandy clay	(0.30)		
0.50 0.50 - 0.70	HV D3 B4		Firm brown, mottled grey, gravelly slightly sandy CLAY with low cobble content. Gravel is subrounded fine to medium of chalk, flint and mudstone. Cobbles are subangular of chalk.		1.20 land drain		
1.50 1.50 - 1.70	HV D5 B6	p 120kPa, r N/A	Stiff bluish grey, mottled brown, CLAY.		1.70 +2.61		
2.00 2.00 - 2.20	D7 B8				(0.80)		
2.50 2.50 - 2.70	D9 B10		Light brown slightly clayey to clayey fine to medium SAND. Rare angular fine gravel of mudstone.		2.50 +1.81		
		10/04/18			(0.50)		
			END OF EXPLORATORY HOLE		3.00 +1.31		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.20 Seepage	Remarks Depth (m) Remarks	Stability Faces A and C collapsed Shoring None Weather Overcast
--	--	--

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP5</h3> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.43 mOD Coordinates (m) E 516601.66 National Grid N 417379.51
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Dark brown slightly gravelly clayey SAND with medium cobble content. Gravel is subangular fine to coarse of clinker, chalk and macadam. Cobbles are subrounded of chalk. (MADE GROUND)		(0.30)		
0.40 - 0.60 0.50	B4 D3		Firm dark brown, mottled orangish brown, slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of chalk and flint. (MADE GROUND)		0.30 +5.13 (0.30)		
1.00 1.00 - 1.20	D5 B6		Firm light brown slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of flint, chalk, mudstone and sandstone.	0.60-1.20 brown mottled grey gravelly clay	0.60 +4.83		
1.50	HV	p 120kPa, r N/A		1.20 land drain			
2.00	HV	p 120kPa, r N/A			(3.50)		1 \approx
2.50 2.50 - 3.00	D7 B8						
4.10 4.10 - 4.30	D9 B10		Firm dark brown sandy CLAY with occasional gravel size pockets of sand.		4.10 +1.33 (0.50)		
		10/04/18					
			END OF EXPLORATORY HOLE		4.60 +0.83		

Groundwater Entries <table border="1"> <thead> <tr> <th>No.</th> <th>Depth (m)</th> <th>Strike (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>1.90</td> <td></td> <td>Seepage</td> </tr> </tbody> </table>	No.	Depth (m)	Strike (m)	Remarks	1	1.90		Seepage	Remarks <table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>	Depth (m)	Remarks			Stability Stable Shoring None Weather Overcast
No.	Depth (m)	Strike (m)	Remarks											
1	1.90		Seepage											
Depth (m)	Remarks													

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	TP6 Sheet 1 of 1
---	---	----------------------------

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.29 mOD Coordinates (m) E 516616.25 National Grid N 417423.18
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 - 0.30	B2		Soft brown sandy slightly gravelly CLAY with frequent rootlets. Gravel is subrounded fine to medium of chalk. (TOPSOIL)		(0.30)		
0.20	D1		Soft brown slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to medium of chalk sandstone and flint.		0.30 +4.99		
1.30	HV	p 120kPa, r N/A		1.10 soft orangish brown sandy clay	(2.60)		
1.30	D3			1.10 land drain			
1.30 - 1.60	B4						
3.50	D5		Brown clayey fine to coarse SAND.		2.90 +2.39		
3.50 - 3.80	B6				(0.90)		
4.00	D7	10/04/18	Firm dark greyish brown CLAY.		3.80 +1.49		
4.00 - 4.20	B8				(0.40)		
			END OF EXPLORATORY HOLE		4.20 +1.09		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.10 Seepage	Remarks Depth (m) Remarks	Stability Faces A and C collapsed from 2.90m Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h2 style="text-align: center;">TP7</h2> Sheet 1 of 1
--	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 35 (Deg)	Ground Level 4.60 mOD Coordinates (m) E 516678.60 National Grid N 556494.03
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20 0.20 0.20 0.20 - 0.50	D1 B2 HV D3 B4	p 120kPa, r N/A	Soft dark brown silty CLAY with rootlets. (TOPSOIL)		(0.20) +4.40		
			Light orangish brown slightly sandy gravelly CLAY. Gravel is subrounded fine to coarse of sandstone and chalk. (MADE GROUND)		(0.30) +4.10		
			Firm brown, mottled light grey, slightly sandy gravelly CLAY with low cobble content. Gravel is subrounded to rounded fine to coarse of chalk and sandstone. Cobbles are subrounded of chalk.		(2.50)		
0.80 0.80 0.80 - 1.00	HV D5 B6	p 120kPa, r N/A					
2.00 2.00 - 2.20	D7 B8						
3.10 3.10 - 3.30	D9 B10		Soft light grey, mottled brown, CLAY with rare subrounded fine to medium gravel of chalk.	3.20-3.90 firm dark brown clay	(0.30) +1.60		
			Dark brown clayey fine to medium SAND with occasional gravel size pockets of sandy clay.		(0.60) +1.30		
3.70 - 3.90 3.80	B12 D11						
4.00 4.00 4.00 - 4.50	HV D13 B14	p 100kPa, r N/A	Firm brown slightly sandy silty CLAY.		(0.60) -0.70		
		10/04/18 Dry					
			END OF EXPLORATORY HOLE		4.50 -0.10		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 4.50 No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
---	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center;">TP8</div> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 10/04/2018 End 10/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.71 mOD Coordinates (m) E 516677.98 National Grid N 417410.00
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.20	D1 B2		Soft dark brown slightly gravelly slightly silty CLAY with frequent rootlets. Gravel is angular to subrounded fine to medium of sandstone and flint. (TOPSOIL)		(0.20)		
0.30 0.30 - 0.40	D3 B4		Light yellowish brown very sandy clayey angular to subangular fine to coarse GRAVEL of limestone and sandstone. (MADE GROUND)		0.20 +5.51		
0.80 0.80 - 1.00	D5 B6				(1.40)		
1.60 1.60 1.60 - 1.80	HV D7 B8	p 120kPa, r N/A	Stiff dark orangish brown, mottled dark brown, CLAY with rare subangular fine gravel of flint.		1.60 +4.11		
2.00 2.00 - 2.20	D9 B10		Stiff light brown, mottled grey, slightly gravelly sandy CLAY. Gravel is subangular fine to coarse of chalk.		(0.40) 2.00 +3.71		
3.20 3.20 - 3.40	D11 B12				(2.20)		
		10/04/18					
			END OF EXPLORATORY HOLE		4.20 +1.51		

Groundwater Entries <table border="1"> <thead> <tr> <th>No.</th> <th>Depth (m)</th> <th>Strike (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>0.70</td> <td></td> <td>Seepage</td> </tr> </tbody> </table>	No.	Depth (m)	Strike (m)	Remarks	1	0.70		Seepage	Remarks <table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>	Depth (m)	Remarks			Stability Faces A and C collapsed from 0.20 to 4.20m Shoring None Weather Overcast
No.	Depth (m)	Strike (m)	Remarks											
1	0.70		Seepage											
Depth (m)	Remarks													

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:25	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h2>TP9</h2> Sheet 1 of 1
---	---	--

Trial Pit Log



Logged WH Checked TC Approved TC	Start 06/04/2018 End 06/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 3.00 m 	Ground Level 4.70 mOD Coordinates (m) E 516725.56 National Grid N 417441.68
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 - 0.40	B2		Soft light brown, mottled greyish brown, slightly sandy slightly gravelly CLAY with frequent rootlets. Gravel is subangular to rounded of chalk and mudstone. (TOPSOIL)		(0.40)		
0.30	D1						
0.40	HV	p 120kPa, r N/A	Firm dark greyish brown, mottled dark grey, slightly sandy CLAY with frequent wood and plant material.		0.40 +4.30		
0.40	D3						
0.40 - 0.60	B4				(0.40)		
0.80	HV	p 120kPa, r N/A	Firm light orangish brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded of predominantly chalk with mudstone and flint.		0.80 +3.90		
0.90	D5						
0.90 - 1.20	B6			1.00-1.20 light yellowish brown sand pockets	(2.20)		
2.20	D7						
2.20 - 2.70	B8						
3.00	D9		Firm dark brown CLAY with rare subrounded fine to medium gravel of mudstone.		3.00 +1.70		
3.20 - 3.70	B10				(1.00)		
4.20	D11		Greyish brown slightly gravelly clayey fine to coarse SAND. Gravel is subrounded fine to medium of mudstone.		4.00 +0.70		
4.20 - 4.50	B12	06/04/18			(0.50)		
			END OF EXPLORATORY HOLE		4.50 +0.20		

Groundwater Entries No. Depth Strike (m) Remarks 1 1.00 Seepage	Remarks Depth (m) Remarks	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:48:26	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <h3>TP10</h3> Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 09/04/2018 End 09/04/2018	Equipment, Methods and Remarks Tracked 360 excavator. Machine excavated.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 6.44 mOD Coordinates (m) E 516698.32 National Grid N 417407.31
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.10 0.10 - 0.30	D1 B2		Soft brown slightly sandy slightly gravelly CLAY. Gravel is angular to rounded fine to coarse of chalk, brick, sandstone and concrete. (MADE GROUND)		(0.50)		
0.50 0.50 - 0.70	HV D3 B4	p 120kPa, r N/A	Firm brown, mottled light grey, slightly sandy gravelly CLAY. Gravel is subangular to subrounded fine to coarse of chalk, mudstone, flint and sandstone.	0.50 concrete block wider than trench on Face D	0.50 +5.94		
1.70 1.70	D5 D6			1.40 low cobble content. Cobbles are subrounded of chalk	(1.60)		
2.20 2.20 - 2.30	HV D7 B8	p 100kPa, r N/A	Firm dark greyish brown, mottled dark grey, slightly gravelly slightly sandy to sandy CLAY. Gravel is subrounded fine to coarse of sandstone.		2.10 +4.34 (0.30)		
2.50 2.50 - 2.70	D9 B10		Firm light brown, mottled light grey, locally light orange brown, slightly gravelly CLAY. Gravel is subrounded to rounded fine to coarse of chalk.		2.40 +4.04 (1.00)		
3.40 3.50 - 3.70	D11 B12		Stiff light brown, mottled grey slightly sandy slightly gravelly CLAY. Gravel is subrounded fine to coarse of sandstone and chalk.		3.40 +3.04 (1.10)		
		09/04/18		4.10 locally slightly sandy gravelly clay			
			END OF EXPLORATORY HOLE		4.50 +1.94		

Groundwater Entries <table border="1"> <thead> <tr> <th>No.</th> <th>Depth</th> <th>Strike (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>1.50</td> <td></td> <td>Seepage</td> </tr> </tbody> </table>	No.	Depth	Strike (m)	Remarks	1	1.50		Seepage	Remarks <table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> </tr> </tbody> </table>	Depth (m)	Remarks			Stability Stable Shoring None Weather Overcast
No.	Depth	Strike (m)	Remarks											
1	1.50		Seepage											
Depth (m)	Remarks													

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit TT1 Sheet 1 of 1
---	---	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 06/04/2018 End 06/04/2018	Equipment, Methods and Remarks Wheeled 360 excavator. Machine excavated. Top strata too friable to do hand vane.	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.22 mOD Coordinates (m) E 516764.39 National Grid N 417439.42
---	--	--	---	--

Samples and Tests		Strata Description		
-------------------	--	--------------------	--	--

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.00 - 0.25	B2		Soft light brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded of flint and sandstone. Occasional rootlets. (MADE GROUND)				
0.25	D1						
1.00 1.00 - 1.25	D3 B4						
2.00 2.00 2.00 - 2.15	HV D5 B6	p 70kPa, r N/A			(3.00)		
3.00 3.00 3.00 - 3.20	HV D7 B8	p 120kPa, r N/A	Dark greyish brown, mottled light brown, CLAY with rare angular to subrounded fine to medium gravel of various lithologies including flint and quartzite.		3.00 +2.22 (0.25)		
3.25 3.25 3.25 - 3.50	HV D9 B10	p 120kPa, r N/A 06/04/18	Dry Firm light brown slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to medium of flint and mudstone.		3.25 +1.97 (0.25)		
			END OF EXPLORATORY HOLE		3.50 +1.72		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) 0.00 - 3.50 Remarks No groundwater encountered during excavation.	Stability Stable Shoring None Weather Overcast
--	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:51:53	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit TT2 Sheet 1 of 1
---	--	---

Trial Pit Log



Logged WH Checked TC Approved TC	Start 05/04/2018 End 06/04/2018	Equipment, Methods and Remarks Tracked 360 excavator Machine excavated pit	Dimension and Orientation Width 0.60 m Length 4.00 m 	Ground Level 5.40 mOD Coordinates (m) E 516764.82 National Grid N 417461.85
---	--	---	---	--

Samples and Tests Strata Description

Depth	Type & No.	Records	Main	Detail	Depth, Level (Thickness)	Legend	Backfill
0.30 0.30 - 0.60	D1 B2	05/04/18	Brown, locally light brown, slightly sandy CLAY with low cobble content. Cobbles are subrounded of flint and sandstone.		(1.40)		
1.30 1.30 - 1.60	D3 B4		Dark greyish brown silty CLAY with occasional wood fragments. Slight organic odour.		1.40 +4.00 (0.60)		
2.10 2.10 2.10 - 2.50	HV D5 B6	p 120kPa, r N/A 06/04/18	Firm light brown, mottled light grey, slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of sandstone, chalk and quartzite.		2.00 +3.40 (0.50)		
			END OF EXPLORATORY HOLE		2.50 +2.90		

Groundwater Entries No. Depth Strike (m) Remarks	Remarks Depth (m) Remarks 0.00 - 2.00 Material too friable for hand vane testing. 0.00 - 2.50 No groundwater encountered during excavation.	Stability Stable Shoring None Weather overcast
---	--	---

Notes: For explanation of symbols and abbreviations see Key to Exploratory Hole Records. All depths and reduced levels in metres. Stratum thickness given in brackets in depth column. Scale 1:25 © Copyright SOCOTEC UK Limited 14/08/2018 13:51:54	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Trial Pit <div style="text-align: center; font-size: 24pt; font-weight: bold;">TT3</div> Sheet 1 of 1
---	---	---

APPENDIX C
INSTRUMENTATION AND MONITORING

Installation Details

Table C1



Installation Details

Instrument Reference	Instrument Type (See Notes)	Installation Date, dd/mm/yyyy	Pipe Diameter, mm	Instrument Base, mbgl	Response Zone Range, mbgl	Pipe Top Details	Headworks	Remarks
BH1 (1)	SP	11/04/2018	50	14.80	12.60 to 15.00	Gas tap	Raised cover	
BH2 (1)	SP	16/04/2018	50	15.10	14.00 to 15.20	Gas tap	Flush cover	
BH3 (1)	SP	18/04/2018	50	28.60	26.60 to 28.60	Gas tap	Flush cover	
BH4 (1)	SP	20/04/2018	50	34.60	28.60 to 34.60	Gas tap	Flush cover	
BH5 (1)	SP	19/04/2018	50	18.50	17.50 to 18.50	Gas tap	Flush cover	
BH6 (1)	SP	16/04/2018	50	34.50	25.50 to 34.50	Gas tap	Raised cover	
WS1 (1)	SP	06/04/2018	50	1.40	1.00 to 1.40	Gas tap	Raised covers	
WS2 (1)	SP	10/04/2018	50	1.20	0.70 to 1.20	Gas tap	Raised cover	
WS3 (1)	SP	10/04/2018	50	3.50	2.50 to 3.50	Gas tap	Raised cover	
WS4 (1)	SP	06/04/2018	50	2.30	1.30 to 2.30	Gas tap	Raised cover	
WS5 (1)	SP	10/04/2018	50	4.30	3.30 to 4.30	Gas tap	Raised cover	
WS6 (1)	SP	11/04/2018	50	3.70	3.10 to 3.70	Gas tap	Raised cover	
WS7 (1)	SP	11/04/2018	50	3.60	3.10 to 3.60	Gas tap	Raised cover	
WS8 (1)	SP	11/04/2018	50	4.10	3.60 to 4.10	Gas tap	Raised cover	

Notes: Type: SP - Standpipe, SPIE - Standpipe Piezometer, HPIE - Hydraulic Piezometer, PPIE - Pneumatic Piezometer, EPIE - Vibrating Wire Piezometer, PWEL - Pumping Well



Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Table

C1

APPENDIX D
GEOTECHNICAL LABORATORY TEST RESULTS

Index Properties – Summary of Results	INDX 1 to 3
Particle Size Distribution Analyses	PSD 1 to 24
Unconsolidated Undrained Triaxial Compression Tests – Summary of Results	UUSUM
Consolidated Undrained Triaxial Compression Tests with Measurement of Pore Water Pressure	CUM 1 to 6 (3 sheets per test)
One Dimensional Consolidation Test	OED 1 to 8
Determination of Consolidation Properties Using a Hydraulic Cell	HC 1 and 3 (2 sheets per test)
Dry Density / Moisture Content Relationship (Light)	COMPL 1 to 7
Dry Density / Moisture Content Relationship (Heavy)	COMPH 1 to 9
California Bearing Ratio	CBR 1 to 11
Chemical Tests	EFS/187041 EFS/187043 EFS/187204 EFS/187902

INDEX PROPERTIES - SUMMARY OF RESULTS

Hole No.	Sample			Soil Description	ρ	ρ_d	W	< 425 μ m sieve	W _L	W _P	I _p	ρ_s	Remarks	
	No.	Depth (m)												type
		from	to											
					Mg/m ³	%	%	%	%		Mg/m ³			
BH1	4	0.50	0.70	B	Greyish brown slightly sandy slightly gravelly silty CLAY.		27	91	54 a	26	28			
BH1	8	2.00	2.45	D	Brown slightly sandy slightly gravelly CLAY.		14	92	43 a	19	24			
BH1	9	2.50	3.00	B	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.							2.71-p		
BH1	17	6.50	6.95	D	Brown slightly sandy slightly gravelly CLAY.		13	82	33 a	15	18			
BH1	22	9.50	9.95	D	Brown slightly sandy slightly gravelly CLAY.		14	88	29 a	15	14			
BH1	27	13.00	13.50	B	Brown slightly gravelly sandy silty CLAY.							2.68-p		
BH1	35	17.00	17.45	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is mainly chalk.							2.72-p		
BH1	36	17.45	17.60	D	Dark grey sandy gravelly CLAY.		13	82	30 a	15	15			
BH1	40	20.40	20.50	D	Grey slightly sandy gravelly CLAY.		22							
BH1	43	22.50	22.70	D	Grey slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.		13							
BH1	46	25.00	25.22	D	Grey slightly gravelly sandy CLAY. Gravel is chalk fragments.		13	89	27 a	15	12			
BH2	2	0.30	0.50	B	Brown slightly sandy gravelly CLAY.		20	56	44 a	22	22			
BH2	5	1.00		D	Brown slightly sandy slightly gravelly CLAY.		22							
BH2	8	1.65	1.80	D	Brown slightly sandy slightly gravelly CLAY.		24	91	42 a	19	23			
BH2	15	3.30	3.75	UT	Firm laminated brown slightly sandy CLAY.		23	100	47 a	22	25			
BH2	28	5.10	5.55	UT	Firm dark brown slightly sandy slightly gravelly CLAY.		16	83	32 a	17	15	2.70-p		
BH2	34	7.10	7.55	D	Brown slightly sandy slightly gravelly CLAY.		18	88	33 a	14	19			
BH2	40	9.50	9.95	UT	Firm brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk fragments.		14	87	32 a	13	19			
BH2	51	13.10	13.55	B	Brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk.		16	89	31 a	15	16			
BH2	63	18.50	19.00	B	Greenish grey slightly sandy SILT.		22	100	23 a	NP				
BH3	3	1.65	2.00	B	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		28	95	37 a	21	16	2.71-p		
BH3	8	4.00	4.45	D	Brown slightly gravelly very sandy silty CLAY.		21							
BH3	12	5.65	6.00	B	Brown slightly sandy slightly gravelly CLAY.		18	85	32 a	15	17	2.70-p		
BH3	19	9.00	9.45	UT	Firm greyish brown slightly sandy slightly gravelly silty CLAY. Gravel contains chalk fragments.		17							
BH3	27	12.00	12.45	UT	Firm brown slightly sandy slightly gravelly CLAY.		17							
BH3	32	13.50	13.95	D	Light brown silty SAND.		25							
BH3	45	23.00	24.00	B	Greenish grey CLAY with chalk fragments.		15							
BH4	1	0.50	1.20	B	Brown slightly sandy slightly gravelly CLAY.		24	95	43 a	21	22			
BH4	7	3.10	3.55	UT	Brown slightly sandy SILT.		21							
BH4	10	4.50	4.95	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY.							2.70-p		
BH4	14	6.00	6.45	UT	Firm brown slightly sandy slightly gravelly CLAY.		14	89	33 a	14	19			

General notes:

All above tests carried out to BS1377 : 1990 unless annotated otherwise. See Remarks for further details

Key : ρ bulk density, linear

W_L Liquid limit

W_P Plastic limit

<425 μ m preparation

ρ_s particle density

ρ_d dry density

a 4 point cone test

NP non - plastic

n from natural soil

-g = gas jar

w moisture content

b 1 point cone test

IP Plasticity Index

s sieved specimen

-p = small pyknometer

* test carried out to BS EN ISO 17892-1 2014

QA Ref
SLR 1
Rev 2.91
Mar 17



Project No A8015-18
Project Name VPI IMMINGHAM

Figure
INDX

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed: 31/07/2018 12:05

INDEX PROPERTIES - SUMMARY OF RESULTS

Hole No.	Sample			Soil Description	ρ	ρ_d	W	< 425 μ m sieve	W _L	W _P	I _p	ρ_s	Remarks	
	No.	Depth (m)												type
		from	to											
					Mg/m ³	%	%	%	%	%	Mg/m ³			
BH4	22	9.00	9.45	UT	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.		15	89	32 a	15	17			
BH4	27	11.15	11.60	D	Brown slightly sandy slightly gravelly CLAY.		12							
BH4	34	15.50	16.00	B	Light brown gravelly SAND.		8.6							
BH4	42	22.00	22.50	B	Grey slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.		17							
BH5	3	0.50		D	Brown slightly sandy slightly gravelly CLAY.		16	96	39 a	19	20			
BH5	11	2.30	2.75	UT	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.		16					2.71-p		
BH5	20	4.50	4.95	UT	Firm laminated brown slightly gravelly sandy CLAY.		17	88	27 a	16	11			
BH5	27	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.		16	82	30 a	14	16			
BH5	35	11.00	11.45	UT	Firm brown slightly sandy slightly gravelly CLAY.		16							
BH5	42	13.00		D	Soft brown slightly gravelly, slightly sandy CLAY.		15							
BH5	51	17.00	17.36	D	Light grey sandy gravelly CLAY.		1.7							
BH5	58	20.00	20.28	B	Greenish grey CLAY with chalk fragments.		4.9							
BH6	1	0.00	0.30	B	Brown very sandy clayey GRAVEL.		20							
BH6	6	2.00	2.45	UT	Very stiff brown mottled grey slightly sandy slightly gravelly CLAY. Gravel contains chalk.							2.71-p		
BH6	9	3.50	4.00	B	Brown slightly silty CLAY.		27							
BH6	14	6.00	6.45	UT	Firm to stiff greyish brown slightly gravelly sandy CLAY. Gravel contains chalk.		15	90	29 a	18	11			
BH6	21	10.00	10.50	B			17							
BH6	25	13.00	13.50	B	Brown slightly sandy slightly gravelly CLAY.		16					2.65-g		
BH6	28	15.00	15.45	D	Light brown sandy gravelly CLAY.		16							
BH6	35	19.50	21.00	B	Greyish brown gravelly CLAY. Gravel is chalk fragments.		17							
TP1	4	0.70	0.90	B	Brown slightly sandy CLAY with occasional chalk fragments.		26							
TP1	8	2.00	2.20	B	Brown slightly sandy slightly gravelly CLAY.		20	96	47 a	19	28	2.69-p		
TP10	8	2.20	2.70	B	Brown slightly sandy slightly gravelly CLAY.		22	95	41 a	19	22			
TP10	12	4.20	4.50	B	Brown SAND.		21							
TP2	1	0.20		D	Dark brown slightly sandy slightly gravelly CLAY.		25							
TP2	8	2.30	2.50	B	Brown slightly sandy slightly gravelly CLAY.		11	94	45 a	19	26			
TP2	12	4.00	4.20	B	Brown slightly gravelly silty SAND.		25					2.72-p		
TP2	13	4.40		D	Brownish grey slightly gravelly sandy CLAY.		16	88	32 a	17	15			
TP3	10	3.40	3.60	B	Light brown SAND.		25					2.69-p		
TP3	12	4.00	4.20	B	Brown very clayey SAND with chalk fragments.		21	92	23 a	14	9			
TP4	4	0.80	1.00	B	Brown slightly sandy CLAY with chalk fragments.		17	94	42 a	17	25			

General notes:

All above tests carried out to BS1377 : 1990 unless annotated otherwise. See Remarks for further details

Key : ρ bulk density, linear

W_L Liquid limit

W_P Plastic limit

<425 μ m preparation

ρ_s particle density

ρ_d dry density

a 4 point cone test

NP non - plastic

n from natural soil

-g = gas jar

w moisture content

b 1 point cone test

IP Plasticity Index

s sieved specimen

-p = small pyknometer

* test carried out to BS EN ISO 17892-1 2014

QA Ref
SLR 1
Rev 2.91
Mar 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
INDX

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed: 31/07/2018 12:05

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104548	Sample Depth (m BGL)	0.50 - 0.70
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	70
90	100	0.0453	68
75	100	0.0323	66
63	100	0.0231	63
50	100	0.0166	59
37.5	100	0.0089	51
28	100	0.0040	38
20	100	0.0035	34
14	100	0.0015	21
10	100		
6.3	99		
5.0	98		
3.35	97		
2.00	96		
1.18	95		
0.600	93		
0.425	91		
0.300	89		
0.212	85		
0.150	79		
0.063	70		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	12.2	

Soil description	Greyish brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		26	26
		45	45
*<60mm values to aid description only		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104626	Sample Depth (m BGL)	2.50 - 3.00
		Sample Type and No	B9
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	82
90	100	0.0446	80
75	100	0.0318	78
63	100	0.0227	75
50	100	0.0162	72
37.5	100	0.0086	62
28	100	0.0037	47
20	100	0.0032	44
14	100	0.0015	31
10	100		
6.3	100		
5.0	99		
3.35	99		
2.00	98		
1.18	97		
0.600	96		
0.425	95		
0.300	94		
0.212	92		
0.150	89		
0.063	82		

Particle density, Mg/m3	2.71	measured
Dry mass of sample, kg	11.1	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		2	2
		16	16
		45	45
*<60mm values to aid description only		36	36

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104655	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	B13
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	75
90	100	0.0463	70
75	100	0.0331	67
63	100	0.0236	65
50	100	0.0168	61
37.5	100	0.0089	54
28	100	0.0041	42
20	100	0.0035	39
14	100	0.0015	29
10	100		
6.3	98		
5.0	98		
3.35	97		
2.00	95		
1.18	94		
0.600	93		
0.425	92		
0.300	90		
0.212	87		
0.150	81		
0.063	75		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	13.1	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		5	5
		21	21
		42	42
*<60mm values to aid description only		33	33

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409105002	Sample Depth (m BGL)	13.00 - 13.50
		Sample Type and No	B27
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	38
90	100	0.0453	35
75	100	0.0328	31
63	100	0.0237	29
50	100	0.0171	26
37.5	100	0.0092	20
28	100	0.0052	17
20	100	0.0038	15
14	99	0.0008	10
10	97		
6.3	96		
5.0	95		
3.35	94		
2.00	92		
1.18	91		
0.600	89		
0.425	87		
0.300	81		
0.212	70		
0.150	54		
0.063	38		

Particle density, Mg/m3	2.68	assumed
Dry mass of sample, kg	8.5	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		8	8
		55	55
		25	25
*<60mm values to aid description only		13	13

Uniformity Coefficient	D60 / D10	196
------------------------	-----------	-----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011418	Sample Depth (m BGL)	0.60 - 1.00
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	44
90	100	0.0484	42
75	100	0.0346	40
63	100	0.0248	36
50	100	0.0178	33
37.5	99	0.0095	23
28	95	0.0053	16
20	93	0.0039	13
14	84	0.0009	1
10	82		
6.3	80		
5.0	79		
3.35	77		
2.00	75		
1.18	73		
0.600	70		
0.425	69		
0.300	66		
0.212	60		
0.150	54		
0.063	44		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
5.1	

Soil description	Dark brown slightly sandy slightly gravelly clayey SILT.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		25	25
		31	31
		37	37
*<60mm values to aid description only		7	7

Uniformity Coefficient	D60 / D10	73
------------------------	-----------	----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011538	Sample Depth (m BGL)	2.70 - 2.80
		Sample Type and No	D12
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	74
90	100	0.0466	71
75	100	0.0333	68
63	100	0.0238	64
50	100	0.0170	62
37.5	100	0.0090	54
28	100	0.0046	44
20	100	0.0038	39
14	100	0.0015	27
10	99		
6.3	96		
5.0	95		
3.35	94		
2.00	93		
1.18	91		
0.600	89		
0.425	88		
0.300	86		
0.212	83		
0.150	77		
0.063	74		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
0.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		19	19
		43	43
*<60mm values to aid description only		30	30

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012751	Sample Depth (m BGL)	9.50 - 9.95
		Sample Type and No	UT40
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	60
90	100	0.0473	58
75	100	0.0338	55
63	100	0.0241	53
50	100	0.0172	49
37.5	99	0.0091	44
28	99	0.0050	36
20	99	0.0037	32
14	99	0.0008	19
10	98		
6.3	97		
5.0	96		
3.35	94		
2.00	93		
1.18	91		
0.600	89		
0.425	87		
0.300	84		
0.212	80		
0.150	73		
0.063	60		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
7.2	

Soil description	Firm brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		32	32
		34	34
*<60mm values to aid description only		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012921	Sample Depth (m BGL)	13.10 - 13.55
		Sample Type and No	B51
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	62
90	100	0.0474	57
75	100	0.0339	54
63	100	0.0242	52
50	100	0.0172	49
37.5	100	0.0091	42
28	100	0.0040	32
20	99	0.0034	30
14	99	0.0015	22
10	99		
6.3	97		
5.0	96		
3.35	95		
2.00	93		
1.18	92		
0.600	90		
0.425	89		
0.300	86		
0.212	81		
0.150	72		
0.063	62		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
15.8	

Soil description	Brown slightly sandy slightly gravelly silty CLAY. Gravel is chalk.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		7	7
		32	32
		37	37
		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102616	Sample Depth (m BGL)	1.65 - 2.00
		Sample Type and No	B3
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	83
90	100	0.0439	79
75	100	0.0313	77
63	100	0.0223	75
50	100	0.0160	71
37.5	100	0.0085	62
28	100	0.0037	48
20	100	0.0032	45
14	100	0.0014	33
10	100		
6.3	99		
5.0	99		
3.35	98		
2.00	97		
1.18	97		
0.600	95		
0.425	95		
0.300	93		
0.212	91		
0.150	89		
0.063	83		

Particle density, Mg/m ³	
2.71	measured
Dry mass of sample, kg	
6.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		14	14
		45	45
		38	38

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102638	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	D8
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	28
90	100	0.0537	26
75	100	0.0382	23
63	100	0.0271	21
50	100	0.0193	18
37.5	100	0.0100	16
28	100	0.0050	13
20	100	0.0041	12
14	100	0.0016	8
10	98		
6.3	98		
5.0	98		
3.35	98		
2.00	98		
1.18	98		
0.600	97		
0.425	91		
0.300	59		
0.212	48		
0.150	35		
0.063	28		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
0.4	

Soil description	Brown slightly gravelly very sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		2	2
		70	70
		19	19
*<60mm values to aid description only		9	9

Uniformity Coefficient	D60 / D10	120
------------------------	-----------	-----

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102754	Sample Depth (m BGL)	9.00 - 9.45
		Sample Type and No	UT19
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	59
90	100	0.0476	57
75	100	0.0340	55
63	100	0.0242	52
50	100	0.0173	50
37.5	100	0.0091	43
28	97	0.0040	33
20	95	0.0035	31
14	95	0.0015	22
10	94		
6.3	92		
5.0	92		
3.35	91		
2.00	89		
1.18	88		
0.600	86		
0.425	85		
0.300	82		
0.212	77		
0.150	69		
0.063	59		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	4.7	

Soil description	Firm greyish brown slightly sandy slightly gravelly silty CLAY. Gravel contains chalk fragments.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		11	11
		30	30
		34	34
*<60mm values to aid description only		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102944	Sample Depth (m BGL)	13.50 - 13.95
		Sample Type and No	D32
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	100		
2.00	100		
1.18	100		
0.600	98		
0.425	85		
0.300	49		
0.212	27		
0.150	16		
0.063	13		

Dry mass of sample, kg	
0.4	

Soil description	Light brown silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	87	87
	Silt	silt+clay =	
	Clay	13	13

Uniformity Coefficient	D60 / D10	Not applicable
-------------------------------	------------------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115116	Sample Depth (m BGL)	5.50 - 6.00
		Sample Type and No	B13
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0472	59
75	100	0.0338	56
63	100	0.0241	54
50	100	0.0172	50
37.5	100	0.0091	43
28	100	0.0039	34
20	100	0.0034	31
14	100	0.0015	25
10	99		
6.3	97		
5.0	97		
3.35	96		
2.00	94		
1.18	92		
0.600	89		
0.425	87		
0.300	84		
0.212	79		
0.150	73		
0.063	61		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
7.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		6	6
		32	32
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120720	Sample Depth (m BGL)	7.10 - 7.55
		Sample Type and No	B26
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0476	58
75	100	0.0340	56
63	100	0.0242	54
50	100	0.0174	50
37.5	100	0.0091	44
28	100	0.0041	34
20	100	0.0035	32
14	100	0.0015	24
10	100		
6.3	98		
5.0	97		
3.35	96		
2.00	94		
1.18	92		
0.600	89		
0.425	87		
0.300	84		
0.212	79		
0.150	72		
0.063	61		

Particle density, Mg/m3		14.1
2.65 assumed		
Dry mass of sample, kg		

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		6	6
		33	33
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092440	Sample Depth (m BGL)	0.00 - 0.30
		Sample Type and No	B1
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	93		
28	87		
20	79		
14	74		
10	68		
6.3	57		
5.0	52		
3.35	46		
2.00	39		
1.18	33		
0.600	28		
0.425	25		
0.300	22		
0.212	19		
0.150	15		
0.063	11		

Dry mass of sample, kg	
6.4	

Soil description	Brown very sandy clayey GRAVEL.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	61	61
	Silt	28	28
	Clay	11	11

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP2
	A8015-18-20180413090532	Sample Depth (m BGL)	4.00 - 4.20
		Sample Type and No	B12
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	99		
2.00	99		
1.18	99		
0.600	98		
0.425	97		
0.300	87		
0.212	55		
0.150	22		
0.063	6		
		Dry mass of sample, kg	
		11.1	

Soil description	Brown slightly gravelly silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		1	1
		93	93
		silt+clay =	
6	6		

Uniformity Coefficient	D60 / D10	3
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP5
	A8015-18-20180410090059	Sample Depth (m BGL)	2.50 - 2.70
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	100		
2.00	100		
1.18	99		
0.600	99		
0.425	99		
0.300	85		
0.212	42		
0.150	14		
0.063	7		

Dry mass of sample, kg	
13.5	

Soil description	Brown silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	92	92
	Silt	silt+clay =	
	Clay	7	7

Uniformity Coefficient	D60 / D10	3
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074235	Sample Depth (m BGL)	0.20 - 0.50
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	73
90	100	0.0459	70
75	100	0.0329	66
63	100	0.0236	63
50	100	0.0170	57
37.5	100	0.0090	49
28	100	0.0052	42
20	100	0.0038	38
14	100	0.0008	26
10	100		
6.3	99		
5.0	99		
3.35	98		
2.00	97		
1.18	97		
0.600	95		
0.425	94		
0.300	92		
0.212	89		
0.150	81		
0.063	73		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
10.6	

Soil description	Brown slightly sandy slightly gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		24	24
		39	39
*<60mm values to aid description only		33	33

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074504	Sample Depth (m BGL)	3.8
		Sample Type and No	D11
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5.0	100		
3.35	99		
2.00	98		
1.18	97		
0.600	94		
0.425	93		
0.300	58		
0.212	49		
0.150	16		
0.063	8		

Dry mass of sample, kg	
1.1	

Soil description	Brown slightly gravelly silty SAND.		
Preparation / Pretreatment	Sieve: natural material		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders	Whole	*<60mm
	Gravel	0	0
	Sand	2	2
	Silt	90	90
	Clay	silt+clay =	
		8	8

Uniformity Coefficient	D60 / D10	4
------------------------	-----------	---

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	none

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091457	Sample Depth (m BGL)	0.3
		Sample Type and No	D3
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	18
90	100	0.0457	18
75	100	0.0327	17
63	100	0.0234	16
50	100	0.0169	15
37.5	100	0.0090	12
28	90	0.0045	10
20	85	0.0037	9
14	75	0.0015	6
10	69		
6.3	61		
5.0	58		
3.35	52		
2.00	46		
1.18	40		
0.600	33	Particle density, Mg/m3	
0.425	31	2.65	assumed
0.300	28	Dry mass of sample, kg	
0.212	26		
0.150	24		
0.063	18	1.1	

Soil description	Brown slightly sandy gravelly silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<math><60\text{mm}</math> values to aid description only</small>	Cobbles / boulders	Whole	*<math><60\text{mm}</math>
		0	0
	Gravel	54	54
		28	28
	Silt	11	11
Clay	7	7	

Uniformity Coefficient	D60 / D10	1347
------------------------	-----------	------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Figure
PSD

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091609	Sample Depth (m BGL)	2.00 - 2.20
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	59
90	100	0.0471	57
75	100	0.0338	54
63	100	0.0241	52
50	100	0.0172	49
37.5	100	0.0091	43
28	100	0.0044	37
20	100	0.0037	35
14	100	0.0015	28
10	99		
6.3	98		
5.0	98		
3.35	97		
2.00	96		
1.18	95		
0.600	93		
0.425	92		
0.300	80		
0.212	74		
0.150	64		
0.063	59		
		Particle density, Mg/m3 2.65 assumed	
		Dry mass of sample, kg 10.4	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		37	37
		29	29
		30	30

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT1
	A8015-18-20180413014845	Sample Depth (m BGL)	2.20 - 2.30
		Sample Type and No	B8
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	61
90	100	0.0476	58
75	100	0.0341	54
63	100	0.0244	51
50	100	0.0174	48
37.5	100	0.0092	40
28	100	0.0049	35
20	100	0.0037	31
14	98	0.0008	21
10	98		
6.3	98		
5.0	98		
3.35	97		
2.00	97		
1.18	96		
0.600	94		
0.425	93		
0.300	90		
0.212	85		
0.150	76		
0.063	61		
		Particle density, Mg/m3 2.65 assumed	
		Dry mass of sample, kg 11.2	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions <small>*<60mm values to aid description only</small>	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		3	3
		35	35
		34	34
		27	27

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited


Figure

PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT2
	A8015-18-20180408083410	Sample Depth (m BGL)	1.00 - 1.25
		Sample Type and No	B4
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	65
90	100	0.0473	63
75	100	0.0337	60
63	100	0.0241	57
50	100	0.0172	53
37.5	100	0.0091	47
28	100	0.0046	41
20	100	0.0038	38
14	100	0.0015	29
10	100		
6.3	100		
5.0	99		
3.35	98		
2.00	96		
1.18	95		
0.600	94		
0.425	92		
0.300	90		
0.212	85		
0.150	77		
0.063	65		

Particle density, Mg/m3	2.65	assumed
Dry mass of sample, kg	13.9	

Soil description	Brown slightly sandy slightly gravelly silty CLAY with rootlets.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		4	4
		32	32
		33	33
*<60mm values to aid description only		32	32

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD

Printed: 05/07/2018 11:36

Particle Size Distribution Analysis

Sample Details:	SAMPLE ID:	Hole No	TT2
	A8015-18-20180408083738	Sample Depth (m BGL)	3.25 - 3.50
		Sample Type and No	B10
		Specimen Ref	



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.0630	46
90	100	0.0474	44
75	100	0.0338	43
63	100	0.0242	40
50	100	0.0173	37
37.5	100	0.0091	33
28	100	0.0043	29
20	100	0.0036	28
14	98	0.0015	24
10	98		
6.3	96		
5.0	95		
3.35	94		
2.00	92		
1.18	91		
0.600	89		
0.425	87		
0.300	68		
0.212	62		
0.150	51		
0.063	46		

Particle density, Mg/m3	
2.65	assumed
Dry mass of sample, kg	
14.0	

Soil description	Brown slightly gravelly sandy silty CLAY.		
Preparation / Pretreatment	Sieve: natural material Hydro: as BS1377		
Remarks			
Sample Proportions	Cobbles / boulders Gravel Sand Silt Clay	Whole	*<60mm
		0	0
		8	8
		46	46
		21	21
*<60mm values to aid description only		25	25

Uniformity Coefficient	D60 / D10	Not applicable
------------------------	-----------	----------------

Test Method	BS 1377 : Part 2 : 1990	
	Sieving	9.2 wet sieve
	Sedimentation	9.5 hydrometer

QA Ref
SLR 2,9
Rev 2.10
Oct 16



1157



SOCOTEC

Project No A8015-18
Project Name VPI IMMINGHAM

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation © Copyright 2016 SOCOTEC UK Limited

Figure
PSD



Printed: 05/07/2018 11:36

UNCONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TESTS WITHOUT MEASUREMENT OF PORE PRESSURE - SUMMARY OF RESULTS

Hole No.	Sample				Soil Description	Density		w	Test type	Dia.	ø3	At failure / end of stage				Membrane Thickness	Remarks				
	No.	Depth (m)		type		bulk	dry					Mg/m3	%	mm	kPa			Axial strain	ø1 - ø3	CU	M O D E
		from	to																		
BH1	15	5.00	5.45	UT	Stiff greyish brown slightly sandy slightly gravelly CLAY.	2.21	1.93	15	UUM	99.4 99.4 99.4	100 200 400	11.4 13.4 18.8	203 216 229	101 108 114	P	0.4					
BH1	20	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY.	2.21	1.92	15	UUM	102.6 102.6 102.6	160 320 640	7.9 10.4 19.8	110 127 163	55 64 82	P	0.4					
BH1	35	17.00	17.45	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is mainly chalk.	2.23	1.96	14	UUM	103.8	250	19.9	506	253	P	0.4	Sample reached 20% axial strain during 1st stage.				
BH1	39	20.00	20.40	UT	Very stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel is chalk.	2.2	1.92	14	UUM UUM	103.6 103.6	250 500	18.4 19.9	524 535	262 268	P	0.4	Sample reached 20% axial strain during 2nd stage.				
BH2	7	1.20	1.65	UT	Firm stiff brown slightly sandy slightly gravelly CLAY	2.05	1.71	20	UUM	103.9 103.9 103.9	25 50 100	7.9 9.8 19.1	166 180 213	83 90 106	P	0.4					
BH2	28	5.10	5.55	UT	Firm dark brown slightly sandy slightly gravelly CLAY.	2.16	1.86	16	UUM	102.7 102.7 102.7	100 200 400	2.5 4.5 19.8	33 43 66	17 22 33	P	0.4					
BH2	44	11.00	11.45	UT	Stiff greyish brown slightly sandy slightly gravelly CLAY.	2.2	1.91	15	UUM	102.8 102.8 102.8	220 440 880	10.9 12.9 19.9	217 225 254	109 113 127	P	0.4					
BH3	19	9.00	9.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.	2.12	1.81	17	UUMR	102.9 102.9 102.9	180 360 720	5.0 6.9 19.8	81 89 113	41 45 56	P	0.4					
BH4	10	4.50	4.95	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY.	2.19	1.91	14	UUM	102.6 102.6 102.6	90 180 360	10.4 12.3 19.7	220 229 246	110 114 123	P	0.4					
BH4	22	9.00	9.45	UT	Firm to stiff dark brown slightly sandy slightly gravelly CLAY. Gravel contains chalk fragments.	2.16	1.87	15	UUM	95.9 95.9 95.9	180 360 720	5.4 6.9 19.7	100 108 148	50 54 74	P	0.4					
BH5	11	2.30	2.75	UT	Very stiff brown slightly sandy slightly gravelly CLAY. Gravel is chalk fragments.	2.14	1.84	16	UUM	102.5 102.5 102.5	45 90 180	16.3 18.8 19.8	537 541 542	268 270 271	P	0.4					
BH5	27	8.00	8.45	UT	Firm greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.19	1.89	16	UUM	101.9 101.9 101.9	160 320 640	4.0 5.9 18.8	69 83 115	35 41 58	P	0.4					
BH6	6	2.00	2.45	UT	Very stiff brown mottled grey slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.13	1.82	17	UUM	102.7 102.7 102.7	40 80 160	10.9 12.4 19.8	446 452 480	223 226 240	P	0.4					
BH6	14	6.00	6.45	UT	Firm to stiff greyish brown slightly sandy slightly gravelly CLAY. Gravel contains chalk.	2.2	1.91	15	UUM	102.5 102.5 102.5	120 240 480	4.0 6.4 19.3	109 134 174	54 67 87	P	0.4					

General notes: Tests carried out in accordance with BS1377: Part 7: 1990, clause 8 for single stage, clause 9 for multistage tests. Specimens nominally 2:1 height diameter ratio and tested at a rate of strain of 2%/minute, unless annotated otherwise. Latex rubber membrane used and membrane correction applied in accordance with BS1377-7 8.5.1.4 unless stated.

Legend
 UU - single stage test (may be in sets of specimens) ø3 cell pressure Mode of failure P plastic
 UUM - multistage test on a single specimen ø1 - ø3 deviator stress B brittle
 suffix R - remoulded or recompacted CU undrained shear strength C compound

QA Ref SLR 2 Rev 2.7 Apr 15	 1157		Project No A8015-18	Figure UUSUM
			Project Name VPI IMMINGHAM	
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 05/07/2018 11:44	


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH1		
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65		
			No	6	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.24
Diameter	mm	103.57
Bulk Density	Mg/m ³	2.10
Water Content	%	19
Dry density	Mg/m ³	1.76
After test		
Bulk Density	Mg/m ³	2.08
Water Content	%	20
Dry density	Mg/m ³	1.73

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	293.8
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	312	325	350	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	12	25	50	kPa	
	Pore pressure at start of consolidation	303	308	324	kPa	
	Pore pressure at end of consolidation	301	300	300	kPa	
	Pore pressure dissipation at end of consolidation	70	95	100	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.12	1.17	1.08	m ² /year
	Coefficient of Compressibility	M _{vi}	0.67	0.48	0.32	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	4.4E-10	1.7E-10	1.1E-10	m/s



Ref
SLR8.1
Rev 86.0
Feb18



1157

Printed:20/07/2018 10:42

Figure

CUM


sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**


Project No	A8015-18	Sample Details:	Hole No	BH1		
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65		
			No	6	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18






Printed:20/07/2018 10:42

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH1		
Project Name	IMMINGHAM		Depth (m BGL)	1.20 - 1.65		
			No	6	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	312	325	350	kPa
Initial pwp	299	300	301	kPa
Initial σ_3'	14	25	49	kPa
Rate of strain	1.51	1.51	1.51	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.54	2.47	4.60	%
$(\sigma_1' / \sigma_3')_f$	6.616	5.321	4.046	
$(\sigma_1' - \sigma_3')_f$	52.8	73.0	111.8	kPa
u_f	303	308	313	kPa
$\sigma_3'_f$	9	17	37	kPa
$\sigma_1'_f$	62	90	148	kPa
A_f	0.08	0.11	0.11	
Time to failure	1.0	1.6	3.0	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	9.8
ϕ'	degrees	31.0
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.594 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:42

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2		
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75		
			No	15	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	202.89
Diameter	mm	103.07
Bulk Density	Mg/m ³	2.03
Water Content	%	25
Dry density	Mg/m ³	1.63
After test		
Bulk Density	Mg/m ³	2.04
Water Content	%	24
Dry density	Mg/m ³	1.64

Soil Description	Firm brown laminated slightly sandy CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	300
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	355	410	520	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	55	110	220	kPa	
	Pore pressure at start of consolidation	348	365	419	kPa	
	Pore pressure at end of consolidation	301	301	302	kPa	
	Pore pressure dissipation at end of consolidation	97	99	98	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	0.97	0.94	0.93	m ² /year
	Coefficient of Compressibility	M _{vi}	0.36	0.18	0.12	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.1E-10	5.1E-11	3.3E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2		
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75		
			No	15	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18






Printed:20/07/2018 10:43

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH2	
Project Name	IMMINGHAM		Depth (m BGL)	3.30 - 3.75	
		No	15	Type	UT
		ID			
		Spec Ref			



Compression stages

Stage	1	2	3	
Cell pressure	355	410	520	kPa
Initial pwp	301	301	302	kPa
Initial σ_3'	54	109	218	kPa
Rate of strain	0.71	0.71	0.71	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.76	3.70	6.40	%
$(\sigma_1' / \sigma_3')_f$	2.839	3.051	2.751	
$(\sigma_1' - \sigma_3')_f$	60.3	150.5	267.7	kPa
u_f	322	337	367	kPa
$\sigma_3'_f$	33	73	153	kPa
$\sigma_1'_f$	93	224	421	kPa
A_f	0.35	0.24	0.24	
Time to failure	2.5	5.2	9.0	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	3.8
ϕ'	degrees	27.4
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.594 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.48
Diameter	mm	102.37
Bulk Density	Mg/m ³	2.19
Water Content	%	20
Dry density	Mg/m ³	1.82
After test		
Bulk Density	Mg/m ³	2.26
Water Content	%	16
Dry density	Mg/m ³	1.94

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	260
Final pore water pressure	kPa	237.3
Final B Value		0.99



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	335	370	440	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	35	70	140	kPa	
	Pore pressure at start of consolidation	314	327	383	kPa	
	Pore pressure at end of consolidation	300	300	302	kPa	
	Pore pressure dissipation at end of consolidation	100	100	98	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	1.30	0.95	0.84	m ² /year
	Coefficient of Compressibility	M _{vi}	0.39	0.25	0.15	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.6E-10	7.4E-11	3.9E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

© Copyright 2017 SOCOTEC UK Limited. All rights reserved


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43




Figure

CUM

sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH3		
Project Name	IMMINGHAM		Depth (m BGL)	5 - 5.45		
			No	10	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	335	370	440	kPa
Initial pwp	300	294	302	kPa
Initial σ_3'	35	76	138	kPa
Rate of strain	1.02	1.02	1.02	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	2.26	3.25	4.98	%
$(\sigma_1' / \sigma_3')_f$	3.480	3.556	3.126	
$(\sigma_1' - \sigma_3')_f$	78.1	138.0	207.3	kPa
u_f	304	316	343	kPa
$\sigma_3'_f$	32	54	98	kPa
$\sigma_1'_f$	110	192	305	kPa
A_f	0.04	0.16	0.20	
Time to failure	2.2	3.2	4.9	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	6.9
ϕ'	degrees	29.4
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:43

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.49
Diameter	mm	103.68
Bulk Density	Mg/m ³	2.22
Water Content	%	14
Dry density	Mg/m ³	1.95
After test		
Bulk Density	Mg/m ³	2.23
Water Content	%	13
Dry density	Mg/m ³	1.97

Soil Description	Firm brown slightly sandy slightly gravelly CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	287.6
Final B Value		0.97



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	365	430	560	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	65	130	260	kPa	
	Pore pressure at start of consolidation	347	374	457	kPa	
	Pore pressure at end of consolidation	303	300	302	kPa	
	Pore pressure dissipation at end of consolidation	94	100	99	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.17	2.09	1.63	m ² /year
	Coefficient of Compressibility	M _{vi}	0.24	0.12	0.07	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	1.6E-10	7.7E-11	3.5E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure

CUM


sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18






Printed:20/07/2018 10:44

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH4		
Project Name	IMMINGHAM		Depth (m BGL)	7.50 - 7.95		
			No	18	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	365	430	560	kPa
Initial pwp	302	300	302	kPa
Initial σ_3'	63	130	258	kPa
Rate of strain	1.56	1.56	1.56	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	2.19	3.40	4.22	%
$(\sigma_1' / \sigma_3')_f$	3.863	3.523	3.183	
$(\sigma_1' - \sigma_3')_f$	146.9	249.6	392.0	kPa
u_f	314	331	380	kPa
$\sigma_3'_f$	51	99	180	kPa
$\sigma_1'_f$	198	348	572	kPa
A_f	0.08	0.12	0.20	
Time to failure	1.4	2.2	2.7	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	15.9
ϕ'	degrees	29.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.596 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure

CUM

sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH5		
Project Name	IMMINGHAM		Depth (m BGL)	11 - 11.45		
			No	35	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.00
Diameter	mm	103.08
Bulk Density	Mg/m ³	2.16
Water Content	%	17
Dry density	Mg/m ³	1.84
After test		
Bulk Density	Mg/m ³	2.17
Water Content	%	17
Dry density	Mg/m ³	1.85

Soil Description	Firm brown slightly sandy slightly gravelly CLAY
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	310
Final pore water pressure	kPa	295
Final B Value		0.96



Consolidation Details	Drainage Conditions	From radial boundary and one end				
	Stage No.	1	2	3		
	Cell Pressure applied	327	355	410	kPa	
	Back Pressure applied	300	300	300	kPa	
	Effective Pressure	27	55	110	kPa	
	Pore pressure at start of consolidation	319	334	369	kPa	
	Pore pressure at end of consolidation	300	300	300	kPa	
	Pore pressure dissipation at end of consolidation	100	100	100	%	
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	0.68	0.76	0.57	m ² /year
	Coefficient of Compressibility	M _{vi}	0.39	0.27	0.20	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	8.2E-11	6.3E-11	3.4E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH5		
Project Name	IMMINGHAM		Depth (m BGL)	11 - 11.45		
			No	35	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44




Figure

CUM

sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH5		
Project Name	IMMINGHAM		Depth (m BGL)	11 - 11.45		
			No	35	Type	UT
			ID			
		Spec Ref				



Compression stages

Stage	1	2	3	
Cell pressure	327	355	410	kPa
Initial pwp	302	300	302	kPa
Initial σ_3'	25	55	108	kPa
Rate of strain	0.50	0.50	0.50	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	0.87	1.60	3.46	%
$(\sigma_1' / \sigma_3')_f$	3.952	3.551	3.172	
$(\sigma_1' - \sigma_3')_f$	35.4	81.6	167.3	kPa
u_f	315	323	333	kPa
σ_{3f}'	12	32	77	kPa
σ_{1f}'	47	114	244	kPa
A_f	0.37	0.28	0.19	
Time to failure	1.7	3.2	6.9	hrs

Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	4.0
ϕ'	degrees	30.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:44

Figure
CUM
sheet 3 of 3


**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6		
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45		
			No	19	Type	UT
			ID			
		Spec Ref				


Specimen Details		
Initial		
Length	mm	203.49
Diameter	mm	102.79
Bulk Density	Mg/m ³	2.14
Water Content	%	17
Dry density	Mg/m ³	1.84
After test		
Bulk Density	Mg/m ³	2.17
Water Content	%	15
Dry density	Mg/m ³	1.88

Soil Description	Soft to firm brown slightly sandy slightly gravelly CLAY.
Specimen Type /Preparation	UNDISTURBED

Saturation Details		Method of Saturation
		Increments of cell and back pressure
Cell pressure increments	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	260
Final pore water pressure	kPa	238
Final B Value		0.96



Consolidation Details	Drainage Conditions		From radial boundary and one end			
	Stage No.		1	2	3	
	Cell Pressure applied		355	410	520	kPa
	Back Pressure applied		300	300	300	kPa
	Effective Pressure		55	110	220	kPa
	Pore pressure at start of consolidation		333	371	459	kPa
	Pore pressure at end of consolidation		300	303	300	kPa
	Pore pressure dissipation at end of consolidation		100	96	100	%
Consolidation parameters (see note to BS1377 : pt 8, clause 6.3.4)	Coefficient of Consolidation	C _{vi}	2.41	1.42	1.38	m ² /year
	Coefficient of Compressibility	M _{vi}	0.36	0.17	0.09	m ² /MN
	Coefficient of Permeability (calculated)	k _{vi}	2.7E-10	7.4E-11	3.8E-11	m/s



Ref
SLR8.1
Rev 86.0
Feb18



Printed:20/07/2018 10:45


Figure
CUM
sheet 1 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6		
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45		
			No	19	Type	UT
			ID			
		Spec Ref				

Shearing stages - graphical data

o failure points



Ref
SLR8.1
Rev 86.0
Feb18





Printed:20/07/2018 10:45

Figure
CUM
sheet 2 of 3

**Consolidated Undrained Triaxial Compression test with Measurement of Pore Water Pressure
(BS1377 : Part 8 : 1990) - Multistage test on a single specimen**

Project No	A8015-18	Sample Details:	Hole No	BH6	
Project Name	IMMINGHAM		Depth (m BGL)	9 - 9.45	
		No	19	Type	UT
		ID			
		Spec Ref			




Compression stages

Stage	1	2	3	
Cell pressure	355	410	520	kPa
Initial pwp	300	300	300	kPa
Initial σ_3'	55	110	220	kPa
Rate of strain	1.80	1.80	1.80	%/hr

Failure conditions

Criterion	Maximum effective principal stress ratio			
	1	2	3	
Axial strain	1.57	3.52	6.15	%
$(\sigma_1' / \sigma_3')_f$	3.142	3.205	3.052	
$(\sigma_1' - \sigma_3')_f$	68.5	143.3	264.7	kPa
u_f	323	345	391	kPa
$\sigma_3'_f$	32	65	129	kPa
$\sigma_1'_f$	101	208	394	kPa
A_f	0.34	0.31	0.34	
Time to failure	0.9	2.0	3.4	hrs



Shear Strength Parameters

at peak stress ratio

		Linear regression
c'	kPa	2.2
ϕ'	degrees	30.1
		Manual re-assessment
c'	kPa	-
ϕ'	degrees	-

Mode of failure



Notes : Deviator stresses corrected for area change, vertical side drains and 0.595 mm thick rubber membrane(s)

Ref
SLR8.1
Rev 86.0
Feb18




Printed:20/07/2018 10:45

Figure
CUM
sheet 3 of 3

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104630	Sample Depth (m BGL)	3.00 - 3.45
		Sample Type and No	UT10
		Specimen Ref	



Soil description

Firm laminated brown slightly sandy slightly gravelly CLAY.

Preparation

Undisturbed

Index properties

Liquid limit %		Plastic limit %	
----------------	--	-----------------	--

(if available)

Specimen details

	Initial	Final	
Particle density	2.70	assumed	Mg/m3
Diameter	75.08		mm
Height	19.11	18.52	mm
Voids ratio	0.581	0.533	
Moisture content	21	21	%
Bulk density	2.06	2.13	Mg/m3
Dry density	1.71	1.76	Mg/m3
Saturation	97	105	%
Average temperature for test	20		oC

Swelling pressure

>50 kPa

Notes :

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
50	0.5806	/	/	/
100	0.5730	0.095	8.4	9
200	0.5587	0.091	16	17
400	0.5384	0.065	7.6	8.1
800	0.5102	0.046	8.6	9.2
100	0.5325	0.021	-	-

Specimen taken 10 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM

Figure


OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011601	Sample Depth (m BGL)	3.30 - 3.75
		Sample Type and No	UT15
		Specimen Ref	





Soil description	Firm laminated brown slightly sandy CLAY.			
Preparation	Undisturbed			
Index properties	Liquid limit %	47	Plastic limit %	22

(if available)			
Specimen details	Initial	Final	
Particle density	2.75	assumed	Mg/m3
Diameter	75.08		mm
Height	18.94	18.04	mm
Voids ratio	0.728	0.646	
Moisture content	26	25	%
Bulk density	2.01	2.08	Mg/m3
Dry density	1.59	1.67	Mg/m3
Saturation	100	105	%
Average temperature for test	20		oC
Swelling pressure	>50		kPa


Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
50	0.7276	/	/	/
100	0.7154	0.142	2.5	2.6
200	0.6930	0.131	1.4	1.5
400	0.6571	0.106	2	2
800	0.6032	0.081	1.5	1.6
100	0.6456	0.038	-	-

Specimen taken 10 mm from base of sample

QA Ref SLR 5.3 Rev 2.16 Nov 16  1157	 SOCOTEC	Project No	A8015-18	Figure	OED
		Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited				Printed: 02/07/2018 15:26	

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413012711	Sample Depth (m BGL)	8.00 - 8.45
		Sample Type and No	UT36
		Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY. Gravel is chalk.	
Undisturbed	
Liquid limit %	Plastic limit %

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

	Initial	Final	
Particle density	2.75	assumed	Mg/m3
Diameter	75.08		mm
Height	19.10	18.20	mm
Voids ratio	0.453	0.385	
Moisture content	16	14	%
Bulk density	2.19	2.27	Mg/m3
Dry density	1.89	1.99	Mg/m3
Saturation	97	101	%
Average temperature for test	20		oC

Swelling pressure not measured kPa

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.4526	/	/	/
50	0.4272	0.350	1.7	1.8
100	0.4141	0.183	2.5	2.7
200	0.3955	0.131	3.2	3.3
400	0.3749	0.074	3.4	3.5
50	0.3846	0.020	-	-

Specimen taken 20 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102646	Sample Depth (m BGL)	5.00 - 5.45
		Sample Type and No	UT10
		Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY.			
Undisturbed			
Liquid limit %		Plastic limit %	

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

	Initial	Final	
Particle density	2.70	assumed	Mg/m ³
Diameter	75.03		mm
Height	18.93	18.18	mm
Voids ratio	0.442	0.385	
Moisture content	16	15	%
Bulk density	2.18	2.24	Mg/m ³
Dry density	1.87	1.95	Mg/m ³
Saturation	100	105	%
Average temperature for test	20		oC

Swelling pressure: not measured kPa

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t50, log) m ² /year	cv (t90, root) m ² /year
0	0.4418	/	/	/
50	0.4229	0.263	2.8	3
100	0.4117	0.157	3.5	3.7
200	0.3943	0.123	3.6	3.8
400	0.3704	0.086	3.8	4.1
50	0.3847	0.030	-	-

Specimen taken 10 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115035	Sample Depth (m BGL)	3.10 - 3.55
		Sample Type and No	UT7
		Specimen Ref	



Soil description	Brown slightly sandy SILT.		
Preparation	Undisturbed		
Index properties	Liquid limit %		Plastic limit %

(if available)		
Specimen details	Initial	Final
Particle density	2.75	assumed
Diameter	75.01	
Height	18.94	18.69
Voids ratio	0.639	0.618
Moisture content	23	21
Bulk density	2.06	2.06
Dry density	1.68	1.70
Saturation	98	94
Average temperature for test	20	

Swelling pressure	not measured	kPa
-------------------	--------------	-----

Notes :

Specimen taken 20 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.6386	/	/	/
50	0.6301	0.104	1.7	1.6
100	0.6245	0.069	1.1	0.91
200	0.6197	0.029	0.55	0.61
400	0.6155	0.013	0.44	0.46
50	0.6175	0.004	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16




Project No A8015-18
Project Name VPI IMMINGHAM

Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120528	Sample Depth (m BGL)	3.40 - 3.85
		Sample Type and No	UT15
		Specimen Ref	



Soil description

Firm to stiff brown slightly sandy slightly gravelly CLAY.
Gravel is chalk.

Preparation

Undisturbed

Index properties

Liquid limit %		Plastic limit %	
----------------	--	-----------------	--

(if available)

Specimen details

	Initial	Final	
Particle density	2.75	assumed	Mg/m ³
Diameter	75.17		mm
Height	18.97	18.50	mm
Voids ratio	0.639	0.599	
Moisture content	23	22	%
Bulk density	2.06	2.10	Mg/m ³
Dry density	1.68	1.72	Mg/m ³
Saturation	99	102	%
Average temperature for test	20		oC

Swelling pressure

>50 kPa

Notes :

Specimen taken 10 mm from base of sample

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t50, log) m ² /year	cv (t90, root) m ² /year
50	0.6393	/	/	/
100	0.6313	0.098	5.7	6.1
200	0.6176	0.084	3.3	1.8
400	0.5970	0.064	2.7	2.9
800	0.5683	0.045	2.7	2.9
100	0.5989	0.028	-	-

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
OED

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092542	Sample Depth (m BGL)	4.00 - 4.45
		Sample Type and No	UT10
		Specimen Ref	



Soil description	Soft brown slightly sandy CLAY.		
Preparation	Undisturbed		
Index properties	Liquid limit %		Plastic limit %

(if available)		
Specimen details	Initial	Final
Particle density	2.75	assumed
Diameter	75.19	
Height	19.12	18.09
Voids ratio	0.664	0.574
Moisture content	24	21
Bulk density	2.05	2.12
Dry density	1.65	1.75
Saturation	99	103
Average temperature for test	20	
Swelling pressure	not measured	

Applied Pressure kPa	Voids ratio	mv m2/MN	cv (t50, log) m2/year	cv (t90, root) m2/year
0	0.6638	/	/	/
50	0.6304	0.401	0.98	1.1
100	0.6096	0.255	1	1
200	0.5815	0.175	1.1	1.1
400	0.5484	0.105	1.5	1.5
50	0.5744	0.048	-	-

Specimen taken 40 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16


Project No	A8015-18
Project Name	VPI IMMINGHAM
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited	

Figure
OED

Printed:
02/07/2018 15:26

ONE DIMENSIONAL CONSOLIDATION TEST

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092658	Sample Depth (m BGL)	9.00 - 9.45
		Sample Type and No	UT19
		Specimen Ref	



Soil description

Firm brown slightly sandy slightly gravelly CLAY. Gravel is chalk.	
Undisturbed	
Liquid limit %	Plastic limit %

Preparation

Index properties

(if available)

Specimen details

Particle density

Diameter

Height

Voids ratio

Moisture content

Bulk density

Dry density

Saturation

Average temperature for test

Swelling pressure

Notes :

	Initial	Final	
Particle density	2.65	assumed	Mg/m ³
Diameter	75.04		mm
Height	18.96	18.02	mm
Voids ratio	0.446	0.374	
Moisture content	17	15	%
Bulk density	2.14	2.21	Mg/m ³
Dry density	1.83	1.93	Mg/m ³
Saturation	98	105	%
Average temperature for test	20		oC

Swelling pressure: not measured kPa

Applied Pressure kPa	Voids ratio	mv m ² /MN	cv (t50, log) m ² /year	cv (t90, root) m ² /year
0	0.4456	/	/	/
50	0.4182	0.380	3.2	3.3
100	0.4053	0.182	4.5	4.8
200	0.3868	0.131	5.4	5.7
400	0.3639	0.083	5.3	5.5
50	0.3737	0.020	-	-

Specimen taken 10 mm from base of sample

QA Ref
SLR 5.3
Rev 2.16
Nov 16



Project No A8015-18
Project Name VPI IMMINGHAM

Figure

OED


Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2016 SOCOTEC UK Limited

Printed:
02/07/2018 15:26

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH2				
	A8015-1820180413011428	Sample Depth (m BGL)	1.20 - 1.65				
		Sample Type and No	UT7				
		Specimen Ref					
Specimen Description	Firm brown slightly sandy slightly gravelly CLAY						
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	26/06/2018				
SPECIMEN DETAILS	Type of sample Preparation	Undisturbed					
	Height	Initial	Final				
	Diameter	19.32	mm				
	Bulk density	71.94	mm				
	Moisture content	2.08	3.52 Mg/m3				
	Dry density	18.0	23.0 %				
	Voids Ratio	1.76	2.67 Mg/m3				
	Degree of Saturation	0.502	%				
	Particle density	95	%				
		2.65	Mg/m3 Assumed				
SWELLING	Swelling pressure		kPa				
	Water taken in during swelling stage		ml				
SATURATION	Cell pressure increments	50	kPa				
Back pressure	Pressure differential	10	kPa				
	Final diaphragm pressure	460	kPa				
	Final back pressure	443	kPa				
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_o$	1.00					
	Water taken in during saturation stage	28.9	ml				
	Voids ratio at end of saturation stage	0.500					
CONSOLIDATION STAGES	Type of drainage	Radial outwards					
	Type of loading	Free strain					
	PWP location	Centre base					
	Centre drain (if applicable)						
	Diameter						
	Material						
	Method of formation						
Stage number		1	2	3	4	5	
Diaphragm pressure		475	500	550	650	500	kPa
Back pressure		450	450	450	450	450	kPa
Initial Pore pressure built up		459	476	486	493	362	kPa
Final pore pressure		450	450	451	450	450	kPa
Effective stress (actual) at end of stage		25	50	99	200	50	kPa
Voids at start		0.500	0.173	0.173	0.121	0.102	
Voids at end		0.222	0.173	0.121	0.102	-0.009	
PWP dissipation		100	100	97	100	100	%
Settlement in stage		0.37	0.24	0.17	0.29	-0.12	mm
Volume change in stage	(water out = +ve)	14.5	2.6	2.7	1.0	5.8	ml
Mv		7.4	1.6	0.9	0.17	-0.671	m2/MN
Cro		400	1.5	1.4	0.53	0	0 m2/year
Csec		0	0	0	0		
Cro method		Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature		20.6	20.6	21.5	21.0	19.6	oC
Remarks							

QA Ref SLD 3, 5/9 Rev 2.7	 SOCOTEC	Project No A8015-18 Project Name VPI IMMINGHAM	Figure HC
Test carried out outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited			Printed: 31/07/2018 12:23



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011428	Sample Depth (m BGL)	1.20 - 1.65
		Sample Type and No	UT7
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
 Project Name VPI IMMINGHAM

Figure

HC

Test carried out outside the scope of UKAS accreditation. © Copyright 2017
 SOCOTEC UK Limited

Printed:
 31/07/2018 12:23

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH4				
	A8015-1820180418115015	Sample Depth (m BGL)	2.00 - 2.45				
		Sample Type and No	UT4				
		Specimen Ref					
Specimen Description							
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	26/06/2018				
SPECIMEN DETAILS	Type of sample Preparation	Undisturbed					
	Height	Initial	Final				
	Diameter	18.86					
	Bulk density	72.13					
	Moisture content	2.04	3.32				
	Dry density	22.0	25.0				
	Voids Ratio	1.67	2.41				
	Degree of Saturation	0.585					
	Particle density	100					
		2.65					
			Mg/m3				
			%				
			Mg/m3				
			%				
			Mg/m3				
			Assumed				
SWELLING	Swelling pressure		kPa				
	Water taken in during swelling stage		ml				
SATURATION	Cell pressure increments	50	kPa				
Back pressure	Pressure differential	10	kPa				
	Final diaphragm pressure	310	kPa				
	Final back pressure	298	kPa				
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_\sigma$	0.99					
	Water taken in during saturation stage	27.2	ml				
	Voids ratio at end of saturation stage	0.560					
CONSOLIDATION STAGES	Type of drainage	Radial outwards	Centre drain (if applicable)				
	Type of loading	Free strain	Diameter				
	PWP location	Centre base	Material				
			Method of formation				
Stage number		1	2	3	4	5	
Diaphragm pressure		325	350	400	500	350	kPa
Back pressure		300	300	300	300	300	kPa
Initial Pore pressure built up		315	321	335	330	255	kPa
Final pore pressure		300	300	300	300	294	kPa
Effective stress (actual) at end of stage		25	50	100	200	56	kPa
Voids at start		0.560	0.312	0.312	0.235	0.182	
Voids at end		0.388	0.312	0.235	0.182	0.102	
PWP dissipation		100	100	100	100	86	%
Settlement in stage		0.00	0.11	0.26	0.21	-0.09	mm
Volume change in stage	(water out = +ve)	8.4	3.7	3.7	2.6	3.9	ml
Mv		4.4	2.2	1.2	0.43	-0.471	m2/MN
Cro		0	36	8.6	7	0	0
Csec			0	0	0		
Cro method		Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature		21.1	20.8	20.3	21.1	21.8	oC
Remarks							



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH4
	A8015-1820180418115015	Sample Depth (m BGL)	2.00 - 2.45
		Sample Type and No	UT4
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
 Project Name VPI IMMINGHAM

Figure
HC


Test carried out outside the scope of UKAS accreditation. © Copyright 2017
 SOCOTEC UK Limited

Printed:
31/07/2018 12:23

Determination of consolidation properties using a hydraulic cell

BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH5				
	A8015-1820180418120419	Sample Depth (m BGL)	1.20 - 1.65				
		Sample Type and No	UT7				
		Specimen Ref					
Specimen Description	Soft to firm brown slightly sandy slightly gravelly CLAY.						
Test Method	BS 1377: Part 6: 1990, clause 3.7	Date of test	11/07/2018				
SPECIMEN DETAILS	Type of sample Preparation	Undisturbed					
	Height	Initial	Final				
	Diameter	18.55		mm			
	Bulk density	72.06		mm			
	Moisture content	2.24	4.58	Mg/m3			
	Dry density	15.0	20.0	%			
	Voids Ratio	1.95	4.02	Mg/m3			
	Degree of Saturation	0.359		%			
	Particle density	111		%			
		2.65		Mg/m3 Assumed			
SWELLING	Swelling pressure			kPa			
	Water taken in during swelling stage			ml			
SATURATION	Cell pressure increments	50		kPa			
Back pressure	Pressure differential	10		kPa			
	Final diaphragm pressure	360		kPa			
	Final back pressure	341		kPa			
	Final pore pressure ratio, $\bar{\sigma}_u / \bar{\sigma}_o$	0.96					
	Water taken in during saturation stage	22.3		ml			
	Voids ratio at end of saturation stage	0.290					
CONSOLIDATION STAGES	Type of drainage	Radial outwards		Centre drain (if applicable)			
	Type of loading	Free strain		Diameter			
	PWP location	Centre base		mm			
				Material			
				Method of formation			
Stage number		1	2	3	4	5	
Diaphragm pressure		375	400	450	550	400	kPa
Back pressure		350	350	350	350	350	kPa
Initial Pore pressure built up		356	369	385	422	246	kPa
Final pore pressure		350	350	350	350	350	kPa
Effective stress (actual) at end of stage		25	50	100	200	50	kPa
Voids at start		0.290	0.145	0.145	0.093	0.041	
Voids at end		0.215	0.145	0.093	0.041	-0.340	
PWP dissipation		100	100	100	100	100	%
Settlement in stage		0.01	0.19	0.22	0.22	-0.62	mm
Volume change in stage	(water out = +ve)	4.2	3.9	2.9	2.9	21.2	ml
Mv		2.3	2.3	0.91	0.48	-2.44	m2/MN
Cro		1.3	29	19	2.7	0	0
Csec		0	0	0	0		
Cro method		Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90	Settlement, root time, t90		
Average stage temperature		20.3	20.1	20.3	21.3	20.6	oC
Remarks							

QA Ref SLD 3, 5/9 Rev 2.7		Project No A8015-18 Project Name VPI IMMINGHAM	Figure HC
Test carried out outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited			Printed: 31/07/2018 12:23



Determination of consolidation properties using a hydraulic cell
BS 1377: Part 6: 1990

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120419	Sample Depth (m BGL)	1.20 - 1.65
		Sample Type and No	UT7
		Specimen Ref	

Graphical data

Voids Ratio v Log Effective Stress

● Loading stage × Unloading stage



Voids ratio plotted at effective stress at the end of the stage.

Cro plotted at the average effective stress during the stage.

QA Ref
SLD 3, 5/9
Rev 2.7



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
HC

Test carried out outside the scope of UKAS accreditation. © Copyright 2017
SOCOTEC UK Limited



Printed:
31/07/2018 12:23

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104626	Sample Depth (m BGL)	2.50 - 3.00
		Sample Type and No	B9
		Specimen Ref	




Soil description	Brown CLAY with chalk fragments.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.78
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	0 %	16
Particle density	2.71 measured - small pycnometer	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure	COMPL
			Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited					Printed: 02/07/2018 15:44	

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH5
	A8015-1820180418120410	Sample Depth (m BGL)	0.50 - 0.80
		Sample Type and No	B4
		Specimen Ref	




Soil description	Brown slightly sandy CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material wassingle sample tested	1.67
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	0 %	18
Particle density	2.55 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:45

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP1
	A8015-18-20180413084026	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m3
Preparation	Original material was natural, single sample tested	1.87
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	4 %	14
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17  1157		Project No	A8015-18	Figure COMPL
		Project Name	VPI IMMINGHAM	
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited				Printed: 02/07/2018 15:45

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP3
	A8015-18-20180410084322	Sample Depth (m BGL)	0.10 - 0.20
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.6, 2.5 kg rammer in a CBR mould	Maximum dry density, Mg/m3
Preparation	Original material was natural, single sample tested	1.72
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	8 %	16
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 05/07/2018 11:42

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP5
	A8015-18-20180410090003	Sample Depth (m BGL)	0.10 - 0.20
		Sample Type and No	B2
		Specimen Ref	




Soil description	Greenish brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.56
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	1 %	24
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure	COMPL
			Project Name	VPI IMMINGHAM		
Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited					Printed: 02/07/2018 15:46	

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP9
	A8015-18-20180410091510	Sample Depth (m BGL)	0.30 - 0.40
		Sample Type and No	B4
		Specimen Ref	




Soil description	Light brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m ³
Preparation	Original material was natural, single sample tested	1.99
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	15 %	12
Particle density	2.65 assumed	
Remarks		



QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:47

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : LIGHT COMPACTION, 2.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TT1
	A8015-18-20180413014653	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	




Soil description	Brown slightly sandy slightly gravelly CLAY.	Derived Parameters +
Test method	BS 1377:part 4:1990: clause 3.5, 2.5 kg rammer in a 1 litre mould	Maximum dry density, Mg/m3
Preparation	Original material wassingle sample tested	1.59
Material > 37.5mm	0 %	Optimum moisture content, %
Material < 37.5mm > 20mm	3 %	20
Particle density	2.65 assumed	
Remarks		

QA Ref SLD 4, 3.5/6 Rev 2.5 Sep 17	 1157		Project No	A8015-18	Figure
			Project Name	VPI IMMINGHAM	
<small>Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited</small>					Printed: 02/07/2018 15:47

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104548	Sample Depth (m BGL)	0.50 - 0.70
		Sample Type and No	B4
		Specimen Ref	



Soil description Greyish brown slightly sandy slightly gravelly CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, separate specimens tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.55 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.74

Optimum moisture content, %
14

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 02/07/2018
 15:37

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH2
	A8015-1820180413011454	Sample Depth (m BGL)	1.80 - 2.25
		Sample Type and No	B10
		Specimen Ref	



Soil description Brown slightly gravelly CLAY. Gravel is chalk

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.70 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.82

Optimum moisture content, %
17

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18

Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:39

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH3
	A8015-1820180413102609	Sample Depth (m BGL)	0.40 - 1.20
		Sample Type and No	B1
		Specimen Ref	



Soil description Brown slightly sandy CLAY with chalk fragments.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.76

Optimum moisture content, %
16

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:40

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	BH6
	A8015-1820180409092443	Sample Depth (m BGL)	0.30 - 0.55
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.80 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.80

Optimum moisture content, %
19

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 05/07/2018
 11:41

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP10
	A8015-18-20180408084806	Sample Depth (m BGL)	0.40 - 0.60
		Sample Type and No	B4
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.95

Optimum moisture content, %
12

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 02/07/2018
 15:40

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP2
	A8015-18-20180413090338	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Dark brown slightly gravelly silty CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 4 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.55

Optimum moisture content, %
25

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
06/07/2018
07:56

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP4
	A8015-18-20180410075427	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown silty CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.80 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.71

Optimum moisture content, %
23

QA Ref
SLD 4, 3.5/6
Rev 2.5
Sep 17



Project No A8015-18
Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
02/07/2018
15:42

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP6
	A8015-18-20180410082549	Sample Depth (m BGL)	0.10 - 0.30
		Sample Type and No	B2
		Specimen Ref	



Soil description Brown CLAY with chalk fragments.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 2 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.82

Optimum moisture content, %
16

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 02/07/2018
 15:42

DRY DENSITY / MOISTURE CONTENT RELATIONSHIP
BS1377 : PART 4 : 1990 : HEAVY COMPACTION, 4.5 kg rammer

Sample Details:	SAMPLE ID:	Hole No	TP10
	A8015-18-20180408084806	Sample Depth (m BGL)	0.40 - 0.60
		Sample Type and No	B4
		Specimen Ref	



Soil description Brown slightly sandy CLAY.

Test method BS 1377:part 4:1990: clause 3.5, 4.5 kg rammer in a 1 litre mould

Preparation Original material was natural, single sample tested

Material > 37.5mm 0 %

Material < 37.5mm > 20mm 0 %

Particle density 2.65 assumed

Remarks

Derived Parameters +

Maximum dry density, Mg/m³
1.95

Optimum moisture content, %
12

QA Ref
 SLD 4, 3.5/6
 Rev 2.5
 Sep 17



Project No A8015-18
 Project Name VPI IMMINGHAM


Figure
COMPH

Opinions and interpretations expressed herein are outside the scope of UKAS accreditation. © Copyright 2017 SOCOTEC UK Limited

Printed:
 02/07/2018
 15:40

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:	Hole No	BH1
	A8015-1820180409104552	Sample Depth (m)	1.00 - 1.20
		Sample Type and No	B5
		Specimen Ref	1



Soil description: Brown slightly sandy slightly gravelly CLAY with rare rootlets.

Test Conditions		
Sample Retained on 20 mm sieve	%	27

Sample Conditions		
Initial Moisture Content	%	22.0
Bulk Density	Mg/m ³	2.02
Dry Density	Mg/m ³	1.66
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	21.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	1.9	2.0
5	1.7	1.8

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	1.9	2.0
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180413011424

Hole No	BH2
Sample Depth (m)	1.00 - 1.20
Sample Type and No	B6
Specimen Ref	1



Soil description	Brown slightly sandy CLAY.
------------------	----------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	3

Sample Conditions		
Initial Moisture Content	%	25.0
Bulk Density	Mg/m ³	1.97
Dry Density	Mg/m ³	1.58
Moisture Content - TOP	%	26.0
Moisture Content - BASE	%	24.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	2.4	3.3
5	3.2	4.1

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	3.2	4.1
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180413102609

Hole No	BH3
Sample Depth (m)	0.40 - 1.20
Sample Type and No	B1
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	21.0
Bulk Density	Mg/m ³	2.03
Dry Density	Mg/m ³	1.68
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Undisturbed	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.7	3.9
5	3.5	3.5

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	3.7	3.9
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-1820180418115011

Hole No	BH4
Sample Depth (m)	1.65 - 2.00
Sample Type and No	B3
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	19.0
Bulk Density	Mg/m ³	2.12
Dry Density	Mg/m ³	1.78
Moisture Content - TOP	%	20.0
Moisture Content - BASE	%	19.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	4.8	4.4
5	4.7	4.2

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	4.8	4.4
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413084055

Hole No	TP1
Sample Depth (m)	0.70 - 0.90
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with occasional chalk fragments.
------------------	--

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	23.0
Bulk Density	Mg/m ³	1.98
Dry Density	Mg/m ³	1.61
Moisture Content - TOP	%	22.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.9	4.6
5	3.4	4.2

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	3.9	4.6
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
<small>Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited</small>			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413084231

Hole No	TP1
Sample Depth (m)	3.40 - 3.60
Sample Type and No	B10
Specimen Ref	1



Soil description	Light brown slightly sandy CLAY.
------------------	----------------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	14.0
Bulk Density	Mg/m ³	2.19
Dry Density	Mg/m ³	1.92
Moisture Content - TOP	%	13.0
Moisture Content - BASE	%	13.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	13.0	15.0
5	13.0	15.0

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	13.0	15.0
-----------------------	-------------	-------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413090359

Hole No	TP2
Sample Depth (m)	0.30 - 0.50
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly sandy slightly gravelly CLAY.
------------------	--

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	20.0
Bulk Density	Mg/m ³	1.92
Dry Density	Mg/m ³	1.60
Moisture Content - TOP	%	21.0
Moisture Content - BASE	%	22.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	6.5	5.0
5	6.0	4.4

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	6.5	5.0
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180410092425

Hole No	TP7
Sample Depth (m)	1.30 - 1.60
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly sandy CLAY with chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	17.0
Bulk Density	Mg/m ³	2.14
Dry Density	Mg/m ³	1.83
Moisture Content - TOP	%	17.0
Moisture Content - BASE	%	17.0

Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	3.4	4.0
5	3.2	4.0


Surcharge applied	kg	16
	kPa	10

Notes :

Accepted CBR %	3.4	4.0
-----------------------	------------	------------

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:	Hole No	TP8
	A8015-18-20180410074518	Sample Depth (m)	3.70 - 3.90
		Sample Type and No	B12
		Specimen Ref	1



Soil description	Brown SAND with occasional chalk fragments.
------------------	---

Test Conditions	
Sample Retained on 20 mm sieve	%

Sample Conditions	
Initial Moisture Content	%
Bulk Density	Mg/m ³
Dry Density	Mg/m ³
Moisture Content - TOP	%
Moisture Content - BASE	%

Preparation	Method of Compaction	
	Undisturbed	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	-	-
5.0	-	-

Surcharge applied	kg	
	kPa	0


Notes :
 Test attempted @ NMC & various dryer MC's, sample protruded from mould at NMC & dryer MC's when CBR testing equipment came into contact with sample.

Accepted CBR %	-	-
-----------------------	---	---

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180413014738

Hole No	TT1
Sample Depth (m)	0.50 - 0.70
Sample Type and No	B4
Specimen Ref	1



Soil description	Brown slightly gravelly CLAY with occasional chalk fragments.
------------------	---

Test Conditions		
Sample Retained on 20 mm sieve	%	2

Sample Conditions		
Initial Moisture Content	%	27.0
Bulk Density	Mg/m ³	2.40
Dry Density	Mg/m ³	1.90
Moisture Content - TOP	%	25.0
Moisture Content - BASE	%	26.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (4.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	0.8	0.9
5	0.7	0.8

Surcharge applied	kg	16
	kPa	10

Notes :


Accepted CBR %	0.8	0.9
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
		Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited		Printed: 14/08/2018 11:15

California Bearing Ratio (BS1377:1990:Part 4 , section 7)

Sample Details:	SAMPLE ID:
	A8015-18-20180408080446

Hole No	TT3
Sample Depth (m)	0.30 - 0.60
Sample Type and No	B2
Specimen Ref	1



Soil description	Brown slightly sandy CLAY.
------------------	----------------------------

Test Conditions		
Sample Retained on 20 mm sieve	%	0

Sample Conditions		
Initial Moisture Content	%	25.0
Bulk Density	Mg/m ³	1.94
Dry Density	Mg/m ³	1.56
Moisture Content - TOP	%	24.0
Moisture Content - BASE	%	27.0


Preparation	Method of Compaction	
	Recompacted - Rammer compaction with specified effort (2.5kg)	
	Soaked test	NO
	Soaking Period	days N/A
	Amount of Swell	mm N/A

Penetration mm	CBR Values %	
	TOP	BASE
2.5	1.6	1.1
5	2.2	1.7

Surcharge applied	kg	16
	kPa	10

Notes :

Accepted CBR %	2.2	1.7
-----------------------	------------	------------

QA Ref SLR 2 Rev 2.7 Apr 15	 SOCOTEC	Project No	A8015-18	Figure CBR
		Project Name	VPI IMMINGHAM	
Test carried out outside the scope of UKAS accreditation. © Copyright 2015 SOCOTEC UK Limited			Printed: 14/08/2018 11:15	

TEST REPORT

Report No. EFS/187041 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG


Site: A8015-18 VPI Immingham

The 4 samples described in this report were registered for analysis by SOCOTEC UK Limited on 23-Jun-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 03-Jul-2018

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of 
SOCOTEC UK Limited
Tim Barnes Operations Director
Energy & Waste Services

Date of Issue: 03-Jul-2018

Tests marked '^' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Where individual results are flagged see report notes for status.

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187041

Consignment No S75653
Date Logged 23-Jun-2018
In-House Report Due 29-Jun-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClustServ	ORGMAT
		Sampled	REPORT A	Organic Matter %
CL/1910777	BH4 1.20-1.65	D	D	D
CL/1910778	TP02 0.30	D	D	D
CL/1910779	BH5 2.90-3.35	D	D	D
CL/1910780	BH2 0.60	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT



Report No. EFS/187043 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham

The 12 samples described in this report were registered for analysis by SOCOTEC UK Limited on 23-Jun-2018. This report supersedes any versions previously issued by the laboratory.


The analysis was completed by: 04-Jul-2018

Tests where the accreditation is set to N or No, and any individual data items marked with a * are not UKAS accredited. Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of
SOCOTEC UK Li
Tim Barnes



Director
Energy & Waste Services

Date of Issue: 04-Jul-2018

Tests marked '^' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187043

Consignment No S75655
Date Logged 23-Jun-2018
In-House Report Due 29-Jun-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClstServ	Dep.Ord	DO Mg if SO4(W)>3000	DO NO3 if pH<5.5	DO Cl if pH>5.5	ICPACIDS	ICPBRE	ICPWSS	KONECL	KoneNO3	ORGMAT	TSBRE1	WSLMS0
		Sampled	REPORT A	DO Cl if pH<5.5				SO4-- (acid sol)	Magnesium (BRE)	SO4-- (H2O sol) mg/l	Chloride:(2:1)	Nitrate (BRE 2:1): mg/l	Organic Matter %	Total Sulphur.	pH (BS1377)
								✓		✓					
CL/1910790	BH2 2.80-3.25	D	D										D		
CL/1910791	BH3 2.00-2.45	D	D										D		
CL/1910792	BH3 3.00-3.45	D	D	D	D	D	D	D	D	D	D	D	D	D	D
CL/1910793	BH6 13.70	D	D				D	D	D	D	D	D	D	D	D
CL/1910794	TP1 0.10	D	D										D		
CL/1910795	TP2 4.00	D	D				D	D	D	D	D	D	D	D	D
CL/1910796	TP3 3.40	D	D										D		
CL/1910797	TP5 0.10	D	D										D		
CL/1910798	TP6 0.40	D	D				D	D	D	D	D	D	D	D	D
CL/1910799	TP8 2.00	D	D										D		
CL/1910800	TP9 0.80	D	D										D		
CL/1910801	TT2 2.00-2.15	D	D				D	D	D	D	D	D	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ICPACIDS	Oven Dried @ < 35°C	Determination of Total Sulphate in soil samples by Hydrochloric Acid extraction followed by ICPOES detection
Soil	ICPWSS	Oven Dried @ < 35°C	Determination of Water Soluble Sulphate in soil samples by water extraction followed by ICPOES detection
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract
Soil	TSBRE1	Oven Dried @ < 35°C	Determination of Total Carbon and/or Total Sulphur in solid samples by high temperature combustion/infrared detection
Soil	WSLM50	Oven Dried @ < 35°C	Determination of pH of 2.5:1 deionised water to soil extracts using pH probe.

Where individual results are flagged see report notes for status.

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT



1252

Report No. EFS/187204 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham

The 11 samples described in this report were registered for analysis by SOCOTEC UK Limited on 28-Jun-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 09-Jul-2018

Tests where the accreditation is set to N or No, and any individual data items marked with a * are not UKAS accredited. Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of
SOCOTEC UK Li
Tim Barnes



Director
Energy & Waste Services

Date of Issue: 09-Jul-2018

Tests marked '^' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187204

Consignment No S75795
Date Logged 28-Jun-2018
In-House Report Due 04-Jul-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClientServ	Dep. Opt	DO Mg if SO4(W)>3000	DO NO3 if pH<5.5	SO4-- (acid sol)	ICPACIDS	ICPBRE	ICPWSS	KONCL	KONNO3	ORGMAT	TSBRE1	W/S/LM50
		Sampled	REPORT A	DO Cl if pH<5.5											
								✓		✓					
CL/1911581	TT02 2.00-2.15	D	D	D	D	D	D	D	D	D	D	D		D	D
CL/1911582	TT03 1.30-1.60	D	D										D		
CL/1911583	BH5 4.00-4.45	D	D				D	D	D	D	D	D		D	D
CL/1911584	BH6 0.00-0.30	D	D										D		
CL/1911585	TP02 3.40-3.50	D	D										D		
CL/1911586	TP6 1.00-1.20	D	D										D		
CL/1911587	TP09 0.80-1.00	D	D				D	D	D	D	D	D		D	D
CL/1911588	BH1 0.45	D	D										D		
CL/1911589	BH1 1.00-1.20	D	D				D	D	D	D	D	D		D	D
CL/1911590	BH2 2.20-2.70	D	D				D	D	D	D	D	D		D	D
CL/1911591	BH2 5.70-6.15	D	D				D	D	D	D	D	D		D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ICPACIDS	Oven Dried @ < 35°C	Determination of Total Sulphate in soil samples by Hydrochloric Acid extraction followed by ICPOES detection
Soil	ICPWSS	Oven Dried @ < 35°C	Determination of Water Soluble Sulphate in soil samples by water extraction followed by ICPOES detection
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract
Soil	TSBRE1	Oven Dried @ < 35°C	Determination of Total Carbon and/or Total Sulphur in solid samples by high temperature combustion/infrared detection
Soil	WSLM50	Oven Dried @ < 35°C	Determination of pH of 2.5:1 deionised water to soil extracts using pH probe.

Where individual results are flagged see report notes for status.

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix

Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

TEST REPORT

Report No. EFS/187902 (Ver. 1)

SOCOTEC UK Doncaster
Askern Road
Carcroft
Doncaster
South Yorkshire
DN6 8DG

Site: A8015-18 VPI Immingham

The 1 sample described in this report were registered for analysis by SOCOTEC UK Limited on 19-Jul-2018. This report supersedes any versions previously issued by the laboratory.

The analysis was completed by: 25-Jul-2018

The following tables are contained in this report:

Table 1 Main Analysis Results (Page 2)
Analytical and Deviating Sample Overview (Page 3)
Table of Method Descriptions (Page 4)
Table of Report Notes (Page 5)
Table of Sample Descriptions (Appendix A Page 1 of 1)

On behalf of
SOCOTEC UK Limited
Tim Barnes


Operations Director
Energy & Waste Services

Date of Issue: 25-Jul-2018

Tests marked 'N' have been subcontracted to another laboratory.

Where samples have been flagged as deviant on the Analytical and Deviating Sample Overview, for any reason, the data may not be representative of the sample at the point of sampling and the validity of the data may be affected.

SOCOTEC UK Limited accepts no responsibility for any sampling not carried out by our personnel.

Customer SOCOTEC UK Doncaster
Site A8015-18 VPI Immingham
Report No S187902

Consignment No S75653
Date Logged 19-Jul-2018
In-House Report Due 25-Jul-2018

Please note the results for any subcontracted analysis (identified with a '^') is likely to take up to an additional five working days.

ID Number	Description	MethodID	ClientServ	ORGMAT
		Sampled	REPORT A	Organic Matter %
CL/1914695	BH1 1.65-1.80	D	D	D

Note: We will endeavour to prioritise samples to complete analysis within holding time; however any delay could result in samples becoming deviant whilst being processed in the laboratory.

If sampling dates are missing or matrices unclassified then results will not be ISO 17025 accredited. Please contact us as soon as possible to provide missing information in order to reinstate accreditation.

Deviating Sample Key	
A	The sample was received in an inappropriate container for this analysis
B	The sample was received without the correct preservation for this analysis
C	Headspace present in the sample container
D	The sampling date was not supplied so holding time may be compromised - applicable to all analysis
E	Sample processing did not commence within the appropriate holding time
F	Sample processing did not commence within the appropriate handling time
Requested Analysis Key	
■	Analysis Required
■	Analysis dependant upon trigger result - Note: due date may be affected if triggered
□	No analysis scheduled
^	Analysis Subcontracted - Note: due date may vary

Where individual results are flagged see report notes for status.

Method Descriptions

Matrix	MethodID	Analysis Basis	Method Description
Soil	ORGMAT	Oven Dried @ < 35°C	Acid Dichromate oxidation of the sample followed by colorimetric analysis of the extract

Report Notes

Generic Notes

Soil/Solid Analysis

Unless stated otherwise,

- Results expressed as mg/kg have been calculated on the basis indicated in the Method Description table.
All results on MCERTS reports are reported on a 105°C dry weight basis with the exception of pH and conductivity.
- Sulphate analysis not conducted in accordance with BS1377
- Water Soluble Sulphate is on a 2:1 water:soil extract

Waters Analysis

Unless stated otherwise results are expressed as mg/l

Nil: Where "Nil" has been entered against Total Alkalinity or Total Acidity this indicates that a measurement was not required due to the inherent pH of the sample.

Oil analysis specific

Unless stated otherwise,

- Results are expressed as mg/kg
- SG is expressed as g/cm³@ 15°C

Gas (Tedlar bag) Analysis

Unless stated otherwise, results are expressed as ug/l

Asbestos Analysis

CH Denotes Chrysotile

TR Denotes Tremolite

CR Denotes Crocidolite

AC Denotes Actinolite

AM Denotes Amosite

AN Denotes Anthophyllite

NAIIS No Asbestos Identified in Sample

NADIS No Asbestos Detected In Sample

Symbol Reference

^ Sub-contracted analysis.

\$\$ Unable to analyse due to the nature of the sample

¶ Samples submitted for this analyte were not preserved on site in accordance with laboratory protocols.

This may have resulted in deterioration of the sample(s) during transit to the laboratory.

Consequently the reported data may not represent the concentration of the target analyte present in the sample at the time of sampling

¥ Results for guidance only due to possible interference

& Blank corrected result

I.S Insufficient sample to complete requested analysis

I.S(g) Insufficient sample to re-analyse, results for guidance only

Intf Unable to analyse due to interferences

N.D Not determined

N.Det Not detected

N.F No Flow

NS Information Not Supplied

Req Analysis requested, see attached sheets for results

P Raised detection limit due to nature of the sample

* All accreditation has been removed by the laboratory for this result

‡ MCERTS accreditation has been removed for this result

§ accreditation has been removed for this result as it is a non-accredited matrix


Note: The Laboratory may only claim that data is accredited when all of the requirements of our Quality System have been met. Where these requirements have not been met the laboratory may elect to include the data in its final report and remove the accreditation from individual data items if it believes that the validity of the data has not been affected. If further details are required of the circumstances which have led to the removal of accreditation then please do not hesitate to contact the laboratory.

APPENDIX E
PHOTOGRAPHS

Rotary Cores
Trial Pits

Plate 1 to 6
Plate 7 to 21

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 1
--------	--	---------

Photographs




Notes:	Project Project No. Carried out for	VPI IMMINGHAM A8015-18 AECOM	Plate 2
--------	---	------------------------------------	------------

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate <p style="text-align: center;">3</p>
--------	--	--

Photographs




Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

4

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 5
--------	---	----------------

Photographs



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 6
--------	--	---------

Photographs



TP1



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 7
--------	--	---------



TP1 Spoil

Notes:	<p>Project VPI IMMINGHAM</p> <p>Project No. A8015-18</p> <p>Carried out for AECOM</p>	Plate 8
--------	---	-------------------

Photographs



TP2



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 9
--------	--	---------



TP2 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

10



TP3



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 11
--------	--	----------



TP3 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

12



TP5



Notes:	<table border="0"> <tr> <td>Project</td> <td>VPI IMMINGHAM</td> </tr> <tr> <td>Project No.</td> <td>A8015-18</td> </tr> <tr> <td>Carried out for</td> <td>AECOM</td> </tr> </table>	Project	VPI IMMINGHAM	Project No.	A8015-18	Carried out for	AECOM	<table border="0"> <tr> <td>Plate</td> <td>13</td> </tr> </table>	Plate	13
Project	VPI IMMINGHAM									
Project No.	A8015-18									
Carried out for	AECOM									
Plate	13									



TP6



Notes:	Project VPI IMMINGHAM Project No. A8015-18 Carried out for AECOM	Plate 14
--------	--	----------



TP6 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

15



TP9 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

16



TP10



Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

17



TP10 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

18

Photographs



TT02



Notes:

Project VPI IMMINGHAM
 Project No. A8015-18
 Carried out for AECOM

Plate

19



TT02 Spoil

Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

20



TT03



Notes:

Project VPI IMMINGHAM
Project No. A8015-18
Carried out for AECOM

Plate

21

Appendix D Laboratory Certifications



Exova Jones Environmental

Registered Address : Exova (UK) Ltd, Lochend Industrial Estate, Newbridge, Midlothian, EH28 8PL

Unit 3 Deeside Point
Zone 3
Deeside Industrial Park
Deeside
CH5 2UA

AECOM
2 City Walk
Leeds
LS11 9AR

Tel: +44 (0) 1244 833780
Fax: +44 (0) 1244 833781



Attention : Alex Freeman

Date : 23rd August, 2018

Your reference : 60569745

Our reference : Test Report 18/7222 Batch 1 18/5333 Batch 1 18/5166 Batch 1 18/5455 Batch 1 18/5

Location : VP1 (TLOR)

Date samples received :

Status : Final report

Issue : 1

Compiled By:



Simon Gomery BSc
Project Manager

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5166	18/5166	18/5166	18/5166	18/5166	18/5166	18/5166	18/5166	18/5333	18/5333	18/5333	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	1-3	4-6	7-9	10-12	13-15	16-18	19-21	1-3	4-6	7-9				
Sample ID	BH06	BH01	TT03	TT02	WS01	WS04	TP10	TT01	TP09	TP07				
Depth	0.40-0.70	0.45-0.70	0.00-1.40	0.50-1.20	1.00-1.25	0.50	0.40-0.60	1.70-1.90	0.30-0.40	1.30-1.60				
COC No / misc														
Containers	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B				
Sample Date	05/04/2018	05/04/2018	06/04/2018	06/04/2018	06/04/2018	06/04/2018	06/04/2018	09/04/2018	09/04/2018	09/04/2018				
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil				
Batch Number	1	1	1	1	1	1	1	1	1	1				
Date of Receipt	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	11/04/2018	11/04/2018	11/04/2018	LOD/LOR	Units	Method No.	
Arsenic ^{#M}	10.7	NDP	9.8	10.8	NDP	8.9	10.7	9.0	6.8	9.4	<0.5	mg/kg	TM30/PM15	
Barium ^{#M}	163	NDP	98	144	NDP	169	112	112	65	127	<1	mg/kg	TM30/PM15	
Beryllium	4.2	NDP	1.0	1.5	NDP	1.3	1.3	1.4	0.7	1.3	<0.5	mg/kg	TM30/PM15	
Cadmium ^{#M}	<0.1	NDP	0.1	0.2	NDP	<0.1	0.2	0.2	0.3	0.2	<0.1	mg/kg	TM30/PM15	
Chromium ^{#M}	81.5	NDP	106.0	75.9	NDP	85.2	87.6	52.6	44.9	69.0	<0.5	mg/kg	TM30/PM15	
Copper ^{#M}	13	NDP	13	21	NDP	15	21	16	11	9	<1	mg/kg	TM30/PM15	
Lead ^{#M}	15	NDP	19	20	NDP	16	26	13	11	15	<5	mg/kg	TM30/PM15	
Mercury ^{#M}	<0.1	NDP	<0.1	<0.1	NDP	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	mg/kg	TM30/PM15	
Nickel ^{#M}	19.7	NDP	23.0	30.9	NDP	30.1	26.4	32.4	19.0	28.6	<0.7	mg/kg	TM30/PM15	
Selenium ^{#M}	2	NDP	1	<1	NDP	2	<1	2	2	2	<1	mg/kg	TM30/PM15	
Total Sulphate as SO4 ^{#M}	-	NDP	-	-	NDP	-	-	-	-	-	<50	mg/kg	TM50/PM29	
Vanadium	79	NDP	56	62	NDP	54	56	46	30	46	<1	mg/kg	TM30/PM15	
Water Soluble Boron ^{#M}	2.5	NDP	1.2	1.7	NDP	2.1	1.5	1.7	0.9	1.0	<0.1	mg/kg	TM74/PM32	
Zinc ^{#M}	53	NDP	57	71	NDP	67	106	61	73	62	<5	mg/kg	TM30/PM15	
Arsenic	-	21.0	-	-	16.3	-	-	-	-	-	<0.5	mg/kg	TM30/PM62	
Barium	-	504	-	-	310	-	-	-	-	-	<1	mg/kg	TM30/PM62	
Beryllium	-	2.1	-	-	1.9	-	-	-	-	-	<0.5	mg/kg	TM30/PM62	
Cadmium	-	3.1	-	-	1.6	-	-	-	-	-	<0.1	mg/kg	TM30/PM62	
Chromium	-	79.8	-	-	68.7	-	-	-	-	-	<0.5	mg/kg	TM30/PM62	
Copper	-	148	-	-	113	-	-	-	-	-	<1	mg/kg	TM30/PM62	
Lead	-	124	-	-	73	-	-	-	-	-	<5	mg/kg	TM30/PM62	
Mercury	-	1.7	-	-	<0.1	-	-	-	-	-	<0.1	mg/kg	TM30/PM62	
Nickel	-	163.1	-	-	92.4	-	-	-	-	-	<0.7	mg/kg	TM30/PM62	
Selenium	-	10	-	-	4	-	-	-	-	-	<1	mg/kg	TM30/PM62	
Total Sulphate as SO4	-	8841	-	-	10971	-	-	-	-	-	<50	mg/kg	TM50/PM29	
Vanadium	-	338	-	-	231	-	-	-	-	-	<1	mg/kg	TM30/PM62	
Water Soluble Boron	-	2.9	-	-	2.6	-	-	-	-	-	<0.1	mg/kg	TM74/PM61	
Zinc	-	1275	-	-	663	-	-	-	-	-	<5	mg/kg	TM30/PM62	
VOC TICs	-	See Attached	-	-	ND	-	-	-	-	-		None	TM15/PM10	
Methyl Tertiary Butyl Ether ^{#M}	-	<6	-	-	<6	-	-	-	-	-	<6	ug/kg	TM15/PM10	
Benzene ^{#M}	-	46	-	-	47	-	-	-	-	-	<5	ug/kg	TM15/PM10	
Toluene ^{#M}	-	7	-	-	15	-	-	-	-	-	<3	ug/kg	TM15/PM10	
Ethylbenzene ^{#M}	-	60	-	-	31	-	-	-	-	-	<3	ug/kg	TM15/PM10	
p/m-Xylene ^{#M}	-	114	-	-	89	-	-	-	-	-	<4	ug/kg	TM15/PM10	
o-Xylene ^{#M}	-	36	-	-	31	-	-	-	-	-	<4	ug/kg	TM15/PM10	
Surrogate Recovery Toluene D8	-	57	-	-	57	-	-	-	-	-	<0	%	TM15/PM10	
Surrogate Recovery 4-Bromofluorobenzene	-	59	-	-	55	-	-	-	-	-	<0	%	TM15/PM10	
SVOC TICs	-	See Attached _{AB}	-	-	See Attached _{AB}	-	-	-	-	-		None	TM16/PM8	

Exova Jones Environmental

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5166	18/5166	18/5166	18/5166	18/5166	18/5166	18/5166	18/5333	18/5333	18/5333	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	1-3	4-6	7-9	10-12	13-15	16-18	19-21	1-3	4-6	7-9			
Sample ID	BH06	BH01	TT03	TT02	WS01	WS04	TP10	TT01	TP09	TP07			
Depth	0.40-0.70	0.45-0.70	0.00-1.40	0.50-1.20	1.00-1.25	0.50	0.40-0.60	1.70-1.90	0.30-0.40	1.30-1.60			
COC No / misc													
Containers	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B	V J B			
Sample Date	05/04/2018	05/04/2018	06/04/2018	06/04/2018	06/04/2018	06/04/2018	06/04/2018	09/04/2018	09/04/2018	09/04/2018			
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil			
Batch Number	1	1	1	1	1	1	1	1	1	1			
Date of Receipt	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	07/04/2018	11/04/2018	11/04/2018	11/04/2018	LOD/LOR	Units	Method No.
TPH CWG													
Aliphatics													
>C5-C6 ^{#M}	-	<0.1 ^{SV}	-	-	<0.1 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>C6-C8 ^{#M}	-	<0.1 ^{SV}	-	-	0.2 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>C8-C10	-	1.0 ^{SV}	-	-	1.1 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>C10-C12 ^{#M}	-	588.8	-	-	51.8	-	-	-	-	-	<0.2	mg/kg	TM5/PM8/PM16
>C12-C16 ^{#M}	-	1627	-	-	343	-	-	-	-	-	<4	mg/kg	TM5/PM8/PM16
>C16-C21 ^{#M}	-	2885	-	-	977	-	-	-	-	-	<7	mg/kg	TM5/PM8/PM16
>C21-C35 ^{#M}	-	5172	-	-	2523	-	-	-	-	-	<7	mg/kg	TM5/PM8/PM16
Total aliphatics C5-35	-	10274	-	-	3896	-	-	-	-	-	<19	mg/kg	TM5/PM8/PM16/PM12/PM10
Aromatics													
>C5-EC7 [#]	-	<0.1 ^{SV}	-	-	<0.1 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>EC7-EC8 [#]	-	<0.1 ^{SV}	-	-	<0.1 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>EC8-EC10 ^{#M}	-	<0.1 ^{SV}	-	-	<0.1 ^{SV}	-	-	-	-	-	<0.1	mg/kg	TM36/PM12
>EC10-EC12 [#]	-	92.9	-	-	10.3	-	-	-	-	-	<0.2	mg/kg	TM5/PM8/PM16
>EC12-EC16 [#]	-	809	-	-	104	-	-	-	-	-	<4	mg/kg	TM5/PM8/PM16
>EC16-EC21 [#]	-	3404	-	-	629	-	-	-	-	-	<7	mg/kg	TM5/PM8/PM16
>EC21-EC35 [#]	-	8205	-	-	3203	-	-	-	-	-	<7	mg/kg	TM5/PM8/PM16
Total aromatics C5-35 [#]	-	12511	-	-	3946	-	-	-	-	-	<19	mg/kg	TM5/PM8/PM16/PM12/PM10
Total aliphatics and aromatics(C5-35)	-	22785	-	-	7842	-	-	-	-	-	<38	mg/kg	TM5/PM8/PM16/PM12/PM10
Natural Moisture Content	20.9	NDP	15.5	20.5	NDP	17.5	17.1	21.1	11.9	13.7	<0.1	%	PM4/PM0
Ammoniacal Nitrogen as N	-	-	-	-	-	-	-	-	-	-	<0.6	mg/kg	TM38/PM20
Ammoniacal Nitrogen as NH4 Chloride ^{#M}	0.8	39.3	<0.6	<0.6	30.5	<0.6	1.5	<0.6	<0.6	<0.6	<0.6	mg/kg	TM38/PM20
Chloride (2:1 Ext BRE)	-	NDP	-	-	NDP	-	-	-	-	-	<2	mg/kg	TM38/PM20
Chloride	-	-	-	-	-	-	-	-	-	-	<0.002	g/l	TM38/PM60
Chloride	-	39	-	-	89	-	-	-	-	-	<2	mg/kg	TM38/PM60
Fluoride	-	4.5	-	-	3.7	-	-	-	-	-	<0.3	mg/kg	TM173/PM20
Hexavalent Chromium [#]	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	mg/kg	TM38/PM20
Nitrate as N	-	-	-	-	-	-	-	-	-	-	<2.5	mg/kg	TM38/PM20
Nitrate as NO3	-	NDP	-	-	NDP	-	-	-	-	-	<2.5	mg/kg	TM38/PM20
Nitrate as NO3	-	<2.5	-	-	<2.5	-	-	-	-	-	<2.5	mg/kg	TM38/PM60
Nitrate as N	-	-	-	-	-	-	-	-	-	-	<2.5	mg/kg	TM38/PM60
Sulphate as SO4 (2:1 Ext) ^{#M}	-	-	-	-	-	-	-	-	-	-	<0.0015	g/l	TM38/PM20
Chromium III	81.5	NDP	106.0	75.9	NDP	85.2	87.6	52.6	44.9	69.0	<0.5	mg/kg	NONE/NONE
Chromium III	-	79.8	-	-	68.7	-	-	-	-	-	<0.5	mg/kg	NONE/NONE
Organic Matter	1.2	NDP	1.5	2.1	NDP	1.0	2.0	0.7	0.7	0.8	<0.2	%	TM21/PM24
Sulphide	-	53	-	-	25	-	-	-	-	-	<10	mg/kg	TM107/PM119
pH ^{#M}	8.07	7.31	7.69	7.78	7.29	8.50	7.26	7.97	8.46	8.25	<0.01	pH units	TM73/PM11
Sample Type	Clay	NDP	Clay	Clay	NDP	Clay	Clay	Clay	Clay	Clay	None		PM13/PM0

Please include all sections of this report if it is reproduced

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5333	18/5333	18/5333	18/5333	18/5333	18/5333	18/5384	18/5384	18/5384	18/5384	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	13-15	16-18	19-21	22-24	25-27	28-29	1-3	7-9	13-15	19-21	LOD/LOR	Units	Method No.
Sample ID	TP08	WS02	TP05	WS05	TP04	WS03	TP06	TP01	TP02	WS06			
Depth	0.20-0.50	0.00-0.50	0.50-0.70	0.50-1.00	0.80-1.00	0.00-1.20	0.40-0.60	0.70-0.90	0.30-0.50	0.00-1.20			
COC No / misc													
Containers	V J B	V J B	V J B	V J B	V J B	V B	V J B	V J B	V J B	V J B			
Sample Date	09/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	11/04/2018	11/04/2018	11/04/2018			
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil			
Batch Number	1	1	1	1	1	1	1	1	1	1			
Date of Receipt	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	12/04/2018	12/04/2018	12/04/2018	12/04/2018			
Arsenic ^{#M}	7.2	11.4	9.0	10.5	7.4	7.3	NDP	NDP	NDP	6.4	<0.5	mg/kg	TM30/PM15
Barium ^{#M}	117	121	162	147	116	169	NDP	NDP	NDP	133	<1	mg/kg	TM30/PM15
Beryllium	1.4	1.3	1.3	1.5	1.1	1.5	NDP	NDP	NDP	1.4	<0.5	mg/kg	TM30/PM15
Cadmium ^{#M}	<0.1	0.3	0.2	0.4	0.2	0.2	NDP	NDP	NDP	0.2	<0.1	mg/kg	TM30/PM15
Chromium ^{#M}	81.4	60.0	60.4	71.5	64.0	65.2	NDP	NDP	NDP	50.1	<0.5	mg/kg	TM30/PM15
Copper ^{#M}	15	20	15	28	11	45	NDP	NDP	NDP	10	<1	mg/kg	TM30/PM15
Lead ^{#M}	15	22	11	34	9	42	NDP	NDP	NDP	10	<5	mg/kg	TM30/PM15
Mercury ^{#M}	<0.1	<0.1	<0.1	<0.1	<0.1	0.2	NDP	NDP	NDP	<0.1	<0.1	mg/kg	TM30/PM15
Nickel ^{#M}	37.3	36.1	28.2	29.8	26.5	45.8	NDP	NDP	NDP	33.3	<0.7	mg/kg	TM30/PM15
Selenium ^{#M}	<1	1	2	2	2	<1	NDP	NDP	NDP	<1	<1	mg/kg	TM30/PM15
Total Sulphate as SO4 ^{#M}	-	701	-	2252	-	6510	NDP	NDP	NDP	-	<50	mg/kg	TM50/PM29
Vanadium	52	67	45	69	39	87	NDP	NDP	NDP	45	<1	mg/kg	TM30/PM15
Water Soluble Boron ^{#M}	1.2	1.8	1.6	2.2	1.5	3.4	NDP	NDP	NDP	1.0	<0.1	mg/kg	TM74/PM32
Zinc ^{#M}	66	131	56	149	50	231	NDP	NDP	NDP	113	<5	mg/kg	TM30/PM15
Arsenic	-	-	-	-	-	-	10.3	26.3	21.6	-	<0.5	mg/kg	TM30/PM62
Barium	-	-	-	-	-	-	118	369	337	-	<1	mg/kg	TM30/PM62
Beryllium	-	-	-	-	-	-	1.3	1.9	1.8	-	<0.5	mg/kg	TM30/PM62
Cadmium	-	-	-	-	-	-	0.3	1.8	0.8	-	<0.1	mg/kg	TM30/PM62
Chromium	-	-	-	-	-	-	36.0	75.1	63.4	-	<0.5	mg/kg	TM30/PM62
Copper	-	-	-	-	-	-	18	205	158	-	<1	mg/kg	TM30/PM62
Lead	-	-	-	-	-	-	28	103	71	-	<5	mg/kg	TM30/PM62
Mercury	-	-	-	-	-	-	<0.1	2.3	1.7	-	<0.1	mg/kg	TM30/PM62
Nickel	-	-	-	-	-	-	29.7	121.9	81.6	-	<0.7	mg/kg	TM30/PM62
Selenium	-	-	-	-	-	-	<1	4	4	-	<1	mg/kg	TM30/PM62
Total Sulphate as SO4	-	-	-	-	-	-	856	16251 ^{AB}	6783	-	<50	mg/kg	TM50/PM29
Vanadium	-	-	-	-	-	-	58	275	186	-	<1	mg/kg	TM30/PM62
Water Soluble Boron	-	-	-	-	-	-	4.4	3.4	3.6	-	<0.1	mg/kg	TM74/PM61
Zinc	-	-	-	-	-	-	84	947	623	-	<5	mg/kg	TM30/PM62
VOC TICs	-	ND	-	ND	-	ND	ND	See Attached	ND	-		None	TM15/PM10
Methyl Tertiary Butyl Ether ^{#M}	-	<6	-	<6	-	<6	<6	<6	<6	-	<6	ug/kg	TM15/PM10
Benzene ^{#M}	-	<5	-	<5	-	<5	<5	45	60	-	<5	ug/kg	TM15/PM10
Toluene ^{#M}	-	<3	-	<3	-	<3	<3	5	19	-	<3	ug/kg	TM15/PM10
Ethylbenzene ^{#M}	-	<3	-	<3	-	<3	<3	39	121	-	<3	ug/kg	TM15/PM10
p/m-Xylene ^{#M}	-	<4	-	<4	-	9	<4	213	115	-	<4	ug/kg	TM15/PM10
o-Xylene ^{#M}	-	<4	-	<4	-	<4	<4	49	54	-	<4	ug/kg	TM15/PM10
Surrogate Recovery Toluene D8	-	93	-	92	-	78	85	52	52	-	<0	%	TM15/PM10
Surrogate Recovery 4-Bromofluorobenzene	-	86	-	77	-	64	74	58	54	-	<0	%	TM15/PM10
SVOC TICs	-	ND	-	ND	-	ND	ND	See Attached	See Attached	-		None	TM16/PM8

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5333	18/5333	18/5333	18/5333	18/5333	18/5333	18/5333	18/5384	18/5384	18/5384	18/5384	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	13-15	16-18	19-21	22-24	25-27	28-29	1-3	7-9	13-15	19-21				
Sample ID	TP08	WS02	TP05	WS05	TP04	WS03	TP06	TP01	TP02	WS06				
Depth	0.20-0.50	0.00-0.50	0.50-0.70	0.50-1.00	0.80-1.00	0.00-1.20	0.40-0.60	0.70-0.90	0.30-0.50	0.00-1.20				
COC No / misc														
Containers	V J B	V J B	V J B	V J B	V J B	V B	V J B	V J B	V J B	V J B				
Sample Date	09/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	11/04/2018	11/04/2018	11/04/2018				
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil				
Batch Number	1	1	1	1	1	1	1	1	1	1				
Date of Receipt	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	12/04/2018	12/04/2018	12/04/2018	12/04/2018	LOD/LOR	Units	Method No.	
TPH CWG														
Aliphatics														
>C5-C6 ^{#M}	-	<0.1	-	<0.1	-	<0.1	<0.1	<0.1 ^{SV}	<0.1 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>C6-C8 ^{#M}	-	<0.1	-	<0.1	-	<0.1	<0.1	<0.1 ^{SV}	1.3 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>C8-C10	-	<0.1	-	<0.1	-	<0.1	<0.1	0.3 ^{SV}	5.6 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>C10-C12 ^{#M}	-	<0.2	-	4.9	-	9.7	<0.2	154.5	325.9	-	<0.2	mg/kg	TM5/PM8/PM16	
>C12-C16 ^{#M}	-	9	-	52	-	101	<4	789	925	-	<4	mg/kg	TM5/PM8/PM16	
>C16-C21 ^{#M}	-	26	-	256	-	367	<7	1715	1534	-	<7	mg/kg	TM5/PM8/PM16	
>C21-C35 ^{#M}	-	82	-	675	-	876	<7	3414	3001	-	<7	mg/kg	TM5/PM8/PM16	
Total aliphatics C5-35	-	117	-	988	-	1354	<19	6073	5793	-	<19	mg/kg	TM5/PM8/PM16/PM12/PM10	
Aromatics														
>C5-EC7 [#]	-	<0.1	-	<0.1	-	<0.1	<0.1	<0.1 ^{SV}	<0.1 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>EC7-EC8 [#]	-	<0.1	-	<0.1	-	<0.1	<0.1	<0.1 ^{SV}	<0.1 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>EC8-EC10 ^{#M}	-	<0.1	-	<0.1	-	<0.1	<0.1	<0.1 ^{SV}	<0.1 ^{SV}	-	<0.1	mg/kg	TM36/PM12	
>EC10-EC12 [#]	-	<0.2	-	<0.2	-	<0.2	<0.2	33.9	103.8	-	<0.2	mg/kg	TM5/PM8/PM16	
>EC12-EC16 [#]	-	<4	-	32	-	37	<4	358	688	-	<4	mg/kg	TM5/PM8/PM16	
>EC16-EC21 [#]	-	17	-	322	-	357	<7	1663	1953	-	<7	mg/kg	TM5/PM8/PM16	
>EC21-EC35 [#]	-	158	-	1581	-	1790	<7	5036	5372	-	<7	mg/kg	TM5/PM8/PM16	
Total aromatics C5-35 [#]	-	175	-	1935	-	2184	<19	7091	8117	-	<19	mg/kg	TM5/PM8/PM16/PM12/PM10	
Total aliphatics and aromatics(C5-35)	-	292	-	2923	-	3538	<38	13164	13910	-	<38	mg/kg	TM5/PM8/PM16/PM12/PM10	
Natural Moisture Content	22.0	20.7	23.8	22.0	17.6	34.3	NDP	NDP	NDP	20.4	<0.1	%	PM4/PM0	
Ammoniacal Nitrogen as N	-	-	-	-	-	-	-	-	-	-	<0.6	mg/kg	TM38/PM20	
Ammoniacal Nitrogen as NH4 Chloride ^{#M}	<0.6	2.6	<0.6	14.2	<0.6	20.2	8.3	41.7	13.5	<0.6	<0.6	mg/kg	TM38/PM20	
Chloride (2:1 Ext BRE)	-	1582	-	54	-	58	NDP	NDP	NDP	-	<2	mg/kg	TM38/PM20	
Chloride	-	-	-	-	-	-	-	-	-	-	<2	mg/kg	TM38/PM60	
Fluoride	-	0.9	-	3.7	-	2.3	6.9	8.0	16.4	-	<0.3	mg/kg	TM173/PM20	
Hexavalent Chromium [#]	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	mg/kg	TM38/PM20	
Nitrate as N	-	-	-	-	-	-	-	-	-	-	<2.5	mg/kg	TM38/PM20	
Nitrate as NO3	-	<2.5	-	<2.5	-	<2.5	NDP	NDP	NDP	-	<2.5	mg/kg	TM38/PM20	
Nitrate as NO3	-	-	-	-	-	-	<2.5	<2.5	<2.5	-	<2.5	mg/kg	TM38/PM60	
Nitrate as N	-	-	-	-	-	-	-	-	-	-	<2.5	mg/kg	TM38/PM60	
Sulphate as SO4 (2:1 Ext) ^{#M}	-	-	-	-	-	-	-	-	-	-	<0.0015	g/l	TM38/PM20	
Chromium III	81.4	60.0	60.4	71.5	64.0	65.2	NDP	NDP	NDP	50.1	<0.5	mg/kg	NONE/NONE	
Chromium III	-	-	-	-	-	-	-	-	-	-	<0.5	mg/kg	NONE/NONE	
Organic Matter	0.7	2.0	1.0	3.9	0.6	7.9	NDP	NDP	NDP	0.6	<0.2	%	TM21/PM24	
Sulphide	-	<10	-	<100 ^{AB}	-	53	<10	30	21	-	<10	mg/kg	TM107/PM119	
pH ^{#M}	7.85	7.52	8.52	7.55	8.09	7.34	7.67	7.22	7.67	8.28	<0.01	pH units	TM73/PM11	
Sample Type	Clay	Clay	Clay	Clay	Clay	Clay	NDP	NDP	NDP	Clay	None		PM13/PM0	

Please include all sections of this report if it is reproduced

Exova Jones Environmental

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5333	18/5333	18/5333	18/5333	18/5333	18/5333	18/5384	18/5384	18/5384	18/5384	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	13-15	16-18	19-21	22-24	25-27	28-29	1-3	7-9	13-15	19-21			
Sample ID	TP08	WS02	TP05	WS05	TP04	WS03	TP06	TP01	TP02	WS06			
Depth	0.20-0.50	0.00-0.50	0.50-0.70	0.50-1.00	0.80-1.00	0.00-1.20	0.40-0.60	0.70-0.90	0.30-0.50	0.00-1.20			
COC No / misc													
Containers	V J B	V J B	V J B	V J B	V J B	V B	V J B	V J B	V J B	V J B			
Sample Date	09/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	11/04/2018	11/04/2018	11/04/2018			
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil			
Batch Number	1	1	1	1	1	1	1	1	1	1	LOD/LOR	Units	Method No.
Date of Receipt	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	11/04/2018	12/04/2018	12/04/2018	12/04/2018	12/04/2018			
Sample Colour	Medium Brown	Medium Brown	Medium Brown	Medium Brown	Medium Brown	Medium Brown	NDP	NDP	NDP	Medium Brown		None	PM13/PM0
Other Items	chalk, carbon	carbon	vegetation, chalk	vegetation, carbon, stones	chalk	vegetation, stones	NDP	NDP	NDP	stones, chalk, vegetation		None	PM13/PM0

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5384	18/5384	18/5384	18/5455	18/5775	18/5775							
J E Sample No.	22-24	25-27	28-30	1-3	1-3	4-6							
Sample ID	BH03	WS07	WS08	BH02	BH04	BH05							
Depth	1.50-2.00	0.30-0.80	0.00-1.20	0.60-1.00	0.50-1.20	1.80-2.25							
COC No / misc													
Containers	V J B	V J B	V J B	V J B	V J B	V J B							
Sample Date	10/04/2018	11/04/2018	11/04/2018	11/04/2018	16/04/2018	17/04/2018							
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil							
Batch Number	1	1	1	1	1	1							
Date of Receipt	12/04/2018	12/04/2018	12/04/2018	13/04/2018	18/04/2018	18/04/2018							
										Please see attached notes for all abbreviations and acronyms			
											LOD/LOR	Units	Method No.
Arsenic ^{#M}	8.9	7.9	12.7	NDP	9.3	8.0					<0.5	mg/kg	TM30/PM15
Barium ^{#M}	133	120	116	NDP	127	129					<1	mg/kg	TM30/PM15
Beryllium	1.2	1.0	1.3	NDP	1.4	1.2					<0.5	mg/kg	TM30/PM15
Cadmium ^{#M}	0.2	0.6	0.2	NDP	0.2	0.1					<0.1	mg/kg	TM30/PM15
Chromium ^{#M}	59.8	67.0	112.0	NDP	62.1	34.6					<0.5	mg/kg	TM30/PM15
Copper ^{#M}	11	8	6	NDP	14	11					<1	mg/kg	TM30/PM15
Lead ^{#M}	13	21	19	NDP	12	12					<5	mg/kg	TM30/PM15
Mercury ^{#M}	<0.1	<0.1	<0.1	NDP	<0.1	<0.1					<0.1	mg/kg	TM30/PM15
Nickel ^{#M}	39.4	22.3	27.6	NDP	30.2	29.6					<0.7	mg/kg	TM30/PM15
Selenium ^{#M}	<1	<1	1	NDP	<1	<1					<1	mg/kg	TM30/PM15
Total Sulphate as SO4 ^{#M}	-	-	-	NDP	-	439					<50	mg/kg	TM50/PM29
Vanadium	42	40	53	NDP	49	36					<1	mg/kg	TM30/PM15
Water Soluble Boron ^{#M}	0.8	1.2	1.1	NDP	1.0	1.0					<0.1	mg/kg	TM74/PM32
Zinc ^{#M}	61	93	79	NDP	55	59					<5	mg/kg	TM30/PM15
Arsenic	-	-	-	35.8	-	-					<0.5	mg/kg	TM30/PM62
Barium	-	-	-	350	-	-					<1	mg/kg	TM30/PM62
Beryllium	-	-	-	2.3	-	-					<0.5	mg/kg	TM30/PM62
Cadmium	-	-	-	1.7	-	-					<0.1	mg/kg	TM30/PM62
Chromium	-	-	-	82.2	-	-					<0.5	mg/kg	TM30/PM62
Copper	-	-	-	291	-	-					<1	mg/kg	TM30/PM62
Lead	-	-	-	126	-	-					<5	mg/kg	TM30/PM62
Mercury	-	-	-	<0.1	-	-					<0.1	mg/kg	TM30/PM62
Nickel	-	-	-	111.9	-	-					<0.7	mg/kg	TM30/PM62
Selenium	-	-	-	4	-	-					<1	mg/kg	TM30/PM62
Total Sulphate as SO4	-	-	-	44355 ^{AB}	-	-					<50	mg/kg	TM50/PM29
Vanadium	-	-	-	227	-	-					<1	mg/kg	TM30/PM62
Water Soluble Boron	-	-	-	4.2	-	-					<0.1	mg/kg	TM74/PM61
Zinc	-	-	-	937	-	-					<5	mg/kg	TM30/PM62
VOC TICs	-	-	-	See Attached	-	-						None	TM15/PM10
Methyl Tertiary Butyl Ether ^{#M}	-	-	-	<6	-	<6					<6	ug/kg	TM15/PM10
Benzene ^{#M}	-	-	-	28	-	<5					<5	ug/kg	TM15/PM10
Toluene ^{#M}	-	-	-	6	-	<3					<3	ug/kg	TM15/PM10
Ethylbenzene ^{#M}	-	-	-	24	-	<3					<3	ug/kg	TM15/PM10
p/m-Xylene ^{#M}	-	-	-	78	-	<4					<4	ug/kg	TM15/PM10
o-Xylene ^{#M}	-	-	-	23	-	<4					<4	ug/kg	TM15/PM10
Surrogate Recovery Toluene D8	-	-	-	51	-	111					<0	%	TM15/PM10
Surrogate Recovery 4-Bromofluorobenzene	-	-	-	51	-	103					<0	%	TM15/PM10
SVOC TICs	-	-	-	ND ^{AB}	-	-						None	TM16/PM8

Please include all sections of this report if it is reproduced

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5384	18/5384	18/5384	18/5455	18/5775	18/5775																
J E Sample No.	22-24	25-27	28-30	1-3	1-3	4-6																
Sample ID	BH03	WS07	WS08	BH02	BH04	BH05																
Depth	1.50-2.00	0.30-0.80	0.00-1.20	0.60-1.00	0.50-1.20	1.80-2.25																
COC No / misc																						
Containers	V J B	V J B	V J B	V J B	V J B	V J B																
Sample Date	10/04/2018	11/04/2018	11/04/2018	11/04/2018	16/04/2018	17/04/2018																
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil																
Batch Number	1	1	1	1	1	1																
Date of Receipt	12/04/2018	12/04/2018	12/04/2018	13/04/2018	18/04/2018	18/04/2018																
							LOD/LOR	Units	Method No.													
TPH CWG																						
Aliphatics																						
>C5-C6 ^{#M}	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>C6-C8 ^{#M}	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>C8-C10	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>C10-C12 ^{#M}	-	-	-	23.2	-	<0.2	<0.2	mg/kg	TM5/PM8/PM16													
>C12-C16 ^{#M}	-	-	-	251	-	<4	<4	mg/kg	TM5/PM8/PM16													
>C16-C21 ^{#M}	-	-	-	858	-	<7	<7	mg/kg	TM5/PM8/PM16													
>C21-C35 ^{#M}	-	-	-	2127	-	<7	<7	mg/kg	TM5/PM8/PM16													
Total aliphatics C5-35	-	-	-	3259	-	<19	<19	mg/kg	TM5/PM8/PM16/PM12/PM10													
Aromatics																						
>C5-EC7 [#]	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>EC7-EC8 [#]	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>EC8-EC10 ^{#M}	-	-	-	<0.1	-	<0.1	<0.1	mg/kg	TM36/PM12													
>EC10-EC12 [#]	-	-	-	<0.2	-	<0.2	<0.2	mg/kg	TM5/PM8/PM16													
>EC12-EC16 [#]	-	-	-	<4	-	<4	<4	mg/kg	TM5/PM8/PM16													
>EC16-EC21 [#]	-	-	-	<7	-	<7	<7	mg/kg	TM5/PM8/PM16													
>EC21-EC35 [#]	-	-	-	40	-	<7	<7	mg/kg	TM5/PM8/PM16													
Total aromatics C5-35 [#]	-	-	-	40	-	<19	<19	mg/kg	TM5/PM8/PM16/PM12/PM10													
Total aliphatics and aromatics(C5-35)	-	-	-	3299	-	<38	<38	mg/kg	TM5/PM8/PM16/PM12/PM10													
Natural Moisture Content	17.1	17.6	24.9	NDP	16.0	16.5	<0.1	%	PM4/PM0													
Ammoniacal Nitrogen as N	-	-	-	-	-	<0.6	<0.6	mg/kg	TM38/PM20													
Ammoniacal Nitrogen as NH4 Chloride ^{#M}	<0.6	<0.6	<0.6	12.8	-	-	<0.6	mg/kg	TM38/PM20													
Chloride (2:1 Ext BRE)	-	-	-	NDP	-	17	<2	mg/kg	TM38/PM20													
Chloride	-	-	-	11	-	-	<0.002	g/l	TM38/PM60													
Fluoride	-	-	-	11.2	-	<0.3	<0.3	mg/kg	TM173/PM20													
Hexavalent Chromium [#]	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	<0.3	mg/kg	TM38/PM20													
Nitrate as N	-	-	-	NDP	-	-	<2.5	mg/kg	TM38/PM20													
Nitrate as NO3	-	-	-	-	-	<2.5	<2.5	mg/kg	TM38/PM20													
Nitrate as NO3	-	-	-	-	-	-	<2.5	mg/kg	TM38/PM60													
Nitrate as N	-	-	-	<2.5	-	-	<2.5	mg/kg	TM38/PM60													
Sulphate as SO4 (2:1 Ext) ^{#M}	-	-	-	-	-	0.0965	<0.0015	g/l	TM38/PM20													
Chromium III	59.8	67.0	112.0	NDP	62.1	34.6	<0.5	mg/kg	NONE/NONE													
Chromium III	-	-	-	-	-	-	<0.5	mg/kg	NONE/NONE													
Organic Matter	0.7	1.1	0.9	NDP	0.6	0.6	<0.2	%	TM21/PM24													
Sulphide	-	-	-	<10	-	-	<10	mg/kg	TM107/PM119													
pH ^{#M}	8.27	8.32	7.86	7.17	7.91	8.12	<0.01	pH units	TM73/PM11													
Sample Type	Clay	Clay	Clay	NDP	Clay	Clay	None		PM13/PM0													

Please see attached notes for all abbreviations and acronyms

Exova Jones Environmental

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Solid

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5384	18/5384	18/5384	18/5455	18/5775	18/5775													
															LOD/LOR	Units	Method No.		
J E Sample No.	22-24	25-27	28-30	1-3	1-3	4-6													
Sample ID	BH03	WS07	WS08	BH02	BH04	BH05													
Depth	1.50-2.00	0.30-0.80	0.00-1.20	0.60-1.00	0.50-1.20	1.80-2.25													
COC No / misc																			
Containers	V J B	V J B	V J B	V J B	V J B	V J B													
Sample Date	10/04/2018	11/04/2018	11/04/2018	11/04/2018	16/04/2018	17/04/2018													
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil													
Batch Number	1	1	1	1	1	1													
Date of Receipt	12/04/2018	12/04/2018	12/04/2018	13/04/2018	18/04/2018	18/04/2018													
Sample Colour	Medium Brown	Medium Brown	Medium Brown	NDP	Medium Brown	Medium Brown												None	PM13/PM0
Other Items	chalk	sand, stones,	sand,vegetation, stones	NDP	chalk, stones	chalk												None	PM13/PM0

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Liquid

Liquids/products: V=40ml vial, G=glass bottle, P=plastic bottle
H=H₂SO₄, Z=ZnAc, N=NaOH, HN=HNO₃

J E Job No.	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222					
J E Sample No.	1-7	8-14	15-21	22-28	29-35	36-42	43-49	50-56					
Sample ID	BH01	BH02	BH03	WS03	WS04	WS05	WS06	DUP01					
Depth													
COC No / misc													
Containers	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G					
Sample Date	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018					
Sample Type	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water					
Batch Number	1	1	1	1	1	1	1	1					
Date of Receipt	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018					
											LOD/LOR	Units	Method No.
Dissolved Arsenic #	<2.5	<2.5	<2.5	<2.5	<2.5	<2.5	<2.5	<2.5			<2.5	ug/l	TM30/PM14
Dissolved Barium #	57	63	63	41	53	33	44	62			<3	ug/l	TM30/PM14
Dissolved Beryllium	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5			<0.5	ug/l	TM30/PM14
Dissolved Boron	132	73	<12	49	54	178	34	<12			<12	ug/l	TM30/PM14
Dissolved Cadmium #	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5			<0.5	ug/l	TM30/PM14
Total Dissolved Chromium #	6.2	6.8	<1.5	6.3	5.4	3.3	<1.5	6.7			<1.5	ug/l	TM30/PM14
Dissolved Copper #	<7	<7	<7	<7	<7	<7	<7	<7			<7	ug/l	TM30/PM14
Dissolved Lead #	<5	<5	<5	<5	<5	<5	<5	<5			<5	ug/l	TM30/PM14
Dissolved Mercury #	<1	<1	<1	<1	<1	<1	<1	<1			<1	ug/l	TM30/PM14
Dissolved Nickel #	2	<2	5	4	3	8	4	5			<2	ug/l	TM30/PM14
Dissolved Selenium #	<3	5	16	<3	<3	<3	<3	<3			<3	ug/l	TM30/PM14
Dissolved Vanadium #	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5			<1.5	ug/l	TM30/PM14
Dissolved Zinc #	12	6	7	<3	<3	10	6	6			<3	ug/l	TM30/PM14
VOC TICs	-	-	-	ND	ND	ND	ND	-				None	TM15/PM10
Methyl Tertiary Butyl Ether #	-	-	-	<0.1	2.8	<0.2 _{AA}	<0.1	-			<0.1	ug/l	TM15/PM10
Benzene #	-	-	-	<0.5	<0.5	<0.5	<0.5	-			<0.5	ug/l	TM15/PM10
Toluene #	-	-	-	<5	<5	<5	<5	-			<5	ug/l	TM15/PM10
Ethylbenzene #	-	-	-	<1	<1	<1	<1	-			<1	ug/l	TM15/PM10
p/m-Xylene #	-	-	-	<2	<2	<2	<2	-			<2	ug/l	TM15/PM10
o-Xylene #	-	-	-	<1	<1	<1	<1	-			<1	ug/l	TM15/PM10
Surrogate Recovery Toluene D8	-	-	-	95	96	98	96	-			<0	%	TM15/PM10
Surrogate Recovery 4-Bromofluorobenzene	-	-	-	96	96	100	101	-			<0	%	TM15/PM10
TPH CWG													
Aliphatics													
>C5-C6 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM36/PM12
>C6-C8 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM36/PM12
>C8-C10 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM36/PM12
>C10-C12 #	<5	<5	<5	<5	<5	<5	<5	<5			<5	ug/l	TM5/PM16/PM30
>C12-C16 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM5/PM16/PM30
>C16-C21 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM5/PM16/PM30
>C21-C35 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM5/PM16/PM30
Total aliphatics C5-35 #	<10	<10	<10	<10	<10	<10	<10	<10			<10	ug/l	TM5/PM16/PM30

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Liquid

Liquids/products: V=40ml vial, G=glass bottle, P=plastic bottle
H=H₂SO₄, Z=ZnAc, N=NaOH, HN=HNO₃

J E Job No.	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222	18/7222				
J E Sample No.	1-7	8-14	15-21	22-28	29-35	36-42	43-49	50-56				
Sample ID	BH01	BH02	BH03	WS03	WS04	WS05	WS06	DUP01				
Depth												
COC No / misc												
Containers	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G				
Sample Date	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018	10/05/2018				
Sample Type	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water				
Batch Number	1	1	1	1	1	1	1	1				
Date of Receipt	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018	12/05/2018				
									LOD/LOR	Units	Method No.	
TPH CWG												
Aromatics												
>C5-EC7 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM36/PM12	
>EC7-EC8 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM36/PM12	
>EC8-EC10 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM36/PM12	
>EC10-EC12 #	<5	<5	<5	<5	<5	<5	<5	<5	<5	ug/l	TM5/PM16/PM30	
>EC12-EC16 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM5/PM16/PM30	
>EC16-EC21 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM5/PM16/PM30	
>EC21-EC35 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM5/PM16/PM30	
Total aromatics C5-35 #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM5/PM16/PM30	
Total aliphatics and aromatics(C5-35) #	<10	<10	<10	<10	<10	<10	<10	<10	<10	ug/l	TM5/PM16/PM30	
MTBE #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
Benzene #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
Toluene #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
Ethylbenzene #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
m/p-Xylene #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
o-Xylene #	<5	<5	<5	-	-	-	-	<5	<5	ug/l	TM31/PM12	
Sulphate as SO4 #	62.9	42.8	94.2	417.5	720.3	983.9	299.8	76.4	<0.5	mg/l	TM38/PM0	
Chloride #	24.3	18.2	26.8	563.4	1280.0	304.2	69.2	26.2	<0.3	mg/l	TM38/PM0	
Nitrate as N #	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	mg/l	TM38/PM0	
Ortho Phosphate as P #	0.19	0.15	<0.03	0.12	<0.03	<0.03	<0.03	<0.03	<0.03	mg/l	TM38/PM0	
Ammoniacal Nitrogen as N #	0.42	0.27	0.06	0.06	0.09	0.87	0.05	0.06	<0.03	mg/l	TM38/PM0	
Hexavalent Chromium	<6	<6	<6	<6	<6	<6	<6	<6	<6	ug/l	TM38/PM0	
Total Dissolved Chromium III	6	7	<6	6	<6	<6	<6	7	<6	ug/l	TM0/PM0	
Total Alkalinity as CaCO3 #	352	300	276	346	378	612	762	274	<1	mg/l	TM75/PM0	
Dissolved Organic Carbon #	<2	<2	<2	6	9	38	3	<2	<2	mg/l	TM60/PM0	
Dissolved Iron II	<0.02	<0.02	0.02	0.10	0.26	1.63	0.15	<0.02	<0.02	mg/l	TM48/PM0	
pH #	7.63	7.40	7.31	6.95	6.83	6.97	7.19	7.28	<0.01	pH units	TM73/PM0	
Total Suspended Solids #	35	<10	19	10	14	21	1787	15	<10	mg/l	TM37/PM0	

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Report : Misc

Solids: V=60g VOC jar, J=250g glass jar, T=plastic tub

J E Job No.	18/5166	18/5333	18/5384	18/5455							LOD/LOR	Units	Method No.
J E Sample No.	1-3	1-3	1-3	1-3									
Sample ID	BH06	TT01	TP06	BH02									
Depth	0.40-0.70	1.70-1.90	0.40-0.60	0.60-1.00									
COC No / misc													
Containers	V J B	V J B	V J B	V J B									
Sample Date	05/04/2018	09/04/2018	10/04/2018	11/04/2018									
Sample Type	Soil	Soil	Soil	Soil									
Batch Number	1	1	1	1									
Date of Receipt	07/04/2018	11/04/2018	12/04/2018	13/04/2018									
Sample Temperature	5.5	8.8	6.7	3.0							<0.1	Degrees C	NONE/NONE

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

SVOC Report : Solid

J E Job No.	18/5166	18/5166	18/5333	18/5333	18/5333	18/5384	18/5384	18/5384	18/5455	18/5775	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	4-6	13-15	16-18	22-24	28-29	1-3	7-9	13-15	1-3	4-6	LOD/LOR	Units	Method No.
Sample ID	BH01	WS01	WS02	WS05	WS03	TP06	TP01	TP02	BH02	BH05			
Depth	0.45-0.70	1.00-1.25	0.00-0.50	0.50-1.00	0.00-1.20	0.40-0.60	0.70-0.90	0.30-0.50	0.60-1.00	1.80-2.25			
COC No / misc Containers	V J B	V J B	V J B	V J B	V B	V J B	V J B	V J B	V J B	V J B			
Sample Date	05/04/2018	06/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	11/04/2018	11/04/2018	11/04/2018	17/04/2018			
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil			
Batch Number	1	1	1	1	1	1	1	1	1	1			
Date of Receipt	07/04/2018	07/04/2018	11/04/2018	11/04/2018	11/04/2018	12/04/2018	12/04/2018	12/04/2018	13/04/2018	18/04/2018			
SVOC MS													
Phenols													
2-Chlorophenol ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2-Methylphenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2-Nitrophenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,4-Dichlorophenol ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,4-Dimethylphenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,4,5-Trichlorophenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,4,6-Trichlorophenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Chloro-3-methylphenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Methylphenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Nitrophenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Pentachlorophenol	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Phenol ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
PAHs													
2-Chloronaphthalene ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2-Methylnaphthalene ^{#M}	1998 _{AB}	<100 _{AB}	127	44	53	<10	2857	4537	1136 _{AB}	<10	<10	ug/kg	TM16/PM8
Naphthalene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	601	1360	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Acenaphthylene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Acenaphthene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	1651	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Fluorene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	2305	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Phenanthrene ^{#M}	<100 _{AB}	<100 _{AB}	<10	124	130	110	1872	7600	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Anthracene	<100 _{AB}	<100 _{AB}	<10	41	46	50	603	1072	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Fluoranthene ^{#M}	<100 _{AB}	<100 _{AB}	<10	29	26	23	<10	1569	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Pyrene ^{#M}	<100 _{AB}	<100 _{AB}	<10	171	110	91	2469	4180	2817 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(a)anthracene	<100 _{AB}	<100 _{AB}	<10	56	89	72	662	1520	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Chrysene	<100 _{AB}	<100 _{AB}	<10	288	318	258	2415	3179	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(b)fluoranthene	<100 _{AB}	<100 _{AB}	<10	159	180	158	796	1190	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(a)pyrene	<100 _{AB}	<100 _{AB}	<10	105	89	96	938	1089	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Indeno(123cd)pyrene	<100 _{AB}	<100 _{AB}	<10	47	37	40	237	263	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Dibenzo(ah)anthracene	<100 _{AB}	<100 _{AB}	<10	38	40	50	255	346	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(ghi)perylene	<100 _{AB}	<100 _{AB}	<10	104	114	105	581	591	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(b)fluoranthene	<100 _{AB}	<100 _{AB}	<10	114	130	114	573	857	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Benzo(k)fluoranthene	<100 _{AB}	<100 _{AB}	<10	45	50	44	223	333	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Phthalates													
Bis(2-ethylhexyl) phthalate	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	1926	3119	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8
Butylbenzyl phthalate	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	<100	<100	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8
Di-n-butyl phthalate	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	<100	<100	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8
Di-n-Octyl phthalate	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	<100	<100	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8
Diethyl phthalate	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	<100	<100	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8
Dimethyl phthalate ^{#M}	<1000 _{AB}	<1000 _{AB}	<100	<100	<100	<100	<100	<100	<1000 _{AB}	<100	<100	ug/kg	TM16/PM8

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

SVOC Report : Solid

J E Job No.	18/5166	18/5166	18/5333	18/5333	18/5333	18/5384	18/5384	18/5384	18/5455	18/5775	Please see attached notes for all abbreviations and acronyms		
J E Sample No.	4-6	13-15	16-18	22-24	28-29	1-3	7-9	13-15	1-3	4-6	LOD/LOR	Units	Method No.
Sample ID	BH01	WS01	WS02	WS05	WS03	TP06	TP01	TP02	BH02	BH05			
Depth	0.45-0.70	1.00-1.25	0.00-0.50	0.50-1.00	0.00-1.20	0.40-0.60	0.70-0.90	0.30-0.50	0.60-1.00	1.80-2.25			
COC No / misc Containers	V J B	V J B	V J B	V J B	V B	V J B	V J B	V J B	V J B	V J B			
Sample Date	05/04/2018	06/04/2018	10/04/2018	10/04/2018	10/04/2018	10/04/2018	11/04/2018	11/04/2018	11/04/2018	17/04/2018			
Sample Type	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil	Soil			
Batch Number	1	1	1	1	1	1	1	1	1	1			
Date of Receipt	07/04/2018	07/04/2018	11/04/2018	11/04/2018	11/04/2018	12/04/2018	12/04/2018	12/04/2018	13/04/2018	18/04/2018			
SVOC MS													
Other SVOCs													
1,2-Dichlorobenzene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
1,2,4-Trichlorobenzene ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
1,3-Dichlorobenzene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
1,4-Dichlorobenzene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2-Nitroaniline	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,4-Dinitrotoluene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
2,6-Dinitrotoluene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
3-Nitroaniline	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Bromophenylphenylether ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Chloroaniline	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Chlorophenylphenylether	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
4-Nitroaniline	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Azobenzene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Bis(2-chloroethoxy)methane	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Bis(2-chloroethyl)ether	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Carbazole	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Dibenzofuran ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	818	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Hexachlorobenzene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Hexachlorobutadiene ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Hexachlorocyclopentadiene	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Hexachloroethane	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Isophorone ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
N-nitrosodi-n-propylamine ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Nitrobenzene ^{#M}	<100 _{AB}	<100 _{AB}	<10	<10	<10	<10	<10	<10	<100 _{AB}	<10	<10	ug/kg	TM16/PM8
Surrogate Recovery 2-Fluorobiphenyl	112 _{AB}	108 _{AB}	114	120	123	108	112	121	114 _{AB}	119	<0	%	TM16/PM8
Surrogate Recovery p-Terphenyl-d14	113 _{AB}	113 _{AB}	104	120	122	116	114	115	130 _{AB}	127	<0	%	TM16/PM8

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

SVOC Report : Liquid

J E Job No. J E Sample No.	18/7222 22-28	18/7222 29-35	18/7222 36-42	18/7222 43-49																		
Sample ID	WS03	WS04	WS05	WS06																		
Depth																						
COC No / misc Containers	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G																		
Sample Date	10/05/2018	10/05/2018	10/05/2018	10/05/2018																		
Sample Type	Ground Water	Ground Water	Ground Water	Ground Water																		
Batch Number	1	1	1	1																		
Date of Receipt	12/05/2018	12/05/2018	12/05/2018	12/05/2018																		
SVOC MS																						
Phenols																						
2-Chlorophenol #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
2-Methylphenol #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
2-Nitrophenol	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
2,4-Dichlorophenol #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
2,4-Dimethylphenol	<1	<1	<1	<1																<1	ug/l	TM16/PM30
2,4,5-Trichlorophenol #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
2,4,6-Trichlorophenol	<1	<1	<1	<1																<1	ug/l	TM16/PM30
4-Chloro-3-methylphenol #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
4-Methylphenol	<1	<1	<1	<1																<1	ug/l	TM16/PM30
4-Nitrophenol	<10	<10	<10	<10																<10	ug/l	TM16/PM30
Pentachlorophenol	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Phenol	<1	<1	<1	<1																<1	ug/l	TM16/PM30
PAHs																						
2-Chloronaphthalene #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
2-Methylnaphthalene #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Naphthalene #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Acenaphthylene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Acenaphthene #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Fluorene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Phenanthrene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Anthracene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Fluoranthene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Pyrene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Benzo(a)anthracene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Chrysene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Benzo(bk)fluoranthene #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Benzo(a)pyrene	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Indeno(123cd)pyrene	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Dibenzo(ah)anthracene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Benzo(ghi)perylene #	<0.5	<0.5	<0.5	<0.5																<0.5	ug/l	TM16/PM30
Phthalates																						
Bis(2-ethylhexyl) phthalate	<5	<5	<5	<5																<5	ug/l	TM16/PM30
Butylbenzyl phthalate	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Di-n-butyl phthalate #	<1.5	<1.5	<1.5	<1.5																<1.5	ug/l	TM16/PM30
Di-n-Octyl phthalate	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Diethyl phthalate #	<1	<1	<1	<1																<1	ug/l	TM16/PM30
Dimethyl phthalate	<1	<1	<1	<1																<1	ug/l	TM16/PM30

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

SVOC Report : Liquid

J E Job No. J E Sample No.	18/7222 22-28	18/7222 29-35	18/7222 36-42	18/7222 43-49											
Sample ID	WS03	WS04	WS05	WS06											
Depth															
COC No / misc Containers	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G	V H HN HCL P G											
Sample Date	10/05/2018	10/05/2018	10/05/2018	10/05/2018											
Sample Type	Ground Water	Ground Water	Ground Water	Ground Water											
Batch Number	1	1	1	1											
Date of Receipt	12/05/2018	12/05/2018	12/05/2018	12/05/2018											
													LOD/LOR	Units	Method No.
SVOC MS															
Other SVOCs															
1,2-Dichlorobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
1,2,4-Trichlorobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
1,3-Dichlorobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
1,4-Dichlorobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
2-Nitroaniline	<1	<1	<1	<1									<1	ug/l	TM16/PM30
2,4-Dinitrotoluene #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
2,6-Dinitrotoluene	<1	<1	<1	<1									<1	ug/l	TM16/PM30
3-Nitroaniline	<1	<1	<1	<1									<1	ug/l	TM16/PM30
4-Bromophenylphenylether #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
4-Chloroaniline	<1	<1	<1	<1									<1	ug/l	TM16/PM30
4-Chlorophenylphenylether #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
4-Nitroaniline	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Azobenzene #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Bis(2-chloroethoxy)methane #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Bis(2-chloroethyl)ether #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Carbazole #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Dibenzofuran #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Hexachlorobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Hexachlorobutadiene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Hexachlorocyclopentadiene	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Hexachloroethane #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Isophorone #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
N-nitrosodi-n-propylamine #	<0.5	<0.5	<0.5	<0.5									<0.5	ug/l	TM16/PM30
Nitrobenzene #	<1	<1	<1	<1									<1	ug/l	TM16/PM30
Surrogate Recovery 2-Fluorobiphenyl	122	118	113	115									<0	%	TM16/PM30
Surrogate Recovery p-Terphenyl-d14	130	125	129	129									<0	%	TM16/PM30

Please see attached notes for all abbreviations and acronyms

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

VOC Report : Liquid

J E Job No.	18/7222	18/7222	18/7222	18/7222									
J E Sample No.	22-28	29-35	36-42	43-49									
Sample ID	WS03	WS04	WS05	WS06									
Depth													
COC No / misc													
Containers	V H H N HCL P G	V H H N HCL P G	V H H N HCL P G	V H H N HCL P G									
Sample Date	10/05/2018	10/05/2018	10/05/2018	10/05/2018									
Sample Type	Ground Water	Ground Water	Ground Water	Ground Water									
Batch Number	1	1	1	1									
Date of Receipt	12/05/2018	12/05/2018	12/05/2018	12/05/2018									
										LOD/LOR	Units	Method No.	
VOC MS													
Dichlorodifluoromethane	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Methyl Tertiary Butyl Ether #	<0.1	2.8	<0.2 ^{AA}	<0.1						<0.1	ug/l	TM15/PM10	
Chloromethane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Vinyl Chloride #	<0.1	<0.1	<0.1	<0.1						<0.1	ug/l	TM15/PM10	
Bromomethane	<1	<1	<1	<1						<1	ug/l	TM15/PM10	
Chloroethane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Trichlorofluoromethane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,1-Dichloroethene (1,1 DCE) #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Dichloromethane (DCM) #	<5	<5	<5	<5						<5	ug/l	TM15/PM10	
trans-1-2-Dichloroethene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,1-Dichloroethane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
cis-1-2-Dichloroethene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
2,2-Dichloropropane	<1	<1	<1	<1						<1	ug/l	TM15/PM10	
Bromochloromethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Chloroform #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,1,1-Trichloroethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,1-Dichloropropene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Carbon tetrachloride #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,2-Dichloroethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Benzene #	<0.5	<0.5	<0.5	<0.5						<0.5	ug/l	TM15/PM10	
Trichloroethene (TCE) #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,2-Dichloropropane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Dibromomethane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Bromodichloromethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
cis-1-3-Dichloropropene	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Toluene #	<5	<5	<5	<5						<5	ug/l	TM15/PM10	
trans-1-3-Dichloropropene	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,1,2-Trichloroethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Tetrachloroethene (PCE) #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,3-Dichloropropane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Dibromochloromethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,2-Dibromoethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Chlorobenzene #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,1,1,2-Tetrachloroethane #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Ethylbenzene #	<1	<1	<1	<1						<1	ug/l	TM15/PM10	
p/m-Xylene #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
o-Xylene #	<1	<1	<1	<1						<1	ug/l	TM15/PM10	
Styrene	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Bromoform #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
Isopropylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,1,2,2-Tetrachloroethane	<4	<4	<4	<4						<4	ug/l	TM15/PM10	
Bromobenzene #	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,2,3-Trichloropropane #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Propylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
2-Chlorotoluene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,3,5-Trimethylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
4-Chlorotoluene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
tert-Butylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,2,4-Trimethylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
sec-Butylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
4-Isopropyltoluene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,3-Dichlorobenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,4-Dichlorobenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
n-Butylbenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,2-Dichlorobenzene #	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
1,2-Dibromo-3-chloropropane	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,2,4-Trichlorobenzene	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Hexachlorobutadiene	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Naphthalene	<2	<2	<2	<2						<2	ug/l	TM15/PM10	
1,2,3-Trichlorobenzene	<3	<3	<3	<3						<3	ug/l	TM15/PM10	
Surrogate Recovery Toluene D8	95	96	98	96						<0	%	TM15/PM10	
Surrogate Recovery 4-Bromofluorobenzene	96	96	100	101						<0	%	TM15/PM10	

Please see attached notes for all abbreviations and acronyms

Exova Jones Environmental

Job number: 18/5166
Sample number: 4
Sample identity: BH01
Sample depth: 0.45-0.70
Sample Type: Soil
Units: ug/kg

Method: VOC
Matrix: Solid

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
565-59-3	Pentane, 2,3-dimethyl-	4.035	90	163
16883-48-0	Cyclopentane, 1,2,4-trimethyl-, (1.alpha.,2.beta.,4.alpha.)-	4.626	91	139
565-75-3	Pentane, 2,3,4-trimethyl-	4.689	80	299
560-21-4	Pentane, 2,3,3-trimethyl-	4.746	80	291
2207-01-4	Cyclohexane, 1,2-dimethyl-, cis-	5.029 - 5.348	87,91	341
6876-23-9	Cyclohexane, 1,2-dimethyl-, trans-	5.105	97	350
2234-75-5	Cyclohexane, 1,2,4-trimethyl-	5.394	80	461
7667-60-9	Cyclohexane, 1,2,4-trimethyl-, (1.alpha.,2.beta.,4.beta.)-	5.493	95	340
3114-55-4	Chlorobenzene-d5	5.621	91	1372
5911-04-6	Nonane, 3-methyl-	5.956	90	820
506-51-4	n-Tetracosanol-1	6.459	80	623
2425-77-6	1-Decanol, 2-hexyl-	6.627	90	890
1678-81-5	Cyclohexane, 1,2,3-trimethyl-, (1.alpha.,2.beta.,3.alpha.)-	6.789	89	372
933-98-2	Benzene, 1-ethyl-2,3-dimethyl-	7.109	90	1034
76089-59-3	1,3-Cyclopentadiene, 1,2,3,4-tetramethyl-5-methylene-	7.344	80	396
2958-76-1	Naphthalene, decahydro-2-methyl-	7.382	86	876

Exova Jones Environmental

Job number: 18/5384 **Method:** VOC
Sample number: 7 **Matrix:** Solid
Sample identity: TP01
Sample depth: 0.70-0.90
Sample Type: Soil
Units: ug/kg

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
-	trans-Decalin, 2-methyl-	7.270	89	357
2958-76-1	Naphthalene, decahydro-2-methyl-	7.384	83	292

Exova Jones Environmental

Job number: 18/5384 **Method:** VOC
Sample number: 13 **Matrix:** Solid
Sample identity: TP02
Sample depth: 0.30-0.50
Sample Type: Soil
Units: ug/kg

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
96-14-0	Pentane, 3-methyl-	3.174	90	334
108-08-7	Pentane, 2,4-dimethyl-	3.646	83	154
565-59-3	Pentane, 2,3-dimethyl-	4.034	94	828
589-34-4	Hexane, 3-methyl-	4.079	94	783
1638-26-2	Cyclopentane, 1,1-dimethyl-	4.108	86	352
872-56-0	Isopropylcyclobutane	4.233	93	432
2815-58-9	Cyclopentane, 1,2,4-trimethyl-	4.626	91	957
589-53-7	Heptane, 4-methyl-	4.778	91	955
2207-01-4	Cyclohexane, 1,2-dimethyl-, cis-	5.023	81	1512
6876-23-9	Cyclohexane, 1,2-dimethyl-, trans-	5.105	97	2017
2207-03-6	Cyclohexane, 1,3-dimethyl-, trans-	5.153	93	1110
2234-75-5	Cyclohexane, 1,2,4-trimethyl-	5.336	83	664
3073-66-3	Cyclohexane, 1,1,3-trimethyl-	5.394	94	4705
619-99-8	Hexane, 3-ethyl-	5.446	80	2024
2216-33-3	Octane, 3-methyl-	5.539	80	1413
3728-57-2	Cyclopentane, 1-methyl-2-propyl-	5.707	93	1148
6236-88-0	Cyclohexane, 1-ethyl-4-methyl-, trans-	5.739	91	2325
19398-86-8	cis-3-Decene	5.810	81	425
15869-94-0	Octane, 3,6-dimethyl-	5.955	91	3026
2847-72-5	Decane, 4-methyl-	6.512	83	3218
-	Oxalic acid, cyclobutyl heptadecyl ester	6.627	80	1626
7058-01-7	Cyclohexane, (1-methylpropyl)-	6.680	81	1990
105-05-5	Benzene, 1,4-diethyl-	6.871	84	754
527-84-4	o-Cymene	7.109	94	1704
-	trans-Decalin, 2-methyl-	7.274	87	2398
95-93-2	Benzene, 1,2,4,5-tetramethyl-	7.344	94	623
2958-76-1	Naphthalene, decahydro-2-methyl-	7.383	92	1088

Exova Jones Environmental

Job number: 18/5166 **Method:** SVOC
Sample number: 5 **Matrix:** Solid
Sample identity: BH01
Sample depth: 0.45-0.70
Sample Type: Soil
Units: ug/kg

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
638-36-8	Hexadecane, 2,6,10,14-tetramethyl-	10.545	95	1411

Exova Jones Environmental

Job number: 18/5384 **Method:** SVOC
Sample number: 8 **Matrix:** Solid
Sample identity: TP01
Sample depth: 0.70-0.90
Sample Type: Soil
Units: ug/kg

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
493-02-7	Naphthalene, decahydro-, trans-	5.805	90	1122
-	trans-Decalin, 2-methyl-	6.326	97	1050
2958-76-1	Naphthalene, decahydro-2-methyl-	6.473	95	2269
62199-51-3	Cyclopentane, 1-pentyl-2-propyl-	7.673	86	1382
90-12-0	Naphthalene, 1-methyl-	7.738	93	3064
3891-98-3	Dodecane, 2,6,10-trimethyl-	8.265	90	2465
13360-61-7	1-Pentadecene	8.387	83	3966
581-42-0	Naphthalene, 2,6-dimethyl-	8.465	97	788
582-16-1	Naphthalene, 2,7-dimethyl-	8.569	93	1403
2131-42-2	Naphthalene, 1,4,6-trimethyl-	9.194	96	4316
2245-38-7	Naphthalene, 1,6,7-trimethyl-	9.293	97	2204
13187-99-0	2-Bromo dodecane	9.775	89	3906
529-05-5	Chamazulene	9.931	93	2686
7350-72-3	1,4-Methanonaphthalene,1,4-dihydro-9-((1-methylethylidene)-	10.004	93	4447
55045-07-3	Dodecane, 2-methyl-8-propyl-	10.064	86	6256
832-69-9	Phenanthrene, 1-methyl-	10.923	86	6045
832-64-4	Phenanthrene, 4-methyl-	11.002	90	5121
89816-75-1	2,6-Dimethyldibenzothiophene	11.262	80	5352
2381-21-7	Pyrene, 1-methyl-	12.528	89	2957
2175-90-8	6,6-Diphenylfulvene	13.086	91	1926
64401-21-4	Pyrene, 1,3-dimethyl-	13.206	90	2930
288246-53-7	Pyridine-3-carboxamide, oxime, N-(2-trifluoromethylphenyl)-	13.865	91	2246
54482-31-4	D-Homoandrostane, (5.alpha.,13.alpha.)-	14.822	90	1244
98496-82-3	Antra-9,10-quinone, 1-(3-hydroxy-3-phenyl-1-triazenyl)-	17.032	86	3885

Exova Jones Environmental

Job number: 18/5384 **Method:** SVOC
Sample number: 14 **Matrix:** Solid
Sample identity: TP02
Sample depth: 0.30-0.50
Sample Type: Soil
Units: ug/kg

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
15869-94-0	Octane, 3,6-dimethyl-	4.547	90	1479
14676-29-0	Heptane, 3-ethyl-2-methyl-	4.635	81	1611
2847-72-5	Decane, 4-methyl-	5.500	83	2762
1678-93-9	Cyclohexane, butyl-	5.581	83	657
493-02-7	Naphthalene, decahydro-, trans-	5.804	93	2381
527-84-4	o-Cymene	5.918	92	2969
933-98-2	Benzene, 1-ethyl-2,3-dimethyl-	6.159	90	1224
95-93-2	Benzene, 1,2,4,5-tetramethyl-	6.305	97	1971
-	trans-Decalin, 2-methyl-	6.326	98	246
13150-81-7	2,6-Dimethyldecane	6.389	89	2040
1758-85-6	Benzene, 2,4-diethyl-1-methyl-	6.609	86	868
53172-84-2	Benzene, (1-methyl-1-butenyl)-	7.438	90	2858
75163-97-2	Octadecane, 2,6-dimethyl-	7.594	90	2717
62199-51-3	Cyclopentane, 1-pentyl-2-propyl-	7.673	90	2810
2613-76-5	1H-Indene, 2,3-dihydro-1,1,3-trimethyl-	7.843	89	7319
3891-98-3	Dodecane, 2,6,10-trimethyl-	8.272	94	7253
582-16-1	Naphthalene, 2,7-dimethyl-	8.465	97	11515
2131-42-2	Naphthalene, 1,4,6-trimethyl-	8.953	96	4000
2245-38-7	Naphthalene, 1,6,7-trimethyl-	9.194	98	7282
829-26-5	Naphthalene, 2,3,6-trimethyl-	9.293	98	7932
3892-00-0	Pentadecane, 2,6,10-trimethyl-	9.775	93	8945
529-05-5	Chamazulene	9.859	94	1926
1921-70-6	Pentadecane, 2,6,10,14-tetramethyl-	10.064	96	17326
7350-72-3	1,4-Methanonaphthalene,1,4-dihydro-9-((1-methylethylidene)-	10.112	86	3154
51282-56-5	Ethyl 5-chloro-2-nitrobenzoate	10.232	92	1565
638-36-8	Hexadecane, 2,6,10,14-tetramethyl-	10.545	96	19194
67388-11-8	4-Methylnaphtho[1,2-b]thiophene	10.803	95	6863
832-64-4	Phenanthrene, 4-methyl-	10.903	90	3804
610-48-0	Anthracene, 1-methyl-	10.923	95	8606
2531-84-2	Phenanthrene, 2-methyl-	11.012	95	9265

Exova Jones Environmental

Job number:	18/5384	Method:	SVOC
Sample number:	14	Matrix:	Solid
Sample identity:	TP02		
Sample depth:	0.30-0.50		
Sample Type:	Soil		
Units:	ug/kg		

Note: Only samples with TICs (if requested) are reported. If TICs were requested but no compounds found they are not reported.

CAS No.	Tentative Compound Identification	Retention Time (minutes)	% Match	Concentration
89816-75-1	2,6-Dimethyldibenzothiophene	11.262	96	4651
31317-19-8	2,7-Dimethyldibenzothiophene	11.371	93	5853
2789-88-0	di-p-Tolylacetylene	11.511	93	6689
85385-68-8	[14]Annulene, 1,6:8,13-bis(methano)-, syn	11.531	93	6356
4443-60-1	Cyclohexane, (1-hexyltetradecyl)-	11.700	81	3109
2380-32-7	Octadecanoic acid, 17-oxo-, methyl ester	12.199	90	519
25186-71-4	3-Chloro-1-anthraquinonecarboxylic acid	13.985	91	1725
288246-53-7	Pyridine-3-carboxamide, oxime, N-(2-trifluoromethylphenyl)-	14.324	91	2517
98496-82-3	Antra-9,10-quinone, 1-(3-hydroxy-3-phenyl-1-triazenyl)-	15.905	86	1164
112-95-8	Eicosane	16.039	90	2080
62016-79-9	Heptacosane, 1-chloro-	16.996	97	12910

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Note:

Asbestos Screen analysis is carried out in accordance with our documented in-house methods PM042 and TM065 and HSG 248 by Stereo and Polarised Light Microscopy using Dispersion Staining Techniques and is covered by our UKAS accreditation. Detailed Gravimetric Quantification and PCOM Fibre Analysis is carried out in accordance with our documented in-house methods PM042 and TM131 and HSG 248 using Stereo and Polarised Light Microscopy and Phase Contrast Optical Microscopy (PCOM). Samples are retained for not less than 6 months from the date of analysis unless specifically requested.

Opinions, including ACM type and Asbestos level, lie outside the scope of our UKAS accreditation.

Where the sample is not taken by a Jones Environmental Laboratory consultant, Jones Environmental Laboratory cannot be responsible for inaccurate or unrepresentative sampling.

Signed on behalf of Jones Environmental Laboratory:

Ryan Butterworth
 Asbestos Team Leader

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Date Of Analysis	Analysis	Result
18/5166	1	BH06	0.40-0.70	3	11/04/2018	General Description (Bulk Analysis)	soil-stones
					11/04/2018	Asbestos Fibres	NAD
					11/04/2018	Asbestos Fibres (2)	NAD
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos ACM (2)	NAD
					11/04/2018	Asbestos Type	NAD
					11/04/2018	Asbestos Type (2)	NAD
					11/04/2018	Asbestos Level Screen	NAD
18/5166	1	BH01	0.45-0.70	6	11/04/2018	General Description (Bulk Analysis)	Soil/Stones
					11/04/2018	Asbestos Fibres	Fibre Bundles
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos Type	Chrysotile
					11/04/2018	Asbestos Level Screen	less than 0.1%
					30/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					30/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					30/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
18/5166	1	TT03	0.00-1.40	9	11/04/2018	General Description (Bulk Analysis)	Soil/Stones
					11/04/2018	Asbestos Fibres	NAD
					11/04/2018	Asbestos Fibres (2)	NAD
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos ACM (2)	NAD
					11/04/2018	Asbestos Type	NAD
					11/04/2018	Asbestos Type (2)	NAD
					11/04/2018	Asbestos Level Screen	NAD
18/5166	1	TT02	0.50-1.20	12	11/04/2018	General Description (Bulk Analysis)	soil/stones
					11/04/2018	Asbestos Fibres	NAD
					11/04/2018	Asbestos Fibres (2)	NAD
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos ACM (2)	NAD
					11/04/2018	Asbestos Type	NAD
					11/04/2018	Asbestos Type (2)	NAD
					11/04/2018	Asbestos Level Screen	NAD

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Date Of Analysis	Analysis	Result
18/5166	1	WS01	1.00-1.25	15	11/04/2018	General Description (Bulk Analysis)	soil/stones
					11/04/2018	Asbestos Fibres	Fibre Bundles
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos Type	Chrysotile
					11/04/2018	Asbestos Level Screen	less than 0.1%
					30/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					30/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					30/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
					30/04/2018	Asbestos PCOM Quantification (Fibres)	<0.001 (mass %)
					30/04/2018	Asbestos Gravimetric & PCOM Total	<0.001 (mass %)
18/5166	1	WS04	0.50	18	11/04/2018	General Description (Bulk Analysis)	soil/stones
					11/04/2018	Asbestos Fibres	NAD
					11/04/2018	Asbestos Fibres (2)	NAD
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos ACM (2)	NAD
					11/04/2018	Asbestos Type	NAD
					11/04/2018	Asbestos Type (2)	NAD
					11/04/2018	Asbestos Level Screen	NAD
18/5166	1	TP10	0.40-0.60	21	11/04/2018	General Description (Bulk Analysis)	soil/stones
					11/04/2018	Asbestos Fibres	NAD
					11/04/2018	Asbestos Fibres (2)	NAD
					11/04/2018	Asbestos ACM	NAD
					11/04/2018	Asbestos ACM (2)	NAD
					11/04/2018	Asbestos Type	NAD
					11/04/2018	Asbestos Type (2)	NAD
					11/04/2018	Asbestos Level Screen	NAD
18/5333	1	TT01	1.70-1.90	3	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	TP09	0.30-0.40	6	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	TP07	1.30-1.60	9	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Date Of Analysis	Analysis	Result
18/5333	1	TP07	1.30-1.60	9	16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	TP08	0.20-0.50	15	16/04/2018	General Description (Bulk Analysis)	soil.stones
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	WS02	0.00-0.50	18	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	TP05	0.50-0.70	21	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	WS05	0.50-1.00	24	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	TP04	0.80-1.00	27	16/04/2018	General Description (Bulk Analysis)	Soil/Stone
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD
					16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5333	1	WS03	0.00-1.20	29	16/04/2018	General Description (Bulk Analysis)	soil.stones
					16/04/2018	Asbestos Fibres	NAD
					16/04/2018	Asbestos Fibres (2)	NAD
					16/04/2018	Asbestos ACM	NAD
					16/04/2018	Asbestos ACM (2)	NAD

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Date Of Analysis	Analysis	Result
18/5333	1	WS03	0.00-1.20	29	16/04/2018	Asbestos Type	NAD
					16/04/2018	Asbestos Type (2)	NAD
					16/04/2018	Asbestos Level Screen	NAD
18/5384	1	TP06	0.40-0.60	3	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	Fibre Bundles
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos Type	Chrysotile
					17/04/2018	Asbestos Level Screen	less than 0.1%
					26/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
					26/04/2018	Asbestos PCOM Quantification (Fibres)	<0.001 (mass %)
					26/04/2018	Asbestos Gravimetric & PCOM Total	<0.001 (mass %)
18/5384	1	TP01	0.70-0.90	9	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	Fibre Bundles
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos Type	Chrysotile
					17/04/2018	Asbestos Level Screen	less than 0.1%
					26/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
					26/04/2018	Asbestos PCOM Quantification (Fibres)	<0.001 (mass %)
					26/04/2018	Asbestos Gravimetric & PCOM Total	<0.001 (mass %)
18/5384	1	TP02	0.30-0.50	15	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	Fibre Bundles
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos Type	Chrysotile
					17/04/2018	Asbestos Level Screen	less than 0.1%
					26/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
					26/04/2018	Asbestos PCOM Quantification (Fibres)	<0.001 (mass %)
					26/04/2018	Asbestos Gravimetric & PCOM Total	<0.001 (mass %)
18/5384	1	WS06	0.00-1.20	21	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	NAD
					17/04/2018	Asbestos Fibres (2)	NAD
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos ACM (2)	NAD
					17/04/2018	Asbestos Type	NAD
					17/04/2018	Asbestos Type (2)	NAD
					17/04/2018	Asbestos Level Screen	NAD
18/5384	1	BH03	1.50-2.00	24	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	NAD
					17/04/2018	Asbestos Fibres (2)	NAD
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos ACM (2)	NAD
					17/04/2018	Asbestos Type	NAD
17/04/2018	Asbestos Type (2)	NAD					

Client Name: AECOM
 Reference: 60569745
 Location: VP1 (TLOR)
 Contact: Alex Freeman

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Date Of Analysis	Analysis	Result
18/5384	1	BH03	1.50-2.00	24	17/04/2018	Asbestos Level Screen	NAD
18/5384	1	WS07	0.30-0.80	27	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	NAD
					17/04/2018	Asbestos Fibres (2)	NAD
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos ACM (2)	NAD
					17/04/2018	Asbestos Type	NAD
					17/04/2018	Asbestos Type (2)	NAD
					17/04/2018	Asbestos Level Screen	NAD
18/5384	1	WS08	0.00-1.20	30	17/04/2018	General Description (Bulk Analysis)	Soil/Stone
					17/04/2018	Asbestos Fibres	NAD
					17/04/2018	Asbestos Fibres (2)	NAD
					17/04/2018	Asbestos ACM	NAD
					17/04/2018	Asbestos ACM (2)	NAD
					17/04/2018	Asbestos Type	NAD
					17/04/2018	Asbestos Type (2)	NAD
					17/04/2018	Asbestos Level Screen	NAD
18/5455	1	BH02	0.60-1.00	3	18/04/2018	General Description (Bulk Analysis)	soil/stones
					18/04/2018	Asbestos Fibres	Fibre Bundles
					18/04/2018	Asbestos ACM	NAD
					18/04/2018	Asbestos Type	Chrysotile
					18/04/2018	Asbestos Level Screen	less than 0.1%
					26/04/2018	Total ACM Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Detailed Gravimetric Quantification (% Asb)	<0.001 (mass %)
					26/04/2018	Total Gravimetric Quantification (ACM + Detailed) (% Asb)	<0.001 (mass %)
					26/04/2018	Asbestos PCOM Quantification (Fibres)	<0.001 (mass %)
					26/04/2018	Asbestos Gravimetric & PCOM Total	<0.001 (mass %)
18/5775	1	BH04	0.50-1.20	3	24/04/2018	General Description (Bulk Analysis)	Soil/Stone
					24/04/2018	Asbestos Fibres	NAD
					24/04/2018	Asbestos Fibres (2)	NAD
					24/04/2018	Asbestos ACM	NAD
					24/04/2018	Asbestos ACM (2)	NAD
					24/04/2018	Asbestos Type	NAD
					24/04/2018	Asbestos Type (2)	NAD
					24/04/2018	Asbestos Level Screen	NAD
18/5775	1	BH05	1.80-2.25	6	24/04/2018	General Description (Bulk Analysis)	Soil/Stone
					24/04/2018	Asbestos Fibres	NAD
					24/04/2018	Asbestos Fibres (2)	NAD
					24/04/2018	Asbestos ACM	NAD
					24/04/2018	Asbestos ACM (2)	NAD
					24/04/2018	Asbestos Type	NAD
					24/04/2018	Asbestos Type (2)	NAD
					24/04/2018	Asbestos Level Screen	NAD

Client Name: AECOM
Reference: 60569745
Location: VP1 (TLOR)
Contact: Alex Freeman

Matrix : Liquid

J E Job No.	Batch	Sample ID	Depth	J E Sample No.	Analysis	Reason

Please note that only samples that are deviating are mentioned in this report. If no samples are listed it is because none were deviating. Only analyses which are accredited are recorded as deviating if set criteria are not met.

NOTES TO ACCOMPANY ALL SCHEDULES AND REPORTS

JE Job No.: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

SOILS

Please note we are only MCERTS accredited (UK soils only) for sand, loam and clay and any other matrix is outside our scope of accreditation.

Where an MCERTS report has been requested, you will be notified within 48 hours of any samples that have been identified as being outside our MCERTS scope. As validation has been performed on clay, sand and loam, only samples that are predominantly these matrices, or combinations of them will be within our MCERTS scope. If samples are not one of a combination of the above matrices they will not be marked as MCERTS accredited.

It is assumed that you have taken representative samples on site and require analysis on a representative subsample. Stones will generally be included unless we are requested to remove them.

All samples will be discarded one month after the date of reporting, unless we are instructed to the contrary.

If you have not already done so, please send us a purchase order if this is required by your company.

Where appropriate please make sure that our detection limits are suitable for your needs, if they are not, please notify us immediately.

All analysis is reported on a dry weight basis unless stated otherwise. Results are not surrogate corrected. Samples are dried at 35°C ±5°C unless otherwise stated. Moisture content for CEN Leachate tests are dried at 105°C ±5°C.

Where Mineral Oil or Fats, Oils and Grease is quoted, this refers to Total Aliphatics C10-C40.

Where a CEN 10:1 ZERO Headspace VOC test has been carried out, a 10:1 ratio of water to wet (as received) soil has been used.

% Asbestos in Asbestos Containing Materials (ACMs) is determined by reference to HSG 264 The Survey Guide - Appendix 2 : ACMs in buildings listed in order of ease of fibre release.

Negative Neutralization Potential (NP) values are obtained when the volume of NaOH (0.1N) titrated (pH 8.3) is greater than the volume of HCl (1N) to reduce the pH of the sample to 2.0 - 2.5. Any negative NP values are corrected to 0.

The calculation of Pyrite content assumes that all oxidisable sulphides present in the sample are pyrite. This may not be the case. The calculation may be an overestimate when other sulphides such as Barite (Barium Sulphate) are present.

WATERS

Please note we are not a UK Drinking Water Inspectorate (DWI) Approved Laboratory .

ISO17025 accreditation applies to surface water and groundwater and usually one other matrix which is analysis specific, any other liquids are outside our scope of accreditation.

As surface waters require different sample preparation to groundwaters the laboratory must be informed of the water type when submitting samples.

Where Mineral Oil or Fats, Oils and Grease is quoted, this refers to Total Aliphatics C10-C40.

DEVIATING SAMPLES

Samples must be received in a condition appropriate to the requested analyses. All samples should be submitted to the laboratory in suitable containers with sufficient ice packs to sustain an appropriate temperature for the requested analysis. If this is not the case you will be informed and any test results that may be compromised highlighted on your deviating samples report.

SURROGATES

Surrogate compounds are added during the preparation process to monitor recovery of analytes. However low recovery in soils is often due to peat, clay or other organic rich matrices. For waters this can be due to oxidants, surfactants, organic rich sediments or remediation fluids. Acceptable limits for most organic methods are 70 - 130% and for VOCs are 50 - 150%. When surrogate recoveries are outside the performance criteria but the associated AQC passes this is assumed to be due to matrix effect. Results are not surrogate corrected.

DILUTIONS

A dilution suffix indicates a dilution has been performed and the reported result takes this into account. No further calculation is required.

BLANKS

Where analytes have been found in the blank, the sample will be treated in accordance with our laboratory procedure for dealing with contaminated blanks.

NOTE

Data is only reported if the laboratory is confident that the data is a true reflection of the samples analysed. Data is only reported as accredited when all the requirements of our Quality System have been met. In certain circumstances where all the requirements of the Quality System have not been met, for instance if the associated AQC has failed, the reason is fully investigated and documented. The sample data is then evaluated alongside the other quality control checks performed during analysis to determine its suitability. Following this evaluation, provided the sample results have not been effected, the data is reported but accreditation is removed. It is a UKAS requirement for data not reported as accredited to be considered indicative only, but this does not mean the data is not valid.

Where possible, and if requested, samples will be re-extracted and a revised report issued with accredited results. Please do not hesitate to contact the laboratory if further details are required of the circumstances which have led to the removal of accreditation.

REPORTS FROM THE SOUTH AFRICA LABORATORY

Any method number not prefixed with SA has been undertaken in our UK laboratory unless reported as subcontracted.

Please include all sections of this report if it is reproduced

All solid results are expressed on a dry weight basis unless stated otherwise.

ABBREVIATIONS and ACRONYMS USED

#	ISO17025 (UKAS Ref No. 4225) accredited - UK.
SA	ISO17025 (SANAS Ref No.T0729) accredited - South Africa.
B	Indicates analyte found in associated method blank.
DR	Dilution required.
M	MCERTS accredited.
NA	Not applicable
NAD	No Asbestos Detected.
ND	None Detected (usually refers to VOC and/SVOC TICs).
NDP	No Determination Possible
SS	Calibrated against a single substance
SV	Surrogate recovery outside performance criteria. This may be due to a matrix effect.
W	Results expressed on as received basis.
+	AQC failure, accreditation has been removed from this result, if appropriate, see 'Note' on previous page.
++	Result outside calibration range, results should be considered as indicative only and are not accredited.
*	Analysis subcontracted to an Exova Jones Environmental approved laboratory.
AD	Samples are dried at 35°C ±5°C
CO	Suspected carry over
LOD/LOR	Limit of Detection (Limit of Reporting) in line with ISO 17025 and MCERTS
ME	Matrix Effect
NFD	No Fibres Detected
BS	AQC Sample
LB	Blank Sample
N	Client Sample
TB	Trip Blank Sample
OC	Outside Calibration Range
AA	x2 Dilution
AB	x10 Dilution

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/S ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
TM0	Not available	PM0	No preparation is required.				
PM4	Gravimetric measurement of Natural Moisture Content and % Moisture Content at either 35°C or 105°C. Calculation based on ISO 11465 and BS1377.	PM0	No preparation is required.				
TM5	Modified USEPA 8015B method for the determination of solvent Extractable Petroleum Hydrocarbons (EPH) with carbon banding within the range C8-C40 GC-FID.	PM16/PM30	Fractionation into aliphatic and aromatic fractions using a Rapid Trace SPE/Water samples are extracted with solvent using a magnetic stirrer to create a vortex.	Yes			
TM5	Modified USEPA 8015B method for the determination of solvent Extractable Petroleum Hydrocarbons (EPH) with carbon banding within the range C8-C40 GC-FID.	PM8/PM16	End over end extraction of solid samples for organic analysis. The solvent mix varies depending on analysis required/Fractionation into aliphatic and aromatic fractions using a Rapid Trace SPE.	Yes		AR	Yes
TM5	Modified USEPA 8015B method for the determination of solvent Extractable Petroleum Hydrocarbons (EPH) with carbon banding within the range C8-C40 GC-FID.	PM8/PM16	End over end extraction of solid samples for organic analysis. The solvent mix varies depending on analysis required/Fractionation into aliphatic and aromatic fractions using a Rapid Trace SPE.	Yes	Yes	AR	Yes
TM5/TM36	please refer to TM5 and TM36 for method details	PM12/PM16/PM30	please refer to PM16/PM30 and PM12 for method details	Yes			
TM5/TM36	please refer to TM5 and TM36 for method details	PM8/PM12/PM16	please refer to PM8/PM16 and PM12 for method details			AR	Yes
TM5/TM36	please refer to TM5 and TM36 for method details	PM8/PM12/PM16	please refer to PM8/PM16 and PM12 for method details	Yes		AR	Yes
PM13	A visual examination of the solid sample is carried out to ascertain sample make up, colour and any other inclusions. This is not a geotechnical description.	PM0	No preparation is required.			AR	
TM15	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds (VOCs) by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.				

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/S ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
TM15	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds (VOCs) by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes			
TM15	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds (VOCs) by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.			AR	Yes
TM15	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds (VOCs) by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes		AR	Yes
TM15	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds (VOCs) by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes	Yes	AR	Yes
TM16	Modified USEPA 8270. Quantitative determination of Semi-Volatile Organic compounds (SVOCs) by GC-MS.	PM30	Water samples are extracted with solvent using a magnetic stirrer to create a vortex.				
TM16	Modified USEPA 8270. Quantitative determination of Semi-Volatile Organic compounds (SVOCs) by GC-MS.	PM30	Water samples are extracted with solvent using a magnetic stirrer to create a vortex.	Yes			
TM16	Modified USEPA 8270. Quantitative determination of Semi-Volatile Organic compounds (SVOCs) by GC-MS.	PM8	End over end extraction of solid samples for organic analysis. The solvent mix varies depending on analysis required.			AR	Yes
TM16	Modified USEPA 8270. Quantitative determination of Semi-Volatile Organic compounds (SVOCs) by GC-MS.	PM8	End over end extraction of solid samples for organic analysis. The solvent mix varies depending on analysis required.	Yes	Yes	AR	Yes
TM21	Modified BS 7755-3:1995, ISO10694:1995 Determination of Total Organic Carbon or Total Carbon by combustion in an Eltra TOC furnace/analyser in the presence of oxygen. The CO2 generated is quantified using infra-red detection. Organic Matter (SOM) calculated as per EA MCERTS Chemical Testing of Soil, March 2012 v4.	PM24	Dried and ground solid samples are washed with hydrochloric acid, then rinsed with deionised water to remove the mineral carbon before TOC analysis.			AD	Yes
TM30	Determination of Trace Metal elements by ICP-OES (Inductively Coupled Plasma - Optical Emission Spectrometry). Modified US EPA Method 200.7, 6010B and BS EN ISO 11885 2009	PM14	Analysis of waters and leachates for metals by ICP OES/ICP MS. Samples are filtered for dissolved metals and acidified if required.				

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/S ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
TM30	Determination of Trace Metal elements by ICP-OES (Inductively Coupled Plasma - Optical Emission Spectrometry). Modified US EPA Method 200.7, 6010B and BS EN ISO 11885 2009	PM14	Analysis of waters and leachates for metals by ICP OES/ICP MS. Samples are filtered for dissolved metals and acidified if required.	Yes			
TM30	Determination of Trace Metal elements by ICP-OES (Inductively Coupled Plasma - Optical Emission Spectrometry). Modified US EPA Method 200.7, 6010B and BS EN ISO 11885 2009	PM15	Acid digestion of dried and ground solid samples using Aqua Regia refluxed at 112.5 °C. Samples containing asbestos are not dried and ground.			AD	Yes
TM30	Determination of Trace Metal elements by ICP-OES (Inductively Coupled Plasma - Optical Emission Spectrometry). Modified US EPA Method 200.7, 6010B and BS EN ISO 11885 2009	PM15	Acid digestion of dried and ground solid samples using Aqua Regia refluxed at 112.5 °C. Samples containing asbestos are not dried and ground.	Yes	Yes	AD	Yes
TM30	Determination of Trace Metal elements by ICP-OES (Inductively Coupled Plasma - Optical Emission Spectrometry). Modified US EPA Method 200.7, 6010B and BS EN ISO 11885 2009	PM62	Acid digestion of as received solid samples using Aqua Regia refluxed at 112.5 °C.			AR	Yes
TM31	Modified USEPA 8015B. Determination of Methylterbutylether, Benzene, Toluene, Ethylbenzene and Xylene by headspace GC-FID.	PM12	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes			
TM36	Modified US EPA method 8015B. Determination of Gasoline Range Organics (GRO) in the carbon chain range of C4-12 by headspace GC-FID.	PM12	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes			
TM36	Modified US EPA method 8015B. Determination of Gasoline Range Organics (GRO) in the carbon chain range of C4-12 by headspace GC-FID.	PM12	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.			AR	Yes
TM36	Modified US EPA method 8015B. Determination of Gasoline Range Organics (GRO) in the carbon chain range of C4-12 by headspace GC-FID.	PM12	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes		AR	Yes
TM36	Modified US EPA method 8015B. Determination of Gasoline Range Organics (GRO) in the carbon chain range of C4-12 by headspace GC-FID.	PM12	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.	Yes	Yes	AR	Yes
TM37	Modified methods USEPA 160.2, EN872:2005 and SMWW 2540D. Gravimetric determination of Total Suspended Solids. Sample is filtered through a 1.5um pore size glass fibre filter and the resulting residue is dried and weighed.	PM0	No preparation is required.	Yes			

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/S ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM0	No preparation is required.				
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM0	No preparation is required.	Yes			
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM20	Extraction of dried and ground or as received samples with deionised water in a 2:1 water to solid ratio using a reciprocal shaker for all analytes except hexavalent chromium. Extraction of as received sample using 10:1 ratio of 0.2M sodium hydroxide to soil for hexavalent chromium using a reciprocal shaker.			AD	Yes
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM20	Extraction of dried and ground or as received samples with deionised water in a 2:1 water to solid ratio using a reciprocal shaker for all analytes except hexavalent chromium. Extraction of as received sample using 10:1 ratio of 0.2M sodium hydroxide to soil for hexavalent chromium using a reciprocal shaker.	Yes	Yes	AD	Yes
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM20	Extraction of dried and ground or as received samples with deionised water in a 2:1 water to solid ratio using a reciprocal shaker for all analytes except hexavalent chromium. Extraction of as received sample using 10:1 ratio of 0.2M sodium hydroxide to soil for hexavalent chromium using a reciprocal shaker.			AR	Yes
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM20	Extraction of dried and ground or as received samples with deionised water in a 2:1 water to solid ratio using a reciprocal shaker for all analytes except hexavalent chromium. Extraction of as received sample using 10:1 ratio of 0.2M sodium hydroxide to soil for hexavalent chromium using a reciprocal shaker.	Yes		AR	Yes
TM38	Soluble Ion analysis using Discrete Analyser. Modified US EPA methods 325.2 (Chloride), 375.4 (Sulphate), 365.2 (o-Phosphate), 353.1 (TON), 354.1 (Nitrite), 350.1 (NH4+), 7196A (Hex Cr)	PM60	As received solid samples are extracted with deionised water in a 2:1 ratio of water to solid.			AR	Yes
TM48	Determination of Ferrous Iron by reaction with Sodium Carbonate and Morfamquat Sulphate which is analysed spectrophotometrically.	PM0	No preparation is required.				
TM50	Acid soluble sulphate (Total Sulphate) analysed by ICP-OES	PM29	Dried and ground solid sample is boiled with dilute hydrochloric acid, the resulting liquor is then analysed.	Yes	Yes	AD	Yes
TM50	Acid soluble sulphate (Total Sulphate) analysed by ICP-OES	PM29	Dried and ground solid sample is boiled with dilute hydrochloric acid, the resulting liquor is then analysed.			AR	Yes

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
TM60	TC/TOC analysis of Waters by High Temperature Combustion followed by NDIR detection. Based on the following modified standard methods: USEPA 9060, APHA Standard Methods for Examination of Water and Wastewater 5310B, ASTM D 7573, and USEPA 415.1.	PM0	No preparation is required.	Yes			
TM65	Asbestos Bulk Identification method based on HSG 248.	PM42	Solid samples undergo a thorough visual inspection for asbestos fibres prior to asbestos identification using TM065.	Yes		AR	
TM73	Modified US EPA methods 150.1 and 9045D and BS1377:1990. Determination of pH by Metrohm automated probe analyser.	PM0	No preparation is required.	Yes			
TM73	Modified US EPA methods 150.1 and 9045D and BS1377:1990. Determination of pH by Metrohm automated probe analyser.	PM11	Extraction of as received solid samples using one part solid to 2.5 parts deionised water.	Yes	Yes	AR	No
TM74	Analysis of water soluble boron (20:1 extract) by ICP-OES.	PM32	Hot water soluble boron is extracted from dried and ground samples using a 20:1 ratio.	Yes	Yes	AD	Yes
TM74	Analysis of water soluble boron (20:1 extract) by ICP-OES.	PM61	As received solid samples are extracted with hot water in a 20:1 ratio of water to soil ready for analysis by ICP.			AR	Yes
TM75	Modified US EPA method 310.1. Determination of Alkalinity by Metrohm automated titration analyser.	PM0	No preparation is required.	Yes			
TM107	Determination of Sulphide/Thiocyanate by Skalar Continuous Flow Analyser	PM119	As received solid samples are extracted with 1M NaOH by orbital shaker for Sulphide and Thiocyanate analysis.			AR	Yes
TM131	Quantification of Asbestos Fibres and ACM, based on HSG248 and SCA method.	PM42	Solid samples undergo a thorough visual inspection for asbestos fibres prior to asbestos identification using TM065.	Yes		AR	Yes
TM173	Analysis of fluoride by ISE (Ion Selective Electrode) using modified ISE method 340.2	PM20	Extraction of dried and ground or as received samples with deionised water in a 2:1 water to solid ratio using a reciprocal shaker for all analytes except hexavalent chromium. Extraction of as received sample using 10:1 ratio of 0.2M sodium hydroxide to soil for hexavalent chromium using a reciprocal shaker.			AR	Yes

JE Job No: 18/7222 18/5333 18/5166 18/5455 18/5775 18/5384

Test Method No.	Description	Prep Method No. (if appropriate)	Description	ISO 17025 (UKAS/S ANAS)	MCERTS (UK soils only)	Analysis done on As Received (AR) or Dried (AD)	Reported on dry weight basis
NONE	No Method Code	NONE	No Method Code				
NONE	No Method Code	NONE	No Method Code			AR	Yes
TM15_A	Modified USEPA 8260. Quantitative Determination of Volatile Organic Compounds, Vinyl Chloride & Styrene by Headspace GC-MS.	PM10	Modified US EPA method 5021. Preparation of solid and liquid samples for GC headspace analysis.			AR	Yes

Appendix E Gas and Groundwater Monitoring Results

Ground Water Monitoring 11/05/18								
Hole ID	Depth to base (m)	Depth to water (m)	Height of well casing from ground level (m)	pH	Temperature (°C)	Specific Conductivity (µS/cm)	RDO concentration (mg/L)	ORP (mV)
WS01	2.57	2.16	0.35	-	-	-	-	-
WS02	1.46	1.37	1.57	-	-	-	-	-
WS03	3.8	1.4	0.29	8.92	10.08	3247.9	0.05	-42
WS04	1.88	0.99	0.37	8.97	11.48	5176.8	0.02	-16.1
WS05	4.38	1	0.28	8.63	10.97	3124.5	0.16	-66.9
WS06	3.75	1.59	0.25	9.07	10.83	1359.6	0.05	-110.2
WS07	3.74	1.83	0.44	9.29	11.5	1302.9	1.18	-70.6
WS08	4.55	3.86	0.4	-	-	-	-	-
BH01	14.82	3.97	0.28	9.17	11.62	751.68	2.32	107.3
BH02	15.26	2.87	0.42	8.46	17.55	424.14	2.22	37.9
BH03	28.91	2.75	0.3	9.11	12.86	692.92	0.35	-36.9
BH04	>30	1.56	-	-	-	-	-	-
BH05	17.91	2.04	-	-	-	-	-	-
BH06	>30	2.33	0.45	-	-	-	-	-

Gas monitoring 11/05/18

Hole ID	Pressure (mb)	Peak Flow (L/hr)	Steady Flow(L/hr)	CO ₂ peak (%)	CO ₂ stable (%)	O ₂ minium (%)	O ₂ stable (%)	CH ₄ peak (%)	CH ₄ stable (%)
WS01	1011	0	0	1	0.7	19.6	19.6	0	0
WS02	1012	0	0	0.4	0.1	20.1	20.2	0	0
WS03	1012	0	0	0.1	0.1	20.5	20.5	0	0
WS04	1012	0	0	0.2	0.2	20.2	20.4	0	0
WS05	1012	0	0	0	0	20.7	20.7	0	0
WS06	1017	0	0	0.1	0.1	20.6	20.7	0	0
WS07	1016	0.4	0.2	0.4	0.2	20.6	20.9	0	0
WS08	1017	4.8	0	0.7	0.5	20.4	20.6	0	0
BH01	1012	0	0	0.4	0.2	20.1	20.3	0	0
BH02	1012	0	0	0.2	0.2	20.5	20.5	0	0
BH03	*	*	*	*	*	*	*	*	*
BH04	1017	0	0	0.1	0.1	20.7	20.7	0	0
BH05	1017	0	0	0.4	0.1	20.1	20.5	0	0
BH06	1017	0	0	0.1	0.1	20.6	20.9	0	0

Note:

Pressure in the morning 1011, peaking at 1017 with the last recording of 1016 taken at the end of the day.

Measurements taken from top of well casing.

Well BH04 and 06 were too deep for the interface probe (30m)

Gas readings for BH03 absent due to gas tap being off

Gas tap dropped down well side of WS08

Water samples from WS06 were very silty and the hole began to run dry during sampling

WS07 ran dry before sampling could take palce

Duplicate water sample of BH03 collected

Ground Water Monitoring 23/05/18			Gas monitoring 23/05/18								
Hole ID	Depth to water (m)	Depth to base (m)	Pressure (mb)	Peak Flow (L/hr)	Steady Flow(L/hr)	CO ₂ peak (%)	CO ₂ stable (%)	O ₂ minium (%)	O ₂ stable (%)	CH ₄ peak (%)	CH ₄ stable (%)
WS01	2.085	2.475	1025	0	0	0.1	0.1	20.3	20.3	0	0
WS02	1.32	1.465	1026	-17	0	3.9	0.1	14.4	20.3	0	0
WS03	1.525	3.72	1025	7.3	0	0.3	0.2	20.3	20.3	0	0
WS04	0.96	1.7	1026	0	0	0.1	0.1	20.3	20.3	0	0
WS05	0.98	4.165	1026	0	0	0.1	0.1	20.3	20.3	0	0
WS06	1.61	3.62	1025	0	0	0.2	0.1	20.3	20.4	0	0
WS07	1.835	3.61	1025	0	0	0.4	0.1	20.2	20.3	0	0
WS08	3.485	4.5	1026	4.8	0	0.2	0	20.4	20.4	0	0
BH01	3.705	14.265	1026	5.3	0	0.6	0.4	19.8	19.9	0	0
BH02	2.66	15.13	1025	0	0	0.1	0.1	20.4	20.4	0	0
BH03	2.57	28.84	1026	0	0	0.8	0.1	20.3	20.4	0	0
BH04	1.31	35.03	1025	0	0	0.1	0.1	20.3	20.3	0	0
BH05	1.865	17.795	1026	0	0	0.2	0.1	20.3	20.3	0	0
BH06	2.195	35.03	1025	0	0	0.1	0.1	20.4	20.4	0	0

Note:

Pressure in the morning 1026, peaking at 1026 with the last recording of 1026 taken at the end of the day.

Measurements taken from top of well casing.

Gas readings from WS02 fluctuated a lot, up and down by approximately 6% for a while before it stabilised

New gas tap placed on WS08

Ground Water Monitoring 01/06/18			Gas monitoring 01/06/18								
Hole ID	Depth to water (m)	Depth to base (m)	Pressure (mb)	Peak Flow (L/hr)	Steady Flow(L/hr)	CO ₂ peak (%)	CO ₂ stable (%)	O ₂ minium (%)	O ₂ stable (%)	CH ₄ peak (%)	CH ₄ stable (%)
WS01	2.11	2.491	1018	0	0	0.5	0.2	20.2	20.4	0	0
WS02	1.367	1.451	1018	0	0	1.3	0.1	19.4	20.6	0	0
WS03	1.482	3.703	1018	5.4	0	0.3	0.3	20.4	20.6	0	0
WS04	0.967	1.676	1018	0	0	0.1	0.1	20.6	20.6	0	0
WS05	1.03	4.417	1017	0	0	0.1	0.1	20.4	20.4	0	0
WS06	1.64	3.622	1017	0	0	0.1	0.1	20.7	20.7	0	0
WS07	1.866	3.599	1017	0	0	0.1	0.1	20.7	20.8	0	0
WS08	3.332	4.5	1016	1.3	0	0.5	0	20.7	20.8	0	0
BH01	3.783	14.285	1018	-1	0	0.7	0.5	19.9	20	0	0
BH02	2.775	15.182	1017	0	0	0.1	0.1	20.6	20.7	0	0
BH03	2.656	28.915	1017	6	0	0.1	0.1	20.4	20.7	0	0
BH04	1.438	35.033	1016	0	0	0.1	0	20.7	20.8	0	0
BH05	1.955	17.838	1016	0	0	0	0	20.7	20.7	0	0
BH06	2.271	34.99	1017	0	0	0.1	0.1	20.7	20.8	0	0


Note:

Pressure in the morning 1018, peaking at 1026 with the last recording of 1016 taken at the end of the day.

Measurements taken from top of well casing.

Appendix F Parametric Study Charts

- A.1 – SPT N Value vs Elevation for Glacial Deposits
- A.2 – Hand Vane Shear Strength Value vs Elevation for Made Ground
- A.3 – Undrained Shear Strength Value vs Elevation for Glacial Deposits
- A.4 – Plasticity Chart for Made Ground
- A.5 – Plasticity Chart for Glacial Deposits
- A.6 – Plasticity Index value vs Elevation for Glacial Deposits
- A.7 – Plasticity Index value vs Elevation for Made Ground
- A.8 – pH Value vs Depth for Superficial Materials (MG and GT)
- A.9 – SO₄ (H₂O Sol) vs Depth for Superficial Materials (MG and GT)
- A.10 – SO₄ (Acid Sol) vs Depth for Superficial Materials (MG and GT)
- A.11 – Total Sulfur (%) vs Depth for Superficial Materials (MG and GT)




SPT N Value vs Elevation

Geological Units: Glacial Deposits (Slightly Sandy Slightly Gravelly Clay)

Figure A.1

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






Hand Vane Shear Strength Value vs Elevation

Geological Units: Cohesive Made Ground

Figure A.2

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






Undrained Shear Strength Value vs Elevation

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)

Figure A.3

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






Plasticity Chart

Geological Unit: Cohesive Made Ground

Figure A.4

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






Plasticity Chart

Geological Unit: Glacial Till (Slightly Sandy Slightly Gravelly Clay)

Figure A.5

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






Plasticity Index vs Elevation

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)
Cohesive Made Ground

Figure A.6

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






pH Value vs Depth

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)
Cohesive Made Ground

Figure A.7

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International






SO4 (H2O Sol) vs Depth

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)
Cohesive Made Ground

Figure A.8

Project Number: 60569745
Project Title: VPI Immingham Energy Park
Client: Vitrol Power International






SO4 (Acid Sol) vs Depth

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)
Cohesive Made Ground

Figure A.9

Project Number: 60569745
Project Title: VPI Immingham Energy Park
Client: Vitrol Power International





Total Sulfur (%) vs Depth

Geological Units: Glacial Till (Slightly Sandy Slightly Gravelly Clay)
Cohesive Made Ground

Figure A.10

Project Number:	60569745
Project Title:	VPI Immingham Energy Park
Client:	Vitol Power International



Appendix G Contamination Assessments

Human Health Soils Risk Assessment

Main data table with columns for Analyte, Human Health GAC, Controlled waters GAC, and various monitoring points (BH01 to WS08). Rows include VOCs, Chlorinated Hydrocarbons, Halogenated Benzenes, PAHs, Phenolics, Halogenated Phenols, Phthalates, TICs, TPH, and BTEX.

Summary table with columns for Number of Result Detects, Minimum Concentration, Maximum Concentration, Average Concentration, Standard Deviation, and Number of Guideline Exceedances. Rows correspond to the analytes in the main table.

Groundwater Contamination Risk Assessment

Main table listing chemical analytes, standards (Drinking Water, Coastal Environmental), and monitoring data (Date, BH01-BH05, WS03-WS06) with numerical values.

Summary table with columns: Number, Minimum, Maximum, Average, Median, Standard, Number, Number of. It provides statistical summaries for various analytes.

Appendix F – Risk Assessment Principles

CSM Risk Assessment Principles

Current good practice recommends that the determination of hazards due to contaminated land is based on the principle of risk assessment, as outlined in the Environment Agency (EA) guidance on Model Procedures for the Management of Land Contamination (CLR 11). For a risk to be present, there must be a viable pollutant linkage; i.e. a mechanism whereby a source of contamination impacts on a sensitive receptor via a pathway.

Using criteria broadly based on those presented in the EA, Chartered Institute of Environmental Health (CIEH) and National House Building Council (NHBC) R&D Publication 66: 'Guidance for the Safe Development of Housing on Land Affected by Contamination' (2008), the magnitude of the risk associated with potential contamination at the site has been assessed. To do this an estimate is made of:

- The magnitude of the potential consequence (i.e. severity); and
- The magnitude of probability (i.e. likelihood).

The severity of the risk is classified according to the criteria in **Table A**, below:

Table A: Severity of Potential Pollutant Linkages

SEVERITY	EXAMPLES
Major	<ul style="list-style-type: none"> - Acute damage to human health, likely to result in significant harm. - Catastrophic damage to buildings/property (e.g. by explosion, sites with high gassing potential, extensive VOC contamination). - Major pollution of controlled waters (e.g. surface watercourses or Principal aquifers/source protection zones). - Significant and lasting damage to sensitive ecosystems or species.
Moderate	<ul style="list-style-type: none"> - Chronic (long-term) risk to human health likely to result in a reduced quality of life. - Significant and costly damage to property, buildings, structures or services. - Pollution of sensitive controlled waters (e.g. surface watercourses or Principal/ Secondary aquifers). - Damage to sensitive ecosystems or species.
Minor	<ul style="list-style-type: none"> - Non-permanent human health effects. - Moderate damage to buildings structures or services. - Pollution of non-sensitive waters (e.g. smaller surface watercourses or non-aquifers). - Damage to non-sensitive ecosystems or species.
Minimal	<ul style="list-style-type: none"> - Temporary discomfort. - Minor (easily repairable) damage to buildings, structures or services. - Short-term decrease in non-sensitive waters quality. - Temporary disturbance of non-sensitive ecosystems.

The probability of the risk occurring is classified according to the criteria in **Table B**, below:

Table B: Likelihood of Risk Occurrence

LIKELIHOOD	EXPLANATION
Highly Likely	- Contaminant linkage may be present that appears very likely in the short-term and risk is almost certain to occur in the long term, or there is evidence of harm to the receptor.
Likely	- Contaminant linkage may be present, and it is probable that the risk will occur over the long term.
Possible	- Contaminant linkage may be present and there is a possibility of the risk occurring, although there is no certainty that it will.
Unlikely	- Contaminant linkage may be present but the circumstances under which harm could occur are improbable.

An overall evaluation of the magnitude of the risk is gained from a comparison of the severity and probability, as shown in **Table C**, below:

Table C: Risk Based on Comparison of Likelihood and Severity

		SEVERITY			
		MAJOR	MODERATE	MINOR	MINIMAL
LIKELIHOOD	HIGHLY LIKELY	Very High	High	Considerable	Medium
	LIKELY	High	Considerable	Medium	Low
	POSSIBLE	Considerable	Medium	Low	Very Low
	UNLIKELY	Medium	Low	Very Low	Negligible

