



SUNNICA ENERGY FARM

EN010106

Volume 6

Environmental Statement

6.2 Appendix 11B: Acoustic Terminology

APFP Regulation 5(2)(a)

Planning Act 2008

Infrastructure Planning (Applications: Prescribed Forms and
Procedure) Regulations 2009



Planning Act 2008

**The Infrastructure Planning
(Applications: Prescribed Forms and
Procedure) Regulations 2009**

Sunnica Energy Farm

**Environmental Statement
Appendix 11B: Acoustic Terminology**

Regulation Reference:	Regulation 5(2)(a)
Planning Inspectorate Scheme Reference	EN010106
Application Document Reference	EN010106/APP/6.2
Author	Sunnica Energy Farm Project Team

Version	Date	Status of Version
Rev 00	18 November 2021	Application Version

Table of contents

1	Acoustic Terminology	1
----------	-----------------------------	----------

Table of Tables

Table 1-1 Acoustic Terminology	1
Table 1-2 Sound Pressure Level in dB L _{pA} for Common Situations	2

1 Acoustic Terminology

Table 1-1 Acoustic Terminology

Noise	Unwanted or unexpected sound.
Frequency (Hz)	The number of cycles per second (i.e., the number of vibrations that occur in one second); subjectively this is perceived as pitch.
Frequency Spectrum	The relative frequency contributions that make up a noise.
"A" Weighting (dB(A))	The human ear does not respond uniformly across the audible frequency range. The "A" weighting is commonly used to simulate the frequency response of the ear.
Decibel (dB)	The decibel is a logarithmic ratio of two values of a variable. The range of audible sound pressures is approximately 2×10^{-5} Pa to 200 Pa. Using decibel notation presents this range in a more manageable form, 0 dB to 140 dB.
Sound Pressure Level (L_p)	Equal to 20 times the logarithm to the base 10 of the ratio of the root mean squared (RMS) sound pressure to the reference sound pressure. In air the reference sound pressure is 2×10^{-5} Pa. Mathematically: $\text{Sound Pressure Level (dB)} = 20 \log_{10} \{p(t) / P_0\}$ Where $P_0 = 2 \times 10^{-5}$ Pa
Ambient Noise Level, $L_{Aeq,T}$	The equivalent continuous A-weighted sound pressure level of the totally encompassing sound in a given situation at a given time that is usually composed of sound from many sources near and far.
Background Noise Level $L_{A90,T}$	The A-weighted sound pressure level of the residual noise at the assessment position that is exceeded for 90% of a given time interval, T, measured using the fast time weighting, F, and quoted to the nearest whole number.
Reference Time Interval, T_r	The specified interval over which an equivalent continuous A-weighted sound pressure level is determined.
Specific Noise Level, $L_{Aeq,Tr}$	The equivalent continuous A-weighted sound pressure level at the assessment position produced by the specific noise source over a given reference time interval.

1.1.1 Between the quietest audible sound and the loudest tolerable sound, there is a ten million to one ratio in sound pressure (measured in pascals, Pa). Because of this wide range, a noise level scale based on logarithms is used in noise measurement called the decibel (dB) scale. Audibility of sound covers a range of approximately 0 to 140 dB.

Table 1-2 Sound Pressure Level in dB L_{pA} for Common Situations

Typical Noise Level, dB L _{pA}	Example
0	Threshold of hearing
30	Rural area at night, still air
40	Public library Refrigerator humming at 2 m
50	Quiet office, no machinery Boiling kettle at 0.5 m
60	Normal conversation
70	Telephone ringing at 2 m Vacuum cleaner at 3 m
80	General factory noise level
90	Heavy goods vehicle from pavement Powered lawnmower, operator's ear
100	Pneumatic drill at 5 m
120	Discotheque – 1 m in front of loudspeaker
140	Threshold of pain