

APPENDIX 13A: GAZETTEER OF CULTURAL HERITAGE ASSETS

APPENDIX 13A: GAZETTEER OF CULTURAL HERITAGE ASSETS

Table 13A.1: Gazetteer of designated assets

REFERENCE	GRID REFERENCE	PERIOD	DESCRIPTION	NO. ON FIG 13.1
1020423	TA 19519 11598	Medieval	Stallingborough Medieval Settlement. Scheduled monument.	1020423
1010947	TA 21356 09996	Medieval	Moated Sites at Healing Hall. Scheduled monument.	1010947
1020023	TA 19495 11819	Medieval	Churchyard Cross, St Peter and St Paul's Church. Scheduled monument.	1020023
1103469	TA 20582 11872	Post-Medieval	129 Station Road, Stallingborough. Grade II listed building.	1103469
1379884	TA 23775 10346	Post-Medieval	Manor Farmhouse, Station Road, Great Coates, Grimsby. Grade II listed building.	1379884
1379419	TA 23586 10242	Post-Medieval	Cordeaux House, 15 Cooks Lane, Great Coates, Grimsby. Grade II listed building.	1379419
1379429	TA 23529 10264	Post-Medieval	19-22 Cooks Lane, Great Coates, Grimsby. Grade II listed building.	1379429
1379430	TA 23470 10248	Post-Medieval	The Manor House including stables and coach house, Cooks Lane, Great Coates. Grade II listed building.	1379430
1379431	TA 23453 10271	Post-Medieval	Dovecote and Stable to north-west of Manor House, Great Coates, Grimsby. Grade II listed building.	1379431
1346978	TA 19506 11837	Post-Medieval	Church of St. Peter and St. Paul, Stallingborough. Grade II* listed building.	1346978

REFERENCE	GRID REFERENCE	PERIOD	DESCRIPTION	NO. ON FIG 13.1
1403222	TA 18415 11627	Modern	Former heavy anti-aircraft gun site, near Stallingborough. Grade II* listed building.	1403222
1379843	TA 23328 09784	Medieval	Church of St. Nicolas, Great Coates, Grimsby. Grade I listed building.	1379843
1379845	TA 24139 09020	Medieval	Church of St. Michael, Little Coates. Grade I listed building.	1379845
1379856	TA 27216 10587	Post-Medieval	Grimsby Haven Dock, Grimsby. Grade II* listed building.	1379856
1379871	TA 27792 11379	Post-Medieval	Hydraulic Accumulator Tower. Grade II* listed building.	1379871
1379870	TA 27844 11348	Post-Medieval	The Dock Tower, Royal Docks. Grade I listed building.	1379870
-	TA 23577 10118	-	Great Coates Conservation Area.	

Table 13A.2: Gazetteer of non-designated assets

REFERENCE	GRID REFERENCE	PERIOD	DESCRIPTION	NO. ON FIG 13.1
0040/1/0	TA 23158 13038	Roman	Roman Enclosure north of Old Fleet Drain. A geophysical survey (1997) of an area of known cropmarks north of Old Fleet Drain revealed areas of magnetic enhancement which were thought to be sites of late Roman/ Romano British pottery manufacture. Roman pottery was recovered during a fieldwalking survey (2005). Subsequent evaluation and excavation (2008) uncovered two phases of a 3rd-4th century ditched field systems, with some earlier and later finds present, as well as evidence for timber buildings and crop processing.	A1
0294/1/0	TA 21853 11369	Medieval	Oldfleet Drain, formerly Healing Beck. A drain marked on the ordnance survey 1887-9 25 inch to 1 mile maps.	A2
0299/1/0	TA 238 129	Modern	Courtaulds Landfill Site 'A'. 20 th century landfill site.	A3
0302/1/0	TA 238 130	Medieval	Historic Settlement of Houflet. Suggested site of Houflet deserted medieval village. The village is perhaps indicated in Domesday - "in Wenflet (?Houflet) there are 2 bovates to geld, there is land for 2 oxen." Houflet is first referred to by this name in a grant of Henry II to Wellow Abbey.	A4
0311/15/0	TA 2248 123	Modern	Hunting Woodland, Healing. An early 20 th century hunting wood on the former marshland of Healing Parish. The woodland contains two areas of tall deciduous trees flanking an area which appears to have been laid out to be scrubland, with low growing bushes and trees surrounding. It is not known for certain what purpose the areas of planting served but it is clearly a deliberate act.	A5

REFERENCE	GRID REFERENCE	PERIOD	DESCRIPTION	NO. ON FIG 13.1
0355/1/0	TA 23310 13703	Modern	Immingham (IM1) Naval Decoy. A Special Fire (Starfish) and QL (poor Blackout) decoy built to fool attacking bombers.	A6
0357/1/0	TA 23200 13700	Modern	Pillbox (searchlight), Stallingborough. A defence electric light or coastal searchlight.	A7
0358/1/0	TA 23846 13102	Post-medieval	Stallingborough Sluice. A sluice built around 1749 to drain land between Grimsby and Immingham.	A8
0359/1/0	TA 23035 13964	Post-medieval	Beacon in Stallingborough. A beacon (for shipping) marked on the 1887–9 OS 25-inch map. One of a pair. Not accurately located.	A9
0359/2/0	TA 22979 13821	Post-medieval	Beacon in Stallingborough. A beacon (for shipping) marked on the 1887–9 OS 25-inch map. One of a pair. Not accurately located.	A10
0364/1/0	TA 21307 12959	Post-medieval	Middle Drain. A land drain marked on the 1887–9 OS 25-inch map.	A11
0365/1/0	TA 22748 13485	Post-medieval	Sheep Pen in Stallingborough. A sheep pen marked on the 1906–8 OS 25-inch map.	A12
0366/1/0	TA 22810 13238	Modern	South Humber Bank Power Station. The current South Humber Bank Power Station, construction of which started in 1994 and began commercial service in 1997.	A13
0553/1/0	TA 22479 13574	Undated	Cropmark Enclosure between South Marsh Road, Hobson Way and Middle Drain, Stallingborough. A Cropmark of enclosures and a ditch shown on aerial photographs. Shown as a very fresh cropmark or earthwork on 1940s aerial photographs, so given the location it may be part of the Immingham SF or QL bombing decoys (HER 0355/1/0).	A14

REFERENCE	GRID REFERENCE	PERIOD	DESCRIPTION	NO. ON FIG 13.1
0647/2/0	TA 21794 13725	Post-medieval	Possible Former Sea Defence Bank in Stallingborough. A possible former sea defence bank, extrapolated from the line of the possible bank in Immingham and an abrupt change in field morphology.	A15
0921/9/0	TA 2129 1279	Post-medieval Modern	South Marsh Road, Stallingborough. A road marked on the 1887–9 OS map. A minor re-alignment now takes the road over the A180 dual carriageway.	A16
0978/1/0	TA 2407 1279	Modern	Rifle Range in Great Coates. A rifle range shown on the 1932–3 OS map built against the sea wall. Two safety observation posts (for monitoring vessels in the Humber and pedestrians on the sea wall), made of re-enforced prefabricated concrete panels, were at OS NGR TA 2400 1309 and OS NGR TA 2444 1267. One still stands, with the remains of a probable warning flag post nearby.	A17
0999/2/0	TA 2377 1309	Modern	Ordnance Survey Trigonometry Station, Healing. A 20 th century concrete pillar designed as a triangulation point and used for accurate surveying.	A18
1030/1/0	TA 2274 1389	Post-medieval	Possible Farmstead in Stallingborough. A pair of buildings, a spring, and an area of trees which may represent an orchard all within a set of small enclosures and shown on the 1887–9 OS map. Probably a small farmstead.	A19
2004/0/0	TA 23442 13161	Modern	Grimsby District Electric Light Railway. A 20th century light railway with electrically driven carriages.	A20
2005/0/0	TA 2226 1300	Modern	London and North Eastern Railway - Grimsby District Light Railway. A light railway marked on the 1932–3 OS map	A21

Table 13A.3: Gazetteer of archaeological events

REFERENCE	ORGANISATION	TYPE	DATE	DESCRIPTION	NO. ON FIG 13.2
ENL140	GSB Prospection	Geophysical survey	1992	Stallingborough, Humberside: Report on Geophysical Survey of Proposed Power Station Site.	E1
ENL147	Oxford Archaeology	Archaeological watching brief	1993	Courtaulds Fibres Landfills and Houflet Deserted Settlement.	E2
ENL103	GSB Prospection	Borehole	1993	Report on Borehole Tests Following Geophysical Survey. Finding from the geophysical survey commissioned by Humber Power Ltd to test for indications of any possible archaeological features or disturbances within the proposed power station site. The survey showed that although parts of the site presented difficulties for magnetic investigation because of interference from the presence of slag used in modern drainage works, there were also areas showing distinct concentrations of magnetic anomalies which appeared likely to be of natural origin.	E3

REFERENCE	ORGANISATION	TYPE	DATE	DESCRIPTION	NO. ON FIG 13.2
ENL260	British Gas Engineering Projects	DBA Archaeological watching brief Archaeological excavation	1994–1996	Brocklesby to Stallingborough High Pressure Pipeline. A scheme of desk-based assessment, aerial photography survey, archaeological fieldwalking and excavation was undertaken prior to the laying of a high-pressure gas main between Brocklesby/ Habrough and Stallingborough. A watching brief was also maintained throughout the construction phase. The surveys identified several areas of archaeological interest, including evidence of prehistoric activity to the south of the former medieval settlement of Habrough and a cropmark complex of indeterminate age and nature south of Eleanor House in Stallingborough.	E4
ENL105	West Yorkshire Archaeological Services	Geophysical survey	1997	Land Adjacent to South Humber Bank Power Station. Areas of magnetic enhancement were identified which are thought to be sites of late Roman/ Romano-British pottery manufacture. Other areas of enhancement could locate areas of clay extraction. A possible double ditched trackway appears to demarcate the areas of industrial activity outlined above. More recent anomalies include field drains, recent field boundaries and evidence of ridge and furrow ploughing.	E5

REFERENCE	ORGANISATION	TYPE	DATE	DESCRIPTION	NO. ON FIG 13.2
ENL 65	North East Lincolnshire Archaeology Service	Archaeological watching brief	1999	Landfill No.3 Acordis Works, Stallingborough, North East Lincolnshire. Roman/ Romano British pottery was found in the area, which is probably related to a site to the north of the drain. The absence of Medieval material indicates the deserted Medieval village of Houflet was not located within the area of this development. The rest of the recovered material related to the post Medieval period.	E6
ENL 262	GSB Prospection	Geophysical survey	2011	Geophysical Survey Report: Proposed Acetylene Facility, Immingham. Responses typical of natural deposits and modern ferrous features (pipes, fencing etc.) dominate the survey results. No definite archaeological anomalies have been identified.	E7
ENL 52	Lindsey Archaeological Services	Field walking	2005	Land North of Old Fleet Drain, Stallingborough. A field walking survey was carried out on land north of Old Fleet Drain in March 2005 as the first stage of an evaluation of the site 140 pieces of Roman pottery were concentrated in a cluster approx. 80m x 60m in area, towards the western end of the field. This concentration coincides with cropmarks recorded on aerial photographs and magnetic anomalies recorded on a geophysical survey carried out in 1997 and may represent the presence of salt making or possibly a pottery kiln of Roman date.	E8

REFERENCE	ORGANISATION	TYPE	DATE	DESCRIPTION	NO. ON FIG 13.2
ENL 90	Lindsey Archaeological Services	Archaeological trial trench evaluation	2005	Land North of Old Fleet Drain, Stallingborough. Evaluation a single 90m long trench across the area of a previously identified Roman pottery scatter. Substantial Roman ditches were revealed which contained pottery dating from the late 3rd to late 4th centuries AD.	E9
ENL263	Naomi Field Archaeological Consultancy	Archaeological excavation	2008	Biomass Generating Station, Hobson Way, Stallingborough. Excavations at Hobson Way, Stallingborough revealed a multi-phased late-Roman rural site in the salt marsh close to the coastline. Two main alignments of ditched field systems, both of 3rd-4th century date were recorded. Demolished buildings were recorded. Environmental evidence pointed to cultivation of cereal crops in the vicinity and processing of grain on site, but the main function of the site may have been seasonal animal husbandry.	E10
ENL224	Humber Archaeology Partnership	Archaeological watching brief	2009	Archaeological Observation and Recording Adjacent to the Middle Drain. The programme of works consisted of the removal of a quantity of topsoil by machine prior to the area being stoned-up to form the base for the works compound. Due to the shallow nature of the works no archaeological deposits or artefacts were revealed.	E11