

# Sheringham Shoal and Dudgeon Offshore Wind Farm Extension Projects

**Environmental Statement** 

Volume 3

Appendix 18.3 – Geomorphological Baseline Survey Technical Report (Revision B) (Tracked)

# **Revision B**

Deadline 3 May 2023 Document Reference: 6.3.18.3.1 APFP Regulation: 5(2)(a)







Title:

### Sheringham Shoal and Dudgeon Offshore Wind Farm Extension Projects Environmental Statement Appendix 18.3.1: Geomorphological Baseline Survey Technical Report (Revision

PINS Document no.: 6.3.18.3.1

**B) (Tracked)** 

Revision: B	
Document no.: C282-RH-Z-GA-00079	
Date:	Classification
<u>May 2023</u>	Final
Prepared by:	
Royal HaskoningDHV	
Approved by:	Date:
<u>Sheery Atkins</u> , Equinor	<u>May 2023</u>



### **Table of Contents**

18.3	GEOMORPHOLOGICAL BASELINE SURVEY TECHNICAL REPORT	9
18.3.1	Introduction	9
18.3.2	Methodology	11
18.3.3	Results	13
	Summary	

# **Table of Tables**

. 11
. 13
. 16
. 20
. 24
. 29
. 33
. 37
. 40
. 43
· · · ·

# **Table of Figures**

Figure 19.2.1, SED and DED	Comparabolagiaal Survey Stur	dy Area 10
Figure To.S.T. SEP and DEP	Geomorphological Survey Stud	dy Area 10

## **Table of Plates**

Plate 18.3.1: Spring Beck	13
Plate 18.3.2: Spring Beck Channel Form	14
Plate 18.3.3: Sediment Sources and Local Impoundment	15
Plate 18.3.4: River Glaven	16
Plate 18.3.5: Online Pond in the River Glaven	17
Plate 18.3.6: River Glaven Channel Form	17
Plate 18.3.7: Glacial Till Bank Composition in the River Glaven	18
Plate 18.3.8: Silt Deposition and Outfall Pipe	18
Plate 18.3.9: River Bure and Example Ditch	20
Plate 18.3.10: River Bure Floodplain and Channel Features	21
Plate 18.3.11: Water-Crowfoot (Left) and Himalayan Balsam (Right)	22
Plate 18.3.12: Swannington Beck – Primary Channel	24
Plate 18.3.13: Swannington Beck – Secondary Channel	25
Plate 18.3.14: Anabranch and Wet Woodland	26
Plate 18.3.15: Weir and Bed Armouring Along the Swannington Beck	27
Plate 18.3.16: Sediment Deposition Upstream of Weir	27
Plate 18.3.17: River Wensum Primary and Secondary Channel	29
Plate 18.3.18: Channel and Floodplain Features	30
Plate 18.3.19: Secondary Channel and Field Ditches	30



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1<u>B</u></del>

Plate 18.3.20: Silt Deposition	31
Plate 18.3.21: Secondary Channel Floodplain Connectivity	32
Plate 18.3.22: Modification of the Secondary Channel	32
Plate 18.3.23: River Tud	33
Plate 18.3.24: River Tud Floodplain Features	34
Plate 18.3.25: Clean Gravel Bed Substrate	35
Plate 18.3.26: Water-Crowfoot and Watercress	35
Plate 18.3.27: River Yare and Floodplain	37
Plate 18.3.28: River Yare Channel Form and Floodplain Features	38
Plate 18.3.29: River Tiffey and Floodplain Features	40
Plate 18.3.30: River Tiffey Channel Form	41
Plate 18.3.31: Sand Ripples	42
Plate 18.3.32: Intwood Stream Channels	43
Plate 18.3.33: Western Channel of the Intwood Stream	44
Plate 18.3.34: Eastern Channel of the Intwood Stream	45
Plate 18.3.35: Western Channel Form	45
Plate 18.3.36: Western Channel Wetland and Example Ditch	
Plate 18.3.37: Glacial Till Bank Composition	46
Plate 18.3.38: Livestock Poaching and Silts on Channel Bed.	47
Plate 18.3.39: Outfall Pipes and Small Culvert	



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <u>-no. 1</u> <u>B</u>

# **Glossary of Acronyms**

BNG	Biodiversity Net Gain
DCO	Development Consent Order
DEP	Dudgeon Offshore Wind Farm Extension Project
GPS	Global Positioning System
PEIR	Preliminary Environmental Information Report
SAC	Special Area of Conservation
SEP	Sheringham Shoal Offshore Wind Farm Extension Project
SSSI	Site of Special Scientific Interest
WFD	Water Framework Directive



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <u>-no. 1</u> <u>B</u>

# Glossary of Terms

Armouring	Armouring occurs when the bed surface of gravel-bed rivers is coarsened relative to the sub-surface.					
Bankfull discharge	Bankfull discharge is the flow that reaches the transition between the channel and its flood plain and is thus morphologically significant.					
Bar	An accumulation of alluvium (usually gravel or sand) caused by a decrease in sediment transport capacity on the inside of meander bends or in the centre of an overwide channel.					
Bed	The bottom of a channel.					
Bed Slope	The inclination of the channel bottom, measured as the elevation drop per unit length of channel.					
Catchment	The total area of land that drains into any given river.					
Coarse sediment	Sediment of grain diameter greater than 2 mm.					
Cobbles	Substrate particles that are smaller than boulders and larger than gravels and are generally 64 - 256 mm in diameter. Can be further classified as small and large cobble.					
Order Limits	The area subject to survey and preliminary impact assessment to inform the DCO, including all permanent and temporary works for SEP and DEP.					
Dudgeon Offshore Wind Farm Extension Project (DEP)	The Dudgeon Offshore Wind Farm Extension onshore and offshore sites including all onshore and offshore infrastructure.					
Erosion	Process that wears away the river bed and banks. Erosion also breaks up the rocks that are carried by the river.					
Equilibrium	Rivers seek a state of dynamic equilibrium between the imposed conditions of valley slope, discharge, and sediment supply, and channel adjustments that can include width, depth, velocity, reach slope, roughness, and sediment size. Over historical time, the channel adjusts to changes in discharge and sediment supply due to human activities, climate change, and extreme events.					
Gravel	Gravel or other shallow sediment deposition on the inside of bends.					
Glide	A section of smooth or rippled flow, deeper flow than run.					
Main Rivers	A statutory type of watercourse in England and Wales, maintained by the Environment Agency (EA). These watercourses are usually larger streams and rivers, but also include some smaller watercourses.					



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1<u>B</u></del>

Ordinary Watercourse	Includes every river, stream, ditch, drain, cut, dyke, sluice, sewer (other than a public sewer) and passage through which water flows and which does not form part of a main river.			
Preliminary Environmental Information Report (PEIR)	The environmental assessment that preceded the Environmental Statement and presented an initial assessment of potential project impacts on sensitive receptors.			
Planform	The planform evolution of meandering rivers occurs as a result of mutual adjustments between meandering form and processes.			
Pool	Discrete areas of deep water typically formed on the outside of meanders.			
Point Bar	Gravel or other shallow sediment deposition on the inside of bends.			
Reach	A section of watercourse between two defined points and/or a length of an individual river which shows broadly similar physical characteristics.			
Riparian	The area of land alongside a river, often planted with trees.			
Riffle	A reach of stream that is characterised by shallow, fast-moving water broken by the presence of rocks and boulders.			
Run	Shallow, fast flowing section, similar in character to a riffle but not a discrete feature.			
Sheringham Shoal Offshore Wind Farm Extension Project (SEP)	The Sheringham Shoal Offshore Wind Farm Extension onshore and offshore sites including all onshore and offshore infrastructure			
Sinuosity	Sinuosity, as applied to stream-channel pattern, is a non- dimensional ratio of the length of the channel thalweg to the length of the stream valley, measured between the same points.			
Silt	As fluvial sediment, silt is sediment with a particle diameter between 0.002 & 0.062 mm. Some classification systems define the lower size limit to be 0.004 mm.			
Scour	The erosive action of running water in streams, which excavates and carries away material from the bed and banks. Scour may occur in both earth and solid rock material and can be classed as general, contraction, or local scour.			
Wetland scrape	Shallow ponds of less than 1 m depth which hold rain or flood water seasonally and which remain damp for much of the year. They are shallow depressions with gently sloping edges which create obvious water features in fields. They can make a significant difference to wildlife and can be created in areas of damp or floodplain.			

Page 7 of 50



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <u>no. 1</u> <u>B</u>

Study area	Area where potential impacts from the project could occur, as defined for each individual EIA topic.				
Sedimentation (Siltation)	The process by which sediment is mechanically deposited from suspension within a fluid, generally water, or ice, thereby accumulating as layers of sediment that are segregated owing to differences in size, shape, and composition of the sediment particles.				
Scour	Removal of sediment such as sand and gravel.				
Substrate	Sediment material that rests at the bottom of a river.				
The Sheringham Shoal Offshore Wind Farm Extension Project (SEP)	The Sheringham Shoal Offshore Wind Farm Extension onshore and offshore sites including all onshore and offshore infrastructure.				
Thalweg	A line connecting the lowest points of successive cross- sections along the course of a valley or river.				
Water Framework Directive	Directive of the European Parliament and of the Council 2000/60/EC establishing a framework for community action in the field of water policy (generally known as the Water Framework Directive (WFD).				
Wetland	Wetland is a low-lying area, including ephemeral-lake floors, in which water either is shallowly ponded on the surface or has a persistent (weeks or longer) near-surface condition of ground- water saturation adequate to support hydrophytic vegetation.				




#### 18.3 GEOMORPHOLOGICAL BASELINE SURVEY TECHNICAL REPORT

#### 18.3.1 Introduction

- 1. Equinor New Energy Limited (hereafter the Applicant) is proposing to extend the existing operational Dudgeon and Sheringham Shoal Offshore Wind Farms named the Dudgeon Offshore Wind Farm Extension Project (hereafter DEP) and the Sheringham Shoal Offshore Wind Farm Extension Project (hereafter SEP). SEP and DEP will include a number of offshore and onshore elements including wind turbines and up to two offshore substations and associated cables to allow connection to the electricity transmission network.
- 2. Royal HaskoningDHV undertook a geomorphological baseline survey of the major watercourses proposed to be crossed by the SEP and DEP Preliminary Environmental Assessment Report (PEIR) boundary. The baseline survey involved a walkover of nine key watercourses to establish and characterise the baseline conditions at those sites prior to starting the site selection process for the Development Consent Order (DCO) limits (see Figure 18.3.1).

#### 18.3.1.1 Aims

- 3. The aim of the geomorphological walkover survey was to characterise the geomorphological baseline conditions of the major watercourses that are proposed to be crossed by SEP and/or DEP.
- 4. Characterising the geomorphology of watercourses provides baseline information on their physical form and the processes (such as sediment transport and deposition) that may influence this form. This baseline information has been used to determine how the watercourses are likely to respond to the construction, operation and decommissioning of SEP and DEP, and has also been used to inform the site selection of the DCO order limits. This baseline environment will then be used to inform the detailed design, construction and monitoring phases of SEP and DEP to ensure the geomorphological and ecological integrity of these watercourses is maintained, and also to inform potential opportunities for Biodiversity Net Gain (BNG).
- 5. The purpose of this report is to present the baseline characteristics of the surveyed watercourses, and to provide an overall understanding of their existing condition against which potential impacts and effects can be assessed. The baseline information gathered during this geomorphological walkover survey has been used to inform the assessments presented in Chapter 18 Water Resources and Flood Risk of the Environmental Statement and Appendix 18.1 Water Framework Directive Compliance Assessment.



		ringham Sh						
	Dudgeon Extension Projects							
l itie:	Title:							
	Figi	ure 18.3.1 Loca		lan				
Docum	En Appendix	vironmental Stater 18.3 Geomorphol Survey Technical	logical B					
	tion Doc. no.:	6.3.18.3						
Legend	Order Li	mits						
	PEIR Bo	oundary						
	Onshore	e Substation Site						
	Survey I	Location						
		ver Water Body						
	- Main Riv	ver						
3.								
ing Wa								
- The								
Y								
Sa								
5								
	Great Brita	in			Ć			
Isle of Man	Isle of Man							
	Presion Hull Groningen Sheffield Coloribu							
	Liverpool Lincoln Assen							
Cym Wa	Keynes Cambridge Den Haad Ambem							
Swansea	Gloucester of Cardiff	Dxford London Southend- on-Sea	Middelbur	g Eindhov	en We Düsseldor			
F	Swansea Cardiff Colchester Derivating Endform Variantes Southampton Brighton Dunkergue Lille Beiglie/							
Coordi	nate Referenc	e System: British Nation	al Grid					
Transfo	prmation WGS	884: OSGB_1936_To_W	/GS_1984_ <sup>8</sup>	7 10 Kilo	metres			
	0 2 4 6 Miles Scale: 1:175,000 Scale at size: A3							
	Equinor Doc. no.: C282-RH-Z-GA-00079 RHDHV Doc. no.: PB8164-RHD-ZZ-ON-DR-Z-0084							
	25/04/2023	Third Issue	DE	SM	ES			
С	28/07/2022	Second Issue	JT	HW	SM			
в			AZ	HW	SM			
B A	29/04/2022	First Issue	DBW/	CUIV				
в	29/04/2022 DATE	First Issue	DRW	СНК	APR			



#### 18.3.2 Methodology

6. This section presents the study area and methodology used to undertake the geomorphological walkover survey.

#### 18.3.2.1 Study Area

7. The PEIR boundary (Figure 18.3.1) was used to define the study area for the targeted geomorphological walkover survey. There are nine major watercourses within this study area. These consisted of all the Main Rivers and/or river water bodies identified under the Water Framework Directive (WFD) in the Anglian River Basin Management Plan. The nine identified watercourses are presented in Table 18.3.1 and Figure 18.3.1. Note that although the watercourses are located within the PEIR boundary, they would not necessarily be crossed by the narrower DCO order limits or the proposed cable route.

Name	Туре	Channel length within cable corridor (m)	Grid Reference
Spring Beck	Main River	1338	TG1102343425
River Glaven	WFD water body	947	TG1192939376
River Bure	Main River	768	TG1318929901
Swannington Beck	WFD water body	271	TG1417818892 TG1422919003
River Wensum	Main River	835	TG1282216767
River Tud	Main River	3115	TG1180811215
River Yare	Main River	412	TG1230008406
River Tiffey	Main River	269	TG1172107438
Intwood Stream	WFD water body	215	TG1940302636
	Main River	209	

#### Table 18.3.1: Surveyed Watercourses

#### 18.3.2.2 Field Survey

- 8. A targeted walkover survey was undertaken to characterise the surface water conditions of these nine watercourses. The survey was undertaken between September 28<sup>th</sup> and October 2<sup>nd</sup> 2020 by an experienced fluvial geomorphologist using best-practice guidance for geomorphological characterisation and monitoring, including:
  - Environment Agency (2003): River Habitat Survey in Britain and Ireland: Field Survey Guidance Manual;
  - Environment Agency (2007): Geomorphological Monitoring Guidelines for River Restoration Schemes; and



Geomorphological	Baseline	Survey	Technical	Report	
(Revision B)					

- River Restoration Centre (2011): Practical River Restoration Appraisal Guidance for Monitoring Options.
- 9. Following the best-practice guidance stated above, a visual inspection was undertaken along the study area for each watercourse. The main characteristics of each watercourse were carefully recorded from the bank top, which included detailed photographs and locations of key features using GPS. The following parameters were recorded in order to characterise the baseline geomorphology of each watercourse:
  - Flow conditions, including dominant flow types and the degree of variability within each reach.
  - Channel form, including planform, width and depth variation, bank form and condition, substrate types and the type and presence of bed forms such as pools, riffles and bars. Particular attention would also be paid to the extent of fine sedimentation on the bed of chalk river habitats.
  - Floodplain characteristics, including connectivity to the river channel, and the structure of the riparian zone.
  - Evidence of channel modification, including enlargement and re-sectioning, artificial bank protection, embankments and in-channel structures.
  - The survey aimed to identify any visual contamination of the watercourse (e.g. excessive sedimentation/smothering, hydrocarbons, sewage fungus, discoloration, etc.) as well as any operating discharges/pipes e.g. septic tank outflows etc. in order to identify any evidence of contamination or local sources of pollution.
- 10. At the proposed crossing points, the targeted walkover survey encompassed the width of the PEIR boundary. All terminology used for the survey was consistent with the latest standard for hydromorphology (CEN, 2018).

#### 18.3.2.3 Survey Limitations

- 11. During the survey, water levels in the watercourses were predominately below bankfull and of low turbidity providing excellent visibility of the bed and banks of each watercourse to enable their overall geomorphological characteristics to be described.
- 12. Access to parts of the River Tud was restricted at the time of the survey. However, it was possible to access a large proportion of the river. Field observations were further validated against aerial photography of inaccessible parts of the river. These restrictions are therefore not considered to have limited the geomorphological characterisation of this water body.



#### 18.3.3 Results

13. The results of the geomorphological walkover survey for those watercourses identified in **Table 18.3.1** and **Figure 18.3.1** are presented in this section.

#### 18.3.3.1 Spring Beck

14. The characteristics of Spring Beck are described in **Table 18.3.2** Spring Beck is a minor watercourse which flows through the village of Weybourne, North Norfolk (**Plate 18.3.1**). Its headwaters are in Hundred Acre Wood above Weybourne, 50m above sea level close to Weybourne railway station. From its source, the beck flows under the track of the North Norfolk Railway and out across an open farmland towards Weybourne village, where it has been heavily modified, flows through housing estates, culverts, marshes and finally discharges through a pipe onto a shingle beach.

#### Table 18.3.2: Details of Spring Beck

Parameter	Details
WFD Water Body	N/A
Water Body ID	N/A
Watercourse Type	Main River (downstream of survey area)
Grid Reference	TG1102343425



Plate 18.3.1: Spring Beck

#### 18.3.3.1.1 Flow Conditions

15. Spring Beck has been modified (see below) and is predominantly characterised by low energy glide and impounded flows, with limited flow diversity or in channel features. Faster flow habitats (such as runs) were observed, although these occurred through the artificial sections of the beck.



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B

#### 18.3.3.1.2 Channel Form



Plate 18.3.2: Spring Beck Channel Form

16. The course of Spring Beck was modified in the eighteenth century in response to the construction of a watermill and dammed to create a substantial mill pond. As such, the beck in places does not follow the natural watercourse alignment and is diverted along an artificial course for some length through the village of Weybourne. The channel form of the beck through the village is therefore predominately straight, with artificial (concrete) bed and banks in places. The channel is approximately 1m – 2m wide at the bank top; 1m wide at the bank base, with a bankfull depth between 0.5m – 1m. Thus, the overall form of the beck through the village displays a typical box shape uniform channel, with limited instream morphological complexity (). On the outskirts of the village, the beck although less confined, displays a U shape uniform channel, typical of drainage ditches in open fields (Plate 18.3.2).

#### 18.3.3.1.3 Soils and Substrates

- 17. Spring Beck within the study area is associated with colluvium soils; loose unconsolidated sediments typically composed of a heterogeneous range of rock types; and sediments ranging from silt to rock fragments of various sizes. The beck is also associated with peat soils, an accumulation of partially decayed vegetation or organic matter.
- 18. The overall substrate of the beck throughout the study area is thus dominated by sands, silts and gravels. The dominant fluvial process appears to be sediment deposition, with slow glide flows, local impoundments caused by small weirs, the mill pond, dense in-stream vegetation, low gradients and low velocities all contributing to the settling out of fine sediments/silts (Plate 18.3.3).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <u>no. 1</u>B



Plate 18.3.3: Sediment Sources and Local Impoundment

- 19. Although a proportion is likely to be derived from exposed banks during higherenergy flows, the majority of the fine sediment load is likely to be sourced from the agricultural fields on the outskirts of the village (i.e. surface runoff) (**Plate 18.3.3**).
- 18.3.3.1.4 Floodplain Characteristics
- 20. Floodplain connectivity is constrained for the majority of Spring Beck's length within the village as a result of channel modifications, with limited floodplain connectivity also on the outskirts of the village due to the U shape (tree lined) uniform channel of the beck.
- 18.3.3.1.5 In-Channel / Riparian Vegetation
- 21. There is limited in-channel aquatic vegetation along Spring Beck throughout the study area, with the beck above the mill pond heavily silted and overgrown with reeds. However, there are places were the banks and margins of the beck are suitably vegetated, although these are mainly associated with urban landscaping.
- 18.3.3.1.6 *Modifications / Structures*
- 22. Spring Beck within the study area was modified in the eighteenth century as part of the construction of a watermill (**Plate 18.3.1**); with the beck flowing through an artificial course (concreted in places) and culverts.



#### 18.3.3.2 River Glaven

23. The characteristics of the River Glaven are described in **Table 18.3.3**. The River Glaven, which is classified as a chalk stream, has its headwaters in Lower Bodham, North Norfolk, within the study area. The headwaters are predominately characterised by a uniform, incised channel which is straight, heavily vegetated and flowing through a low gradient glacial till floodplain and woodland (**Plate 18.3.4**). There is limited floodplain connection and the channel is overall dominated by glide flows, silt deposition and leaf litter, with occasional faster flowing run sections and a deep online pond. Key sediment sources include local bank scour, access tracks, outfall pipes and upstream land management.

Table 18.3.3: Details of the River Glaven

Parameter	Details
WFD Water Body	Glaven
Water Body ID	GB105034055780
Watercourse Type	WFD Water Body
Grid Reference	TG1192939376



Plate 18.3.4: River Glaven

#### 18.3.3.2.1 Flow Conditions

24. The River Glaven within the study area is predominantly characterised by glide flows, with occasional faster flowing run sections and a deep slow flowing online pond considerably larger than the inflow and outflow channel of the River Glaven (Plate 18.3.5).



Geomorphological Baseline Survey Technical Report Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 (Revision B) Rev. no. 1B




Plate 18.3.5: Online Pond in the River Glaven

18.3.3.2.2 Channel Form



Plate 18.3.6: River Glaven Channel Form

25. The channel has straight planform sections within the study area, which are incised in places into the floodplain and surrounded by agricultural fields and fishing lakes. The banks are relatively steep, stable and well vegetated throughout the study area. The channel (not including the online pond) varies between 1m – 5m wide at the bank top; 0.5m – 1.5m wide at the bank base, with a bankfull depth between 1m – 2m. The overall channel morphology of the River Glaven displays a predominately uniform channel, with the exception of the start and end locations of the study area in which the River Glaven displays more complex geomorphology, including a high flow bench or two-stage channel on the left bank (Plate 18.3.6).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B

#### 18.3.3.2.3 Soils and Substrate



Plate 18.3.7: Glacial Till Bank Composition in the River Glaven

26. The River Glaven within the study area is associated with glacial till, with the banks of the river comprised of clay, sand, gravel, cobbles and boulders (**Plate 18.3.7**).



Plate 18.3.8: Silt Deposition and Outfall Pipe

27. The substrate of the River Glaven throughout the study area is thus dominated by clay, sand, boulders, minerals, and gravel. The dominant fluvial process appears to be sediment deposition, with slow flows, low gradients, dense in-channel vegetation (undergrowth) and low velocities contributing to the settling out of fine sediments/silts (Plate 18.3.8).



Geomorphological Baseline Survey Technical Report Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 (Revision B) Rev. no. 1B

28. A portion of the fine sediment load is likely to be derived from exposed banks during higher-energy flows, outfall pipes, drainage ditches, access tracks and road runoff (noted towards the far downstream end of the study area). The adjacent agricultural fields are also likely to be a major source of fine sediment load through diffuse surface runoff.

#### 18.3.3.2.4 Floodplain Characteristics

- 29. Limited floodplain connectivity along the River Glaven was observed throughout the study area due to the slightly raised flood embankments and incised nature of the channel in places.
- 18.3.3.2.5 In-Channel / Riparian Vegetation
- 30. The banks and margins are well vegetated, with the channel itself encroached by dense vegetation, such as grasses and bracken in places reducing flow velocities, although there was limited in-channel aquatic plants (macrophytes).
- 18.3.3.2.6 Modifications / Structures
- 31. The banks of the River Glaven within the study area are slightly raised to provide flood protection of adjacent agricultural fields, with access tracks and culverts also present. However, no hard engineering bank protection works were observed during the walkover survey.



#### 18.3.3.3 River Bure

- 32. The characteristics of the River Bure are described in **Table 18.3.4**. Rising in Melton Constable, North Norfolk, the River Bure, which is classified as a chalk stream, passes through the internationally important Norfolk Broads and discharges into the sea at Great Yarmouth.
- 33. The River Bure within the study area is characterised by varied channel morphology with several ditches in the floodplain contributing to habitat complexity. Very little silt deposition along the channel bed was observed and water-crowfoot (*Ranunculus* spp.) was present. Good floodplain connection is clearly evident and in places the River Bure has a two-stage channel consisting of high and low flow channels within a wider channel belt (**Plate 18.3.9**). Key sediment sources include local bank scour, ditches and upstream land management. Himalayan balsam (*Impatiens glandulifera*) is present in the study area.

Parameter	Details
WFD Water Body	Bure (u/s confluence with Scarrow Beck)
Water Body ID	GB105034055690
Watercourse Type	Main River
Grid Reference	TG1318929901

#### Table 18.3.4: Details of the River Bure



Plate 18.3.9: River Bure and Example Ditch

#### 18.3.3.3.1 Flow Conditions

34. The River Bure within the study area is characterised by various flow types, including glides, runs and pools, while the drainage ditches in the floodplain are generally associated with slow flows (trickles) connecting small narrow glide or pool flow habitats (**Plate 18.3.9**).



Geomorphological Baseline Survey Technical Report Do (Revision B) Re

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B

#### 18.3.3.3.2 Channel Form

35. The channel has a straight planform within the study area, although displays geomorphological complexity varying in size and shape surrounded by agricultural fields, woodland and open fields with wetland (marsh) features. In general, the banks are relatively stable and well vegetated with the channel size between 4m – 6m at the bank top; 2m – 3m wide at the bank base, with a bankfull depth between 1m – 2m. The main channel is contained within a wider channel belt (approximately 100m – 250m wide) also consisting of a network of ditches and vegetated islands forming a wetland (marsh) system (Plate 18.3.10). The River Bure within the wider channel belt takes the form of a large two-stage channel.





Plate 18.3.10: River Bure Floodplain and Channel Features



#### 18.3.3.3.3 Soils and Substrate

- 36. The River Bure within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel vegetation, such as sedges and grasses) providing good filtration of water.
- 37. The substrate of the River Bure throughout the study area is thus dominated by clay and sand. The dominant fluvial process appears to be sediment transport with very little silt deposition observed on the bed and margins of the river during the walkover survey.
- 38. Although very little silt deposition was observed, any likely sediment load into the River Bure would be associated with upstream land management. The lack of silt deposition along the River Bure within the study area was most likely in response to the stable nature of the channel, wetland and associated vegetation perhaps acting like a filtration system.

#### 18.3.3.3.4 Floodplain Characteristics

- 39. Good floodplain connectivity or interaction with the wider channel belt of the River Bure within the study area was clearly evident during the walkover survey.
- 18.3.3.3.5 In-Channel / Riparian Vegetation





Plate 18.3.11: Water-Crowfoot (Left) and Himalayan Balsam (Right)

40. The banks and margins of the River Bure are well vegetated and dominated by poor semi-improved grassland with occasional shrubs. There is good coverage of aquatic plants along the bed of the river, including pockets of water-crowfoot (Plate 18.3.11). The channel belt has an array of terrestrial and wetland plants, although Himalayan balsam is present.



 Geomorphological
 Baseline
 Survey
 Technical
 Report
 Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1

 (Revision B)
 Rev. no. 1B

#### 18.3.3.3.6 *Modifications / Structures*

41. No modifications or structures, such as hard engineering bank protection works were observed during the walkover, although directly downstream of B1354 bridge water is abstracted from the River Bure.



#### 18.3.3.4 Swannington Beck

42. The characteristics of the Swannington Beck are described in Table 18.3.5 Swannington Beck is a tributary of the River Wensum within the Broadland and Broads region of Norfolk. The primary channel of the beck displays varied flow habitats and morphology and meanders through open agricultural and grazing fields (Plate 18.3.12).

Parameter	Details
WFD Water Body	Swannington Beck
Water Body ID	GB105034051070
Watercourse Type	WFD Water Body
Grid Reference	TG1417818892 (South branch, primary channel) TG1422919003 (North branch, secondary channel)

Table 18.3.5: Details of Swannington Beck



Plate 18.3.12: Swannington Beck – Primary Channel



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1</del> B

43. The primary channel is also heavily vegetated, tree lined and incised in places (deep and narrow), with limited floodplain connectivity. Substrate sediments are comprised of clay, sands and gravels, with clean pockets of sand and gravel evident, and silt deposition in places (**Plate 18.3.12**). Likely sediment load into the Swannington Beck would be associated with local bank erosion and upstream land management, although banks of the beck within the study area are well fenced which has reduced the impacts of livestock poaching (trampling). The secondary channel (or northern arm) of the Swannington Beck is a smaller watercourse which is wide, deep, straight, tree lined with good marginal vegetation (sedges, bladed grasses – iris). The bed of watercourse is predominantly comprised of silts (**Plate 18.3.13**).



Plate 18.3.13: Swannington Beck – Secondary Channel

#### 18.3.3.4.1 Flow Conditions

44. The primary channel of the Swannington Beck within the study area is characterised by various flow habitats including runs, riffles, glides and pools; while the secondary channel was generally associated with slow flows (trickles) in response to dense inchannel vegetation, which connected small narrow glide or pool flow habitats.

#### 18.3.3.4.2 Channel Form

45. The primary channel of the Swannington Beck has a sinuous planform within the study area. However, the channel is predominantly constrained by riparian and in places characterised by a deep and narrow channel. The bank top width of the channel is between 5m – 7m and width at the base between 3m – 5m. Bankfull depth is approximately 2m (Plate 18.3.12).



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <u>no. 1</u> <u>B</u>

- 46. Given the tree lined nature of the channel, the majority of morphological adjustment is through increasing the bed gradient (slope) of the Swannington Beck. Other channel form adjustments, such as the development of anabranches (and inchannel bars) were evident along the beck, with anabranches generally formed through avulsion triggered by debris accumulation (Plate 18.3.14).
- 47. The secondary channel of the Swannington Beck is wide and relatively deep (incised), with dense in-channel vegetation. The channel size is approximately 5m at the bank top, 1m at the bank base, with a bankfull depth of approximately 1m.



Plate 18.3.14: Anabranch and Wet Woodland

- 18.3.3.4.3 Soils and Substrate
- 48. The Swannington Beck within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel vegetation, such as sedges and grasses) providing good filtration of water.
- 49. The substrate of the primary channel of the Swannington Beck throughout the study area is thus dominated by clay and sand. The dominant fluvial process appears to be sediment deposition triggered by slow flows, debris and impoundment caused by a small weir (**Plate 18.3.15** and **Plate 18.3.16**). The bed in some places was also armoured, in which coarse grains were on the surface protecting finer particles underneath from erosion (**Plate 18.3.15**).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B



Plate 18.3.15: Weir and Bed Armouring Along the Swannington Beck



Plate 18.3.16: Sediment Deposition Upstream of Weir.

- 50. The secondary channel of the Swannington Beck is dominated by silts in response to slow flows and debris causing settling out of fine sediments.
- 51. Likely sediment load into the Swannington Beck would be associated with local bank erosion, access tracks and upstream land management. However, the banks of the beck along the primary channel within the study area are well fenced which has reduced the impacts of livestock poaching (and fine sediment input).



#### 18.3.3.4.4 Floodplain Characteristics

52. Limited floodplain connectivity along the Swannington Beck was observed throughout the study area in response to the predominantly incised nature of both channels.

#### 18.3.3.4.5 In-Channel / Riparian Vegetation

53. The banks and margins of both channels of the Swannington Beck are well vegetated, with the channels themselves encroached by dense vegetation in places reducing flow velocities. However, there was limited in-channel aquatic plants (macrophytes) in the primary channel, although the smaller watercourse did contain star moss (*Tortula ruralis*). There are also small areas of meadowsweet *Filipendula ulmaria*, hemp agrimony *Eupatorium cannabinum*, wild angelica *Angelica sylvestris* and purple loosestrife *Lythrum salicaria* on the banks.

#### 18.3.3.4.6 Modifications / Structures

54. No modifications or structures, such as hard engineering bank protection works were observed during the walkover. However, along the primary channel of the Swannington Beck, water is abstracted upstream of the small weir at grid reference TG 14193 18842.



 Geomorphological Baseline Survey Technical Report
 Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1

 (Revision B)
 Rev. no. 1B

#### 18.3.3.5 River Wensum

- 55. The characteristics of the River Wensum are described in **Table 18.3.6**. The River Wensum, a chalk stream, rises to the west of Fakenham, then flows southeast for 50km towards Norwich and the River Yare, of which it is a major tributary. The river is a biological Site of Special Scientific Interest (SSSI) and Special Area of Conservation (SAC). The primary channel of the River Wensum within the study area is characterised by a straight to sinuous planform which is wide, deep and slow flowing in places and dominated by glide flow habitat, with good marginal vegetation comprised of sedges, bladed grasses iris and reeds (**Plate 18.3.17**). There is good floodplain connection as evident by small wetlands, back waters and an overall wetted floodplain.
- 56. The secondary channel (or northern arm) of the River Wensum is a small, straight and incised watercourse, with good marginal vegetation, although dominated by inchannel vegetation in places (Plate 18.3.17).

Parameter	Details
WFD Water Body	Wensum US Norwich
Water Body ID	GB105034055881
Watercourse Type	Main River
Grid Reference	TG1282216767



Plate 18.3.17: River Wensum Primary and Secondary Channel

#### 18.3.3.5.1 Flow Conditions

57. The primary channel of the River Wensum within the study area is characterised by various flow habitats including runs and glides; while the secondary channel was generally associated with slow flows, in response to dense in-channel vegetation, which connected small narrow glide or pool flow habitats.



Geomorphological Baseline Survey Technical Report Doc. (Revision B) Rev.

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B

#### 18.3.3.5.2 Channel Form



Plate 18.3.18: Channel and Floodplain Features.

58. The primary channel of the River Wensum has a straight to sinuous planform within the study area and flows through an open floodplain characterised by a wide and deep channel, with the bank top width between 8m – 10m and width at the base between 5m – 6m. Bankfull depth is approximately 2m (Plate 18.3.17). Key channel and floodplain features include small benches (steps in the channel which accumulate organic debris and silts), backwaters and wetlands, providing geomorphic complexity and habitat diversity (Plate 18.3.18).




Plate 18.3.19: Secondary Channel and Field Ditches

59. The secondary channel of the River Wensum is wide and relatively deep (incised), with dense in-channel vegetation. The channel size is approximately 5m at the bank top; 1m at the bank base, with a bankfull depth of approximately 0.5m – 1m. Three small ditches connect to the secondary channel along its length (**Plate 18.3.19**).

#### 18.3.3.5.3 Soils and Substrate

60. The River Wensum within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel vegetation, such as sedges and grasses) providing good filtration of water.



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1<u>B</u></del>

61. The substrate of the primary channel of the River Wensum throughout the study area is thus dominated by clay and sand. The dominant fluvial process appears to be sediment deposition triggered by slow glide flows allowing fine sediments to settle out on the riverbed and backwaters (**Plate 18.3.20**). The banks of the river were well fenced in places with no evidence of livestock poaching. Likely sediment load into the primary channel of the River Wensum would be associated with local bank erosion, access tracks, and upstream land management.



Plate 18.3.20: Silt Deposition

- 62. The secondary channel of the River Wensum and field ditches are dominated by silts in response to slow flows and debris causing settling out of fine sediments (Plate 18.3.20).
- 18.3.3.5.4 Floodplain Characteristics
- 63. Good floodplain connectivity along the primary channel of the River Wensum within the study area was clearly evident during the walkover survey (**Plate 18.3.21**).
- 64. Good floodplain connectivity was also evident towards Old Fakenham Road (downstream end of study area) along the secondary channel in response to the change in channel morphology, with the channel not incised and channel banks gently sloping allowing inundation of the floodplain in places (Plate 18.3.21).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B



Plate 18.3.21: Secondary Channel Floodplain Connectivity

- 18.3.3.5.5 In-Channel / Riparian Vegetation
- 65. The river channel is bordered by dense marginal vegetation, mostly common reed *Phragmites australis*. The riverbed appears to be stony/gravelly with submerged aquatic vegetation including crowfoot species. Dense vegetation (such as grasses) encroaches on the secondary channel in places, reducing flow velocities.
- 18.3.3.5.6 Modifications / Structures



Plate 18.3.22: Modification of the Secondary Channel

66. No modifications or structures, such as hard engineering bank protection works were observed during the walkover along the primary channel of the River Wensum, although the secondary channel in places is modified with stone bank protection along the back of a housing estate. Two small pipes also discharge into the secondary channel towards the downstream end of the study area (Plate 18.3.22).



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <u>no. 1</u> <u>B</u>

#### 18.3.3.6 River Tud

67. The characteristics of the River Tud are described in **Table 18.3.7**. The River Tud, a tributary of the River Wensum in Central Norfolk, has its source south of East Dereham, where it then flows in an easterly direction for 27 kilometres to its confluence with the River Wensum below the village of Hellesdon. The River Tud within the study area is characterised by a straight to gently sinuous planform which is wide and shallow in places and dominated by varied flow habitats including glides, runs, pools and riffles (Plate 18.3.23). The river has good marginal vegetation dominated by sedges, bladed grasses, iris and reeds, with good coverage of aquatic plants along the bed of the river, including pockets of water-crowfoot. There is good floodplain connection, although livestock poaching does occur along the River Tud within the study area.

Table 18.3.7: Details of the River Tud

Parameter	Details
WFD Water Body	Tud
Water Body ID	GB105034051000
Watercourse Type	Main River
Grid Reference	TG1180811215

#### 18.3.3.6.1 Flow Conditions



#### Plate 18.3.23: River Tud

68. The River Tud within the study area is characterised by various flow types, including glides, runs, pools and riffles, with strong eddies observed on the outside of meander bends.



Geomorphological Baseline Survey Technical Report D (Revision B) R

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B

#### 18.3.3.6.2 Channel Form




Plate 18.3.24: River Tud Floodplain Features

69. The River Tud has a straight to sinuous planform within the study area and flows through an open floodplain characterised by a wide and shallow channel, with the bank top width between 5m – 8m and width at the base between 4m – 5m. Bankfull depth is approximately 2m (Plate 18.3.23). Key channel and floodplain features include small benches (steps in the channel which accumulate organic debris and silts), relic channels, drainage ditches, scrapes (or ponds) and wetlands, providing geomorphic complexity and habitat diversity (Plate 18.3.24).

#### 18.3.3.6.3 Soils and Substrate

70. The River Tud within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel and marginal vegetation, such as sedges and grasses) providing good filtration of water and clean gravels (**Plate 18.3.25**).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del>B



Plate 18.3.25: Clean Gravel Bed Substrate

- 71. The substrate of the River Tud throughout the study area is thus dominated clay and sand. The dominant fluvial process appears to be sediment transport with very little sediment deposition on the bed during the time of the walkover (**Plate 18.3.25**). However, fine sediments were evident along the margins of the river.
- 72. Despite livestock poaching prevalent within the study area, there was minimal fine sediments on the riverbed, although poaching is likely to be a key sediment source along with point source pollution from ditches (iron leaching observed in one ditch) and upstream land management. A potential reason why livestock poaching did not have an impact on bank erosion and thus contribute more as a sediment source, appears to be in response to the well vegetated floodplain, banks and margins of the River Tud (Plate 18.3.23).
- 18.3.3.6.4 Floodplain Characteristics
- 73. Good floodplain connectivity along the River Tud within the study area was clearly evident during the walkover survey (**Plate 18.3.24**).
- 18.3.3.6.5 In-Channel / Riparian Vegetation



Plate 18.3.26: Water-Crowfoot and Watercress



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1</del> B

74. The River Tud throughout the study area has good marginal vegetation dominated by sedges, bladed grasses, iris and reeds, with good coverage of aquatic plants along the bed of the river, including extensive areas of water-crowfoot (*Ranunculus aquatilis*) and pockets of watercress. There are scattered trees on the banks and the immediate surrounds of the river are improved grassland pasture.

#### 18.3.3.6.6 Modifications / Structures

75. No modifications or structures, such as hard engineering bank protection works were observed along the River Tud during the walkover survey or through inspection of aerial photos.



## 18.3.3.7 River Yare

76. The characteristics of the River Yare are described in Table 18.3.8. The River Yare rises to the south of Dereham and flows eastwards through the central region of Norfolk passing the isolated marshland settlement of Berney Arms before entering the tidal lake of Breydon Water and discharging into the North Sea at Gorleston. The River Yare within the study area is characterised by a straight to sinuous planform which is wide and deep in places and dominated by glide and pool flow types (Plate 18.3.27). The river has good marginal vegetation including sedges, bladed grasses, iris and reeds, with good floodplain connection. The floodplain contains small wetland scrapes (or ponds) and backwaters (Plate 18.3.27).

Table 18.3.8: Details of the River Yard	Э
---	---

Parameter	Details
WFD Water Body	Yare (u/s confluence with Tiffey - Lower)
Water Body ID	GB105034051290
Watercourse Type	Main River
Grid Reference	TG1230008406



Plate 18.3.27: River Yare and Floodplain

# 18.3.3.7.1 Flow Conditions

77. The River Yare within the study area is characterised by glide and pool flow types.



Geomorphological Baseline Survey Technical Report (Revision B)

# 18.3.3.7.2 Channel Form



Plate 18.3.28: River Yare Channel Form and Floodplain Features

78. The River Yare has a straight to sinuous planform within the study area and flows adjacent to Colton Wood and open floodplain, characterised by a wide and deep channel, with the bank top width between 5m – 8m and width at the base between 4m – 5m. Bankfull depth is approximately 2m. Key channel and floodplain features include wetland scrapes and backwaters (Plate 18.3.28).

### 18.3.3.7.3 Soils and Substrate

- 79. The River Yare within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel and marginal vegetation, such as sedges and grasses) providing good filtration of water.
- 80. The substrate of the River Yare throughout the study area is thus dominated by clay and sand. The dominant fluvial process appears to be sediment deposition. Likely sediment load into the River Yare would be associated with local bank erosion, access tracks and upstream land management.
- 18.3.3.7.4 Floodplain Characteristics
- 81. Good floodplain connectivity along the River Yare within the study area was clearly evident during the walkover survey (**Plate 18.3.27**).
- 18.3.3.7.5 In-Channel / Riparian Vegetation
- 82. The banks and margins of River Yare are well vegetated with terrestrial species. However, there was limited in-channel aquatic plants (macrophytes) along the River Yare, although dense patches of in-channel vegetation, such as rushes, were observed towards the upstream end of the study area.



#### 18.3.3.7.6 Modifications / Structures

83. Other than a small footbridge towards the downstream limits of the study area adjacent to Colton Wood, no major modifications or structures such as hard engineering bank protection works, were observed along the River Yare during the walkover survey.



## 18.3.3.8 River Tiffey

84. The characteristics of the River Tiffey are described in **Table 18.3.9**. The River Tiffey, a tributary of the River Yare, rises near Hethel and flows north-eastwards through the central region of Norfolk and several villages before joining the River Yare near Barford. The River Tiffey within the study area is characterised by a relatively straight planform which is deep and narrow in places and dominated by glide and pool flow habitats (**Plate 18.3.29**). The river has good marginal vegetation including sedges, bladed grasses, iris, bull rushes and reed, with good floodplain connection. The floodplain contains ditches, a small lake (offline pond) and wet woodland (**Plate 18.3.29**).



Plate 18.3.29: River Tiffey and Floodplain Features

Table 1	8.3.9: I	Details	of the	River	Tiffey
---------	----------	---------	--------	-------	--------

Parameter	Details
WFD Water Body	Tiffey
Water Body ID	GB105034051282
Watercourse Type	Main River
Grid Reference	TG1172107438

18.3.3.8.1 Flow Conditions

85. The River Tiffey within the study area is characterised by glide and pool flow habitats.



# 18.3.3.8.2 Channel Form

86. The River Tiffey has a straight to sinuous planform within the study area and flows adjacent to woodland and open floodplain characterised by a relatively deep and narrow channel, with the bank top width between 4m – 5m and width at the base between 2m – 3m. Bankfull depth is approximately 2m (Plate 18.3.30). Key channel and floodplain features include several straight ditches 2m wide and approximately 0.5m deep which are well vegetated in places; and a small lake which was once used for angling (Plate 18.3.29). The lake is approximately 20m wide by 50m in length, although much of the lake has now been infilled within a planted woodland (Plate 18.3.29).



Plate 18.3.30: River Tiffey Channel Form

#### 18.3.3.8.3 Soils and Substrate

- 87. The River Tiffey within the study area is associated with riverine clay, sands and gravels, with the banks predominantly composed of clay and sand (i.e. clay to sandy loam banks), with the properties of the soils (along with the in-channel and marginal vegetation, such as sedges and grasses) providing good filtration of water.
- 88. The substrate of the River Tiffey throughout the study area is thus dominated by clay and sand. The dominant fluvial process appears to be sediment deposition in response to the slow flows (low velocities) contributing to the settling out of sediments. However, there was minimal silt deposition, with the majority of deposition associated with coarser sediments, such as sand (Plate 18.3.31).
- 89. Likely sediment load into the River Tiffey would be associated with local bank erosion and upstream land management.



Geomorphological Baseline Survey Technical Report Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 (Revision B) Rev. no. 1B



Plate 18.3.31: Sand Ripples

- 18.3.3.8.4 Floodplain Characteristics
- 90. Good floodplain connectivity along the River Tiffey within the study area was clearly evident during the walkover survey (**Plate 18.3.31**).
- 18.3.3.8.5 In-Channel / Riparian Vegetation
- 91. The river channel is surrounded by grasslands of varying quality, including marshy and semi-improved neutral grasslands to the north. To the south of the river, there are areas of fen (flood-plain mire), pockets of wet broadleaved woodland and a network of small drainage ditches and ponds which feed into the river. The banks and margins of the River Tiffey are well vegetated, although there was limited inchannel aquatic plants (macrophytes) along the bed of the river. Himalayan balsam is present within the study area.
- 18.3.3.8.6 Modifications / Structure
- 92. No major modifications or structures such as hard engineering bank protection works, were observed along the River Tiffey during the walkover survey.



#### 18.3.3.9 Intwood Stream

93. The characteristics of the Intwood Stream are described in **Table 18.3.10**. Intwood Stream, a tributary of the River Yare, rises near Mulbarton, and flows north-eastward through Swardeston and Keswick, where it then meets the River Yare. The Intwood Stream within the study area is characterised by two connected watercourses, a predominately main larger western channel (the WFD water body) and a smaller eastern channel (the Main River) (**Plate 18.3.2**).

Parameter	Details
WFD Water Body	Intwood Stream
Water Body ID	GB105034051240
Watercourse Type	WFD water body and Main River
Grid Reference	TG1940302636

Table 18.3.10: Details of Intwood Stream



Plate 18.3.32: Intwood Stream Channels



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1</del> <u>B</u>

94. The western channel of the Intwood Stream within the study area is characterised by a straight planform which varies in size and shape from a deep incised channel to a wide and shallow channel with good floodplain connectivity. The channel has varied flow habitats including glides, riffles and runs and contains wooded debris, with good marginal vegetation comprised of sedges, bladed grasses and iris (**Plate 18.3.33**). Floodplain features include ditches and ponds, although livestock poaching is prevalent along the western channel contributing to silt deposition on the bed. However, in places the bed shows some good clean sand and gravel deposition, associated with the glacial till nature of the surrounding soils, which are free of silt.



Plate 18.3.33: Western Channel of the Intwood Stream

95. The eastern channel of the Intwood Stream within the study area is a smaller watercourse than the western channel and resembles a wide shallow drainage ditch, although does display varied flow habitats, including runs, riffles and pools, with pockets of pond weed. There is good marginal vegetation, such as bull rushes and sedges; and there is good floodplain connectivity (**Plate 18.3.34**). However, livestock poaching is also prevalent contributing to silt deposition on the channel bed. However, in places the bed shows some good clean coarse sand and gravel substrates (associated with the glacial till nature of the surrounding soils) which are free of silt.



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <u>no. 1</u>B



Plate 18.3.34: Eastern Channel of the Intwood Stream

- 96. A pipe discharges into a land drainage ditch which joins the channel towards the downstream end of the study area. The central reach of the eastern channel also has a culvert providing access to the inner floodplain.
- 18.3.3.9.1 Flow Conditions
- 97. The western channel of the Intwood Stream within the study area is characterised by various flow types including glides, riffles and runs; while the eastern channel, to a lesser degree also displays similar flow habitats.
- 18.3.3.9.2 Channel Form



Plate 18.3.35: Western Channel Form



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1<u>B</u></del>

98. The western channel of the Intwood Stream appears to have a modified planform which has been historically straightened, although despite this does show some geomorphic complexity within the study area varying in size and shape. The channel flows through an open floodplain and woodland, with the morphology of channel being deep and incised to wide and shallow, with good floodplain connectivity (see below). In places the channel had a bank top width between 3m - 4m and width at the base between 1m - 2m. Bankfull depth various between 1m - 2m (Plate 18.3.36).



Plate 18.3.36: Western Channel Wetland and Example Ditch

- 99. Key channel and floodplain features included backwaters, ditches and wetlands, providing geomorphic complexity and habitat diversity (**Plate 18.3.36**).
- 100. The eastern channel of the Intwood Stream within the study area is a smaller watercourse than the western channel and resembles a wide shallow drainage ditch, although does display some geomorphic complexity. The channel size is between 1 m 2 m at the bank top; and approximately 1 m at the bank base, with a bankfull depth between 1 m 1.5 m (Plate 18.3.34).
- 18.3.3.9.3 Soils and Substrate



Plate 18.3.37: Glacial Till Bank Composition



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1
(Revision B)					Rev. <del>no. 1</del> <u>B</u>

- 101. The Intwood Stream within the study area is associated with glacial till with the banks of the channels through the study area comprised of clay, sand, boulders, minerals, and gravel (Plate 18.3.37).
- 102. The Intwood Stream channels throughout the study area are thus dominated by clay, sand, boulders, minerals, and gravel. There is not one dominant fluvial process, with both sediment deposition and transport occurring at a similar degree along both channels in response to the varied nature of the flow habitats.



Plate 18.3.38: Livestock Poaching and Silts on Channel Bed.

- 103. A portion of fine sediment load along the channels is likely to be derived from exposed banks caused by livestock poaching, with higher-energy flows further eroding the banks contributing to fine silts on the channel beds (**Plate 18.3.38**). In addition, a pipe discharges into a land drainage ditch which joins the channel towards the downstream end of the study area potentially allowing fine sediment and/or contaminants to enter the watercourse **Plate 18.3.38**.
- 18.3.3.9.4 Floodplain Characteristics
- 104. Good floodplain connectivity along the Intwood Stream channels throughout the study area was clearly evident during the walkover survey (**Plate 18.3.36**).
- 18.3.3.9.5 In-Channel / Riparian Vegetation
- 105. The banks and margins of the Intwood Stream channels are well vegetated, with some in-channel aquatic plants (macrophytes).



Geomorphological Baseline Survey Technical Report (Revision B)

Doc. No. C282-RH-Z-GA-00079 6.3.18.3.1 Rev. <del>no. 1</del><u>B</u>

#### 18.3.3.9.6 Modifications / Structures



Plate 18.3.39: Outfall Pipes and Small Culvert

106. Two pipe outfalls drain into a land drainage ditch which joins the eastern channel towards the downstream end of the study area. The central reach of the eastern channel also has a culvert providing access to the inner floodplain (**Plate 18.3.39**).



## 18.3.4 Summary

- 107. The geomorphological walkover survey undertaken between September 28<sup>th</sup> and October 2<sup>nd</sup> 2020 has demonstrated that watercourses in the study area predominantly consist of lowland, low gradient channels, which despite flowing across varied land uses do vary in the degree of morphological complexity and flow habitats, with some channels having good floodplain connectivity resulting in array of geomorphic features, such as wetland scraps, ditches and ponds, providing a diversity of habitats for wildlife.
- 108. The channel banks and margins of the watercourses are generally well vegetated with sedges and bladed grasses (iris) with good coverage of in-channel aquatic plants (macrophytes) along some watercourses, in particular those which had clean sandy substrates and classified as chalk streams (Rivers Glaven, Bure and Wensum). The non-native invasive species, Himalayan balsam, was recorded within the study area (River Bure and Tiffey).
- 109. Although a proportion is likely to be derived from exposed banks during higherenergy flows, the majority of the fine sedimentation observed along most watercourses is likely to be sourced from adjacent agricultural fields and upstream land management.
- 110. The results of the walkover survey have been used to inform the baseline assessment presented in Chapter 18 Water Resources and Flood Risk of the Environmental Statement. The results have also been used as the basis of the assessment of potential impacts from SEP and DEP on the geomorphology and physical habitat condition of surface waters presented in Chapter 18 Water Resources and Flood Risk; and the assessment of potential impacts on the hydromorphological quality elements supported by river water bodies presented in Appendix 18.1 Water Framework Directive Compliance Assessment. Further discussion regarding the outcomes of this survey and the implications for SEP and DEP are provided in these reports.



Geomorphological	Baseline	Survey	Technical	Report	Doc. No. C
(Revision B)					Rev. <del>no. 1</del> B

# References

Environment Agency (2003) River Habitat Survey in Britain and Ireland: Field Survey Guidance Manual. Environment Agency, Bristol.

Environment Agency (2007) Geomorphological monitoring guidelines for river restoration schemes. Environment Agency, Bristol.

European Committee for Standardization (CEN) (2018) Water Quality – Guidance standard for assessing the hydromorphological features of rivers. CEN, Brussels.