

Longfield Solar Farm

Arboricultural Impact Assessment (Part 2 of 2)

Document Reference: EN010118/EX/8.13

Revision 1.0

October 2022

Longfield Solar Energy Farm Ltd

APFP Regulation 5(2)(q)

Planning Act 2008

Infrastructure Planning (Applications: Prescribed Forms and Procedure)

Regulations 2009

PROJECT

LONGFIELD SOLAR

CLIENT

LONGFIELD SOLAR **ENERGY FARM LTD** CONSULTANT

Plumer House, Third Floor, East Wing, Tailyour Road Plymouth, PL6 5DH Tel +44(0)1752 676700 Fax +44(0)870 238 6023 www.aecom.com

GENERAL NOTES

- 1. TREE CATEGORIES AS DEFINED BY BS 5837:2012 2. TREE LOCATIONS ARE BASED ON THE OS MAPPING, AERIAL IMAGERY, AND GPS CO-ORDINATES FROM ON SITE WALKOVER. 3.* INDICATES A TREE / GROUP WHOSE POSITION IS APPROXIMATE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS. 4. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM ARBORICULTURAL REPORT.
- 5. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR A MONOCHROME COPY SHOULD NOT BE RELIED UPON.
- 6. DRAWING REFERNCES:

 2022-01-05 Longfield Solar Farm RLB.dwg

 4077_LGF_DR_PRE_0001M.dwg


 X_Longfield Base plan mapping.dwg

 Longfield Solar Farm Detailed Drawings 010222.dwg

 OS_MasterMap_653820_858315_OS_Mastermap_081220.dwg

 GH-125724005-RLB P08.dwg

KEY PLAN




SITE BOUNDARY



ISSUE/REVISION

400 kV CABLE ROUTE (W/ 20M WORKING WIDTH) OTHER CABLE ROUTES



DRAWING STATUS

PROJECT NUMBER

60640215


SHEET TITLE


TREE PROTECTION PLAN (SHEET 00)


SHEET NUMBER


REV.


60640215-ACM-XX-XX-AB-TPP-000























PROJECT

LONGFIELD SOLAR

CLIENT

LONGFIELD SOLAR **ENERGY FARM LTD** CONSULTANT

AECOM


Plumer House, Third Floor, East Wing, Tailyour Road Plymouth, PL6 5DH Tel +44(0)1752 676700 Fax +44(0)870 238 6023 www.aecom.com


GENERAL NOTES

- 1. TREE CATEGORIES AS DEFINED BY BS 5837:2012 2. TREE LOCATIONS ARE BASED ON THE OS MAPPING, AERIAL IMAGERY, AND GPS CO-ORDINATES FROM ON SITE WALKOVER. 3.* INDICATES A TREE / GROUP WHOSE POSITION IS APPROXIMATE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS. 4. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM
- ARBORICULTURAL REPORT. 5. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.
- 6. DRAWING REFERNCES:
- 1.DIAWING REFERINCES:

 2022-01-05 Longfield Solar Farm RLB.dwg
 4077_LGF_DR_PRE_0001M.dwg
 X_Longfield Base plan mapping dwg
 Longfield Solar Farm Detailed Drawings 010222.dwg
 OS_MasterMap_653820_858315_OS_Mastermap_081220.dwg
 GH-125724005-RLB P08.dwg

KEY PLAN





TPF — TREE PROTECTION FENCING


CONSTRUCTION EXCLUSION ZONE (TRACKING OF PLANT, MATERIALS STORAGE, EXCAVATION AND ALL OTHER CONSTRUCTION ACTIVITIES ARE EXCLUDED WITHIN THESE AREAS FOR THE PURPOSES OF PROTECTING TREE HEALTH) CONSTRUCTION WORKING ZONE
(MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT) GROUND PROTECTION ZONE
(MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH
THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)

PROPOSED DEVELOPMENT LAYOUT (BASED UPON DRAWING REFERENCES LISTED IN THE GENERAL NOTES SECTION) VETERAN TREE MARKER (INDICATES POSITION OF A VETERAN TREE)

ANCIENT WOODLAND (WITH 15M BUFFER ZONE)
(AREA CLASSIFIED AS AN ANCIENT WOODLAND) TREE PRESERVATION ORDER
(AREA COVERED BY A TREE PRESERVATION ORDER [TPO])

400 kV CABLE ROUTE (W/ 20M WORKING WIDTH) OTHER CABLE ROUTES
(W/ 6.5M WORKING WIDTH)

ISSUE/REVISION



DRAWING STATUS

PROJECT NUMBER


60640215

SHEET TITLE

TREE PROTECTION PLAN (SHEET 9)

SHEET NUMBER


REV.



ENERGY FARM LTD


1. TREE CATEGORIES AS DEFINED BY BS 5837:2012 2. TREE LOCATIONS ARE BASED ON THE OS MAPPING, AERIAL IMAGERY, AND GPS CO-ORDINATES FROM ON SITE WALKOVER. 3.* INDICATES A TREE / GROUP WHOSE POSITION IS APPROXIMATE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.

5. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.



EXISTING TREE, GROUP, WOODLAND, OR HEDGE TO BE RETAINED EXISTING TREE, GROUP, WOODLAND, OR HEDGE TO BE ROOT PROTECTION AREA OF RETAINED TREES

> CONSTRUCTION WORKING ZONE
> (MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT) (MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)



PROJECT

LONGFIELD SOLAR

LONGFIELD SOLAR **ENERGY FARM LTD** CONSULTANT

Plumer House, Third Floor, East Wing, Tailyour Road Plymouth, PL6 5DH Tel +44(0)1752 676700 Fax +44(0)870 238 6023 www.aecom.com

GENERAL NOTES

- 1. TREE CATEGORIES AS DEFINED BY BS 5837:2012 2. TREE LOCATIONS ARE BASED ON THE OS MAPPING, AERIAL IMAGERY, AND GPS CO-ORDINATES FROM ON SITE WALKOVER. 3.* INDICATES A TREE / GROUP WHOSE POSITION IS APPROXIMATE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS.
- ARBORICULTURAL REPORT. 5. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.
- 6. DRAWING REFERNCES:
- b. DKAWING REFERNCES:

 2022-01-05 Longfield Solar Farm RLB.dwg

 4077_LGF_DR_PRE_0001M.dwg


 X_Longfield Base plan mapping dwg

 Longfield Solar Farm Detailed Drawings 010222.dwg

 OS_MasterMap_653820_858315_OS_Mastermap_081220.dwg

 GH-125724005-RLB P08.dwg

KEY PLAN



SITE BOUNDARY EXISTING TREE, GROUP, WOODLAND, OR HEDGE TO BE RETAINED EXISTING TREE, GROUP, WOODLAND, OR HEDGE TO BE

ROOT PROTECTION AREA OF RETAINED TREES

TPF — TREE PROTECTION FENCING

CONSTRUCTION EXCLUSION ZONE (TRACKING OF PLANT, MATERIALS STORAGE, EXCAVATION AND ALL OTHER CONSTRUCTION ACTIVITIES ARE EXCLUDED WITHIN THESE AREAS FOR THE PURPOSES OF PROTECTING TREE HEALTH) CONSTRUCTION WORKING ZONE
(MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH

THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT) GROUND PROTECTION ZONE (MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)

PROPOSED DEVELOPMENT LAYOUT (BASED UPON DRAWING REFERENCES LISTED IN THE GENERAL NOTES SECTION) VETERAN TREE MARKER

(INDICATES POSITION OF A VETERAN TREE)

ANCIENT WOODLAND (WITH 15M BUFFER ZONE)
(AREA CLASSIFIED AS AN ANCIENT WOODLAND) TREE PRESERVATION ORDER

400 kV CABLE ROUTE (W/ 20M WORKING WIDTH) OTHER CABLE ROUTES (W/ 6.5M WORKING WIDTH)

ISSUE/REVISION

P01 22.09.22 FIRST ISSUE I/R DATE DESCRIPTION

DRAWING STATUS

PROJECT NUMBER


SHEET TITLE

TREE PROTECTION PLAN (SHEET 11)

SHEET NUMBER

REV.

60640215-ACM-XX-XX-AB-TPP-011



PROJECT

LONGFIELD SOLAR

LONGFIELD SOLAR **ENERGY FARM LTD** CONSULTANT

Plumer House, Third Floor, East Wing, Tailyour Road Plymouth, PL6 5DH Tel +44(0)1752 676700 Fax +44(0)870 238 6023 www.aecom.com

GENERAL NOTES

- 1. TREE CATEGORIES AS DEFINED BY BS 5837:2012 2. TREE LOCATIONS ARE BASED ON THE OS MAPPING, AERIAL IMAGERY, AND GPS CO-ORDINATES FROM ON SITE WALKOVER. 3.* INDICATES A TREE / GROUP WHOSE POSITION IS APPROXIMATE AS BASED UPON AERIAL PHOTOGRAPHY AND ON SITE OBSERVATIONS. 4. PLANS SHOULD BE READ IN CONJUNCTION WITH THE AECOM
- ARBORICULTURAL REPORT. 5. THE ORIGINAL OF THIS DRAWING WAS PRODUCED IN COLOUR - A MONOCHROME COPY SHOULD NOT BE RELIED UPON.
- 6. DRAWING REFERNCES: b. DKAWING REFERNCES:

 2022-01-05 - Longfield Solar Farm RLB.dwg

 4077_LGF_DR_PRE_0001M.dwg


 X_Longfield Base plan mapping dwg


 Longfield Solar Farm - Detailed Drawings - 010222.dwg

 OS_MasterMap_653820_858315_OS_Mastermap_081220.dwg

 GH-125724005-RLB P08.dwg

KEY PLAN





ROOT PROTECTION AREA OF RETAINED TREES

CONSTRUCTION EXCLUSION ZONE (TRACKING OF PLANT, MATERIALS STORAGE, EXCAVATION AND ALL OTHER CONSTRUCTION ACTIVITIES ARE EXCLUDED WITHIN THESE AREAS FOR THE PURPOSES OF PROTECTING TREE HEALTH) CONSTRUCTION WORKING ZONE
(MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT)


GROUND PROTECTION ZONE (MANAGED CONSTRUCTION PROCESSES PERMITTED IN ACCORDANCE WITH THE PRINCIPLES SET OUT WITHIN THE ARBORICULTURAL IMPACT ASSESSMENT) (BASED UPON DRAWING REFERENCES LISTED IN THE GENERAL NOTES SECTION)

VETERAN TREE MARKER (INDICATES POSITION OF A VETERAN TREE)

ANCIENT WOODLAND (WITH 15M BUFFER ZONE)
(AREA CLASSIFIED AS AN ANCIENT WOODLAND) TREE PRESERVATION ORDER
(AREA COVERED BY A TREE PRESERVATION ORDER [TPO])

400 kV CABLE ROUTE (W/ 20M WORKING WIDTH) OTHER CABLE ROUTES

ISSUE/REVISION



DRAWING STATUS

PROJECT NUMBER

60640215

SHEET TITLE

TREE PROTECTION PLAN (SHEET 12)

SHEET NUMBER

REV.

60640215-ACM-XX-XX-AB-TPP-012

Appendix F Outline Tree Protection Measures

F.1 Outline Tree Protection Measures

The default position as set out by BS 5837:2012 is that retained trees must be protected from construction operations with the erection of robust protective fencing positioned on the outer edge of the RPA or crown spread (whichever is greatest). All site operations will be restricted to the area outside of tree protection fencing and this area will form a Construction Exclusion Zone (CEZ) unless agreed otherwise. Protection measures will be installed as set out in the Tree Protection Plan included as Appendix E of this report.

The area inside the fence and any additional tree protection measures will be sacrosanct and must not be removed or altered without the prior approval of the LPA Tree Officer. Any damage to tree protection measures must be reported immediately.

Fencing shall be constructed with robust vertical and horizontal scaffold framework with weldmesh panels firmly attached as per BS 5837:2012 Figure 2 (included below). Vertical support poles and bracing poles must be located with care to avoid underground utility services and will be sited to avoid the structural roots of retained trees.

Alternative equivalent robust and immovable fencing specification including site hoarding will also be appropriate.

Suitable all weather signage will be fixed to fencing to notify site staff and visitors of the construction exclusion zone and its purpose (example included as Appendix G).




Figure 14 - Default specification for protective barrier

When entering and exiting the site the fencing contractor must avoid the production of ruts on the unprotected surface of the ground.

Protective fencing and ground protection shall stay in place until all development operations have been completed and the prior consent of the LPA Tree Officer and/or an arboriculturist has been obtained.

F.2 Ground Protection

Should access be unavoidable within the RPA of a retained tree, fit for purpose ground protection must be in place which is sufficient to protect the structure of the soil from damage based on the heaviest anticipated load.

As set out in section 6.2.3.3 of BS5837:2012 the following ground protection measures will be appropriate:

- Suitable ground protection for pedestrian only access will comprise a single thickness of scaffold boards set on a compressible layer of 100mm of woodchip on a geotextile separation layer.
- Pedestrian operated plant up to two tonnes in weight would require the use of a proprietary ground protection system (such as Ground Guards or Eve Trakway or equivalent) set on a minimum depth of 150mm woodchip or sharp sand.
- Heavier loads will require ground protection to an engineering specification in conjunction with arboricultural advice.

As a guide the threshold beyond which root development is significantly affected is a bulk density ranging from 1.4g per cm³ for clay soils, to 1.75g per cm³ for sandy soils.

Tree protective measures shall stay in place until all construction operations are completed and removal is agreed with the Site arboriculturist and/or the Local Authority Tree Officer as appropriate.

F.3 General guidance for the management of exposed roots

7.1.1 Excavation must only take place within the RPA of a retained tree with the prior agreement of an arboriculturist and the Local Authority Tree Officer. All excavation must be undertaken using hand tools or compressed air (such as an air spade).

The following general principles will apply:

Individual or small groups of roots less than 25mm in diameter will be retained
where possible but can be severed with a sharp tool such as secateurs or
pruning saws to leave a clean cut end (ideally 100mm back from the face of the
excavation to account for future regrowth) where they pose an obstruction.

- Where roots are encountered which are larger than 25mm in diameter or where significant groups of smaller roots are found, the advice of an arboriculturist must be sought to decide an appropriate course of action (following consultation with the Local Authority Tree Officer where appropriate).
- Roots must only be exposed for the minimum period possible. In the interim
 period any exposed roots must be completely covered with dampened hessian
 sacking (which may require ongoing re wetting) to avoid drying out and
 exposure to light (which can result in the death of roots). Backfill for excavations
 should utilise the parent material and must not be significantly compacted.

F.4 Storage, use and mixing of materials

The use, mixing and washing of materials can lead to run off or inadvertent spillage into tree root zones. Many substances often used on construction sites can be toxic to tree roots (such as concrete, fuels, salts, builders sand and herbicides), can result in the death of tree roots and beneficial soil organisms; and have a significant impact on the future health and appearance of trees.

The storage of materials can result in an effective raised soil level. This buries tree roots at depths where air and water are less available and can lead to the decline or death of the tree.

For these reasons the storage of materials and any washing, mixing or refuelling must take place in agreed allocated areas at least 10m from the edge of the RPA of retained trees.

Any slope effect must be taken into account and where there is a potential for run off, heavy duty polythene sheeting and sandbags must be in place as bunding to prevent toxic materials reaching RPAs.

Appendix G Tree Protection Signage (Example)



TREE PROTECTION AREA KEEP OUT! (TOWN & COUNTRY PLANNING ACT 1990) TREES ENCLOSED BY THIS FENCE ARE PROTECTED BY PLANNING CONDITIONS AND/OR ARE THE SUBJECTS OF A TREE PRESERVATION ORDER. CONTRAVENTION OF A TREE PRESERVATION ORDER MAY LEAD TO CRIMINAL PROSECUTION ANY INCURSION INTO THE PROTECTED AREA MUST BE WITH THE WRITTEN PERMISSION OF THE LOCAL PLANNING AUTHORITY

