

## Raywood, Simon

---

**From:** Asset.Protection <Asset.Protection@severntrent.co.uk>  
**Sent:** 19 December 2023 11:31  
**To:** STW Ofwat; ni.mail.distribution@notifications.service.gov.uk; Cottam Solar Project  
**Subject:** RE: EN010133 – Cottam Solar Project J-220617-19846  
**Attachments:** STW Asset Protection Precautions.pdf

You don't often get email from asset.protection@severntrent.co.uk. [Learn why this is important](#)

ST Classification: UNMARKED

Dear Cottam Solar Project Case Team

Please be advised that, according to our records, there are no assets within the updated location plan. However, if you do indeed identify any assets you believe are the responsibility of Severn Trent Water, please consult with us in Asset Protection.

Please see attached general precautions.

Kind regards  
Anna Cheung

Asset Protection  
Asset Strategy & Planning  
Chief Engineer



---

**From:** STW Ofwat <STWOfwat@severntrent.co.uk>  
**Sent:** 19 December 2023 08:54  
**To:** Asset.Protection <Asset.Protection@severntrent.co.uk>; Bill-Networks Walton [REDACTED]  
[REDACTED] Anna Cheung <[REDACTED]>  
**Subject:** FW: EN010133 – Cottam Solar Project

ST Classification: UNMARKED

Morning all,

Please see below email relating to EN010133 – Cottam Solar Project.

Can you please advise if you will be responding to this?

The due date to respond is 21/12/2023 & another one 28/01/2024.

Thanks,

Kind regards

*Deepika Verma*  
Group Compliance & Assurance Assistant

Mob: [REDACTED]

Email: [REDACTED]



**From:** NI Mail Distribution <[ni.mail.distribution@notifications.service.gov.uk](mailto:ni.mail.distribution@notifications.service.gov.uk)>

**Sent:** 18 December 2023 17:43

**To:** STW Ofwat <[STWOfwat@severntrent.co.uk](mailto:STWOfwat@severntrent.co.uk)>

**Subject:** EN010133 – Cottam Solar Project

You don't often get email from [ni.mail.distribution@notifications.service.gov.uk](mailto:ni.mail.distribution@notifications.service.gov.uk). [Learn why this is important](#)

**Caution:** This is an external email originating outside Severn Trent. Think before you click on links or open attachments.



# Application by Cottam Solar Project Limited for an Order Granting Development Consent for the Cottam Solar Project

## Planning Act 2008 – Section 89

The Infrastructure Planning (Examination Procedure) Rules 2010 – Rules 8(3) and 9 (“the Examination Procedure Rules”)

The Infrastructure Planning (Compulsory Acquisition) Regulations 2010 (“the CA Regulations”) – Regulations 4 to 9

## Procedural Decisions relating to the Applicant’s Change Request Application and Amending the Examination Timetable

Unique Reference: COTT-SP41

Dear Sir/Madam,

Please find below a link to a letter from the Examining Authority that has been published on the National Infrastructure Planning website.

The letter provides the Examining Authority's Response to the Applicant's change request application dated 8 December 2023 and can be found at <http://infrastructure.planninginspectorate.gov.uk/document/EN010133-001377>.

The letter also provides notification of a variation to the Examination Timetable for the above application due to the Applicant's change request application. The revised Examination timetable can be found here <https://national-infrastructure-consenting.planninginspectorate.gov.uk/projects/EN010133/examination-timetable>.

You can also view the letter under the Documents tab on the project webpage of the National Infrastructure Planning website:

<https://infrastructure.planninginspectorate.gov.uk/projects/east-midlands/cottam-solar-project/>

Yours faithfully,

Cottam Solar Project Case Team

National Infrastructure Planning

Helpline: 0303 444 5000

Email: [CottamSolarProject@planninginspectorate.gov.uk](mailto:CottamSolarProject@planninginspectorate.gov.uk)

Web: <https://infrastructure.planninginspectorate.gov.uk/> (National Infrastructure Planning)

Web: [www.gov.uk/government/organisations/planning-inspectorate](http://www.gov.uk/government/organisations/planning-inspectorate) (The Planning Inspectorate)

X: @PINSgov

This communication does not constitute legal advice.

Please view our Privacy Notice before sending information to the Planning Inspectorate.

privileged or trade secret information protected by law. If you have received this message in error please delete it and notify us immediately by telephoning +44 2477715000. If you are not the intended recipient you must not use, disclose, distribute, reproduce, retransmit, retain or rely on any information contained in this email. Please note the Companies reserve the right to monitor email communications in accordance with applicable law and regulations. To the extent permitted by law, neither the Companies or any of their subsidiaries, nor any employee, director or officer thereof, accepts any liability whatsoever in relation to this email including liability arising from any external breach of security or confidentiality or for virus infection or for statements made by the sender as these are not necessarily made on behalf of the Companies. Reduce waste! Please consider the environment before printing this email



# **SEVERN TRENT WATER**

## **GENERAL CONDITIONS AND PRECAUTIONS TO BE TAKEN WHEN CARRYING OUT WORK ADJACENT TO SEVERN TRENT WATER'S APPARATUS**

Please ensure that a copy of these conditions is passed to your representative and/or your Contractor on site. If any damage is caused to STW apparatus, the person, Contractor or Subcontractor responsible must inform STW immediately on:

**0800 783 4444 (24 hours)**

These general conditions and precautions apply to the public sewerage, water distribution and telemetry systems. The conditions include sewers which are the subject of an Agreement under Section 104 of the Water Industry Act 1991 and mains installed in accordance with the Agreement for the self construction of water mains. Please be aware that due to The Private Sewers Transfer Regulations June 2011, the number of public sewers has increased, but many of these are not shown on the public sewer record. However, some idea of their positions may be obtained from the position of inspection covers and their existence must be anticipated.

On request, STW will issue a copy of the plan showing the approximate locations of STW apparatus although in certain instances a charge will be made. The position of private drains, private sewers and water service pipes to properties are not normally shown but their presence must be anticipated. This plan is furnished as a general guide only and no warranty as to its accuracy is given or implied. The plan must not be relied upon in the event of excavations or other works in the vicinity of STW apparatus. No person or Company shall be relieved from liability for damage caused by reason of the actual position and/or depths of STW apparatus being different from those shown on the plan.

In order to achieve safe working conditions adjacent to any apparatus the following should be observed:

1. All STW apparatus should be located by hand digging prior to the use of mechanical excavators.
2. All information set out in any plans received from us, or given by our staff at the site of the works, about the position and depth of the mains, is approximate. Every possible precaution should be taken to avoid damage to our apparatus. You or your contractor must ensure the safety of our equipment and will be responsible for the cost of repairing any damage caused.
3. Water mains are normally laid at a depth of 900mm. No records are kept of customer service pipes which are normally laid at a depth of 750mm; but some idea of their positions may be obtained from the position of stop tap covers and their existence must be anticipated.
4. During construction work, where heavy plant will cross the line of STW apparatus, specific crossing points must be agreed with the Company and suitably reinforced where required. These crossing points should be clearly marked and crossing of the line of STW apparatus at other locations must be prevented.
5. Where it is proposed to carry out piling or boring within 20 metres of any STW apparatus, STW should be consulted to enable any affected STW apparatus to be surveyed prior to the works commencing.
6. Where excavation of trenches adjacent to any STW apparatus affects its support, the STW apparatus must be supported to the satisfaction of STW. Water mains and some sewers are pressurised and can fail if excavation removes support to thrust blocks to bends and other fittings.
7. Where a trench is excavated crossing or parallel to the line of any STW apparatus, the backfill should be adequately compacted to prevent any settlement which could subsequently cause



damage to the STW apparatus. In special cases, it may be necessary to provide permanent support to STW apparatus which has been exposed over a length of the excavation before backfilling and reinstatement is carried out. There should be no concrete backfill in contact with the STW apparatus.

8. No apparatus should be laid along the line of STW apparatus irrespective of clearance. Above ground apparatus must not be located within a minimum of 3 metres either side of the centre line of STW apparatus for smaller sized pipes and 6 metres either side for larger sized pipes without prior approval. No manhole or chamber shall be built over or around any STW apparatus.
9. A minimum radial clearance of 300 millimetres should be allowed between any plant being installed and existing STW apparatus. - We reserve the right to increase this distance where strategic assets are affected.
10. Where any STW apparatus coated with a special wrapping is damaged, even to a minor extent, STW must be notified and the trench left open until the damage has been inspected and the necessary repairs have been carried out. In the case of any material damage to any STW apparatus causing leakage, weakening of the mechanical strength of the pipe or corrosion-protection damage, the necessary remedial work will be recharged.
11. It may be necessary to adjust the finished level of any surface boxes which may fall within your proposed construction. Please ensure that these are not damaged, buried or otherwise rendered inaccessible as a result of the works and that all stop taps, valves, hydrants, etc. remain accessible and operable. Minor reduction in existing levels may result in conflict with apparatus such as valve spindles or tops of hydrants housed under the surface boxes. Checks should be made during site investigations to ascertain the level of such apparatus in order to determine any necessary alterations in advance of the works.
12. With regard to any proposed resurfacing works, you are required to contact STW on the number given above to arrange a site inspection to establish the condition of any STW apparatus in the nature of surface boxes or manhole covers and frames affected by the works. STW will then advise on any measures to be taken, in the event of this a proportionate charge will be made.
13. You are advised that Severn Trent Water Limited will not agree to either the erection of posts, directly over or within 1.0 metre of valves and hydrants,
14. No explosives are to be used in the vicinity of any STW apparatus without prior consultation with STW.

### **TREE PLANTING RESTRICTIONS**

There are many problems with the location of trees adjacent to sewers, water mains and other STW apparatus and these can lead to the loss of trees and hence amenity to the area which many people may have become used to. It is best if the problem is not created in the first place. Set out below are the recommendations for tree planting in close proximity to public sewers, water mains and other STW apparatus.

15. Please ensure that, in relation to STW apparatus, the mature root systems and canopies of any tree planted do not and will not encroach within the recommended distances specified in the notes below.
16. Both Poplar and Willow trees have extensive root systems and should not be planted within 12 metres of a sewer, water main or other STW apparatus.
17. The following trees and those of similar size, be they deciduous or evergreen, should not be planted within 6 metres of a sewer, water main or other STW apparatus. E.g. Ash, Beech, Birch, most Conifers, Elm, Horse Chestnut, Lime, Oak, Sycamore, Apple and Pear.



18. STW personnel require a clear path to conduct surveys etc. No shrubs or bushes should be planted within 2 metre of the centre line of a sewer, water main or other STW apparatus.
19. In certain circumstances, both the Company and landowners may wish to plant shrubs/bushes in close proximity to a sewer, water main or other STW apparatus for screening purposes. The following are shallow rooting and are suitable for this purpose: Blackthorn, Broom, Cotoneaster, Elder, Hazel, Laurel, Privet, Quickthorn, Snowberry, and most ornamental flowering shrubs.