



A63 Castle Street Improvement, Hull

DCO Documents Errata

TR010016/APP/6.1
HE51408-MMSJV-GEN-S0-RP-ZH-000016
~~27 August~~ 10 September 2019

A63 Castle Street Improvement, Hull

DCO Documents Errata

| Revision Record | | | | | | |
|-----------------|---------------------|-----------------|----------------|------------------|-----------|---------------|
| Rev No | Date | Originator | Checker | Approver | Status | Suitability |
| P01 | 10 May 2019 | A Sadler | C Stott | J McKenna | S4 | Shared |
| P02 | 1 July 2019 | A Sadler | C Stott | J McKenna | S4 | Shared |
| P03 | 5 Aug 2019 | A Sadler | C Stott | J McKenna | S4 | Shared |
| P04 | 27 Aug 2019 | A Sadler | C Stott | J McKenna | S4 | Shared |
| <u>P05</u> | <u>10 Sept 2019</u> | <u>A Sadler</u> | <u>C Stott</u> | <u>J McKenna</u> | <u>S4</u> | <u>Shared</u> |

This document has been prepared on behalf of Highways England by Mott MacDonald Sweco JV for Highways England's Collaborative Delivery Framework (CDF). It is issued for the party which commissioned it and for specific purposes connected with the above-captioned project only. It should not be relied upon by any other party or used for any other purpose. Mott MacDonald Sweco JV accepts no responsibility for the consequences of this document being relied upon by any other party, or being used for any other purpose, or containing any error or omission which is due to an error or omission in data supplied to us by other parties.

This document contains confidential information and proprietary intellectual property. It should not be shown to other parties without consent from Highways England.

Prepared for:

Highways England
Lateral
8 City Walk
Leeds
LS11 9AT

Prepared by:

Mott MacDonald Sweco JV
Stoneham Place, Stoneham Lane
Southampton, Hampshire
SO50 9NW

| Contents | Page |
|--|-------------|
| <u>1 Introduction</u> | <u>2</u> |
| <u>2 6.1 Environmental Statement Volume 1 Main Text (APP-023).....</u> | <u>3</u> |
| <u>3 6.2 Environmental Statement Volume 2 Figures 2.5.4 & 2.5.6 (APP-025).....</u> | <u>61</u> |
| <u>4 6.2 Environmental Statement Volume 2 Figure 10.2 (APP-036)</u> | <u>64</u> |
| <u>5 6.2 Environmental Statement Volume 2 Figure 15.2 (APP-040)</u> | <u>66</u> |
| <u>6 6.7 Ecology and Nature Conservation Assessment (APP-065).....</u> | <u>69</u> |
| <u>7 6.11 Register of Environmental Actions and Commitments (APP-068)</u> | <u>71</u> |
| <u>8 7.1 Planning Statement (APP-070).....</u> | <u>75</u> |
| <u>9 7.3 Outline Environmental Management Plan (APP-072).....</u> | <u>76</u> |
| <u>10 7.4 Transport Assessment Report (APP-073).....</u> | <u>78</u> |

1 Introduction

- 1.1.1 This Errata lists amendments to the Development Consent Order (DCO) documents which formed the A63 Castle Street Improvement, Hull application submitted to the Planning Inspectorate in September 2018. The Errata focuses upon corrections as opposed to typographical errors. Documents are presented in the order with which they were submitted for DCO.

2 6.1 Environmental Statement Volume 1 Main Text (APP-023)

Table 2.1: Environmental Statement Volume 1 Main Text

| Page | Paragraph/ Table | Published text | Correction |
|------|------------------|--|--|
| 37 | 2.5.2 | In totality the areas measure approximately: Option A 332,534m ² (Arco) and Option B 332,157m ² (Staples), which is around 33 hectares (see Sections Error! Reference source not found.2-9-14 to Error! Reference source not found.2-9-15 for more details). | In totality the areas measure approximately: Option A 330,430m ² (Arco) and Option B 332,157m ² (Staples), which is around 33 hectares (see Sections Error! Reference source not found.2-9-14 to Error! Reference source not found.2-9-15 for more details). |
| 37 | 2.5.3 | The permanent area of land required for the footprint of the Scheme (excluding the land needed temporarily during construction) measures approximately 79.926m ² . The current land use for the permanent footprint for the Scheme is primarily the existing road, associated footways, cycleways, roadside verges and central reserve. The realignment of Mytongate Junction and the addition of slip roads however require additional permanent land take from the following sites as shown on Volume 2, Figure 2.3 Scheme Site Boundary. The approximate areas are as follows: <ul style="list-style-type: none"> Arco Ltd - 3,501m² Staples - 10m² Kingston Retail Park - 937m² Trinity Burial Ground - 2,632m² Holiday Inn - 2,249m² | The permanent area of land required for the footprint of the Scheme (excluding the land needed temporarily during construction) measures approximately 79.704m ² . The current land use for the permanent footprint for the Scheme is primarily the existing road, associated footways, cycleways, roadside verges and central reserve. The realignment of Mytongate Junction and the addition of slip roads however require additional permanent land take from the following sites as shown on Volume 2, Figure 2.3 Scheme Site Boundary. The approximate areas are as follows: <ul style="list-style-type: none"> Arco Ltd - 3,502m² Staples - 10m² Kingston Retail Park - 822m² Trinity Burial Ground - 2,632m² Holiday Inn - 2,249m² |
| 38 | 2.5.4 | Land requiring permanent rights of access for maintenance and easement on land other than the public highway (in the vicinity of the Arco site and at Humber Dock Marina), totals approximately 23,551m ² . | Land requiring permanent rights of access for maintenance and easement on land other than the public highway (in the vicinity of the Arco site and at Humber Dock Marina), totals approximately 5,138m ² . |
| 38 | 2.5.5 | The Scheme Site also includes the land required temporarily to construct the Scheme. This land measures approximately 232,420m ² . It includes the sites of the Myton Centre (approximately 4,400m ²), Earl de Grey public house and Castle Buildings (approximately 968m ²) | The Scheme Site also includes the land required temporarily to construct the Scheme. This land measures approximately 233,291m ² . It includes the sites of the Myton Centre (approximately 4,312m ²), Earl de Grey public house and Castle Buildings (approximately 961m ²) |

| Page | Paragraph/ Table | Published text | Correction |
|------|------------------|---|--|
| | | and an area within the Humber Dock Marina (approximately 8,463m ²). | and an area within the Humber Dock Marina (approximately 8,463m ²). |
| 49 | 2.6.38 | The bridge deck width would be 3m to allow for un-segregated foot and cycle use. | The bridge deck width would be 3m between parapets to allow for un-segregated foot and cycle use. |
| 53 | 2.6.50 | <p>A combined footway and cycleway along the length of both sides of the A63 would be provided as shown on Volume 2, Figure 2.5 Sheets 2, 3 and 5 The Scheme proposals. The shared facility would generally be 3m wide, however there are some locations where space is restricted and the width would be reduced to a minimum of 2m as follows:</p> <ul style="list-style-type: none"> between Castle Buildings and Princes Quay car park on the north side of the A63 for approximately 55m in front of Warehouse No. 6 (Ask restaurant) on the north side of the A63 for approximately 25m in front of Humber Dock Marina, Holiday Inn and Trinity Burial Ground on the south side of the A63 for approximately 400m adjacent to Kingston Retail Park and in front of Arco on the south side of the A63 for approximately 450m | <p>A combined footway and cycleway along the north side of the A63 and along Blackfriargate would be provided as shown on Volume 2, Figure 2.5 Sheets 2, 3 and 5 The Scheme proposals. The shared facility would generally be 3m wide, however there are some locations where space is restricted and the width would be reduced to a minimum of 2m as follows:</p> <ul style="list-style-type: none"> in front of Castle Buildings for approximately 25m from Castle Buildings east to the rear of Princes Quay car park for approximately 122m from Castle Buildings west to the end of the Earl de Grey public house for approximately 55m |
| 54 | 2.6.52 | <p><u>The existing signalised pedestrian crossings at Market Place would be removed and pedestrians and cyclists would use a ramp from the A63 to access High Street to take them under the A63. The ramp would be realigned and the visibility for NMUs would be further improved by removing existing dense vegetation. A replacement planting scheme has been proposed in front of the Magistrates' Court which consists of tree planting with low growing shrub understorey, therefore ensuring no net loss of vegetation, but improved visibility long term. See Volume 2, Figure 9.8 Landscape proposals for more details. On the south side of the A63, pedestrians and cyclists would be routed along Humber Street. This would also be improved for NMUs with a new combined footway and cycleway with vegetation clearance to improve visibility. Users would re-join</u></p> | <p><u>The existing signalised pedestrian crossings at Market Place would be retained and pedestrians and cyclists would use a ramp from the A63 to access High Street to take them under the A63. The ramp would be realigned and the visibility for NMUs would be further improved by removing existing dense vegetation. A replacement planting scheme has been proposed in front of the Magistrates' Court which consists of tree planting with low growing shrub understorey, therefore ensuring no net loss of vegetation, but improved visibility long term. See Volume 2, Figure 9.8 Landscape proposals for more details. On the south side of the A63, pedestrians and cyclists would be routed along Blackfriargate. This would also be improved for NMUs with a new combined footway and cycleway with vegetation clearance to improve visibility. Pedestrian users would re-join the A63 via the</u></p> |

| Page | Paragraph/ Table | Published text | Correction | | | | |
|------|---|--|---|---|-------------------------|-----------------|--------------------------|
| | | <u>the A63 either via Queen Street or by continuing along Blanket Row and Humber Dock Street.</u> | <u>retained Queen Street signalised pedestrian crossing. Cyclists would travel along the existing Blanket Row and Humber Dock Street or could travel further west by taking a route along the existing High Street, Queen Street, Wellington Street (existing cycle route) and Manor House Street.</u> | | | | |
| 54 | 2.6.53 | <u>It would be possible for NMUs to cross other side roads, as at present. With the exception of Mytongate Junction, crossings of side roads would be uncontrolled. Casual crossing of the A63 by NMUs would be prevented by a barrier within the central reserve and provision of pedestrian guard rails in footways or nearside verges at high-risk locations.</u> | <u>It would be possible for NMUs to cross other side roads, as at present. With the exception of Mytongate Junction, Market Place and Queen Street, crossings of side roads would be uncontrolled. Casual crossing of the A63 by NMUs would be prevented by a barrier within the central reserve and provision of pedestrian guard rails in footways or nearside verges at high-risk locations.</u> | | | | |
| 66 | 2.9.6 | There is no traffic management requirement for phase 0. | Delete text | | | | |
| 182 | 7.7.7 | <u>It is proposed that the A63 remain in use throughout the works in order that its capacity is maximised. Right hand turns at Mytongate would be maintained throughout the works.</u> | <u>It is proposed that the A63 remain in use throughout the works in order that its capacity is maximised.</u> | | | | |
| 317 | Table 10.4 Non-statutory designated sites (row 13) | <table border="1"> <tr> <td>SNCI</td> <td>Forelyke stream cycle track - south of Chamberlain Road (177)</td> <td>No information provided</td> <td>1.6km northeast</td> </tr> </table> | SNCI | Forelyke stream cycle track - south of Chamberlain Road (177) | No information provided | 1.6km northeast | Remove row 13 from table |
| SNCI | Forelyke stream cycle track - south of Chamberlain Road (177) | No information provided | 1.6km northeast | | | | |
| 335 | Table 10.8 Summary of valuation of ecological receptors, Ecological receptor column (row 3) | Trinity Burial Ground SNCI, River Hull SNCI | Trinity Burial Ground SNCI, River Hull SNCI, Mudflats to the south of Sammy's Point SNCI | | | | |
| 340 | 10.7.17 | <u>River Hull SNCI</u> Direct impacts to the River Hull SNCI are unlikely. | <u>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</u> Direct impacts to the River Hull SNCI and Mudflats to the south of Sammy's Point SNCI are unlikely. | | | | |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|---|---|
| 347 | 10.7.54 | <u>River Hull SNCI</u> Road drainage would not discharge to the River Hull during the Operation Phase and there would therefore be no risks to water quality within the river. | <u>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</u> Road drainage would not discharge to the River Hull during the Operation Phase and would not impact upon the River Hull SNCI or Mudflats to the south of Sammy's Point SNCI. There would therefore be no risks to water quality within the river. |
| 351 | Table 10.9 Characterisation process of ecological impacts | n/a | Replace Table 10.9 with revised Table 10.9 below. Impacts are separated into a column for construction and a column for operation as requested in WQ1.2.6 (new/revised text in red). Replacement table also takes into account changes arising from mudflats to the south of Sammy's Point SNCI as requested in WQ1.2.2 (new/revised text in red). |
| 366 | 10.8.11 | <i>River Hull SNCI</i> Neutral residual impacts are predicted to the River Hull SNCI during the Construction Phase, following the implementation of pollution protection mitigation measures. | <i>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</i> Neutral residual impacts are predicted to the River Hull SNCI and Mudflats to the south of Sammy's Point SNCI during the Construction Phase, following the implementation of pollution protection mitigation measures. |
| 369 | 10.8.31 | <i>River Hull SNCI</i> · With no increase in noise or air pollution and no water discharges into this river, there is predicted to be neutral residual impacts to the SNCI during operation. | <i>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</i> With no increase in noise or air pollution and no water discharges into this river, there is predicted to be neutral residual impacts to these SNCIs during operation. |
| 372 | Table 10.10 Summary of ecological receptors, Ecological receptor column (row 4) | River Hull SNCI | River Hull SNCI and Mudflats to the south of Sammy's Point SNCI |
| 378 | Table 10.10 Summary of ecological receptors, Ecological receptor | Aquatic Invertebrates Humber Estuary SSSI River Hull SNCI | Aquatic Invertebrates Humber Estuary SSSI River Hull SNCI |

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|--|--|
| | column (row 11) | | Mudflats to the south of Sammy's Point SNCI |
| 385 | 11.1.6 | Impacts ranging from large / very large beneficial to very large adverse significance during construction include the alteration of ground elevations, which has the potential to alter flood routes depending on the scale and source of the flooding and the phase of construction. Impacts can be of adverse or beneficial significance depending on the location. Management of flood risk during construction would be outlined in the OEMP and would include use of the Environment Agency's Flood Warning service. | Impacts ranging from very large beneficial to very large adverse significance during construction include the alteration of ground elevations, which has the potential to alter flood routes depending on the scale and source of the flooding and the phase of construction. Impacts can be of adverse or beneficial significance depending on the location. Management of flood risk during construction would be outlined in the OEMP (including the Flood Emergency Plan (FEP)) and would include use of the Environment Agency's Flood Warning service |
| 386 | 11.1.10 | Alteration of ground elevations as a result of the Scheme result in a complex pattern of flooding impacts on the Humber floodplain primarily related to the presence of the underpass and the raising of road levels to the east and west of the underpass. Operation flood risk impacts range from large / very large beneficial to very large adverse significance depending on the location on the floodplain and the source and extent of the flooding. | Alteration of ground elevations as a result of the Scheme result in a complex pattern of flooding impacts on the Humber floodplain primarily related to the presence of the underpass and the raising/lowering of road levels to the east and west of the underpass. Operation flood risk impacts range from very large beneficial to very large adverse significance depending on the location on the floodplain and the source, extent and severity of the flooding. |
| | 11.1.11 | There is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team who consider an appropriate response, for example, the closure of the underpass. This response would be implemented by the local emergency services. This procedure has been updated and amended to reflect the particular requirements of flooding of the underpass. The revised procedure was written in consultation with relevant stakeholders including Highways England, the emergency services and the Humber Local Resilience Forum. | There is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team who consider an appropriate response, for example, the closure of the underpass. This response would be implemented by the local emergency services. This procedure has been updated and amended to reflect the particular requirements of flooding of the underpass. The revised procedure was written in consultation with relevant stakeholders including Highways England, the emergency services and the Humber Local Resilience Forum. The updated procedures include measures to enable physical closure of the underpass during flood events, including those events with minimal or no warning, such as a flood defence breach. |

| Page | Paragraph/ Table | Published text | Correction |
|------|------------------|--|---|
| | 11.4.9 | <p>The Environment Agency, to discuss existing flood risk information including flood models; agree the approach to, and discuss the outcomes of, the flood risk assessment (FRA) (including the agreement on which flood scenarios to assess) and the water quality impact assessment; and to consult on the mitigation measures for flood risk and water quality impacts from the proposed discharge into the Humber. The Environment Agency was also consulted on the approach to and findings of the groundwater assessment, as well as the groundwater modelling approach. Following a meeting in August 2018 subsequent to a review of the draft FRA, the Environment Agency requested additional information on flood risk to be provided at a later date. These additional requirements are summarised in Volume 3, Appendix 11.9 Additional flood risk assessment information requirements.</p> | <p>The Environment Agency, to discuss existing flood risk information including flood models; agree the approach to, and discuss the outcomes of, the flood risk assessment (FRA) (including the agreement on which flood scenarios to assess) and the water quality impact assessment; and to consult on the mitigation measures for flood risk and water quality impacts from the proposed discharge into the Humber. The Environment Agency was also consulted on the approach to and findings of the groundwater assessment, as well as the groundwater modelling approach. Following a meeting in August 2018 subsequent to a review of the draft FRA, the Environment Agency requested additional information on flood risk to be provided at a later date. These additional requirements are summarised in Volume 3, Appendix 11.9 Additional flood risk assessment information requirements. Detailed and regular consultation with the Environment Agency was ongoing prior to and during the DCO Examination process, the Statement of Common Ground¹ provides details of all consultation with the Environment Agency including the provision of additional information as outlined in Volume 3, Appendix 11.9 Additional flood risk information.</p> |
| 402 | 11.4.19 | <p>Consultation has taken place with HCC and the Environment Agency throughout the FRA to agree the scope of the assessment, the flood scenarios to be considered and to review the results of the impact assessment and discuss mitigation measures including emergency procedures.</p> | <p>Consultation has taken place with HCC and the Environment Agency prior to the DCO application and during the subsequent DCO Examination process to agree the scope of the assessment, the flood scenarios to be considered and to review the results of the impact assessment and discuss mitigation measures including emergency procedures. The consultation with the Environment Agency also highlighted the requirement to consider extreme (H++)²</p> |

¹ Highways England's A63 Castle Street Improvement, Hull, TR010016, Statement of Common Ground (SoCG) with the Environment Agency

² Environment Agency (2016). Adapting to Climate Change: Advice for Flood and Coastal Erosion Risk Management Authorities

| Page | Paragraph/ Table | Published text | Correction | | | | | | |
|--|---|---|--|--|---|--|--|--|--|
| | | | and the recently released UKCP18 ³ climate change allowances. Furthermore, the Environment Agency requested specific consideration of the impacts of flood defences breaches on the Scheme. Details of this consultation are provided in the relevant Statement of Common Ground ¹ and a list of the additional information provided is given in ES Volume 3, Appendix 11.9 Additional flood risk information. | | | | | | |
| 403 | 11.4.20 | The Environment Agency requested additional information on flood risk to be provided at a later date; these requirements are summarised in Volume 3, Appendix 11.9 Additional flood risk assessment information requirements. | The Environment Agency requested additional information on flood risk to be provided following the publication of the FRA with the DCO application. These requirements are summarised in Volume 3, Appendix 11.9 Additional flood risk assessment information requirements. | | | | | | |
| 403 | Table 11.4: Flooding scenarios considered in the FRA | <table border="1"> <tr> <td>Tidal (undefended) from Humber Estuary</td> <td>These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place.</td> <td>1 in 200 1 in 200 plus climate change</td> </tr> </table> | Tidal (undefended) from Humber Estuary | These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place. | 1 in 200 1 in 200 plus climate change | <table border="1"> <tr> <td>Tidal (undefended) from Humber Estuary</td> <td>These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place.</td> <td>1 in 200 1 in 200 plus climate change 1 in 200 plus H++ climate change</td> </tr> </table> | Tidal (undefended) from Humber Estuary | These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place. | 1 in 200 1 in 200 plus climate change 1 in 200 plus H++ climate change |
| Tidal (undefended) from Humber Estuary | These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place. | 1 in 200 1 in 200 plus climate change | | | | | | | |
| Tidal (undefended) from Humber Estuary | These scenarios consider tidal flooding from the Humber Estuary if the existing Humber flood defences were not in place. | 1 in 200 1 in 200 plus climate change 1 in 200 plus H++ climate change | | | | | | | |
| 403 | Table 11.4: Flooding scenarios considered in the FRA | n/a | <p>Add row:</p> <table border="1"> <tr> <td>Humber north bank defence breaches</td> <td>These scenarios consider breaches of the existing Humber north bank tidal flood defences at four locations within the study area. These scenarios are based on information supplied by Hull City Council.</td> <td>1 in 200 plus climate change</td> </tr> </table> | Humber north bank defence breaches | These scenarios consider breaches of the existing Humber north bank tidal flood defences at four locations within the study area. These scenarios are based on information supplied by Hull City Council. | 1 in 200 plus climate change | | | |
| Humber north bank defence breaches | These scenarios consider breaches of the existing Humber north bank tidal flood defences at four locations within the study area. These scenarios are based on information supplied by Hull City Council. | 1 in 200 plus climate change | | | | | | | |
| 417 | 11.5.38 | According to the SFRA, the city of Hull, and the Scheme are protected from flooding by the existing Humber Estuary and River Hull flood defences. The Humber Estuary defences generally provide a standard level of protection to a 1 in 200-year event, but in some areas, for example, to the east of Albert Dock East the level of protection falls to a 1 in 5-year event. New flood defences have been installed in Albert Dock (completed in November 2015) which provide a standard level of protection to a 1 in 200-year event. The River Hull defences generally provide a standard level of protection greater than a 1 in 200-year event. | According to the SFRA, the city of Hull, and the Scheme are protected from flooding by the existing Humber Estuary and River Hull flood defences. The Humber Estuary defences generally provide a standard level of protection to a 1 in 200-year event, but in some areas, for example, to the east of Albert Dock East the level of protection falls to a 1 in 5-year event. New flood defences have been installed in Albert Dock (completed in November 2015) which provide a standard level of protection to a 1 in 200-year event. The River Hull defences generally provide a standard level of protection greater than a 1 in 200-year event. The Environment Agency currently have a scheme under construction (the Humber Hull Frontages ⁴) to install and | | | | | | |

³ Met Office (2019). UK Climate Projections (UKCP18). <https://www.metoffice.gov.uk/research/collaboration/ukcp>

⁴ <https://consult.environment-agency.gov.uk/yorkshire/humber-hull-frontages/>

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|---|--|
| | | | upgrade 7km of flood defences on the north bank of the Humber at Hull from St. Andrew's Quay to Victoria Dock. This scheme will improve the standard of protection to the defences in the study area to 1 in 200 years plus an allowance for climate change to 2040. Climate change effects beyond 2040 will be addressed through a 'managed adaptive' approach with the defences designed and constructed to facilitate easier upgrades in the future. The Humber Hull Frontages scheme is scheduled for completion in March 2021. |
| 418 | 11.5.42 | <p>Predictions from the flood risk model developed for Volume 3 Appendix 11.2 Flood risk assessment confirm that under baseline conditions:</p> <ul style="list-style-type: none"> There are some isolated areas of minor surface water flooding to the north and east of the Scheme. There was no predicted surface water flooding within the Scheme area. In the vicinity of the Scheme Site, predicted flooding under a 1 in 200-year return period wave overtopping event from the Humber Estuary reaches the periphery of the Scheme area resulting in flooding to the west and south of Mytongate Junction and parts of Kingston Retail Park. This assumes the existing Humber flood defences are in place and the Albert Dock gate is closed. Without the Humber north bank flood defences, the extent of flooding under a 1 in 200-year return period tidal event is widespread with significant areas of Hull affected. Flood depths reach a maximum of 1.2m along the existing A63. The failure of the Hull Tidal Surge Barrier to close would result in extensive flooding west of the River Hull (the flood risk model does not consider the area to the east of the River Hull) under a tidal event with a return period of 1 in 200-years. The A63 east of Mytongate Junction is flooded up to a maximum of 1m in places with flooding extending north of Mytongate Junction to Ferensway and Anlaby Road. It is noted that the | <p>Predictions from the flood risk model developed for Volume 3 Appendix 11.2 Flood risk assessment confirm that under baseline conditions:</p> <ul style="list-style-type: none"> There are some isolated areas of minor surface water flooding to the north and east of the Scheme. There was no predicted surface water flooding within the Scheme area. Predicted flooding under a 1 in 200-year return period wave overtopping event from the Humber Estuary reaches the Scheme area resulting in flooding of the A63 to the east of Mytongate Junction and parts of Kingston Retail Park. During such an event, the underpass would be flooded. This assumes the existing Humber flood defences are in place and the Albert Dock gate is closed. Without the Humber north bank flood defences, the extent of flooding under a 1 in 200-year return period tidal (i.e. undefended) event is widespread with significant areas of Hull and all of the Scheme site area affected. Flood depths reach a maximum of 0.38m along the existing A63. The failure of the Hull Tidal Surge Barrier to close would result in extensive flooding west of the River Hull (the flood risk model does not consider the area to the east of the River Hull) under a tidal event with a return period of 1 in 200-years. The A63 to east of Mytongate Junction is flooded up to a maximum of 0.47m in places with flooding extending north of Mytongate Junction to Ferensway and |

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|--|--|
| | | failure of the Hull Tidal Surge Barrier to close during a high tide event is extremely unlikely as it is fitted with a system to automatically close the barrier if the power fails. | Anlaby Road. It is noted that the failure of the Hull Tidal Surge Barrier to close during a high tide event is extremely unlikely as it is fitted with a system to automatically close the barrier if the power fails. |
| 439 | 11.6.17 | Mitigation of extreme flooding impacts from tidal, fluvial and pluvial sources during construction should be considered in the OEMP. The construction of the underpass would create excavations where construction workers and plant would be at risk. Standby temporary pumping arrangements may be required to remove any flood water and this would be subject to best practice guidance to control discharges to sewer or surface waters. Emergency and evacuation procedures would be incorporated into the OEMP in response to all sources of flooding and would include use of the Environment Agency Flood Warning service. | Mitigation of extreme flooding impacts from tidal, fluvial and pluvial sources during construction should be considered in the OEMP and detailed in a Flood Emergency Plan (FEP) prior to construction. The construction of the underpass would create excavations where construction workers and plant would be at risk. Standby temporary pumping arrangements may be required to remove any flood water and this would be subject to best practice guidance to control discharges to sewer or surface waters. Emergency and evacuation procedures would be incorporated into the OEMP and FEP in response to all sources of flooding and would include use of the Environment Agency Flood Warning service. |
| 442 | 11.6.35 | For extreme tidal flooding events such as those witnessed on 5 December 2013, there is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team at the North East Regional Control Centre (NERCC) who consider an appropriate response, for example, the closure of the underpass. This procedure is currently being reviewed for the Scheme. The Flood Emergency Evacuation Plan Report is appended to Volume 3, Appendix 11.2 Flood risk assessment. A summary of the key aspects of the Plan are provided below: <ul style="list-style-type: none"> Upon receipt of a flood alert, personnel from the Area Maintenance Team (AMT) and key assets (including a high-volume pump owned by Highways England) will be put on 'standby' for deployment. Upon receipt of a flood warning, the NERCC will monitor the underpass via CCTV, variable message signs (VMS) will be activated to direct traffic away from the underpass and | For extreme tidal flooding events such as those witnessed on 5 December 2013, there is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team at the North East Regional Control Centre (NERCC) who consider an appropriate response, for example, for the closure of the underpass. This procedure has been reviewed and revised (in consultation with the Environment Agency, Hull City Council, the emergency services and Highways England) for the Scheme. The Flood Emergency Evacuation Plan Report is appended to Volume 3, Appendix 11.2 Flood risk assessment. A summary of the key aspects of the Plan are provided below: <ul style="list-style-type: none"> Upon receipt of a flood alert, personnel from the Area Maintenance Team (AMT) and key assets (including a temporary, mobile, high-volume pump owned by Highways England) will be put on 'standby' for deployment. Upon receipt of a flood warning, the NERCC will monitor the underpass via |

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|---|---|
| | | <p>personnel from the AMT will be moved closer to the underpass to put in place a physical road closure, if required.</p> <ul style="list-style-type: none"> Upon receipt of a severe flood warning, the high-volume pump will be moved to the underpass and a physical road closure will be put in place by the AMT personnel. VMS will direct traffic away from the underpass and long pre-agreed strategic diversion routes. The underpass will be monitored via CCTV. All relevant measures outlined above would remain in place until a 'Warnings no longer in force' notification is issued by the Environment Agency. The underpass pumping station would have high volume alarms to alert the NERCC to pump failure, which would trigger the above closure responses, if required. This would only be required in the event of a failure of all other warnings and would provide a last chance warning of flooding of the underpass. The plan would be under the ownership of Highways England with a review every 2 years. | <p>CCTV, variable message signs (VMS) will be activated to direct traffic away from the underpass and personnel from the AMT will be moved closer to the underpass to put in place a physical road closure, if required.</p> <ul style="list-style-type: none"> Upon receipt of a severe flood warning, the high-volume pump will be moved to the underpass and a physical road closure will be put in place by the AMT personnel. VMS will direct traffic away from the underpass and long pre-agreed strategic diversion routes. The underpass will be monitored via CCTV. The FEOP also includes procedures to be rapidly put in place and the underpass closed, in the event of a minimal or no warning flood event such as a defence breach. All relevant measures outlined above would remain in place until a 'Warnings no longer in force' notification is issued by the Environment Agency. During the recovery phase, the temporary, high-volume pumps will be deployed in combination with the underpass surface water pumping station to drain the underpass of flood waters. Following this, the AMT will clear the carriageway and an assessment will be made as to whether the underpass can safely be re-opened to traffic. The underpass pumping station would have high volume alarms to alert the NERCC to pump failure, which would trigger the above closure responses, if required. This would only be required in the event of a failure of all other warnings and would provide a last chance warning of flooding of the underpass. The plan would be under the ownership of Highways England with a review every 3 years. |
| 443 | 11.6.36 | The flood defences at Albert Dock have been upgraded by the Environment Agency in 2015 which provides a 1 in 100 to 1 in 200-year standard of protection. Furthermore, there are current proposals to upgrade remaining | The flood defences at Albert Dock have been upgraded by the Environment Agency in 2015 which provides a 1 in 100 to 1 in 200-year standard of protection. Furthermore, the Humber Hull Frontages ⁴ defence upgrade scheme is currently |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| | | sections of the Humber North Bank flood defences as part of the £42m Humber Hull Frontages projects. The standard of protection of the Scheme would be for a return period of 1 in 200 years with an allowance for climate change to the 2040s. The remaining climate change allowance would be accounted for with a 'managed adaptive approach' which would allow for easier upgrading of the defences in the future. Further details will be provided in line with Volume 3, Appendix 11.9 Additional flood risk information requirements. | under construction and scheduled for completion in 2021. The standard of protection of the Scheme would be increased to a return period of 1 in 200 years with an allowance for climate change to the 2040s. The remaining climate change allowance would be accounted for with a 'managed adaptive approach' which would allow for easier upgrading of the defences in the future. Further details are provided in line with Volume 3, Appendix 11.2 Flood risk assessment. |
| 455 | Table 11.15: Significance of potential residual impacts on surface water features during construction | n/a | Amend Table 11.15 row "Changes in flood flow routes due to alteration of ground elevations and construction of structures" as below. (New text in red). |
| 486 | 11.7.68 | A summary of the impacts is provided in Table 11.16 for scenarios with the greatest impact for a given flooding source. The magnitude of the impact is defined in Table 11.2 and significance in Table 11.3. Climate change impacts are discussed in Section 11.8. | A summary of the impacts is provided in Table 11.18 for scenarios with the greatest impact for a given flooding source. The magnitude of the impact is defined in Table 11.2 and significance in Table 11.3. Climate change impacts are discussed in Section 11.8. Furthermore, the spatial pattern and magnitude of impact is dependent on the inclusion or exclusion of the central vertical concrete barrier (VCB) along the mainline within the Scheme. Table 11.18 presents a summary of impacts for both scenarios, i.e. VCB included in the Scheme and VCB excluded from the Scheme. The assessment provided in the paragraphs below is based on scenarios with the VCB included. |
| 487 | Table 11.18 Summary of magnitude of peak | n/a | Replace Table 11.18 with revised Table 11.18 below. |
| 489 | 11.7.70 | Flooding to the Scheme from a 1 in 200-year return period wave overtopping | During a 1 in 200-year return period wave overtopping event from the Humber |

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|--|---|
| | | event from the Humber is predicted to reach the periphery of the Scheme study area, which would result in some increased flooding in Queen's Gardens resulting in an impact of moderate adverse magnitude (Table 11.18). | flooding is predicted to reach the Scheme area and flood the A63 carriageway east of Mytongate Junction as well as flooding the underpass itself. Areas to the north and south of the eastern extent of the Scheme as well as Queen's Gardens and Kingston Retail Park would have increased flooding resulting in an impact of major adverse magnitude (Table 11.18). |
| 490 | 11.7.71 | Conversely to the above, the Scheme decreases maximum predicted flood depths within the boundary of the Scheme Site resulting in an impact of minor beneficial magnitude (Table 11.18). | Conversely to the above, the Scheme decreases maximum predicted flood depths within the boundary of the Scheme Site as well as in areas to the north of Mytongate Junction resulting in an impact of major beneficial magnitude (Table 11.18). |
| 490 | 11.7.72 | Flooding from a wave overtopping event from the Humber for a 1 in 1000-year event is predicted to extend north of the Scheme Site beyond Hull Royal Infirmary and to flood the proposed underpass. Under this scenario, predicted maximum flood depths in the underpass structure and westbound exit slip road are 6m and 2.05m respectively; an impact of major adverse magnitude (Table 11.18). There is a predicted increase in flood depth in the Kingston Retail Park car park under the Scheme scenario of 0.40m; an impact of minor adverse magnitude (Table 11.18). The proposed underpass would prevent some flood water extending northwards past Mytongate Junction resulting in a decrease in predicted flood depth by up to 0.1m in the area between Anlaby Road and Castle Street; an impact of moderate beneficial magnitude (Table 11.18). Impacts of minor beneficial magnitude also occur within the Scheme Site Boundary (not including the underpass and westbound exit slip road) due to an increase in ground levels. Impacts of minor beneficial magnitude also occur in areas to the north-west of St Stephen's Shopping Centre. | Flooding from a wave overtopping event from the Humber for a 1 in 1000-year event is predicted to extend north of the Scheme Site beyond Hull Royal Infirmary and to flood the proposed underpass. Under this scenario, predicted maximum flood depths in the underpass structure and westbound exit slip road are 5.8m and 2.05m respectively; an impact of major adverse magnitude (Error! Reference source not found,Table 44.48). There is a predicted increase in flood depth in the Kingston Retail Park car park under the Scheme scenario of 0.30m; an impact of major adverse magnitude (Error! Reference source not found,Table 44.48). Increases in flood depth of a major adverse magnitude are also present south of the Scheme to the west of the underpass (around Waverley Street and Kingston Retail Park) and moderate to major adverse magnitude to the south of the eastern extent of the Scheme (around Blanket Row and Blackfriargate). The proposed underpass would prevent some flood water extending northwards past Mytongate Junction resulting in a decrease in predicted flood depth by up to 0.2m in the area around Myton Street; an impact of major beneficial magnitude (Error! Reference source not found,Table 44.48). Impacts of major beneficial magnitude also occur within the Scheme Site Boundary (not including the underpass and westbound exit slip road) due to an increase in ground levels. Impacts of major beneficial magnitude |

| Page | Paragraph/ Table | Published text | Correction |
|------|---------------------|---|---|
| | | | also occur in areas to the of the Scheme including Princes Dock, Market Place and the surrounding streets. |
| 490 | 11.7.73 | Tidal flooding of the Scheme from the River Hull could occur in the event of the Hull Tidal Surge Barrier failing to close. This is unlikely as it incorporates a system to automatically close the barrier in the event of a power failure. However, if the barrier failed to close, under a 1 in 200-year event the underpass structure would be flooded to a predicted maximum depth of 3.4m and the westbound diverging slip road would be flooded to a maximum depth of 0.65m; both impacts of major adverse magnitude (Error! Reference source not found,Table 11.18). Consequently, the presence of the underpass has the effect of preventing flood flows reaching the area north and west of Mytongate Junction, particularly around the Junction of Ferensway and Anlaby Road as well as the area south of Mytongate Junction (Kingston Retail Park car park and Trinity Burial Grounds) removing flood waters in both of these locations, resulting in an impact of moderate beneficial magnitude (Error! Reference source not found,Table 11.18). There would be a predicted increase in maximum flood depths in the Humber and Railways Docks resulting in an impact of minor adverse magnitude (Error! Reference source not found,Table 11.18). Consequently, flood flows are diverted towards the Princes Quay water body, with a predicted maximum flood depth of 0.60m in the water body; an impact of moderate adverse magnitude (Error! Reference source not found,Table 11.18). | Tidal flooding of the Scheme from the River Hull could occur in the event of the Hull Tidal Surge Barrier failing to close. This is unlikely as it incorporates a system to automatically close the barrier in the event of a power failure. However, if the barrier failed to close, under a 1 in 200-year event the underpass structure would be flooded to a predicted maximum depth of 3.4m and the westbound diverging slip road would be flooded to a maximum depth of 0.65m; both impacts of major adverse magnitude (Error! Reference source not found,Table 11.18). Consequently, the presence of the underpass has the effect of preventing flood flows reaching the area north and west of Mytongate Junction, particularly around the Junction of Ferensway and Anlaby Road as well as the area south of Mytongate Junction (Kingston Retail Park car park and Trinity Burial Grounds) removing flood waters in both of these locations, resulting in an impact of major beneficial magnitude (Error! Reference source not found,Table 11.18). There would be a predicted increase in maximum flood depths in Princes Dock resulting in an impact of major adverse magnitude although levels in the Humber and Railway Docks would be reduced resulting in an impact of major beneficial magnitude (Error! Reference source not found,Table 11.18). Streets to the north and south of the eastern Scheme extent would see flood depth increases ranging from moderate to major adverse magnitude. |
| 490 | 11.7.74 | The predicted impact of the Scheme on tidal flooding from the River Hull under a 1 in 1000-year event with the Hull Tidal Surge Barrier failing to close results in the same impact magnitudes as described above for the 1 in 200-year event. The more extensive flooding (greater predicted flood depths) in this event result in the flooding of Humber and Railway docks, with an increase in predicted flood depth of 1.03m under the Scheme scenario; an impact of major | The predicted impact of the Scheme on tidal flooding from the River Hull under a 1 in 1000-year event with the Hull Tidal Surge Barrier failing to close results is similar to that described above for the 1 in 200-year event. Impacts of moderate and major adverse magnitude are predicted in areas to the south-east and south-west of the underpass respectively (Error! Reference source not found,Table 11.18). Under this scenario, the proposed underpass is completely flooded with |

| Page | Paragraph/ Table | Published text | Correction |
|------|--|--|--|
| | | adverse magnitude (Error! Reference source not found, Table 11.18). Under this scenario, the proposed underpass is completely flooded with flood waters beginning to extend westwards along the A63. However, the extent of beneficial effects is greater south of the existing A63, in Kingston Retail Park and areas to the north of the A63 around St Luke's Street and Osborne Street resulting in an impact of moderate beneficial magnitude. | flood waters beginning to extend westwards along the A63. However, the extent of beneficial effects is greater in areas to the north of the A63 around St Luke's Street and Osbourne Street resulting in an impact of major beneficial magnitude. Under this scenario, there is no beneficial impact at Humber Dock Marina. The magnitude of the adverse impact is reduced to moderate adverse at Princes Dock compared to large adverse for the 1 in 200-year event. |
| 495 | Table 11.20: Significance of potential residual impacts on surface water features during operation | n/a | Amend Table 11.20 row "Alteration of flood flow routes due to the changes in ground levels and construction of structures" as below. (New text in red) . |
| 503 | 11.8.1 | <ul style="list-style-type: none"> Conversely, the impact of climate change on rising sea levels and wave height has significant effects on the flooding in Hull. Sea levels are predicted to increase by 1.125m between 2011 and 2125 and wave heights are expected to increase by 10%. When incorporating climate change impacts into the flood risk predictions for the 1 in 200-year return period wave overtopping from the Humber Estuary, the area of the flooding extends well beyond the boundaries of the Scheme Site reaching depths of up to 1.20m in the study area. | <ul style="list-style-type: none"> Conversely, the impact of climate change on rising sea levels and wave height has significant effects on the flooding in Hull. Sea levels are predicted to increase by 1.125m between 2011 and 2115 and wave heights are expected to increase by 10%. When incorporating climate change impacts into the flood risk predictions for the 1 in 200-year return period wave overtopping from the Humber Estuary, the area of the flooding extends well beyond the boundaries of the Scheme Site reaching depths of up to 1.20m in the study area. |
| 504 | 11.8.1 | n/a | <p>Add as follows:</p> <ul style="list-style-type: none"> Extreme (H++)² allowances for the effects of climate change on sea level rise were considered for 'undefended' tidal flooding from the Humber Estuary. The extent of flooding and magnitude of impacts as a result of the Scheme were similar to those for the 1 in 200-year undefended tidal flooding from the Humber Estuary. |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| | | | <ul style="list-style-type: none"> Revised climate change allowances for mean sea level rise were released in December 2018, known as UKCP18³. Further information on these allowances is provided in Volume 3 Appendix 11.2 Flood Risk Assessment. |
| 507 | 11.10.1 | An exception to this is that alterations of ground elevations during construction would alter flood flow routes and result in potential residual impacts ranging from very large adverse in some areas to large / very large beneficial significance in other areas on the Humber floodplain. | An exception to this is that alterations of ground elevations during construction would alter flood flow routes and result in potential residual impacts ranging from very large adverse in some areas to very large beneficial significance in other areas on the Humber floodplain. |
| 508 | 11.10.6 | There is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team who consider an appropriate response, for example, the closure of the underpass. This response would be implemented by the local emergency services. This procedure has been updated and amended to reflect the particular requirements of flooding of the underpass. The revised procedure was written in consultation with relevant stakeholders including Highways England, the emergency services and the Humber Local Resilience Forum. | There is an existing procedure in place whereby flood alerts from the Environment Agency are issued to the Highways England Emergency Planning team who consider an appropriate response, for example, the closure of the underpass. This response would be implemented by the Area Maintenance Team on behalf of Highways England. This procedure has been updated and amended to reflect the particular requirements of flooding of the underpass. The revised procedure was written in consultation with relevant stakeholders including Highways England, the emergency services and the Humber Local Resilience Forum. These revised procedures, known as the Flood Emergency and Evacuation Plan, include measures to enable the safe and rapid physical closure of the underpass in the event of a minimal or no warning flood event, such as a flood defence breach. |
| 592 | Table 14.8 Private property and associated land take – predicted effects/row 2 | <p>1A. Arco Ltd</p> <p>Temporary land take at Arco Ltd (Option A):</p> <p>Option A would involve the site currently held by Arco Ltd being used as a bentonite farm / concrete batching plant / materials treatment / jet grouting compound. In this scenario, a total of 14,407m² temporary land take is likely to be required. This is the preferred site for the compound.</p> | <p>1A. Arco Ltd</p> <p>Temporary land take at Arco Ltd (Option A):</p> <p>Option A would involve the site currently held by Arco Ltd being used as a bentonite farm / concrete batching plant / materials treatment / jet grouting compound. In this scenario, a total of 14,409m² temporary land take is likely to be required. This is the preferred site for the compound.</p> |
| 592 | Table 14.8 Private | Permanent land take at Arco Ltd | Permanent land take at Arco Ltd |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|---|---|
| | property and associated land take – predicted effects/row 4 | (Option A): If the Arco site is used, it is anticipated that there will be approximately 3,501m ² of permanent land take at Arco Ltd and 1,764m ² of 'permanent rights' required. | (Option A): If the Arco site is used, it is anticipated that there will be approximately 3,502m ² of permanent land take at Arco Ltd and 1,766m ² of 'permanent rights' required. |
| 592 | Table 14.8 Private property and associated land take – predicted effects/row 5 | Temporary land take at Staples site (Option A): Option A: If the Arco site is used, the Staples site would experience 71m ² of temporary land take and the buildings would not be demolished. | Temporary land take at Staples site (Option A): Option A: If the Arco site is used, the Staples site would experience 108m ² of temporary land take and the buildings would not be demolished. |
| 594 | Table 14.8 Private property and associated land take – predicted effects/row 20 | Temporary land take at the Myton Centre: Land take would be required at the Myton Centre of 3,994m ² . It is proposed the site will be used as a temporary car park for contractor staff working. It will be used for the full 5-year construction period. Current land use: HCC property. | Temporary land take at the Myton Centre: Land take would be required at the Myton Centre of 4,312m ² . It is proposed the site will be used as a temporary car park for contractor staff working. It will be used for the full 5-year construction period. Current land use: HCC property. |
| 595 | Table 14.8 Private property and associated land take – predicted effects/row 24 | Temporary land take at Kingston Retail Park (Option A): It is anticipated that 6,737m ² will be acquired for the project from the Kingston Retail Park under Option A (Arco). This would involve the loss of parking spaces impacting on retail outlets ability to trade | Temporary land take at Kingston Retail Park (Option A): It is anticipated that 6,733m ² will be acquired for the project from the Kingston Retail Park under Option A (Arco). This would involve the loss of parking spaces impacting on retail outlets ability to trade |
| 595 | Table 14.8 Private property and associated land take – predicted effects/row 26 | Permanent land take at Kingston Retail Park (Option A): 937m ² likely to be acquired. Due to the constraints of the Scheme corridor, land-take from Kingston Retail Park is unavoidable. The Scheme footprint has been reduced as much as possible but operational and safety requirements dictate that some parking spaces would be permanently lost, potentially impacting on the ability of the retail outlets located there to trade as before. | Permanent land take at Kingston Retail Park (Option A): 822m ² likely to be acquired. Due to the constraints of the Scheme corridor, land-take from Kingston Retail Park is unavoidable. The Scheme footprint has been reduced as much as possible but operational and safety requirements dictate that some parking spaces would be permanently lost, potentially impacting on the ability of the retail outlets located there to trade as before. |

| Page | Paragraph/ Table | Published text | Correction | | | |
|--|---|---|--|---|--|--|
| 603 | Table 14.13: Community severance – operational effects: Location 10: Market Place | <table border="1"> <tr> <td>Location 10: Market Place – east / west signal controlled crossing. Signal controlled crossing would be removed and replaced with an uncontrolled crossing</td> <td>The removal of the signal-controlled crossing would make it harder for vulnerable groups to cross the road affecting their access to the community facilities identified above.</td> <td>The effect on journey severance is a change in significant Chapter traveller</td> </tr> </table> | Location 10: Market Place – east / west signal controlled crossing. Signal controlled crossing would be removed and replaced with an uncontrolled crossing | The removal of the signal-controlled crossing would make it harder for vulnerable groups to cross the road affecting their access to the community facilities identified above. | The effect on journey severance is a change in significant Chapter traveller | Remove row from table. |
| Location 10: Market Place – east / west signal controlled crossing. Signal controlled crossing would be removed and replaced with an uncontrolled crossing | The removal of the signal-controlled crossing would make it harder for vulnerable groups to cross the road affecting their access to the community facilities identified above. | The effect on journey severance is a change in significant Chapter traveller | | | | |
| 608 | Table 14.16: Summary of significance of effects following mitigation – permanent effects: Category: Community severance, Location 10 | <table border="1"> <tr> <td>Location 10: Market Place east / west signalled controlled crossing</td> <td>Adverse sign change from 15 Effects or</td> </tr> </table> | Location 10: Market Place east / west signalled controlled crossing | Adverse sign change from 15 Effects or | Remove row from table. | |
| Location 10: Market Place east / west signalled controlled crossing | Adverse sign change from 15 Effects or | | | | | |
| 609 | 15.1.4 | Provisions for NMUs as part of the operational scheme include new combined footway and cycleway facilities, pedestrian, cycle and disabled user bridges at Porter Street and Princes Quay, signalised crossings at Mytongate Junction and a reconfigured ramp from the A63 to High Street. | Provisions for NMUs as part of the operational scheme include new combined footway and cycleway facilities to the north of the A63 and along Blackfriargate, improving the footway to the south of the A63, pedestrian, cycle and disabled user bridges at Porter Street and Princes Quay, signalised crossings at Mytongate Junction and a reconfigured ramp from the A63 to High Street. | | | |
| 609 | 15.1.5 | Effects on NMUs and views from the road are also considered to be slight adverse during operation and slight beneficial for driver stress. | Effects on views from the road are also considered to be slight adverse during operation and slight beneficial for driver stress, whilst effects on NMUs would be neutral on balance. | | | |
| 631 | 15.7.4 | To the east of Mytongate Junction, existing signalised crossings close to Humber Dock Street and at Market Place would be maintained until phase 3, whilst improvements would be made to High Street for NMUs (as detailed in 15.6.8 below) during phase 0. | To the east of Mytongate Junction, existing signalised crossings across the A63 close to Humber Dock Street and at Market Place would be maintained until phase 3, whilst improvements would be made to High Street for NMUs (as detailed in 15.6.8 below) during phase 0. | | | |
| 632 | 15.7.4 | A free 'shuttle bus' service would also be provided during construction, and this would pick up and drop off NMUs at | A free 'shuttle bus' service would also be provided if feasible during construction, and this would pick up and drop off NMUs | | | |

| Page | Paragraph/ Table | Published text | Correction |
|------|------------------|--|---|
| | | predetermined locations either side of the A63 and would also include wheelchair access facilities. | at predetermined locations either side of the A63 and would also include wheelchair access facilities. |
| 632 | 15.7.6 | <p>A combined footway and cycleway would be provided on both sides of the A63, along its length. This is shown on Volume 2, Figure 15.2. The shared facility would generally be 3m wide, however there are some locations where space is restricted and the width would be reduced to a minimum of 2m as follows:</p> <ul style="list-style-type: none"> between Castle Buildings and Princes Quay car park on the north side of the A63 for approximately 55m in front of Warehouse No. 6 (Ask restaurant) on the north side of the A63 for approximately 25m in front of Humber Dock Marina, Holiday Inn and Trinity Burial Ground on the south side of the A63 for approximately 400m adjacent to Kingston Retail Park and in front of Arco on the south side of the A63 for approximately 450m | <p>A combined footway and cycleway would be provided to the north of the A63 and along Blackfriargate, whilst the footway to the south of the A63 would be improved. This is shown on Volume 2, Figure 15.2. The shared facility would generally be 3m wide, however there are some locations where space is restricted and the width would be reduced to a minimum of 2m as follows:</p> <ul style="list-style-type: none"> in front of Castle Buildings for approximately 25m from Castle Buildings east to the rear of Princes Quay car park for approximately 122m from Castle Buildings west to the end of the Earl de Grey public house for approximately 55m |
| 633 | 15.7.8 | <p><u>The existing signalised pedestrian crossings at Market Place would be removed and pedestrians and cyclists would use a ramp from the A63 to access High Street to take them under the A63. The ramp would be realigned and the visibility for NMUs would be further improved by removing existing dense vegetation. On the south side of the A63, pedestrians and cyclists would be routed along Blackfriargate. This would also be improved for NMUs with a new combined footway and cycleway with vegetation clearance to improve visibility. Users would re-join the A63 either via Queen Street or by continuing along Blanket Row and Humber Dock Street.</u></p> | <p><u>The existing signalised pedestrian crossings at Market Place would be retained to allow for east/west movements but would be moved very slightly to the north on the eastbound slip to Market Place. The signalised crossing across the A63 for north/south movements at Market Place would be removed and instead, pedestrians and cyclists would use a ramp from the A63 to access High Street to take them under the A63. The ramp would be realigned and the visibility for NMUs would be further improved by removing existing dense vegetation. On the south side of the A63, pedestrians and cyclists would be routed along Blackfriargate. This would also be improved for NMUs with a new combined footway and cycleway with vegetation clearance to improve visibility. Pedestrian users would re-join the A63 either via the retained Queen Street signalised crossing. Cyclists would travel along the existing Blanket Row and Humber Dock Street or could travel further west by taking a route along the existing High</u></p> |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| | | | <u>Street, Queen Street, Wellington Street (existing cycle route) and Manor House Street.</u> |
| 633 | 15.7.9 | <u>It would also be possible for NMUs to cross other side roads, as is the case at present. With the exception of Mytongate Junction, crossings of side roads would be uncontrolled. Casual crossing of the A63 by NMUs would be prevented by a barrier within the central reservation and provision of pedestrian guard rail in footways or nearside verges at high-risk locations</u> | <u>It would also be possible for NMUs to cross other side roads, as is the case at present. With the exception of Mytongate Junction, Market Place and Queen Street, crossings of side roads would be uncontrolled. Casual crossing of the A63 by NMUs would be prevented by a barrier within the central reservation and provision of pedestrian guard rail in footways or nearside verges at high-risk locations</u> |
| 634 | Table 15.9: Construction – views from the road assessment : Location Hessle Road (A63 between St James Street and the Mytongate Junction, including the Junction/Commentary | Travelling east, there would be direct views of construction. This would include views of works to create footways and cycleways on either side of the Scheme as well as soft landscaping. | Travelling east, there would be direct views of construction. This would include views of works to create shared footways and cycleways to the north of the Scheme and along Blackfriargate to the south of the A63 as well as soft landscaping. |
| 642 | <u>Table 15.10: Construction stage impacts for motorised users (drivers stress): Market Place/Frustration</u> | <u>The majority of the works at Market Place would be completed during phases 1 and 3 of the construction period. Market Place would remain open for the duration of the construction period. During this period, additional driver frustration would be expected for vehicle travellers using this junction, due to the presence of traffic management and likely congestion. This would reduce to pre-construction levels for the remainder of the construction period, when works would be concentrated on the A63.</u> | <u>The majority of the works at Market Place would be completed during phases 1 and 3 of the construction period. Market Place would remain open for the duration of the construction period. During this period, additional driver frustration would be expected for vehicle travellers using this junction, due to the presence of traffic management and likely congestion. This would reduce to pre-construction levels for the remainder of the construction period, when works would be concentrated on the A63. The change in speed limit at Market Place would slightly increase frustration for motorised until they familiarise themselves with this permanent change.</u> |
| 642 | <u>Table 15.10:</u> | <u>The existing NMU crossing points would be removed during phase 1 of</u> | <u>The existing NMU crossing points from east to west across Market Place would</u> |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| | <u>Construction stage impacts for motorised users (drivers stress): Market Place/Fear of potential accidents</u> | <u>construction. This may result on a low level increase in fear of potential accidents until motorists and NMUs become accustomed to the new crossing.</u> | <u>be retained however the crossing over the A63 would be removed and there may be some temporary diversions put in place alongside the A63 during construction, which may result in a low level increase in fear of potential accidents until motorists and NMUs become accustomed to the change in conditions. The change in speed limit would reduce adverse effects for NMUs and motorists and this would become the permanent solution.</u> |
| 643 | <u>Table 15.10: Construction stage impacts for motorised users (drivers stress): Queen Street/Frustration</u> | <u>Queen Street would remain open for the duration of the construction period, although traffic management would be in place during phase 1 to enable the amendments to pedestrian crossings and slip-roads in this location. During this period, driver frustration would be expected for vehicle travellers, due to the presence of traffic management and likely congestion. For the remainder of construction, traffic management would be in place due to ongoing construction on the main A63 carriageway, which would result in reduced levels of driver frustration.</u> | <u>Queen Street would remain open for the duration of the construction period, although traffic management would be in place during phase 1 to enable the amendments to pedestrian crossings and slip-roads in this location. During this period, driver frustration would be expected for vehicle travellers, due to the presence of traffic management and likely congestion. For the remainder of construction, traffic management would be in place due to ongoing construction on the main A63 carriageway, which would result in reduced levels of driver frustration. The change in speed limit at Queen Street would slightly increase frustration for motorises until they familiarise themselves with this permanent change.</u> |
| 643 | <u>Table 15.10: Construction stage impacts for motorised users (drivers stress): Queen Street/Fear of potential accidents</u> | <u>The existing NMU crossing points would be removed during phase 1 of construction. This may result in a low-level increase in fear of potential accidents until motorists and NMUs become accustomed to the new crossing.</u> | <u>The existing NMU crossing points from east to west across Queen Street would be retained, however the crossing over the A63 would be removed and there may be some temporary diversions put in place alongside the A63 during construction, which may result in a low level increase in fear of potential accidents until motorists and NMUs become accustomed to the change in conditions. The change in speed limit would reduce adverse effects for NMUs and motorists and this would become the permanent solution.</u> |
| 645 | 15.8.8 | Mitigation such as the provision of a free 'shuttle bus' and signed diversion routes would minimise effects for NMUs. | Mitigation such as the provision of a free 'shuttle bus' if feasible and signed diversion routes would minimise effects for NMUs. |
| 645 | <u>Table 15.11: Construction stage</u> | <u>During construction, temporary diversions are likely to be required whilst works are undertaken to upgrade the footway to a combined</u> | <u>During construction, temporary diversions are likely to be required whilst works are undertaken to upgrade the footway to a combined footpath/cycleway to the north</u> |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| | (temporary) effects for the main NMU journeys: Location 1/Comment ary | footpath/cycleway, which would result in a significant effect due to journey time increases and also a reduction in journey experience/amenity due to the presence of construction plant and construction noise/dust for the full duration of construction. | of the A63 and to realign or improve the footway to the south of the A63, which would result in a significant effect due to journey time increases and also a reduction in journey experience/amenity due to the presence of construction plant and construction noise/dust for the full duration of construction. |
| 646 | Table 15.11: Construction stage (temporary) effects for the main NMU journeys: Location 3/Comment ary | During construction, temporary diversions are likely to be required whilst works are undertaken to upgrade the footway to a combined footpath/cycleway. | During construction, temporary diversions are likely to be required whilst works are undertaken to upgrade the footway on the north side of the A63 to a combined footpath/cycleway and to realign or improve the footway to the south of the A63. |
| 647 | Table 15.11: Construction stage (temporary) effects for the main NMU journeys: Location 8/Comment ary | The crossing adjacent to Humber Dock Street is anticipated to remain open for the first 2 phases of construction, which would ensure that journey times are unaffected. During phase 3 the signal controlled crossings at Humber Dock Street and Market Place are anticipated to be closed, and NMUs diverted towards the underpass at High Street, which would result in a temporary significant effect due to journey time increases. | The crossing adjacent to Humber Dock Street is anticipated to remain open for the first 2 phases of construction, which would ensure that journey times are unaffected. During phase 3 the signal controlled crossings at Humber Dock Street and Market Place across the A63 are anticipated to be closed, and NMUs diverted towards the underpass at High Street, which would result in a temporary significant effect due to journey time increases. |
| 647 | Table 15.11: Construction stage (temporary) effects for the main NMU journeys: Location 10/Commentary | During the first two phases on construction, access across the Market Place junction for NMUs would be maintained by use of the existing pedestrian crossing. Works to upgrade the High Street underpass, with the provision of a new NMU access route linking the Market Place junction with the High Street underpass, would be undertaken during this period. Once these upgrades are in place, the signalised crossing over Market Place would be closed. For NMUs, the change during construction would be adverse not significant at worst for the first 3 months. For the rest of the construction period, the arrangement would be the permanent solution, and the effects upon NMUs are therefore considered within the operational assessment. | Access across the Market Place junction for NMUs would be maintained by use of the existing pedestrian crossing for the majority of construction. Some short diversions do have the potential to be required for a temporary period as the signalised crossing on the eastbound slip to Market Place would be moved very slightly, which could result in some minor journey length and time increases. |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|--|--|
| 647 | Table 15.11: Construction stage (temporary) effects for the main NMU journeys: Location 11/Commentary | <u>As with the Market Place crossing, during the first two phases on construction, access across the Queen Street junction is anticipated to be maintained by use of the existing pedestrian crossing. Once upgrades to the High Street, as well as the provision of a new combined footway/cycleway along Blackfriargate are in place, the signalised crossing over Queen Street would be closed. The change during construction would be adverse not significant at worst for the first three months. For the rest of the construction period, the arrangement would be the permanent solution.</u> | <u>As with the Market Place crossing, access across the Queen Street junction is anticipated to be maintained for the majority of construction. Some short diversions do have the potential to be required for a temporary period which could result in some minor journey length and time increases</u> |
| 648 | Table 15.11: Construction stage (temporary) effects for the main NMU journeys: Location 17/Commentary | Upgrades to the existing footway the A63 to provide a continuous combined footway cycleway would be the permanent solution and is therefore considered within the operational stage assessment. | Upgrades to the existing footway along the south of the A63 would be the permanent solution and is therefore considered within the operational stage assessment. |
| 655 | 15.8.24 | <u>To the south and west of the A63 Castle Street, driver stress would be moderate with or without the Scheme. This is with the exception of Daltry Street, where in part driver stress would be high with or without the Scheme, and also for Commercial Road where driver stress is predicted to be high with the Scheme for a portion of the road, but moderate without the Scheme. In addition, there would be a slight increase in traffic flows for roads to the southern extents of the Scheme, with the Scheme in place and also a decrease in average speeds during peak times, along roads including Daltry Street, Commercial Road, High Street, Kingston Street and Queen Street, which would cause an increase in driver frustration. Conversely, there would also be traffic flow decreases and also average speed increases with the Scheme in place along Jackson Street, English Street and Neptune Street and Daltry Street, which would see an improvement in driver frustration.</u> | <u>To the south and west of the A63 Castle Street, driver stress would be moderate with or without the Scheme. This is with the exception of Daltry Street, where in part driver stress would be high with or without the Scheme, and also for Commercial Road where driver stress is predicted to be high with the Scheme for a portion of the road, but moderate without the Scheme. In addition, there would be a slight increase in traffic flows for roads to the southern extents of the Scheme, with the Scheme in place and also a decrease in average speeds during peak times, along roads including Daltry Street, Commercial Road, High Street, Kingston Street and Queen Street, which would cause an increase in driver frustration. The permanent change in speed limit along Queen Street would result in a slight increase in driver frustration for motorists, but equally would reduce the fear of potential accidents for motorists and NMUs with a slight improvement in safety. Conversely, there would also be traffic flow decreases and</u> |

| Page | Paragraph/ Table | Published text | Correction |
|------|--|--|--|
| | | | <u>also average speed increases with the Scheme in place along Jackson Street, English Street and Neptune Street and Daltry Street, which would see an improvement in driver frustration.</u> |
| 655 | 15.8.25 | <u>To the north of the A63 Castle Street, driver stress experienced by vehicle travellers would again largely be moderate with or without the Scheme, although driver stress would be high along Anlaby Road and Rawling Way. Driver stress is predicted to increase from moderate to high along Market Place due to flow increases and average speed decreases during peak hours. This could be due to the Dagger Lane, Fish Street and Vicar Lane/A63 connections being stopped up with the Scheme in place, diverting a greater proportion of traffic along Market Place. Driver stress would decrease along these roads with the Scheme in place with traffic no longer using these roads from the A63. A decrease in driver frustration is predicted along Anlaby Road, Rawling Way, Walker Street, Porter Street and Osborne Street.</u> | <u>To the north of the A63 Castle Street, driver stress experienced by vehicle travellers would again largely be moderate with or without the Scheme, although driver stress would be high along Anlaby Road and Rawling Way. Driver stress is predicted to increase from moderate to high along Market Place due to flow increases and average speed decreases during peak hours. This could be due to the Dagger Lane, Fish Street and Vicar Lane/A63 connections being stopped up with the Scheme in place, diverting a greater proportion of traffic along Market Place. The permanent change in speed limit at Market Place would result in a slight increase in driver frustration for motorists, but equally would reduce the fear of potential accidents for motorists and NMUs with a slight improvement in safety. Driver stress would decrease along these roads with the Scheme in place with traffic no longer using these roads from the A63. A decrease in driver frustration is predicted along Anlaby Road, Rawling Way, Walker Street, Porter Street and Osborne Street.</u> |
| 657 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 1/Comment ary | The provision of a combined footway and cycleway for the full length of the Scheme to the north of the A63, and footway to the south, would be considered beneficial for NMUs, as the new pavement has potential to improve journey quality. | The provision of a combined footway and cycleway for the full length of the Scheme to the north of the A63, along Blackfriargate to the south and improved footway to the south of the A63, would be considered beneficial for NMUs, as the new pavement has potential to improve journey quality. |
| 660 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 10/Change in facilities | <u>Signal controlled crossing would be removed and replaced with an uncontrolled crossing.</u> | <u>Signal controlled crossing would be retained for east/west movements.</u> |
| 660 | Table 15.13: | <u>The removal of the controlled crossings for east/west movement on Market</u> | <u>The retention of the controlled crossings for east/west movement on Market Place</u> |

| Page | Paragraph/ Table | Published text | Correction |
|------|--|---|---|
| | Permanent impacts of the Scheme on NMUs: Location 10/Commentary | Place would result in a degradation of the existing facilities, leading to an adverse impact for all NMUs and a Significant reduction in amenity. NMUs would be forced to wait for a break in traffic flows from vehicles passing on and off the A63 to Market Place, where increases are predicted for traffic travelling northbound along Market Place. This places NMUs in greater direct conflict with vehicle traffic, which would be substantially worse for vulnerable users such as the visually impaired and those with mobility constraints. However, the design of the slip roads (including sight lines) in this location, coupled with the predicted traffic flow changes have been thoroughly assessed from a road safety perspective, and it has been confirmed that removing the crossing at this location would not result in an increased safety risk for NMUs. As a result, whilst adverse impacts are predicted due to the loss of the facility and increased inconvenience for NMUs, the change with the Scheme in place is considered to be acceptable from a safety perspective. | would ensure no changes in journey length and no degradation in facilities. There is potential for traffic flow increases for northbound traffic along Market Place which could result in adverse impacts on NMU amenity, however the permanent change in speed limit would result in beneficial impacts on amenity. On balance a neutral effect is predicted at this location for NMUs. |
| 661 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 11/Change in facilities | Signal controlled crossing would be removed and replaced with an uncontrolled crossing. | Signal controlled crossing would be retained for east/west movements. |
| 661 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 11/Commentary | The removal of the controlled crossing for east/west movement on Queen Street and replacement with an uncontrolled crossing would result in a degradation of the existing NMU facilities and a Significant reduction in amenity for NMUs. Following completion of works NMUs would be required to cross two single carriageway roads, with increases in traffic traveling westbound on to the A63 from Queen Street. | The retention of the controlled crossings for east/west movement on Queen Street would ensure no changes in journey length and no degradation in facilities. There is potential for traffic flow increases for northbound traffic along Market Place which could result in adverse impacts on NMU amenity, however the permanent change in speed limit would result in beneficial impacts on amenity. On balance a neutral effect is predicted at this location for NMUs. |
| 661 | Table 15.13: Permanent | Adverse significant | Neutral |

| Page | Paragraph/ Table | Published text | Correction |
|------|--|---|---|
| | impacts of the Scheme on NMUs: Location 11/Impact | | |
| 662 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 17/Change in facilities | Vehicular access stopped up. NMU access maintained. With the combined footway and cycleway to the south of the A63. | Vehicular access stopped up. NMU access maintained with the footway to the south of the A63. |
| 662 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 17/Commentary | The removal of vehicle access at this location, whilst maintaining access for NMUs for the Holiday Inn, would be of benefit for NMUs by removing the potential for conflict with vehicular traffic, and subsequently improving amenity through the continuation of the combined footway and cycleway. | The removal of vehicle access at this location, whilst maintaining access for NMUs for the Holiday Inn, would be of benefit for NMUs by removing the potential for conflict with vehicular traffic, and subsequently improving amenity through the continuation of the footway. |
| 663 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 19/Change in facilities | No access between the A63 and Humber Dock Street. Combined cycleway and footway provided along the A63 (3m wide here). Ramped access to Princes Quay Bridge also provided in this location. | No access between the A63 and Humber Dock Street. Footway provided along the A63 (3m wide here). Ramped access to Princes Quay Bridge also provided in this location. |
| 663 | Table 15.13: Permanent impacts of the Scheme on NMUs: Location 19/Commentary | The combined footway and cycleway along the A63 would be continued in this location. | The footway along the A63 would be continued in this location. |
| 667 | 15.8.35 | The Market Place crossing would be closed for NMUs with the implementation of the Scheme. | The Market Place crossing of the A63 would be removed for NMUs with the implementation of the Scheme, although the signalised crossing for east/west movements would be retained here and also at Queen Street. |
| 669 | 15.9.7 | Once the Scheme is operational, some adverse effects would be experienced | Once the Scheme is operational, some adverse effects would be experienced for |

| Page | Paragraph/ Table | Published text | Correction |
|------|--|--|---|
| | | <p><u>for NMUs due to the changes to amenity and increase in journey length. The removal of at grade crossings and their replacement with pedestrian, cycle and disabled user bridges would have the benefit of separating NMUs from vehicle traffic. However, this would increase journey length and inconvenience some NMUs, particularly those with mobility constraints. However, adverse effects would be partially offset through the provision of upgraded facilities such as the combined footway and cycleway on either side of the A63, new signal controlled crossings at Ferensway and Commercial Road, and the removal of vehicle traffic from some routes. These measures would be of benefit to NMUs making journeys within the study area. The overall effects are considered to be adverse at worst, and not significant.</u></p> | <p><u>NMUs due to some changes in amenity as a result of traffic flow changes and increases in journey length and times. The removal of at grade crossings and their replacement with pedestrian, cycle and disabled user bridges would have the benefit of separating NMUs from vehicle traffic which would improve amenity for some users. However, this would increase journey length and inconvenience some NMUs, particularly those with mobility constraints. However, adverse effects would be offset through the provision of upgraded facilities such as the combined footway and cycleway to the north side of the A63 and along Blackfriargate, new signal controlled crossings at Ferensway and Commercial Road, and the removal of vehicle traffic from some routes. These measures would be of benefit to NMUs making journeys within the study area, improving safety for example. The overall effects on NMUs are considered to be neutral and not significant.</u></p> |
| 684 | Table 16.7 Significance of combined effects | n/a | Replace Table 16.7 with revised Table 16.7 below as discussed in comments on WQ1.10.10. (new/revised text in red). |

ES Table 10.9: Characterisation process of ecological impacts (revised)

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|---|--|----------------------------|---|--|
| Humber Estuary Value: International Conservation of Habitats and Species Regulations 2017 | Potential impacts from piling into Humber Dock Marina during construction of Princes Quay footbridge would include noise, vibration, dust, sedimentation, groundwater contamination and silting. Potential air quality impact small % of NOx increase on existing amounts. Potential death, injury or disturbance to marine fauna during construction of Princes Quay footbridge. | Potential discharge of pollution from A63 to enter the Estuary through drainage system. Unknown impact on tidal mud and shales. (Drainage design has since changed and surface water will be entering the existing Yorkshire Water system). Potential pollution impacts during operation from spillages in underpass due to higher drainage area. Potential air quality impact small % of NOx increase on existing amounts. | SI: -ve | Drainage design would ensure that adequate surface water interceptors are incorporated. Surface water would discharge onto existing rock armour in the Estuary. Trained marine fauna ecologists would act as observers to check that the dock area and up to 500m beyond the dock gates is clear of marine animals. The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary. A soft start-up of machinery to disperse any potential fish, birds or mammals present in the dock. Impacts from piling fully assessed in AIES. Temporary protection during construction detailed in CEMP. | Risk of accidental indirect impact. Small and unlikely to be Significant (Design must ensure no residual impact) Scheme certain to be insignificant in terms of air quality Noise levels in parts of the site during operation would reduce. Water quality would not be significantly impacted during operation. Probable. Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation. |
| | | | PO: unlikely | | |
| | | | CO: indirect | | |
| | | | EC: small | | |
| | | | SZ: not assessed | | |
| | | | RE: not assessed | | |
| | | | DU: Permanent | | |
| | | | TF: N/A | | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|--|---|--|--|--|
| | | | | <p>Current amounts of NOx already exceed environmental standards. Very small negligible increase.</p> <p>Water quality would not be impacted by operational discharges and spillages as underpass drainage system would incorporate a shut-off valve and below-ground attenuation units to allow isolation and containment of contaminants.</p> | |
| <p>Trinity Burial Ground SNCI Value: County/Unitary Authority Area</p> <p>Hull City Council designation</p> | <p>Permanent loss of 36 veteran mature trees (additional 36 to facilitate disinterment) and woodland understorey.</p> <p>Lighting of SNCI during construction at night and light pollution from new Junction during operation.</p> | <p>Light pollution from new Junction during operation.</p> | <p>SI: -ve</p> <p>PO: certain</p> <p>CO: direct</p> <p>EC: large 0.7ha</p> <p>SZ: complete loss</p> <p>RE: not reversible</p> <p>DU: permanent</p> <p>TF: avoid breeding bird season</p> | <p>Root protection zones on remaining trees.</p> <p>Compensation includes replanting 55 larger native trees (>30cm diameter) close to Trinity Burial Ground. The understorey in the remaining area of Trinity Burial Ground is to include some native shrubs and plants.</p> <p>Lighting during construction to directed away from remaining trees.</p> | <p>Certain permanent loss of large area of habitat and mature trees. Significant.</p> <p>Certain significant permanent extra light pollution during operation.</p> |
| River Hull SNCI | | | <p>SI: -ve</p> <p>PO: unlikely</p> | | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|---|---|--|--|--|
| <p>Mudflats to the south of Sammy's Point SNCI</p> <p>Value: County/Unitary Authority Area</p> <p>Hull City Council designation</p> | <p>Indirect impacts from pollution during construction.</p> | | CO: indirect | <p>Mitigation by standard pollution prevention measures.</p> | <p>Unlikely, very small indirect pollution incident during construction. Not significant. No impacts expected during operation.</p> |
| | | | EC: v small | | |
| | | | SZ: not assessed | | |
| | | | RE: not assessed | | |
| | | | DU: Permanent | | |
| TF: N/A | | | | | |
| <p>UKBAP (NERC Act 2006 S41) Priority Habitats – Value: National</p> <p>'deciduous woodland' and broad-leaved woodland' – Trinity Burial Ground SNCI.</p> <p>'mudflats', 'saltmarsh', 'intertidal substrate foreshore –</p> | <p>Trinity Burial Ground as in SNCI above.</p> <p>Indirect and direct impacts from pollution spillages during construction.</p> | | Based on highest impacts which are to woodland habitats SI: -ve | <p>'deciduous woodland' and broad-leaved woodland' – mitigation and compensation as in Trinity Burial Ground SNCI above.</p> <p>'mudflats', 'saltmarsh', 'intertidal substrate foreshore – mud – Mitigation by standard pollution prevention measures.</p> | <p>Certain, permanent loss of large area of habitat and mature trees. Significant. Operational impacts from lighting pollution.</p> <p>Unlikely, very small indirect pollution incident in Construction Phase only. Not significant.</p> |
| | | | PO: certain | | |
| | | | CO: direct | | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|--|--|---|
| <p>mud' Princes Dock; Humber Dock basin; Adjacent to site compounds at Neptune Street, Wellington Street Island Wharf and Livingstone Road.</p> <p>'Intertidal substrate foreshore – man made – Humber Dock Marina; Princes Dock.</p> <p>Section 41 of the NERC Act 2006</p> | <p>Humber Dock Marina would be directly impacted by piling to create supports for the deck that would carry the proposed Princes Quay footbridge (noise, vibrations, and disturbance of sediments).</p> <p>Impacts from the moving of Spurn Lightship could include additional disturbance of sediments.</p> | | <p>EC: large 0.7ha</p> <p>SZ: complete loss</p> <p>RE: not reversible</p> <p>DU: permanent</p> <p>TF: avoid breeding bird season</p> | <p>No mitigation for habitats within Humber Dock Marina.</p> <p>The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary.</p> | <p>Certain, direct, temporary, large, reversible impacts of noise, vibration and sediment disturbance. Significant.</p> <p>No adverse impacts during operation expected and no residual impacts</p> <p>Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation.</p> |
| <p>Scattered Amenity Trees</p> <p>Value: Local – main site</p> <p>Hull City Council Local Biodiversity Action Plan</p> | <p>245 amenity trees (outside of Trinity Burial Ground) are to be removed to accommodate the Scheme.</p> | | <p>SI: -ve</p> <p>PO: certain</p> <p>CO: direct</p> <p>EC: not assessed</p> <p>SZ: loss</p> <p>RE: reversible</p> <p>DU: temporary</p> <p>TF: avoid breeding bird season</p> | <p>Compensation by 307 x native tree planting incorporated into landscape plan. Trees to be managed.</p> | <p>Certain, direct loss of the majority of trees within the Scheme Site. Would take time for compensation to replace maturity of trees lost. Significant.</p> <p>No significant operational impacts.</p> <p>Residual impacts – no loss of trees overall, slight gain.</p> |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|----------------------------|---|---|
| <p>Standing Water</p> <p>Value: Regional – Humber Dock Marina; Railway Dock</p> <p>‘regularly occurring populations of species which may be considered at an International level’ (IAN 130/10)</p> | <p>Humber Dock Marina would be directly impacted by piling to create supports for the deck that would carry the proposed new Princes Quay Bridge (noise, vibrations, and disturbance of sediments).</p> <p>Impacts from moving of Spurn Lightship could include additional disturbance of sediments.</p> <p>Impacts from indirect pollution during construction.</p> | | SI: -ve | <p>No mitigation for habitats within Humber Dock Marina or Railway Dock during piling.</p> <p>The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary.</p> <p>All docks - Mitigation by standard pollution prevention measures.</p> | <p>Certain, direct, temporary disturbance to standing water habitat of Humber Dock Marina. Significant.</p> <p>Both docks - Unlikely, very small indirect pollution incident.</p> <p>No impacts during operation.</p> <p>No residual impacts.</p> <p>Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation.</p> |
| | | | PO: certain | | |
| | | | CO: direct | | |
| | | | EC: not assessed | | |
| | | | SZ: disturbance | | |
| | | | RE: reversible | | |
| | | | DU: temporary | | |
| TF: N/A | | | | | |
| <p>Ephemeral/short Perennial</p> <p>Value: Local - site compounds at Wellington Street Island Wharf, Livingstone Road and Neptune Street</p> | <p>Impacts from loss of vegetation during site clearance.</p> | | SI: -ve | <p>Small area of habitat to be left in each site compound. Compounds to be left to regenerate after use.</p> | <p>Certain, direct, temporary loss of habitat which would regenerate quickly.</p> <p>No impacts during operation or residual impacts. Not significant.</p> |
| | | | PO: certain | | |
| | | | CO: direct | | |
| | | | EC: 100% | | |
| | | | SZ: complete loss | | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|---|---|---|--|---|
| Section 41 of the NERC Act 2006 Hull City Council Local Biodiversity Action Plan | | | RE: reversible DU: temporary TF: avoid breeding bird season | | |
| Hedgerows Value: Local - site compounds at Livingstone Road, A63 eastbound recovery base and Staples site; car park site at the Myton Centre. Section 41 of the NERC Act 2006 | Loss of 5 x species-poor intact hedgerows, four of which are not connected to the wider surrounds or act as a green corridor. One is (A63 eastbound recovery base) connected to the wider area as it runs alongside the verge of the A63. | | SI: -ve PO: certain CO: direct EC: 100% SZ: loss RE: reversible DU: temporary TF: avoid breeding bird season | The species-poor hedgerows present in site compound – Myton Centre is approximately 45m in length and is to be compensated with 104m length of hedgerow containing species of native hedgerow woody plants . This would be managed during operation. The hedgerow in site compound – Livingstone Road, the one in Staples site and the one in site compound – A63 eastbound recovery base are to be re-instated only. | Temporary, certain loss of habitats that would benefit over time in Operation Phase from compensatory measures and management. Not significant. |
| Terrestrial Invertebrates | Woodland in Trinity Burial Ground has potential to support UKBAP and Hull | | SI: -ve PO: certain CO: direct | Woodland in Trinity Burial Ground – mitigation and | Certain, permanent loss of large area of habitat and mature trees. Significant. |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|--|---|---|---|---|
| <p>Value: Local - Trinity Burial Ground SNCI; site compounds at Wellington Street Island Wharf, Livingstone Road and Neptune Street</p> <p>Section 41 of the NERC Act 2006 Hull City Council Local Biodiversity Action Plan</p> | <p>BAP species. Habitat to be lost.</p> <p>Ephemeral/short perennial habitat in other two compounds has potential to support UKBAP and Hull BAP species. Habitat to be lost.</p> | | <p>EC: 0.7ha of woodland; 100% of ephemeral/short perennial</p> <p>SZ: All animals in these areas</p> <p>RE: Not reversible (woodland) reversible (ephemeral/short perennial)</p> <p>DU: Temporary</p> <p>TF: N/A</p> | <p>compensation as in Trinity Burial Ground SNCI above.</p> <p>Small area of ephemeral/short perennial habitat to be left in each site compound. Compounds to be left to regenerate after use.</p> | <p>Less habitat during operation.</p> <p>Certain, direct, temporary loss of habitat which would regenerate quickly. No impacts during operation. Not significant.</p> |
| <p>Aquatic Invertebrates</p> <p>Value: National – Humber Estuary SSSI</p> <p>The Wildlife and Countryside Act 1981 as amended (primarily by the Countryside and Rights of Way Act 2000)</p> <p>Value: Local – River Hull SNCI; Mudflats</p> | <p>Potential impacts from pollution events during construction (death or injury), disturbance from piling to install Princes Quay Bridge including noise, vibration, disturbance of sediments.</p> <p>Potential impacts (death or injury) from pollution</p> | | <p>SI: -ve</p> <p>PO: Unlikely</p> <p>CO: indirect</p> <p>EC: not assessed</p> <p>SZ: not assessed</p> <p>RE: reversible</p> | <p>The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary.</p> <p>A soft start-up of machinery to disperse any potential animals present in the dock.</p> <p>Full assessment of impacts is to be undertaken in the AIES.</p> | <p>Unlikely, indirect, temporary impacts from piling and pollution events.</p> <p>No impacts during operation. Not significant.</p> |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|---|---|--|--|--|
| to the south of Sammy's Point SNCI Section 41 of the NERC Act 2006 | events during construction. | | DU: temporary TF: N/A | Mitigation by standard pollution prevention measures. | |
| Fish (Sea and river lamprey) Value: International - Humber Dock Marina; Railway Dock; site compounds at Neptune Street, Wellington Street Island Wharf and Livingstone Road; Conservation of Habitats and Species Regulations 2017 Fish (European eel, salmon, sea trout) Value: Local - Humber Dock Marina; Railway Dock; site compounds at Neptune Street, | Direct impacts (injury, death or injury) to fish are likely during the piling works to construct Princes Quay Bridge. Indirect disturbance impacts from noise, vibration and sediment disturbance. Impacts (death, injury) from indirect pollution during construction. | | SI: -ve PO: probable CO: direct EC: not assessed SZ: disturbance RE: reversible | Trained marine fauna ecologists would act as observers to check that the dock area and up to 500m beyond the dock gates is clear of marine animals. The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary. A soft start-up of machinery to disperse any potential fish, birds or mammals present in the dock. Full assessment of impacts undertaken in the AIES. Mitigation by standard pollution prevention measures. | Probable direct and indirect impacts during piling. Temporary and reversible. No impacts during operation. Not significant. Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation. |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|---|--|--|
| Wellington Street Island Wharf and Livingstone Road Section 41 of the NERC Act 2006 Eels (England and Wales) Regulations 2009 | | | DU: temporary TF: N/A | | |
| Reptiles Value: Local - site compound at the A63 eastbound recovery base The Wildlife and Countryside Act 1981 as amended | Impacts from loss and severance of habitats. Potential killing or injury during site clearance. | | SI: -ve PO: probable CO: direct EC: 0.3ha in A63 Eastbound layby SZ: loss of habitat RE: reversible DU: temporary TF: avoid site clearance in hibernation season | Ecological Clerk of Works (ECoW) being present prior to vegetation clearance to search the area where vegetation is to be removed first. Habitats to be reinstated. | Certain temporary loss of habitat that would be reinstated with no operational or residual impacts. Not significant. |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|--|--|--|---|---|
| <p>Birds</p> <p>Value: International - site compounds at Neptune Street, Wellington Street Island Wharf and Livingstone Road</p> <p>Conservation of Habitats and Species Regulations 2017</p> <p>Wildlife and Countryside Act 1981 (as amended)</p> <p>Value: Local - Main site; Trinity Burial Ground SNCI; site compounds at land south east of Mytongate Junction, A63 eastbound recovery base, Arco site and Staples site; car park site at the Myton Centre</p> <p>Section 41 of the NERC Act 2006</p> | <p>International - In all three site compounds, bird species the Humber Estuary was designated for were observed either adjacent to the site compounds in the mudflats or flying over the site compounds. Impacts to these bird species are likely to be from pollution or noise, vibration and sight disturbance during construction.</p> <p>Local – loss of breeding habitat. Lighting of Trinity Burial Ground SNCI during construction at night.</p> | <p>Light pollution from new Junction during operation due to lack of trees.</p> <p>Lighting of Trinity Burial Ground SNCI during operation at night.</p> | <p>SI: -ve</p> <p>PO: probable</p> <p>CO: indirect</p> <p>EC: not assessed</p> | <p>The erection of hoardings to block the works in the site compounds from view and reduce noise emissions.</p> <p>Monitoring bird surveys are to be carried out at the site compounds during construction in order to record the species of birds present and the effects of any noise or sight pollution upon them. If it is found that the noise and sight levels are impacting the wading bird population, then changes can be put into place to make these levels acceptable.</p> <p>At site compound – Wellington Street Island Wharf, trained marine fauna ecologists would act as observers to check that the dock area and up to 500m beyond the dock gates is clear of marine birds.</p> <p>The dock gates would be closed during piling to control</p> | <p>International – probable, temporary indirect impacts during construction with no impacts during operation or residual impacts expected. Not significant.</p> <p>Local – Certain permanent loss of habitat in Trinity Burial Ground. Impacts from light pollution during operation. Significant.</p> <p>Temporary, certain loss of habitat in other site compounds that would be reinstated with no operational impacts. No impacts from light pollution during operation or residual impacts. Not significant.</p> <p>Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation.</p> |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|---|---|-----------------------------|
| Hull City Council Local Biodiversity Action Plan | | | SZ: disturbance, loss of habitat | and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary. A soft start-up of machinery to disperse any potential birds present in the dock. | |
| | | | RE: Not reversible (Trinity Burial Ground) reversible (all other sites) | Full assessment of impacts is to be undertaken in the AIES. Mitigation by standard pollution prevention measures to remove habitat outside of breeding season. | |
| | | | DU: permanent (Trinity Burial Ground) temporary (all other sites) | Habitats to be re-instated with the exception of Trinity Burial Ground. Lighting to be directed away from remaining trees during construction. | |
| | | | TF: avoid site clearance in breeding season | Mitigation planting would replace some lost habitat. Habitat enhancement would improve bird nesting and feeding opportunities. | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|---|---|---|---|--|---|
| <p>Aquatic mammals</p> <p>Value: International - Humber Dock Marina; Railway Dock; site compounds at Neptune Street, Wellington Street Island Wharf and Livingstone Road</p> <p>Conservation of Habitats and Species Regulations 2017. Wildlife and Countryside Act 1981 (as amended)</p> | <p>Grey seals may venture onto the site and fall in trenches causing injury or death. They could be disturbed by the lighting during construction.</p> <p>Disturbance during construction of Princes Quay Bridge from noise, vibration and sediment disturbance.</p> <p>Impacts from indirect pollution and lighting during construction.</p> | | <p>SI: -ve</p> <p>PO: unlikely</p> <p>CO: indirect</p> <p>EC: not assessed</p> <p>SZ: disturbance</p> <p>RE: reversible</p> | <p>Mitigation should include that trenches should be covered at night to prevent grey seal from falling in, or trenches should include an earth ramp to allow them to climb out. At night in the three site compounds, lighting should be directed away from the water. Mitigation for the construction of the Princes Quay footbridge includes:</p> <p>Trained marine fauna ecologists would act as observers to check that the dock area and up to 500m beyond the dock gates is clear of marine animals.</p> <p>The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary.</p> <p>A soft start-up of machinery to disperse any potential animals present in the dock.</p> | <p>Unlikely, indirect impacts during piling and construction works. Temporary and reversible.</p> <p>No impacts during operation or residual impacts. Not significant</p> <p>Impacts to the Humber Estuary designated sites has been concluded as not significant in the HRA Screening Report for Princes Quay currently undergoing consultation.</p> |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|---|---|--|---|--|
| | | | DU: temporary TF: N/A | Full assessment of impacts is to be undertaken in the AIES. Mitigation by standard pollution prevention measures. Lighting not directed on water during operation. | |
| Bats Pipistrelle bats Value: Local – All areas Conservation of Habitats and Species Regulations 2017. Wildlife and Countryside Act 1981 (as amended) | Loss of potential roosts within trees and old wall in Trinity Burial Ground. Small possibility of unidentified roost presence in trees in Trinity Burial Ground SNCI when felling. Loss of foraging area for a small number of pipistrelle bats in Trinity Burial Ground and severance of commuting route to it | Light pollution from new Junction during operation due to lack of trees. | SI: -ve PO: certain CO: direct | Precautionary avoidance measures are to include that demolition of trees in Trinity Burial Ground SNCI would be overseen by a bat licensed ECoW. Trees would be felled sectionally and sections searched by ECoW or left overnight for bats to exit before removal from site. Compensation includes the erection of bat boxes on the remaining trees in Trinity Burial Ground SNCI. | Certain, direct, permanent loss of historic roost, potential tree roosts to be compensated for. Certain, direct, permanent loss of foraging and commuting habitat would be partially replaced over time as it matures. Certain, permanent extra light pollution during operation. Significant. |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|----------|--|---|---|---|-----------------------------|
| | <p>across Mytongate Junction.</p> <p>Lighting of Trinity Burial Ground SNCI during construction at night</p> | | <p>EC: 1 disused roost, 0.7ha foraging habitat lost for small number of bats</p> <p>SZ: disturbance</p> <p>RE: not reversible</p> <p>DU: permanent</p> <p>TF: outside of sensitive periods for bats</p> | <p>Compensation includes that the larger native trees are to be replanted on the verges at either side of the A63 in a line extending from Trinity Burial Ground to the Myton Centre. The large height of the trees would provide habitat 'hop-overs' for bats and reduce collisions with traffic. The larger trees would also be planted in the soft estate in the new Mytongate Junction. This should recreate the linear commuting route to Trinity Burial Ground.</p> <p>Lighting to be directed away from remaining trees during construction.</p> <p>During operation, mitigation would be to use covers to direct lighting where it is needed at the ground and not directly light up linear features.</p> | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|----------------------------|---|--|
| <p>Otters</p> <p>Value – Local - Humber Dock Marina; Railway Dock; site compounds at Neptune Street, Wellington Street Island Wharf and Livingstone Road</p> <p>Conservation of Habitats and Species Regulations 2017.</p> <p>Wildlife and Countryside Act 1981 (as amended)</p> | <p>Otters may venture onto the site and fall in trenches.</p> <p>Disturbance during construction of Princes Quay Bridge from noise, vibration and sediment disturbance.</p> <p>Impacts from indirect pollution and lighting during construction.</p> | | SI: -ve | Mitigation would include that trenches are to be covered at night to prevent otter from falling in, or trenches are to include an earth ramp to allow otter to climb out. | <p>Unlikely, direct and indirect impacts during piling and construction works.</p> <p>Temporary and reversible.</p> <p>No impacts during operation or residual impacts. Not significant.</p> |
| | | | PO: unlikely | At night in the three site compounds, lighting should be directed away from the water. Mitigation for the construction of the Princes Quay Bridge includes: | |
| | | | CO: indirect | Trained marine fauna ecologists would act as observers to check that the dock area and up to 500m beyond the dock gates is clear of marine animals. | |
| | | | EC: not assessed | The dock gates would be closed during piling to control and contain silt and sediment and absorb noise and vibration from entering the Humber Estuary. | |
| | | | SZ: disturbance | A soft start-up of machinery to disperse any potential animals present in the dock. | |
| | | | RE: reversible | | |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|--|--|--|
| | | | DU: temporary TF: N/A | Full assessment of impacts is to be undertaken in the AIES. Mitigation by standard pollution prevention measures. Lighting not directed on water during operation. | |
| Hedgehogs Value: Local – Terrestrial areas Section 41 of the NERC Act 2006 | Woodland to be permanently lost in Trinity Burial Ground SNCI has potential to support hedgehogs. Habitats elsewhere to be temporarily lost. Impacts to individuals during vegetation clearance. | | SI: -ve PO: probable CO: direct EC: 0.7ha of Trinity Burial Ground, not assessed rest of site SZ: disturbance, loss of habitat RE: not reversible DU: permanent TF: N/A | Ecological Clerk of Works (ECoW) being present prior to vegetation clearance to search the area where vegetation is to be removed first. Habitats to be re-instated with the exception of Trinity Burial Ground SNCI. | Certain, temporary loss of habitat that would be re-instated with no operational or residual impacts with the exception of permanent loss of part of Trinity Burial Ground. Potentially significant. |
| Invasive species | Legal impact of allowing these species to spread. | | SI: N/A | Cotoneaster plants are to be removed and the arisings | Probable, direct legal impact of spreading these species to |

| Resource | Proposed activity, biophysical change, related to receptor structure and function (impact) during construction | Proposed activity, biophysical change, related to receptor structure and function (impact) during operation | Characterisation of impact | Mitigation proposals | Summary of characterisation |
|--|--|---|---|---|---|
| Schedule 9 of the Wildlife and Countryside Act 1981 (as amended) cotoneaster (main site – A63 and Market Place Junction and A63 and Queen Street Junction); land south east of Mytongate Junction | | | PO: probable CO: direct EC: not assessed SZ: not assessed RE: reversible DU: temporary TF: legal constraint | and topsoil in these areas to be treated as controlled waste. To be disposed of at a suitably licensed or permitted disposal facility. Biosecurity method statements for both species. The site is to be maintained during the Operation Phase and it is unlikely that the cotoneaster or false acacia would return after removal in the Construction Phase. Should this happen, it would be removed during maintenance. | be mitigated fully and no spread is predicted. Not significant. |
| <p>Key</p> <p>SI (Sign): Positive (beneficial (+ve)) or Negative (adverse (-ve))</p> <p>PO (Probability of Occurring): Certain, Probable, Unlikely</p> <p>CO (Complexity): Direct, Indirect, Cumulative</p> <p>EC (Extent): Area measures and percentage of total (e.g. area of habitat/territory lost)</p> <p>SZ (Size): Description of level of severity of influence (e.g. complete loss, number of animals affected)</p> <p>RE (Reversibility): Reversible or Not Reversible (can the effect be reversed, whether or not this is planned)</p> <p>DU (Duration): Permanent (P) or Temporary (T) in ecological terms. Where differing timescales are determined in relation to the life cycle of the receptor, these should be defined.</p> <p>TF (Timing and frequency): Important seasonal and/or life cycle constraints and any relationship with frequency considered.</p> | | | | | |

ES Table 11.15: Significance of potential residual impacts on surface water features during construction (amend row)

| Potential impact | Feature | Attribute | Quality | Importance | Mitigation | Magnitude of impact | Significance |
|--|-------------------|--------------------|------------------------------|------------|---|--|--|
| Changes in flood flow routes due to alteration of ground elevations and construction of structures | Humber Floodplain | Conveyance of flow | Properties within floodplain | Very high | OEMP and Flood Emergency Plan (FEP) to include emergency procedures to evacuate Scheme in the event of extreme flooding. Temporary pumping arrangements within OEMP to discharge flood waters to sewer or surface waters subject to consent, only compliant water to be discharged to Humber Estuary, non-compliant water collected and discharged off site. | Moderate-Major beneficial to Major adverse – depending on the location, source and scale of the flooding in relation to the Scheme area. Refer to Error! Reference source not found, Table 11.18 and explanatory text for further details. | Large/ Very Large beneficial to Very Large adverse |

ES Table 11.18: Summary of magnitude of peak impact from selected sources and scenarios from the FRA (replaced)

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|--|--|--|
| Pluvial (VCB In) Figure 13.3 | A 1 in 100-year return period event with 30% increase in rainfall intensity for climate change impacts | No change in flood depths across Scheme and study area - neutral | No change in flood depths across Scheme and study area - neutral |
| Pluvial (VCB Out) Figure 13.73 | | No change in flood depths across Scheme and study area - neutral | No change in flood depths across Scheme and study area - neutral |
| Tidal – Humber Wave Overtopping (VCB In) Figure 13.18 | A 1 in 200-year return period event | Underpass – increase of maximum flood depth of up to 5.8m – major adverse | A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial |
| | | Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse | Commercial Road south of underpass and A63 carriageway east of underpass – reduction of maximum flood depths of up to 0.4m – major beneficial |
| | | Small areas of Kingston Retail Park – increase of maximum flood depth of up to 0.2m – major adverse | Myton Street and Osborne Street – reduction in maximum flood depth of up to 0.4m – major beneficial |
| | | Blanket Row, Blackfriargate, High Street and surrounding streets – increase of maximum flood depth of up to 0.1m – moderate adverse | Railway Dock – reduction in maximum flood depth of up to 0.10m – moderate beneficial |
| | | Finkle Street and Sewer Lane and surrounding streets north of the A63 – increase of maximum depth of up to 0.3m – major adverse | Edgar Street and Alfred Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial |
| | | Queens Gardens – increase in maximum depth of up to 0.4m – major adverse | |
| Tidal – Humber Wave Overtopping (VCB Out) | | Underpass – increase of maximum flood | A63 Castle Street east of Mytongate Junction – reduction |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|--------------------------------------|---|--|
| Figure 13.82 | | <p>depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse</p> <p>Small areas of Kingston Retail Park – increase of maximum flood depth of up to 0.2m – major adverse</p> <p>Blackfriargate, Blanket Row and surrounding streets – increase in maximum flood depth of up to 0.10m – moderate adverse</p> <p>Sewer Lane – increase in maximum flood depth of up to 0.20m – major adverse</p> <p>Market Place, Lowgate, Alfred Gelder Street and surrounding streets – increase in maximum flood depth of up to 0.10m – moderate adverse</p> <p>Posterngate – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>Princes Quay – increase in maximum flood depth of up to 0.10m – moderate adverse</p> <p>Queens Gardens – increase in maximum depth of up to 0.4m – major adverse</p> | <p>in maximum flood depth of >0.4m – major beneficial</p> <p>Commercial Road south of underpass and A63 carriageway east of underpass – reduction of maximum flood depths of up to 0.4m – major beneficial</p> <p>Myton Street and Osborne Street – reduction in maximum flood depth of up to 0.4m – major beneficial</p> <p>Railway Dock – reduction in maximum flood depth of up to 0.10m – moderate beneficial</p> <p>Edgar Street, English Street and Alfred Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| Tidal – Humber Wave Overtopping (VCB In) Figure 13.21 | A 1 in 1000-year return period event | Underpass – increase of maximum flood | A63 Castle Street east of Mytongate Junction – reduction |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|-----------------|----------|---|---|
| | | <p>depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse</p> <p>Kingston Retail Park and Waverley Street – increase of maximum flood depth of up to 0.3m – major adverse</p> <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Lister Street, English Street, Alfred Street and surrounding streets – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Jackson Street, Neptune Street, Daltry Street and Madeley Street – increase in maximum flood depth of up to 0.10m – moderate adverse</p> <p>Humber Dock Marina and Railway Dock Marina – increase in maximum flood depth of up to 0.10m – moderate adverse</p> <p>Blackfriargate and High Street surrounding streets – increase of maximum flood depth of up to 0.1m – moderate adverse</p> <p>Blanket Row, Finkle Street, Sewer Lane and Humber Street –</p> | <p>in maximum flood depth of >0.4m – major beneficial</p> <p>Princes Quay – reduction of maximum flood depths of greater than 0.4m – major beneficial</p> <p>A1079 Ferensway north of underpass – reduction of maximum flood depth of up to 0.66m – major beneficial</p> <p>A1079 Ferensway, A1105 Anlaby Road and surrounding streets to the west – reduction of maximum flood depths of up to 0.1m – moderate beneficial</p> <p>Myton Street, Osborne Street and surrounding streets – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Posterngate, Dagger Lane and Market Place – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Queens Gardens, and northern part of Market place – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|---|--|---|--|
| | | <p>increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Commercial Road, Kingston Street and Railway Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | |
| Tidal – Humber Wave Overtopping (VCB Out) Figure 13.84 | | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Lister Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Queens Gardens – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Blanket Row and Blackfriargate – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Humber Dock Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Myton Street, trundle Street and A1079 Ferensway north of Mytongate Junction – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Osborne Street, St Luke's Street, Carr Lane, A1106 Anlaby Road and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| Tidal – Humber Wave Overtopping (VCB In) Figure 13.24 | A 1 in 200-year return period event with consideration of climate change | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Osborne Street, Adelaide Street – reduction of maximum</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|----------|--|---|
| | | <p>of >0.5m – major adverse</p> <p>Kingston Retail Park and Waverley Street – increase of maximum flood depth of up to 0.1m – moderate adverse</p> <p>Humber Dock Marina – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Porter Street and Brisbane Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Kingston Street and surrounding streets – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Myton Street and Roper Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>flood depth of up to 0.1m – moderate beneficial</p> <p>A1079 Ferensway north of Mytongate Junction – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Princes Dock and Princes Dock Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Queen’s Gardens, Guildhall Road, Alfred Gelder Street and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| <p>Tidal – Humber Wave Overtopping (VCB Out) Figure 13.88</p> | | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>A1079 Ferensway north of Mytongate Junction, Adelaide Street and Osborne Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Princes Dock, princes Dock Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|--|---|--|
| | | <p>Myton Street and Roper Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Brisbane Street and Porter Street - increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Humber Dock Marina, Wellington Street and Railway Street - increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>Queen’s Gardens, Guildhall Road, Alfred Gelder Street, Lowgate and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| <p>Tidal – Humber Undefended (VCB In) Figure 13.33</p> | <p>A 1 in 200-year return period event (without existing flood defences)</p> | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Lister Street, English Street and Waverley Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Blanket Row, Blackfriargate, Humber Street, Finkle Street and Sewer Lane - increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Myton Street, Roper Street, Osborne Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>A1079 Ferensway, Carr Lane, West Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> <p>Princes Dock, Princes Dock Street, Posterngate, Market Place and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> <p>Dock Street, Baker Street and Francis Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|---|--|---|--|
| Tidal – Humber Undefended (VCB Out) Figure 13.91 | | Underpass – increase of maximum flood depth of up to 5.8m – major adverse Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse Kingston Retail Park – increase of maximum flood depth of up to 0.1m – moderate adverse | A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial Myton Street, Roper Street, Osborne Street – reduction in maximum flood depth of up to 0.3m – major beneficial A1079 Ferensway, Carr Lane, Upper Union Street and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial |
| Tidal – Humber Undefended (VCB In) Figure 13.36 | A 1 in 200-year return period event with consideration of climate change (without existing flood defences) | Underpass – increase of maximum flood depth of up to 5.8m – major adverse Westbound diverge slip road – increase of maximum flood depth of >0.5m – major adverse Kingston Retail Park – increase in maximum flood depth of up to 0.2m – major adverse Lister Street, English Street and Waverley Street – increase in maximum flood depth of up to 0.1m – moderate adverse Blanket Row, Blackfriargate, Humber Street, Finkle Street and Sewer Lane - increase in maximum flood depth of up to 0.1m – moderate adverse | A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial Myton Street, Roper Street, Osborne Street – reduction in maximum flood depth of up to 0.3m – major beneficial A1079 Ferensway, Carr Lane, West Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial Princes Dock, Princes Dock Street, Posterngate, Market Place and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial Dock Street, Baker Street and Norfolk Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial |
| Tidal – Humber Undefended (VCB Out) Figure 13.93 | | Underpass – increase of maximum flood depth of up to 5.8m – major adverse | A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|--|---|--|
| | | <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> <p>Kingston Retail Park – increase of maximum flood depth of up to 0.1m – moderate adverse</p> | <p>Myton Street, Roper Street, Osborne Street – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>A1079 Ferensway, Carr Lane, Upper Union Street, West Street and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| Tidal Humber Undefended (VCB In) Figure 13.69 | A 1 in 200-year return period event with consideration of extreme (H++) climate change (without existing flood defences) | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Lister Street, Waverley Street and English Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Blanket Row, Blackfriargate, Sewer Lane and Humber Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>A1079 Ferensway north of Mytongate Junction, Myton Street, Roper Street and surrounding streets – reduction in maximum flood depth of up to 0.2m – major beneficial</p> <p>A1079 Ferensway north to West Street, Carr Lane, Osborne Street, Upper Union Street and surrounding streets – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> <p>Princes Dock, Princes Dock Street, Posterngate, Market Place, Lowgate, Alfred Gelder Street and Dock Street – reduction in maximum flood depth of up to 0.1m – moderate beneficial</p> |
| Tidal from River Hull (VCB In) Figure 13.43 | A 1 in 200-year return period event (tidal barrier fails to close) | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Eastern and central Kingston Retail Park – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Railway Dock Marina and Humber Dock Marina –</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|----------|---|--|
| | | <p>Small areas of west of Kingston Retail Park – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>William Street and Porter Street – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Princes Dock – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>Blanket Row, Sewer Lane, Finkle Street and Humber Dock Street – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>Humber Street, Queen Street and surrounding streets – increase in maximum flood depth of up 0.1m – moderate adverse</p> <p>Posterngate, Market Place, Fish Street, Dagger Lane and Vicar Lane – increase in maximum flood depth of up 0.3m – major adverse</p> | <p>reduction in maximum flood depth of up to 0.2m – major beneficial</p> |
| <p>Tidal from River Hull (VCB Out) Figure 13.99</p> | | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> <p>Small areas of west of Kingston Retail Park – increase in maximum</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Myton Street, Osborne Street, St Luke's Street and surrounding streets – reduction in maximum flood depth of up to 0.4m – major beneficial</p> <p>Central and eastern Kingston Retail Park – reduction in</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|---|--|--|--|
| | | <p>flood depth of up to 0.3m – major adverse</p> <p>William Street and Porter Street – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Princes Dock – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Blanket Row, Humber Street, Queen Street and surrounding streets – increase in maximum flood depth up to 0.1m – moderate adverse</p> <p>Market Place, Vicar Lane, Fish Street and Dagger Lane – increase in maximum flood depth of up to 0.3m – major adverse</p> | <p>maximum flood depth of up to 0.3m – major beneficial</p> <p>Humber Dock Marina and Railway Dock Marina – reduction in maximum flood depth of up to 0.2m – major beneficial</p> |
| <p>Tidal from River Hull (VCB In) Figure 13.46</p> | <p>A 1 in 1000-year return period event (tidal barrier fails to close)</p> | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>Waverley Street – increase in maximum flood depth of up to 0.3m – major adverse</p> <p>Edgar Street, William Street and Porter Street – increase in maximum flood depth</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>A1079 Ferensway, Osborne Street, St Luke's Street and surrounding streets – decrease in maximum flood depth of up to >0.5m – major beneficial</p> <p>Porter Street, Waterhouse Lane, West Street, Prospect Street and surrounding streets – reduction in maximum flood depth of up to 0.3m – major beneficial</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|--|----------|---|---|
| | | <p>of up to 0.2m – major adverse</p> <p>Blanket Row, Queen Street, Nelson Street and surrounding streets – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Princes Dock and Princes Dock Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> | |
| <p>Tidal from River Hull (VCB Out) Figure 13.99</p> | | <p>Underpass – increase of maximum flood depth of up to 5.8m – major adverse</p> <p>Westbound diverge slip road – increase of maximum flood depth of up >0.5m – major adverse</p> <p>Kingston Retail Park – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Waverley Street – increase in maximum flood depth of up to 0.4m – major adverse</p> <p>Lister Street, Edgar Street and William Street – increase in maximum flood depth of up to 0.2m – major adverse</p> <p>Porter Street – increase in maximum flood depth of up to 0.1m – moderate adverse</p> <p>Princes Dock and Princes Dock Street –</p> | <p>A63 Castle Street east of Mytongate Junction – reduction in maximum flood depth of >0.4m – major beneficial</p> <p>Humber Dock Marina and Railway Dock Marina – decrease of maximum flood depth of up to 0.3m – major beneficial</p> <p>Osborne Street, St Luke’s Street, Myton Street – reduction in maximum flood depth of greater than 0.4m – major beneficial</p> <p>Waterhouse Lane, Porter Street and A1079 Ferensway – reduction in maximum flood depth of up to 0.3m – major beneficial</p> <p>Margaret Moxon Way, West Street, North Street and Wright Street – reduction in maximum flood depth of up to 0.2m – major beneficial</p> |

| Flooding source | Scenario | Areas of adverse impact \ magnitude | Areas of beneficial impact \ magnitude |
|---|--|---|--|
| | | <p>increase of maximum flood depth of up to 0.1m – moderate adverse</p> <p>Blanket Row, Sewer Lane, Finkle Street, Fish Street, Dagger Land and Vicar Lane – increase of maximum flood depth of up to 0.1m – moderate adverse</p> | |
| <p>Combined fluvial and tidal from River Hull Figure 14.53</p> | <p>A 1 in 200-year return period event (tidal barrier fails to close)</p> | <p>No change in flood depths across Scheme and study area - neutral</p> | <p>No change in flood depths across Scheme and study area - neutral</p> |
| <p>Combined fluvial and tidal from River Hull Figure 14.56</p> | <p>A 1 in 1000-year return period event (tidal barrier fails to close)</p> | <p>No change in flood depths across Scheme and study area - neutral</p> | <p>No change in flood depths across Scheme and study area - neutral</p> |

ES Table 11.20: Significance of potential residual impacts on surface water features during operation (amend row)

| Potential impact | Feature | Attribute | Quality | Importance | Mitigation | Magnitude of impact | Significance |
|--|-------------------|--------------------|----------------------------------|------------|--|---|---|
| Alteration of flood flow routes due to the changes in ground levels and construction of structures | Humber floodplain | Conveyance of flow | Properties within the floodplain | Very high | Underpass drainage designed for 1 in 100-year, plus 30% allowance for climate change, rainfall event. Emergency procedures in case of pump failure or extreme flooding event including no/minimal warnings in the event of a flood defence breach (Flood Emergency and Evacuation Plan (FEEP)). | <p>Ranges from Moderate Major beneficial to Major adverse depending on the location, source and extent of flooding and return period of event. Further detail is provided in Error! <u>Reference source not found, Table 11.18.</u></p> | Very Large adverse to Large/Very Large beneficial |



ES Table 16.7: Significance of combined effects (revised)

| Receptor | Cultural features | | Residential property | | Community amenities and business | |
|--|---|------------------|---|---|---|---|
| | Construction | Operation | Construction | Operation | Construction | Operation |
| Air quality | - | - | Not significant adverse | Not significant adverse | Not significant adverse | Not significant adverse |
| Noise and vibration | Negligible increase | Not significant | Significant adverse | Significant adverse to significant beneficial | Minor increase | Not significant |
| Cultural heritage | Large adverse | Large adverse | - | - | Large adverse | Large adverse |
| Landscape | Large adverse landscape | Large adverse | Moderate adverse landscape | Significant adverse and beneficial visual | Large adverse landscape | Large adverse |
| Ecology and nature conservation | Large adverse | Large adverse | - | - | Large adverse | Large adverse |
| Road drainage and the water environment | - | - | Very large beneficial to very large adverse | Very large beneficial to very large adverse | Very large beneficial to very large adverse | Very large beneficial to very large adverse |
| Geology and soils | No significant adverse or beneficial residual effects | | | | | |
| Materials | No significant adverse or beneficial residual effects | | | | | |
| People and communities | Moderate adverse | Moderate adverse | - | - | Moderate adverse | Moderate adverse |
| Effects on all travellers | No significant adverse or beneficial residual effects | | | | | |
| Overall Significance of Combined Effects | Moderate adverse | | | | | |

3 6.2 Environmental Statement Volume 2 Figures 2.5.4 & 2.5.6 (APP-025)

3.1.1 Replace ES Volume 2 Figure 2.5.4 The Scheme Proposals – Sheet 3 of 6 and Figure 2.5.6 The Scheme Proposals – Sheet 5 of 6 (APP-025) with the new Figures 2.5.4 and 2.5.6 below. Changes are as follows:

- Locations of the combined footpath & cycleway have been clarified.
- Signalised crossings as Market Place and Queen Street are to be retained.



Key to symbols


- Permanent land take
- Temporary land take
- Preferred main compound at Arco (Option A)
- Alternative main compound at Staples (Option B)
- Ward boundary

| Rev | Date | Amendment Details | Drawn | Checked | App'd |
|-----|------------|---------------------------------------|-------|---------|-------|
| P04 | 10/07/2019 | Combined Footpath/Cycleway Amendments | WF | AS | AS |
| P03 | 10/09/2018 | Boundary Amendments | WF | AS | AS |
| P02 | 31/07/2018 | Key Changes | WF | AS | AS |
| P01 | 26/03/2018 | Boundary Amendments | WF | AS | AS |

| | | | | | |
|-----------------------------|--|--|--|--|--|
| Mott MacDonald Sweco | | | | | |
| | | | | | |

| | | | | |
|--------------------------------------|--|--------|-----------|----|
| Drawing Status | | SHARED | Authority | S4 |
| Project Title | | | | |
| A63 CASTLE STREET IMPROVEMENTS, HULL | | | | |

| | | | | | | | | | |
|---|----------------------|----------|------------|----------|------------|---------|------------|----------|------------|
| Drawing Title | | | | | | | | | |
| VOLUME 2 FIGURE 2.5.4 THE SCHEME PROPOSALS - SHEET 3 OF 6 | | | | | | | | | |
| Scale | 1:5,000 | Designed | ED | Drawn | WF | Checked | ED | Approved | PB |
| Original By | AD | Date | 10/07/2019 | Date | 10/07/2019 | Date | 10/07/2019 | Date | 10/07/2019 |
| Drawing Number | 514508 - MMSJV - EGN | | | Revision | 514508 | | Revision | | |
| Location | SO - DR - LE | | | Number | 000021 | | Number | | |
| | | | | | P04 | | | | |



Key to symbols

- Permanent land take
- Temporary land take
- Preferred main compound at Arco (Option A)
- Alternative main compound at Staples (Option B)
- Ward boundary

| PO5 | 26/09/2018 | Signalised crossings at Market Place/Queen Street | WF | AS | AS |
|-----|------------|---|-------|---------|-------|
| PO4 | 10/07/2018 | Combined Footpath/Cycleway Amendments | WF | AS | AS |
| PO3 | 10/09/2018 | Boundary Amendments | WF | AS | AS |
| PO2 | 31/07/2018 | Key Changes | WF | AS | AS |
| PO1 | 26/03/2018 | Boundary Amendments | WF | AS | AS |
| Rev | Date | Amendment Details | Drawn | Checked | App'd |

Mott MacDonald Sweco


Client: **MacDonald Sweco**

Drawing Title: **A63 CASTLE STREET IMPROVEMENTS, HULL**

Volume: **VOLUME 2 FIGURE 2.5.6 THE SCHEME PROPOSALS - SHEET 5 OF 6**

| Rev | 1:5,000 | Original Date | Design | Check | Draw | Check | Draw | Check | Draw |
|-----|---------|---------------|--------|-------|------|-------|------|-------|------|
| AS | AS | 26/09/2018 | WF | ED | WF | ED | WF | ED | WF |
| AS | AS | 10/07/2018 | WF | ED | WF | ED | WF | ED | WF |

Drawing No: **514508 - MMSJV - EGN**
Project No: **514508**
Location: **SO - DR - LE** - 000023
Number: **P05**



1 take
1 take
n compound at Arco (Option
n compound at Staples (Option B)

| | | | |
|------------------------------|-------|---------|-------|
| Footpath/Cycleway Amendments | WF | AS | AS |
| Amendments | WF | AS | AS |
| Signages | WF | AS | AS |
| Amendments | WF | AS | AS |
| Amendment Details | Drawn | Checked | App'd |

MacDonald Sweco

Client: **ghways england**

Drawing Title: **EET HULL**

Volume: **IE 2.5.6 PROPOSALS - SHEET 5 OF 6**

| Rev | 1:5,000 | Original Date | Design | Check | Draw | Check | Draw | Check | Draw |
|-----|---------|---------------|--------|-------|------|-------|------|-------|------|
| AS | AS | 10/07/2018 | WF | ED | WF | ED | WF | ED | WF |
| AS | AS | 10/07/2018 | WF | ED | WF | ED | WF | ED | WF |

Drawing No: **514508 - MMSJV - EGN**
Project No: **514508**
Location: **SO - DR - LE** - 000023
Number: **P04**

Field Code Changed

4 6.2 Environmental Statement Volume 2 Figure 10.2 (APP-036)

4.1.1 Replace ES Volume 2 Figure 10.2 Non-statutory designated sites (APP-036) with the new Figure 10.2 Non-statutory designated sites as below. Changes are as follows:


- The key has been replaced.
- Sammy's Point Site of Nature Conservation Interest (SNCI) has been added to Figure 10.2 as the mudflats are 250m from the Site boundary.


5 6.2 Environmental Statement Volume 2 Figure 15.2 (APP-040)

5.1.1 Replace ES Volume 2 Figure 15.2 Proposed non-motorised users facilities and closure for the Scheme (APP-040) with the revised Figure 15.2 as below.

Changes are as follows:

- Locations of the combined footpath & cycleway have been clarified.
- Signalised crossings at Market Place and Queen Street are to be retained.





Field Code Changed

6 6.7 Ecology and Nature Conservation Assessment (APP-065)

Table 6.1: Ecology and Nature Conservation Assessment

| Page | Paragraph/ Table | Published text | Correction | | | | |
|------|---|--|--|---|-------------------------|-----------------|--------------------------|
| 25 | Table 10.4 Non-statutory designated sites (row 13) | <table border="1"> <tr> <td>SNCI</td> <td>Fordgate stream cycle track - south of Chamberlain Road (177)</td> <td>No information provided</td> <td>1 dam northeast</td> </tr> </table> | SNCI | Fordgate stream cycle track - south of Chamberlain Road (177) | No information provided | 1 dam northeast | Remove row 13 from table |
| SNCI | Fordgate stream cycle track - south of Chamberlain Road (177) | No information provided | 1 dam northeast | | | | |
| 44 | Table 10.8 Summary of valuation of ecological receptors, Ecological receptor column (row 3) | Trinity Burial Ground SNCI, River Hull SNCI | Trinity Burial Ground SNCI, River Hull SNCI, Mudflats to the south of Sammy's Point SNCI | | | | |
| 49 | 10.7.17 | <u>River Hull SNCI</u> Direct impacts to the River Hull SNCI are unlikely. | <u>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</u> Direct impacts to the River Hull SNCI and Mudflats to the south of Sammy's Point SNCI are unlikely. | | | | |
| 56 | 10.7.54 | <u>River Hull SNCI</u> Road drainage would not discharge to the River Hull during the Operation Phase and there would therefore be no risks to water quality within the river. | <u>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</u> Road drainage would not discharge to the River Hull during the Operation Phase and would not impact upon the River Hull SNCI or Mudflats to the south of Sammy's Point SNCI. There would therefore be no risks to water quality within the river. | | | | |
| 60 | Table 10.9 Characterisation process of ecological impacts | n/a | Replace Table 10.9 with revised Table 10.9 (see above). Impacts are separated into a column for construction and a column for operation as requested in WQ1.2.6 (new/revised text in red). Replacement table also takes into account changes arising from mudflats to the south of Sammy's Point SNCI as requested in WQ1.2.2 (new/revised text in red). | | | | |
| 75 | 10.8.11 | <i>River Hull SNCI</i> Neutral residual impacts are predicted to the River Hull SNCI during the Construction Phase, following the implementation of pollution protection mitigation measures. | <i>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</i> Neutral residual impacts are predicted to the River Hull SNCI and Mudflats to the south of Sammy's Point SNCI during the Construction Phase, following the | | | | |

| Page | Paragraph/ Table | Published text | Correction |
|------|---|---|--|
| | | | implementation of pollution protection mitigation measures. |
| 78 | 10.8.31 | <i>River Hull SNCI</i> With no increase in noise or air pollution and no water discharges into this river, there is predicted to be neutral residual impacts to the SNCI during operation. | <i>River Hull SNCI and Mudflats to the south of Sammy's Point SNCI</i> With no increase in noise or air pollution and no water discharges into this river, there is predicted to be neutral residual impacts to these SNCIs during operation. |
| 83 | Table 10.10 Summary of ecological receptors, Ecological receptor column (row 4) | River Hull SNCI | River Hull SNCI and Mudflats to the south of Sammy's Point SNCI |
| 87 | Table 10.10 Summary of ecological receptors, Ecological receptor column (row 11) | Aquatic Invertebrates Humber Estuary SSSI River Hull SNCI | Aquatic Invertebrates Humber Estuary SSSI River Hull SNCI Mudflats to the south of Sammy's Point SNCI |

7 6.11 Register of Environmental Actions and Commitments (APP-068)

Table 7.1: Register of Environmental Actions and Commitments

| Page | Reference | Published text | Correction |
|-------|------------|---|--|
| 34 | E5 | Clearance of potential nesting habitat outside breeding season (in particular for bats and birds). | Clearance of potential bird nesting habitat to take place outside of the March – August (inclusive) breeding season. |
| 34 | E5 | n/a | Add new bullet: <ul style="list-style-type: none"> Felling of trees to be undertaken only in September/October and April to take account of the sensitive roosting periods for bats. |
| 41 | W13 | n/a | Add row W13 – see below for details |
| 50 | T3 | <ul style="list-style-type: none"> A free 'shuttle bus' service would also be provided during construction, and this would pick up and drop of NMUs at predetermined locations either side of the A63 and would also include wheelchair access facilities. | <ul style="list-style-type: none"> A free 'shuttle bus' service would also be provided if feasible during construction, and this would pick up and drop of NMUs at predetermined locations either side of the A63 and would also include wheelchair access facilities. |
| 50/51 | Footnote 1 | <ul style="list-style-type: none"> Archaeological Project Design Arboricultural Implications Assessment Arboricultural Method Statement; Landscape and Ecology Management Plan Handover Environmental Management Plan Marine Mammal Mitigation Plan Groundwater Monitoring Plan Erosion Prevention and Sediment Control Plan Noise and Vibration Management Plan Materials Management Plan Site Waste Management Plan Foundation Works Risk Assessment Materials Logistics Plan Community Relations Strategy Traffic and Transport Management Plan | <ul style="list-style-type: none"> Archaeological Project Design Arboricultural Implications Assessment Arboricultural Method Statement Landscape and Ecology Management Plan Handover Environmental Management Plan Marine Mammal Mitigation Plan Groundwater Monitoring Plan Flood Evacuation Plan Flood Emergency and Evacuation Plan Erosion Prevention and Sediment Control Plan Noise and Vibration Management Plan Materials Management Plan Site Waste Management Plan Foundation Works Risk Assessment Materials Logistics Plan Community Relations Strategy Traffic and Transport Management Plan |

Register of Environmental Actions and Commitments (REAC) (APP68) and Outline Environmental Management Plan (OEMP),
Annex B (APP-072) —Add new row W13

| Ref | ES ref. | DCO ref. | Works information ref. | Objective | Action (including any monitoring required) | Achievement criteria and reporting requirements (if applicable) | How the Action is to be implemented | Responsible Person (s) | When P = Pre-construction C = Construction O = Operation A = All | Completion record |
|---|---------|----------|------------------------|--|--|---|---|--------------------------|--|--|
| <u>Remove strikethrough text below in 'Action' column</u> | | | | | | | | | | |
| NV1 | CH7 | - | - | <u>The control of noise and vibration arising from the works and compounds to minimise disturbance in community.</u> | <ul style="list-style-type: none"> · <u>Best practicable means for the control of noise and vibration to applied as a matter of course and as described in Section 79(9) of the Environmental Protection Act 1990, to reduce noise to a minimum shall be employed at all times.</u> · <u>Procedures for noise control and the assessment of site noise shall be in accordance with BS 5228, Part 1:2009+A1:2014. Contractor requirements are set out in the Appendix 1/9 'Control of Noise and Vibration'.</u> · <u>Measures would be set out in the CEMP to control potential noise impacts from site traffic. This may include the following:</u> <ul style="list-style-type: none"> - <u>Vehicles should not wait or queue up with engines running on the site or on the public highway</u> - <u>Manage deliveries to prevent queuing of site traffic at access points and the need for vehicles to reverse</u> - <u>Use of adjustable or directional audible vehicle-reversing alarms or use of alternative warning systems, e.g. white noise alarms</u> · <u>Other, more specific forms of construction mitigation are as follows:</u> <ul style="list-style-type: none"> - <u>The A63 remains in use throughout the works in order that its capacity is maximised. Right hand turns at</u> | <p><u>Mitigation measures included in the CEMP</u></p> <p><u>Consultation with HCC Principal Environmental Health Officer with public relations managed throughout the Construction Phase.</u></p> <p><u>Noise insulation and temporary rehousing to be offered to those meeting the criteria set out in Annex E.4 of BS 5228 Part 1 2009+A1:2014</u></p> | <p><u>Contractual responsibilities between Highways England and the Principal Contractor.</u></p> <p><u>Local Authority</u></p> | <p><u>Contractor</u></p> | <p><u>C, O</u></p> | <p><u>Signature:</u></p> <p><u>Date:</u></p> |

| Ref | ES ref. | DCO ref. | Works information ref. | Objective | Action (including any monitoring required) | Achievement criteria and reporting requirements (if applicable) | How the Action is to be implemented | Responsible Person (s) | When P = Pre-construction C = Construction O = Operation A = All | Completion record |
|-----|---------|----------|------------------------|-----------|---|---|-------------------------------------|------------------------|--|-------------------|
| | | | | | <p><u>Mytongate Junction would be maintained throughout the works.</u></p> <ul style="list-style-type: none"> - <u>Temporary acoustic barrier fencing to be provided along the northern carriageway edge between the Myton Centre and William Booth House when construction activities are programmed to occur along in this section of the Scheme.</u> - <u>Monitoring of phases would be conducted in order to verify that noise levels associated with traffic flows during construction do not cause significant adverse effects at noise sensitive receptors.</u> - <u>Proactive communication with local residents, businesses and road users to address their concerns and opinions on the traffic management (TM) phasing.</u> - <u>Safe access and egress would be maintained to all businesses and residential properties. Emergency routes to be available throughout the Scheme construction programme of works at all times.</u> - <u>Every effort would be made to ensure that there are no late removals of the TM after overnight lane closures. The overnight closures required are discussed below.</u> - <u>A minimum of 2 weeks prior notice to be given to occupiers of affected properties via letter drop and press release.</u> - <u>Noise mitigation measures may include procurement of low noise plant options, time restrictions on certain noisy activities, temporary noise barriers and</u> | | | | | |

| Ref | ES ref. | DCO ref. | Works information ref. | Objective | Action (including any monitoring required) | Achievement criteria and reporting requirements (if applicable) | How the Action is to be implemented | Responsible Person (s) | When P = Pre-construction C = Construction O = Operation A = All | Completion record |
|---------------------------------------|---------|----------|------------------------|---|---|---|--|------------------------|--|-------------------------|
| | | | | | tool box briefings to operatives on quite working. | | | | | |
| Add new row W13 below | | | | | | | | | | |
| W13 | CH11 | | | To limit impacts of flooding on construction workers and the public | <ul style="list-style-type: none"> EA flood warning service to be subscribed to throughout construction. If flood alert or flood warning received, information to be shared with relevant personnel. Emergency procedures documented in the Flood Emergency and Evacuation Plan (FEEP) (ES Volume 3 Appendix 11.2 Appendix B) to be instigated for safe evacuation of the underpass and surrounding areas of the Scheme during operation. CEMP to include emergency procedures based on the FEEP to evacuate construction footprint in the event of extreme flooding. Procedures to account for all sources of flooding including tidal, pluvial and fluvial flooding. | Mitigation measures should be included in the CEMP | Contractual responsibilities between Highways England and the Principal Contractor | Contractor | C O | Signature: Date: |

8 7.1 Planning Statement (APP-070)

Table 8.1: Planning Statement

| Page | Paragraph/Table | Published text | Correction |
|------|-----------------|---|---|
| 27 | 4.4.5 | These include the combined footway and cycleway on either side of the A63, new signal controlled crossings at Ferensway and Commercial Road and the removal of vehicle traffic from some routes. | These include the combined footway and cycleway to the north of the A63, upgraded footway provision on the southern side of the A63, new signal controlled crossings at Ferensway and Commercial Road and the removal of vehicle traffic from some routes. |
| 46 | 6.1.6 | The Scheme will provide benefits to NMUs, creating a safer environment by separating NMUs from vehicle traffic and providing a combined footway and cycleway on either side of the A63, and a new signalised crossing at Mytongate Junction to improve access across the A63. | The Scheme will provide benefits to NMUs, creating a safer environment by separating NMUs from vehicle traffic and providing a combined footway and cycleway on the northern side of the A63, upgraded footway provision on the southern side of the A63, and a new signalised crossing at Mytongate Junction to improve access across the A63. |

9 7.3 Outline Environmental Management Plan (APP-072)

Table 9.1: Outline Environmental Management Plan

| Page | Table/Reference | Published text | Correction |
|-------|---|---|--|
| 16 | Table 4.1 Permits, consents and licences | Flood Risk Activity – Environment Agency Permit is required if work is carried out on or near a main river, on or near a flood defence structure, in a flood plain, or near a flood defence. | Permit is required for any regulated flood risk activities such as activity within 1km of sea defence structure. Remove row from table |
| 18 | Table 4.1 Permits, consents and licences | Listed Building Consent Planning (Listed Buildings and Conservation Areas) Act 1989 Secretary of State 3/4 consents required for Earl de Grey public house and Hamber Dock. 1/2 consents required for reworking equipment on Castle Buildings and Warehouse No. 6. | Earl de Grey public house – consent required in advance of dismantling. Hamber Dock – consent required for alteration of northern dock wall during construction of Prince Oahu Bridge. Hamber Dock – consent required for re-siting of the Span Lightship. Castle Buildings and Warehouse No. 6 – consent required for vibration monitoring equipment. Remove row from table |
| 18/19 | Table 4.1 Permits, consents and licences | Scheduled Monument Consent Ancient Monuments and Archaeological Areas Act 1979 Secretary of State 1 consent required for Eboracry Gate and archaeological remains only if service and utility diversions are within the boundary of the Scheduled Monument. Reviewing team – consent will be required in the event of any service and utility diversions excavations with the boundary of the Scheduled Monument. Remove row from table | Remove row from table |
| 34 | E5 | Clearance of potential nesting habitat outside breeding season (in particular for bats and birds). | Clearance of potential bird nesting habitat to take place outside of the March – August (inclusive) breeding season. |
| 34 | E5 | n/a | Add new bullet: · Felling of trees to be undertaken only in September/October and April to take account of the sensitive roosting periods for bats. |
| 41 | W13 | n/a | Add row W13 – see above for details |
| 50 | T3 | · A free ‘shuttle bus’ service would also be provided during construction, and this would pick up and drop of NMUs at predetermined locations either side of the A63 and would also include wheelchair access facilities. | · A free ‘shuttle bus’ service would also be provided if feasible during construction, and this would pick up and drop of NMUs at predetermined locations either side of the A63 and would also include wheelchair access facilities. |
| 50/51 | Footnote 1 | · Archaeological Project Design · Arbicultural Implications Assessment · Arbicultural Method Statement; · Landscape and Ecology Management Plan · Handover Environmental Management Plan · Marine Mammal Mitigation Plan · Groundwater Monitoring Plan · Erosion Prevention and Sediment Control Plan | · Archaeological Project Design; · Arbicultural Implications Assessment · Arbicultural Method Statement · Landscape and Ecology Management Plan · Handover Environmental Management Plan · Marine Mammal Mitigation Plan · Groundwater Monitoring Plan · Flood Evacuation Plan · Flood Emergency and Evacuation Plan |

| Page | Table/Reference | Published text | Correction |
|------|-----------------|---|---|
| | | <ul style="list-style-type: none"> · Noise and Vibration Management Plan · Materials Management Plan · Site Waste Management Plan · Foundation Works Risk Assessment · Materials Logistics Plan · Community Relations Strategy · Traffic and Transport Management Plan | <ul style="list-style-type: none"> · Erosion Prevention and Sediment Control Plan · Noise and Vibration Management Plan · Materials Management Plan · Site Waste Management Plan · Foundation Works Risk Assessment · Materials Logistics Plan · Community Relations Strategy · Traffic and Transport Management Plan |

10 7.4 Transport Assessment Report (APP-073)

Table 10.1: Transport Assessment Report

| Page | Paragraph/Table | Published text | Correction |
|------|-----------------|--|--|
| 47 | 6.1.2 | However, adverse effects would be partially offset through the provision of upgraded facilities such as the combined footway and cycleway on either side of the A63, a new grade separated crossing at Ferensway and Commercial Road, and the removal of vehicle traffic from some routes. | However, adverse effects would be partially offset through the provision of upgraded facilities such as the combined footway and cycleway to the north of the A63, upgraded footway provision on the southern side of the A63, a new grade separated crossing at Ferensway and Commercial Road, and the removal of vehicle traffic from some routes. |