

A303 Amesbury to Berwick Down

TR010025

Deadline 10 8.5(2) Statement of Common Ground – National Trust (TRACKED CHANGES)

APFP Regulation 5(2)(q)

Planning Act 2008

The Infrastructure Planning (Examination Procedure) Rules 2010

October 2019





Infrastructure Planning

Planning Act 2008

The Infrastructure Planning (Examination Procedure) Rules 2010

A303 Amesbury to Berwick Down

Development Consent Order 20[**]

STATEMENT OF COMMON GROUND – National Trust

Regulation Number:	Regulation 5(2)(q)
Planning Inspectorate Scheme	TR010025
Reference	
Application Document Reference	8.5(2)
Author:	A303 Amesbury to Berwick Down Project
	Team, Highways England and National Trust

Version	Date	Status of Version
Rev 0	03.05.2019	Deadline 2 Issue
Rev 1	09.08.2019	Deadline 7 Issue
Rev 2	02.10.2019	Deadline 10 Issue



STATEMENT OF COMMON GROUND

This Statement of Common Ground has been prepared and agreed by (1) Highways England Company Limited and (2) The National Trust for Places of Historic Interest or Natural Beauty.

Signed.....
[NAMEDerek Parody]

Project Manager Director

on behalf of Highways England Date: [DATE02 October 2019]

i sun a d

Signed.....

[NAMENick Simms]

[POSITIONProject Manager]

on behalf of The National Trust for Places of Historic Interest or Natural Beauty

Date: [DATE02 October 2019]



CONTENTS

1	Introduction	5
2	Record of Engagement	7
3	Matters Agreed	12
4	Matters Under Discussion	79
5	Matters Not Agreed	118



1 Introduction

1.1 Purpose of this document

- 1.1.1 This Statement of Common Ground ("SoCG") has been prepared in respect of the proposed A303 Amesbury to Berwick Down improvement project ("the Application") made by Highways England Company Limited ("Highways England") to the Secretary of State for Transport ("Secretary of State") for a Development Consent Order ("the Order") under section 37 of the Planning Act 2008 ("PA 2008").
- 1.1.2 The order, if granted would authorise Highways England to carry out the following works:
 - A northern bypass of Winterbourne Stoke with a viaduct over the River Till valley;
 - A new junction between the A303 and A360 to the west of and outside the WHS, replacing the existing Longbarrow roundabout;
 - A twin-bore tunnel approximately 2 miles (3.3km) long, past Stonehenge;
 and
 - A new junction between the A303 and A345 at the existing Countess roundabout.
- 1.1.3 This SoCG does not seek to replicate information which is available elsewhere within the Application documents. All documents are available at the deposit locations and/or the Planning Inspectorate website.
- 1.1.4 The SoCG has been produced to confirm to the Examining Authority where agreement has been reached between the parties to it, and where agreement has not (yet) been reached. SoCGs are an established means in the planning process of allowing all parties to identify and so focus on specific issues that may need to be addressed during the examination.

1.2 Parties to this Statement of Common Ground

- 1.2.1 This SoCG has been prepared by (1) Highways England as the Applicant and (2) The National Trust for Places of Historic Interest or Natural Beauty.
- 1.2.2 Highways England became the Government-owned Strategic Highways Company on 1 April 2015. It is the highway authority in England for the strategic road network and has the necessary powers and duties to operate, manage, maintain and enhance the network. Regulatory powers remain with the Secretary of State. The legislation establishing Highways England made provision for all legal rights and obligations of the Highways Agency to be conferred upon or assumed by Highways England.



- 1.2.3 As noted in the National Trust's Relevant Representation [RR-2344] at paragraph 1.1, the National Trust is Europe's largest conservation charity with more than five million members. Established over 125 years ago, its primary purpose is to promote the preservation of special places for the benefit of the nation. To achieve this aim, the National Trust owns and manages places of historic interest and natural beauty; it also has the ability to declare its land to be held inalienably. The National Trust is the largest private landowner in the UK and owns 850 hectares of the Stonehenge landscape within the World Heritage Site ("WHS"). This SoCG deals with issues that are relevant to the National Trust in its capacity as an affected landowner and in its capacity as a major conservation organisation.
- 1.2.4 Collectively Highways England and the National Trust are referred to as 'the parties'.

1.3 Terminology

- 1.3.1 In the tables in the Issues chapter of this SoCG "Not Agreed" indicates a final position and "Under discussion" indicates where these points will be the subject of on-going discussion between the parties with the aim, wherever possible, to resolve, or refine, the extent of disagreement between the parties. "Agreed" indicates where the issue has been resolved.
- 1.3.2 It can be taken that any matters not specifically referred to in the Issues chapter of this SoCG are not of material interest or relevance to the National Trust, and therefore have not been the subject of any discussions between the parties. As such, those matters can be read as agreed, only to the extent that they are either not of material interest or relevance to the National Trust.



2 Record of Engagement


2.1.1 A summary of the meetings and correspondence that has taken place between Highways England and the National Trust in relation to the Application is outlined in Table 2-1.

Table 2-1 Record of Engagement

Date	Form of correspondence	Key topics discussed and key outcomes (the topics should align with the Issues tables)
19/01/17	Consultation Response	January 2017 A303 Consultation Response
07/09/17	Preferred Route Announcement – Landowner Meeting	Meeting to discuss the preferred route to be taken forward by Highways England
15/11/17	Survey meeting	Meeting to discuss groundwater pumping surveys
30/11/17	Landowner Meeting	Reviewing the updated design in respect of the National Trust's land holdings. Provide details of any accommodation works for their tenant farmers and land take required on surface and for the tunnel
30/01/18	Landowner Meeting	Update on the consultation materials and plans for the public consultation
31/01/18	Statutory consultation general invite	Landowner Invitational Event
07/02/18	Statutory consultation section 42 notice	Section 42 consultation invite
20/03/18	S42 Notification	S42d extended consultation letter
28/03/18	S42 Notification	S42 Non-Statutory Undertaker
28/03/18	Land requirements meeting	Review plan showing proposed land requirements over National Trust land and discuss process for agreement
24/04/18	Consultation Response	2018 Consultation Response sent by Phillip Morris for The National Trust for Places of Historic Interest or Natural Beauty
11/06/18	Land requirements meeting	Discuss design progress following consultation and review updated plan/strategy



		details showing proposed land requirements
31/07/18	Land requirements meeting	Discuss outstanding concerns and understand strategy for inalienable land
18/10/18	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
26/10/18	Provision of link to DCO documents and confirmed land requirements	Provision of plan and table showing National Trust land requirements
03/12/18	S.56 notice	Service of notice under s.56
02/12/18	Meeting with National Trust and Heritage Monitoring & Advisory Group (HMAG) regarding tunnel restriction	Discuss land and restriction requirements and concerns
11/12/18	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
10/01/19	Provision of SoCG programme and plot details	Response to request for programme and plot areas
11/01/19	Relevant Representation received	National Trust provided copy of Relevant Representation [RR-2344] as provided to the Planning Inspectorate
15/02/19	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
01/03/19	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
11/04/19	Provision of draft tunnel restriction terms	Set out provisional terms of tunnel restriction for discussion
18/04/19	Key issues and concerns	Discuss key themes of outstanding concerns and identify strategy to resolve
07/05/19	Written Representation received	National Trust provided copy of Written Representation as provided to the Planning Inspectorate
05/06/19	Provision of link to Highways England responses to National Trust Written Representation [REP2-115]	Clarified position on Highways England's position on each of the points raised in National Trust's Written Representation
10/06/19	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
19/06/19	Access for West Amesbury and Park Farms	Discuss options and requirements for access over National Trust land





19/06/19	Land requirements and SoCG meeting	Discuss outstanding concerns and understand strategy for inalienable land
02/07/19	Tunnel restriction with HMAG and National Trust	Explanation of tunnel restriction details and agreement in principle on broad terms
16/07/19	Accommodation works meeting	Presentation of accommodation works proposals and understand outstanding concerns
17/07/19	Provision of draft updated Outline Environmental Management Plan ("OEMP") for discussion	Highways England provided a copy of the draft updated OEMP for review at meeting of 23/07/19
23/07/19	OEMP meeting	Discuss updated drafting of the OEMP
24/07/19	Draft SoCG	Provision of drafted SoCG
31/07/19	SoCG discussion	Identified matters agreed, not agreed and still outstanding for majority of issues
01/08/19	SoCG discussion	Discuss and understand matters agreed, not agreed and still outstanding
08/08/19	SoCG discussion and agreement for DL7	Discuss and understand matters agreed, not agreed and still outstanding
25/07/19	Draft restrictive covenant	Provision of draft restrictive covenant
31/07/19	Meeting	Discussion on outstanding issues
01/08/19	SoCG discussion	Discuss and understand matters agreed, not agreed and still outstanding
05/08/19	Updated SoCG	Provision of updated SoCG
07/08/19	Restrictive covenant information provided	Provision of further details relating to restriction, proposed consultation process and document deliverables tracker
07/08/19	Email summary of concerns	Receipt of details from National Trust on outstanding concerns
08/08/19	Accommodation works provided	Provision of updated accommodations works proposal
08/08/19	Meeting to discuss outstanding concerns	Discussion on outstanding issues
09/08/19	Updated SoCG provided	Provision of updated SoCG, receipt of National Trust



		comments and confirmation of SoCG to issue for DL7
13/08/19	Email summary of concerns	Receipt of details from National Trust on outstanding concerns
13/08/19	Email response to concerns	Provision of note on response to National Trust's points of 07/08/2019
14/08/19	SoCG meeting	Discussion on outstanding issues
15/08/19	Restrictive covenant - comments	Receipt of comments from National Trust on draft restrictive covenant wording
20/08/19	Discussions to seek to resolve objection and OEMP provided	Provision of proposals, requirement wording and OEMP for comment
23/08/19	Proposals provided	Provision of updated proposals
27/08/19	Comments on proposals to resolve objection	Receipt of comments on proposals
28/08/19	Restrictive covenant provided	Provision of updated restrictive covenant drafting incorporating National Trust comments
30/08/19	Restrictive covenant meeting	Discussion on restriction depth details and earthworks discussion
02/09/19	OEMP - comments	Receipt of comments from National Trust on updated OEMP
02/09/19	Comments on proposals to resolve objection	Receipt of comments from National Trust on proposals
05/09/19	SoCG meeting	Discuss and understand matters agreed, not agreed and still outstanding
06/09/19	Draft final SoCG	Provision of updated SoCG
11/09/19	OEMP/DAMS/agreement meeting	Discuss and understand outstanding points on the relevant documents
19/09/19	Meeting on proposals	Finalising drafting of proposals
23/09/19 – 27/09/19	OEMP/DAMS/proposals/ restrictive covenant discussions	Final negotiations and agreement of proposals to resolve objection, OEMP, DAMS and restrictive covenant. National Trust withdrew its objection to land acquisition
30/09/19	SoCG meeting	Discuss and understand matters agreed, not agreed and still outstanding. Provision of updated SoCG for review



02/10/19	Finalised SoCG	Confirmation and signing of
		SoCG

- 2.1.2 In addition to Table 2-1 above, the National Trust has also attended the following stakeholder A303 Amesbury to Berwick Down groups:
 - Stakeholder Strategy Board;
 - Heritage Monitoring & Advisory Group;
 - Scientific Committee;
 - UNESCO World Heritage Committee Engagement Group;
 - Environmental Group;
 - Communications Group;
 - Benefits Steering Group; and
 - Attendance at regular design progress reviews held by Highways England, to participate in discussion on matters of design with potential to impact on the Outstanding Universal Value ("OUV") of the WHS.
- 2.1.3 It is agreed that this is an accurate record of the key meetings and consultation undertaken between (1) Highways England and (2) The National Trust for Places of Historic Interest or Natural Beauty in relation to the issues addressed in this SoCG.



3 Matters Agreed

Table 3-1 Matters Agreed

Ref	Document Reference	Para Ref	Sub- section/ Discipline	National Trust Comment	Highways England Response	Status
3.1	[RR-2344]	2.1	Context	The Trust owns more than 800 ha of the Stonehenge part of the Stonehenge, Avebury and Associated Sites World Heritage Site (WHS), and we take our role as custodians very seriously. Currently, the busy A303 road cuts through the WHS, having a major adverse impact on its Outstanding Universal Value (OUV), and acting as a barrier to people and wildlife seeking to access and explore the landscape. In addition, the Trust is aware of the longstanding challenges of highway access to the South West via the A303 route corridor.	Noted.	Agreed
3.2	[RR-2344]	2.2	Context	The Trust therefore welcomed the announcement of the Government's intention to invest in a bored tunnel to remove a large part of the existing A303 from the Stonehenge landscape. We consider that – if well-designed and delivered with the utmost care for the surrounding archaeology and chalk grassland landscape – it could provide an overall benefit to the WHS. More specifically it could help to reunite the landscape, providing improvements to monument setting, tranquillity and access for both	Noted.	Agreed



				people and wildlife.		
3.3	[RR-2344]	3.1	Areas of interest	In responding to the proposed scheme, the Trust's key areas of interest are cultural heritage, landscape, ecology and public access. This applies to both the potential benefits and any adverse impacts, and to the design, mitigation, construction and the operational phase. In addition, we have an interest in related matters such as appearance, noise and vibration, artificial light, air quality, water quality, public amenity and implications for visitor experience and land management. Finally, we have an interest in the overall planning balance and in the draft DCO, including its Requirements, compliance and monitoring.	Noted.	Agreed
3.4	[RR-2344]	6.1 & 7.3	Land - Inalienability of land	The DCO includes the need for land that is owned by the Trust to be compulsorily acquired, and as such the Trust is considered an 'affected person'. In 1907 Parliament gave the Trust a power to declare land 'inalienable', and the Trust's land at the Stonehenge landscape is today held inalienably. In order to build the proposed scheme, Highways England would need to compulsorily acquire National Trust inalienable land. The Trust promises to look after its special places 'for ever, for everyone'.	Highways England understands that the land owned by the National Trust which it is proposing to compulsorily acquire pursuant to the DCO is held inalienably.	Agreed
3.5	[RR-2344]	7.1	Progress of scheme	The National Trust is a significant landowner at the Stonehenge landscape, and is an advocate of a solution for the A303 that would remove a large part of the existing A303 from the WHS, reuniting the	NotedHighways England has responded to the issues and concerns raised by the National Trust, and the parties are now in agreement on these matters, alongside the agreed drafting of the	Agreed



				landscape, whilst protecting the integrity of this special place. We welcome the progress made by Highways England to date. At present, based on our initial appraisal of the DCO documents, we have a range of issues and concerns that we intend to raise through the DCO process.	OEMP, DCO and DAMS. There has now been sufficient resolution of issues raised to enable the Trust to withdraw objection of compulsory acquisition of its land.	
3.6	Meeting 15 th February 2019	-	Countess Farm		In a meeting with the National Trust on 15 February 2019, Highways England provided a commitment that Countess Farm would be provided with a preconstruction condition survey.	Agreed
3.7	Meeting 15th February 2019 WR [REP2-115]	6.10.	Noise and vibration - Vibration effects at Stonehenge Cottages	The National Trust is concerned that the impact of vibration at the Stonehenge Cottages during construction of the proposed scheme may have been underestimated. The precise method of calculation of predicted vibration levels from tunnelling has not been referenced. Requirement: the National Trust considers that further investigations into the potential for vibration impacts at the Stonehenge Cottages are required to determine if the current level of proposed mitigation is sufficient.	In a meeting with the National Trust on 15 February 2019, Highways England provided a commitment that Stonehenge Cottages would be provided with a condition survey prior to tunnel works. The OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013]) requires the contractor to undertake a vibration scoping appraisal of the works to construct the Scheme, as well as preand post-tunnelling operation condition surveys (MW-NOI5), and vibration monitoring at Stonehenge Cottages commencing when the Tunnel Boring Machine ("TBM") is approaching (MW-NOI6). As a conservative approach monitoring of vibration at Stonehenge Cottages is proposed to start when the TBM is within 250m of the Cottages. At this distance the predicted vibration level is less than half the Lowest Observed	Agreed



					Adverse Effect Level (LOAEL) for vibration annoyance effects, and therefore this would allow for a period of monitoring to occur before there is a risk of perceptible vibration. MW-NOI5 contains obligations relating to remedial works at the Cottages, if required.	
3.8	[RR-2344]	5.1.1	DCO - Insufficient detail	At this stage the DCO documentation does not sufficiently show critical detail across a broad range of matters in relation to both design and delivery. The Trust would like to see this detail defined through the DCO, and where this is not appropriate seeks provision within the DCO to ensure the Trust is a consultee on all key aspects of the detailed design and delivery through Requirements and bespoke protective provisions. This has been provided in general terms through updates to the DCO and OEMP by setting out requirements for consultation around the progression of detailed design post Examination, and during the Preliminary Works and Main Works construction period. While National Trust-considers that further work is required to finalise this consultation process (set out separately elsewhere in this document) With the consultation process in the OEMP now agreed, on this basis the principle of the level of detail included in the DCO is agreed.	The design has been fixed to an appropriate level for the DCO application. The detailed design will be developed through the detailed design stage of the project, with stakeholder involvement taking place as set out in section 4 of the OEMP, which has been agreed with the National Trust. Through this process, Highways England has, and will continue to engage with the National Trust on all relevant aspects of the detailed design and delivery of the Scheme throughout its life.	Agreed
3.9	[RR-2344] WR [REP2-115]	5.1.4 6.8.1 0	Byways Open to All Traffic (BOATS)	The current use of the BOATs within the WHS causes an adverse impact on the OUV of the WHS. To address this Policy 6 of the Stonehenge & Avebury and Associated Sites WHS Management Plan (2015)	Changing the status of the existing BOATs is beyond the scope of the Scheme and is a matter for Wiltshire Council to consider as the local highway authority. Highways England wishes to	Agreed



6.11.	requires the management, 'of vehicular access to byways within the WHS to avoid damage to archaeology, improve safety and encourage exploration of the landscape on foot whilst maintaining access for emergency, operational and farm vehicles and landowners.' We are concerned that neither this scheme, nor the cumulative impacts of this scheme in combination with the existing BOATs within the WHS, should exacerbate the damage to OUV already caused. In addition, the benefits to OUV afforded by the scheme's removal of traffic within a substantial proportion of the WHS should not be undermined, either by increased usage of the existing BOATs, or use (legally or illegally) by motorised users on new PRoWs created as part of the scheme. Requirements: care should be taken in approval of any detail in relation to the scheme not to encourage increased use of PRoWs by motorised users where that would harm the OUV of the WHS. Additionally the status of the current BOATs (Byways Open to All Traffic) require further consideration to ensure compatibility with the overall configuration of the other forms of access and Rights of Way within the WHS post scheme construction. The approach to BOATs in the proposed Scheme, is agreed, subject to the design principles and commitments set out in the OEMP. The National Trust has previously	ensure that the Scheme is integrated within the existing byway network and, where the appropriate opportunity exists, create legacy benefits for non-motorised users in accordance with its Strategic Business Plan and Road Investment Strategy, which are aligned with Government policy to encourage walking, cycling and horse-riding through national and local policies and plans. Highways England has made submissions to the Examination setting out that it does not support the provision of a link between Byways 11 and 12.	



				stated the removal of motorised vehicles from the BOATS could be seen as positive progression if that was to be introduced as part of the Scheme, however this is not currently proposed. The National Trust would not be in agreement with the provision of a link between Byways 11 and 12 for motorised users, if this were to be introduced as part of the Scheme.		
3.10	[RR-2344] WR [REP2-115]	5.1.5 6.8.5	Limits of deviation	The Trust is content with the tunnel LoDs; that the impact of their implementation has been included in the Applicant's assessment work; and that should the LoDs be utilised to any extent, the mitigation measures for this will be appropriately controlled within the provisions of the DAMS.	Agreed	Agreed
3.11	[RR-2344]	5.1.7	Ecology – Adequacy of OEMP and assessment	There was formerly insufficient detail in the OEMP (Outline Environmental Management Plan) to allow us to adequately assess if the approach to mitigation, establishment methodology, and subsequent management is wholly suitable. In some cases we have identified areas where proposals should be strengthened, for example mitigation for European Protected Species at the Countess flyover, and the potential for improved east-west ecological connectivity. We also sought further clarity on the interrelationship of, and how information will transfer through, the OEMP to the CEMP, and to the LEMP (Landscape & Ecology Management Plan) and HEMP.	Agreed	Agreed



				The OEMP has now been updated and information provided to sufficiently reassure the National Trust on this general issue. Details are still under discussion in relation to the process for consultation and further OEMP updates (covered elsewhere).		
3.12	[RR-2344] WR [REP2-115]	6.2 6.12. 5	Land - Temporary possession (Article 29)	Article 29 - 'Temporary use of land for constructing the authorised development': The Trust understands from the Applicant that the land in Plot 5-37 is no longer required to be subject to powers of temporary possession, but, were it to remain subject to powers of temporary possession, the Trust, would require consultation on the use of the land in this plot. With reference to the ability of the Applicant to temporarily occupy land which may then be acquired permanently; the Trust has noted the ability that would exist for occupation of Trust land even when only sub-soil acquisition is to take place. This has been tempered by an assurance by the Applicant that this would be limited to monitoring activities only. The Trust agrees to the principles of temporary possession under article 29, subject to agreement of a record of the above as a protection in a properly documented binding written form with the Applicant.	Having reviewed the land requirements for plot 05-37, it is agreed that the Scheme can be carried out without the need for this plot, and a commitment will be provided to the National Trust in this regard. It is agreed that no temporary possession powers will be used at the surface of plots 06-08, 06-11, 06-13, 07-02, 07-05, 07-07, 07-13, 08-02, 08-07, 08-09, 08-10, 08-11, 08-22, and temporary possession powers would be limited to subsoil level only. Access will be required at the surface of these plots in order to undertake surveys.	Agreed subject to drafting
3.13	[RR-2344] WR [REP2-115]	6.2 6.12. 5	Land - Temporary possession (Article 30)	Article 30 – 'Temporary use of land for maintaining the authorised development': The National Trust understands that there is a need to include some powers to temporarily use land to maintain the authorised development once it is built and operating. However, the use of such powers	The Applicant's response to the Written Question DCO.1.12 [REP2-030], considers the definition of "maintain" and related issues. It is clear that maintenance of the authorised development would not lead to environmental effects that have not been	Agreed



must be proportionate and subject to appropriate controls. Given that, as currently defined in the dDCO, 'maintain' includes powers not only to 'inspect, repair, adjust, alter and remove', but also to 'reconstruct', the Trust has concerns about the justification for such wide powers to be exercised over land within and/or adjoining the WHS. The breadth and type of works that could be required to maintain the authorised development have the potential for unassessed and unmitigated adverse impacts to arise in relation to the OUV of the WHS.

Requirements: with regards to the National Trust's own land, the Trust requires the Applicant to agree a mechanism by which it will consult the Trust on, and allow the Trust to agree to the proposed use of its land for any temporary purposes. This could be secured through amendments to the dDCO either within Articles 29 and 30 or in protective provisions for the Trust.

The Trust has now reached agreement with the Applicant on this matter.

assessed (see DCO.1.12(iii)). Indeed, the draft DCO submitted at Deadline 69 [REP6-005REP9-004] contains an amendment to the definition of "maintain" in article 2, such that the following proviso has been added: "...provided such works do not give rise to any materially new or materially different environmental effects to those identified in the environmental statement". Temporary possession for the purposes of maintenance under article 30 may only be taken on the service of not less than 28 days notice and the notice is required to state the part of the authorised development for which possession is required, and the purpose for which possession will be taken (see article 30(3)). Additionally, temporary possession of land may only be taken during the "maintenance period" defined in paragraph 11 as the period of five years beginning with the date on which that part of the authorised development came into use or was opened to the public.

The Applicant will continue to discussarticles 29 and 30 with the National Trust with a view to reaching anaccommodation acceptable to bothparties.

The matters raised by the Trust in response to Articles 29 and 30 have been sufficiently resolved.



3.14	Environmental Statement	-	Methodology	The methodology for environmental impact assessment including assessment of cumulative effects is agreed.	Agreed	Agreed
3.15	Environmental Statement	-	Data collection methods	The methods used in the ES for data collection, relevant to the NT's interests are agreed	Agreed	Agreed
3.16	Environmental Statement	-	Baseline data	The baseline data used in the ES for considering environmental effects/impacts are agreed	Agreed	Agreed
3.17	WR [REP2-115]	6.2.4	Agriculture - Combine Harvester Access via Countess Farm	As detailed in our summary of oral submissions put at the Compulsory Acquisition Hearings [REP5-019], the Trust stated that it has (on request of the Applicant) engaged in discussion on this matter to provide provision for access arrangements outside of the Order Limits across the Trust's estate. There is a proposal to provide this access using a route and in a form which is in principle acceptable to the Trust and the Applicant. This has been offered to the affected party for consideration. The Trust considers that it has made its position clear as to the extent and provision of access that it feels is appropriate within the WHS and which it can offer.	Details of the combine harvester access is set out in Highways England's response to Written Question Ag.2.5 [REP6-019] and CA.2.43 [REP6-026]. Highways England and National Trust are in agreement on the requirement and offer to provide an access to benefit Park Farm and West Amesbury Farm for combine harvester access only.	Agreed
3.18	WR [REP2-115]	6.5.1	Compulsory Acquisition - Extent of acquisition proposed	Articles 3, 5, 7 and 19 to 30 and Schedules 1, 3, 4, 6, 7 and 11. These provisions comprise the powers to construct the scheme, make variations to it and to acquire land or rights, permanently or temporarily. Negotiation is under way with the Applicant on these provisions with a view to the National Trust being able to confirm in, or	a) Highways England's land referencing exercise has confirmed the accuracy of boundaries of the plans in terms of the National Trust's ownership, including verification against the registered titles and confirmation from the National Trust through land interest questionnaires. Highways England believes the land ownership shown in the Book of	Agreed



				before, the compulsory acquisition hearing it has requested whether: a) the boundaries of the plans are accurate in terms of Trust ownership c) in all other respects whether the dDCO accurately and clearly records the extent of the Trust's existing land rights and the extent of the powers that are being sought over them.	Reference is an accurate record of the National Trust's ownership. c) Highways England believes that the Book of Reference accurately and clearly records the extent of the National Trust's existing land rights and the Book of Reference and Schedules 4, 6 and 7 of the draft DCO [REP6-005 and REP6-006REP9-004] sets out the extent of the compulsory acquisition powers and temporary use powers that are being sought.	
3.19	WR [REP2-115]	6.5.2	Compulsory Acquisition – Ownership, access and protection	Specific issues that will be addressed within those discussions will also include: a) whether the extent of the land and rights required is the minimum necessary to achieve the public purpose underlying the scheme and namely whether the Trust should retain ownership of the land it is deemed to own underneath any existing carriageways after any stopping up provisions in the DCO take effect, and if not, whether adequate safeguards exist to regulate the use of this land in the interest of protecting the WHS b) whether adequate access arrangements are being proposed to support future use of all land retained by the Trust c) whether through requirements, protective provisions, control documents or other means there can be satisfactory controls identified over the extent and design of the works, how they will be carried out and thereafter operated.	The Applicant is discussing these issues with the National Trust. a) The existing A303 has been included within the Order land for permanent acquisition by Highways England to ensure land is secured to construct and maintain the new restricted byway and private means of access, and to provide rights for statutory undertakers to access apparatus. Highways England is continuing discussions with the National Trust to reach an agreement in regard to this ownership. The position is agreed in principle, and documentation is being drafted has been agreed to secure the position. b) Adequate access arrangements provided to support the use of the land retained by the National Trust are included in the Scheme, shown on the Rights of Way and Access Plans [APP-009] and described in Schedule 3 to the	Agreed subject to- drafting



				The Applicant and the Trust are inagreement in principle have reached an agreed position in relation to matters of the ownership of land underneath carriageways, access arrangements and other control documents. However, this is subject to the agreement of adequate documentation.	draft DCO [REP6-005 and REP6-006REP9-004]. c) As detailed above, Highways England is confident that the mechanisms included within the draft DCO [REP6-005 and REP6-006REP9-004] including its requirements, the updated DAMS [REP6-013 and REP6-014REP9-017] and the updated OEMP [REP6-011 and REP6-012REP9-013] submitted at Deadline 6, are appropriate in the context of this Scheme. This is now agreed with the National Trust., but will-continue to discuss these matters with the National Trust with a view to addressing its concerns.	
3.20	WR [REP2-115]	6.8.6	Heritage and historic environment - Cutting Design	The National Trust is content that in principle the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the overarching cutting design, subject to the consultation process provided that those protections are complied with as required throughout the life of the scheme detailed design development and construction (covered elsewhere).	Agreed	Agreed
3.21	WR [REP2-115]	6.8.7	Heritage and historic environment - Variable Message Signs and Signage	The National Trust is content that in principle the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of signage (including variable message signs), subject to the consultation process provided that those	Agreed	Agreed



				protections are complied with as required throughout the life of the scheme detailed design-development and construction (including consultation on positioning of signage) - (consultation matters covered elsewhere).		
3.22	WR [REP2-115]	6.8.1	Heritage and historic environment - Haul Roads	The Trust's understanding is that within the WHS, haul roads will be contained within the footprint of the final construction, and there will be no creation of additional haul routes across the WHS. The OEMP [REP4-020] has a commitment (D-CH31) which satisfactorily addresses this issue. This comment is subject to any wider comment on the OEMP.	Agreed	Agreed
3.23	WR [REP2-115]	6.8.1	Heritage and historic environment - Lighting	The Trust is content that the final OEMP as- updated does provide sufficient controls in respect of the design of the lighting scheme. Subject to the consultation process provided that those protections are complied with as required throughout detailed design the life of the scheme development and construction (covered elsewhere).	Agreed	Agreed
3.24	WR [REP2-115]	6.8.1	Heritage and historic environment – Fencing and Gates	The Trust is content that in principle the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the design of the fencing and gating scheme, subject to the consultation process provided that those protections are complied with as required throughout detailed design the life of the scheme development and construction (covered elsewhere).	Agreed	Agreed



3.25	[RR-2344] WR [REP2-115]	5.1.3 6.11. 1	Rights of Way Sustainable transport	The overall Rights of Way strategy needs further consideration, especially in regard to the proposed treatment of the current A303 and the redundant portion of the A360 and other NMU (Non-Motorised User) access post scheme construction. The Trust is now in agreement that the consultation arrangements now in place adequately provide means to address this issue.	The new and altered public rights of way for the Scheme are shown on the Rights of Way and Access Plans [APP-009]. The Applicant considers its proposals in respect of public rights of way will improve provision for non-motorised users in and around the WHS. In respect of the detailed design of the public rights of way created or altered by the Scheme, Highways England hasprepared an update to the OEMP (arevised version of which was submitted at Deadline 6 [REP6-011 and REP6-012REP9-013] which contains additional design commitments, the design vision, design principles to help guide the development of the detailed design together with a robust stakeholder consultation mechanism to involve heritage stakeholders, including the National Trust, in the development of aspects of the detailed design within the WHS. This includes consultation with heritage stakeholders, including the National Trust, on aspects of the design of public rights of way within the WHS. The OEMP includes commitments to consult with the SCDG (of which National Trust will beis a member) on public rights of way provision including surfacing, materials, fencing and gating. There are also four design principles in respect of public rights of way and a	Agreed



					number of commitments in items D-CH26. Compliance with the OEMP (a revised-version of which was submitted at Deadline 6 [REP6-011 and REP6-012REP9-013]) is secured via requirement 4 in Schedule 2 to the draft DCO [REP6-005 and REP6-006REP9-004].	
3.26	WR [REP2-115]	6.8.8	Rights of Way and non motorised users – Width of new bound surfaces on A360 and A303	a) any bound surface should be a maximum of 3m in width, with a visually recessive finish in keeping with the character of the surrounding landscape	Agreed, and secured through item D-CH26 of the OEMP.	Agreed
3.27	WR [REP2-115]	6.8.9	Rights of Way and non motorised users – Surfacing of new restricted byways on A303	Contra to the Applicant's statement in 6.1 Environmental Statement Chapter 6, 6.17, Table 6.7 the National Trust understands HMAG had not agreed the design for the NMU route on the line of the redundant A303 at the time of submission of the application. While subsequent-Subsequent discussions between the Applicant and the Trust (among others) have been positive and it is understood that this will be considered as part of the consultation process set out in section 4 of the OEMP no substantive written commitments have been received with regard to the design of the A303 NMU route.	Within the WHS, commitments with regard to surfacing are set out at items D-CH2, D-CH3 and D-CH14 of the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012REP9-013] which provides for, respectively, the breaking up of the redundant A303 and A360 within the WHS, and that provision of surfacing within the WHS shall be developed in consultation with National Trust, Historic England, English Heritage and Wiltshire Council. Furthermore, the OEMP commits (at paragraph 4.5.3) to consult with the SCDG (of which National Trust	Agreed



					will be a member) on public rights of way provision including surfacing, materials, fencing and gating. Through the ongoing Heritage Partners Design Review meetings, the Applicant has developed a series of Design Principles to guide the detailed design of elements of the Scheme, including the public rights of way within the WHS, which is incorporated into the updated OEMP as Chapter 4. The latest version of these principles was submitted at Deadline 6-9 [REP6-011 and REP6-012 REP9-013].	
3.28	WR [REP2-115]	6.8.8 and 6.8.9	Rights of Way and non motorised users – A360 and A303 chalk grassland	b) any area not used as a formal surface should become chalk grassland priority habitat (as defined by the Habitats Directive 2010 Annex I habitat types) in line with Policies 3g and 3h of the Stonehenge & Avebury and Associated Sites WHS Management Plan (2015)	As shown in ES Table 8.14 the strategy being pursued for habitat creation will provide substantial net gain of habitat that is appropriate to the local landscape and contributes to local objectives for biodiversity gain. This will include the creation of significant areas of new chalk grassland habitat within the Order limits, as shown illustratively on the Environmental Masterplan [APP-059] and detailed in Chapter 8 of the Environmental Statement [APP-046], Sections 8, 8.8.14 – 8.8.21, 8.9.65 – 8.9.66, and Table 8.14 (item MW-BIO2 of the OEMP secures the establishment of the new habitats shown within Environmental Masterplan).	Agreed
3.29	WR [REP2-115]	6.8.8 and 6.8.9	Rights of Way and non motorised users – A360 and	c) no 'urban' infrastructure such as rubbish bins, benches, kerbing or significant drainage infrastructure should be installed, and any signage for the new PRoW should be non-reflective and in-keeping with the character of the WHS, and should be	Agreed, see item D-CH27 of the OEMP.	Agreed



			A303 urban infrastructur e	designed and located in such a way as to ensure no adverse impacts on the OUV of the WHS		
3.30	WR [REP2-115]	6.2.3	Agriculture - Decommissi oning of the A303	Requirements: clarification is sought on the maintenance, management, and future liability responsibilities for the land of what will become the decommissioned A303 The National Trust is content that in principle the DCO requirements and design commitments and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the management and maintenance of the decommissioned A303, subject to the consultation process provided that those protections are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere). The exact nature of management and maintenance to be carried out is still a matter for discussion for the detailed design process and will be developed during the implementation of the scheme. The Trust is now in agreement that the consultation arrangements now in place adequately provide means to address this issue.	The future management of the length of decommissioned A303 to become restricted byway will become the responsibility of Wiltshire Council as public rights of way authority. The mechanics for this will beare dealt with in a legal agreement between Highways England and Wiltshire Council. Highways England intends to retain responsibility for the section of decommissioned A303 to the east of Stonehenge Road – this area is expected to be managed as part of its soft estate. Controls over the extent and design of the works, how they will be carried out and thereafter operated are contained in the OEMP, an updated version of which was submitted at Deadline 6 9 [REP6-011 and REP6-012REP9-013] of the examination, secured via Paragraph 4 of Schedule 2 to the draft DCO [REP6-005 and REP6-006REP9-004]. Item MW-G11 of the OEMP provides for the provision of a Handover Environmental Management Plan to be developed on the basis of the most recent CEMP and LEMP. This will deal with the ongoing maintenance of the Scheme where it will remain within Highways England's (or its appointed maintenance body) remit.	Agreed



3.31	WR	6.4.1	Biodiversity,	The fourth objective of the Applicant's	Agreed	Agreed
	[REP2-115]		biological	scheme is 'to improve biodiversity. In the	1.9	
	[[([] 2 [] 0]		environment	Environmental Statement (ES) Chapter 8.		
			and ecology	Page 8-3, 8.2.5 it states that the National		
			- General	Planning Policy Framework (NPPF) 2018		
			'net gain'	provides for 'minimising impacts and		
			and	providing net gains for biodiversity, including		
			ecological	by establishing coherent ecological networks		
			networks	that are more resilient to current and future		
				pressures' and 8.2.7 'which encourages		
				developers to look beyond maintaining		
				existing biodiversity value and actively		
				encourages provision of additional benefits		
				for biodiversity which contribute to future		
				proofing the natural environment.' In		
				addition, ES Chapter 8, Page 8-65, 8.9.72		
				states that - 'The chalk grassland of the		
				Scheme would enhance the west east		
				connectivity, improving ecological network		
				along the whole length from Yarnbury Castle		
				to Amesbury'. In ES Chapter 8 Page 4-47,		
				8.8.17 states that – 'In the eastern section of		
				the Scheme the opportunities for habitat		
				creation will be focused on the slopes of		
				cuttings and along the existing A303'. Due to		
				the current proposal for a surfaced track of		
1				3-4 meters wide along the length of the line		
				of the redundant A303, the area remaining		
1				for establishing a green byway of species		
1				rich chalk grassland and the delivery of a		
				coherent ecological network, necessary to		
1				enhance connectivity, will be severely		
1				constrained within the remaining width of the		
				single carriageway.		
				Requirement: if a net gain for biodiversity is		
				an objective of the scheme as outlined by		



				the Applicant, every available area that is suitable should be used for the creation of species rich chalk grassland and further provision should be provided to restore or enhance species rich chalk grassland beyond the existing line of the road though appropriate introduction or supplementation of wildflower species.		
				The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the principle of creating chalk grassland, subject to the consultation process provided that those protections are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere).		
3.32	WR [REP2-115]	6.4.5	Biodiversity, biological environment and ecology - The creation of habitats using chalk substrate (ES Chapter 8, Page 8.47, 8.8.19)	Requirements: further information is required on the treatment of the phosphatic chalk and if it is to be incorporated into the substrate for nutrient poor soils, whether it is suitable for chalk grassland vegetation establishment. The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the principle of creating chalk	As detailed within Chapter 10 (paragraphs 10.6.77-79) of the Environmental Statement [APP-048], in order to assess the availability of phosphorus in the Phosphatic Chalk, phosphorus leachate testing was undertaken in February 2018 on the Phosphatic Chalk cores obtained during the EP Ground Investigation and held in storage. A total of 16 Phosphatic Chalk samples, collected at depths ranging between 8.45m bgl and 32.6m bgl and corresponding with the proposed tunnel	Agreed



				habitats, subject to the consultation process- provided that those protections are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere).	vertical alignment, were submitted for leachate analysis for a suite comprising reactive phosphorus (also known as orthophosphate) and selected major ions. The results of the additional leachate analyses reported concentrations of reactive phosphorus below the laboratory level of detection of 0.05mg/l in all 16 samples. Concentrations of leachable total phosphorus were also recorded below the laboratory level of detection of 1mg/l. The leachate test results suggest that the dominant calcium carbonate chemistry of the Chalk is likely to generate a precipitation (mineral formation) rather than a dissolution environment, such that the rock is unlikely to yield large concentrations of dissolved phosphorus. This means that the material would not have a deleterious effect on the water quality of the River Till. The establishment of suitable chalk grassland would be achieved even if some of the phosphatic chalk is at the surface. This is because	
					·	
3.33	WR [REP2-115]	6.4.6	Biodiversity, biological environment and ecology - Trees	ES Chapter 8 page 8-31 Table 8.11 provides a summary evaluation of habitats present within the Scheme and study area. These sections only reference a single veteran beech tree located to the north of King Barrow Ridge. There are a number of	It is considered that sufficient safeguards for trees have been included within the DCO documentation. As detailed within MW-LAN3 of the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012 REP9-013]) an Aboricultural Mitigation	Agreed



veteran trees on King Barrow Ridge with high or moderate bat roost potential. *Requirements*: the National Trust seeks assurance that Root Protection Zones have sufficiently been taken into consideration so that the construction operations will not have any adverse impact on the stability of trees in this location.

The Trust is in principle content that the DCO requirements and design commitments and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of the consideration of Root Protection Zones, subject to the consultation process provided that those protections are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere).

Strategy (AMS) shall be prepared to protect trees retained within and immediately adjacent to the order limits which should deal with the concerns raised. This shall consider the following standards:

- BS 3936-1: Nursery stock. Specification for trees and shrubs;
- BS 3936-4: Nursery stock.
 Specification for forest trees, poplars and willows;
- BS 3882: Specification for topsoil and requirements for use;
- BS 3998: Tree Work. Recommendations:
- BS 4428: Code of practice for general landscape operations (excluding hard surfaces);
- BS8545 Trees from nursery to independence in the landscape;
- BS 5837: Trees in relation to design, demolition and construction; and
- BS 6031: Code of practice for earthworks.

Alternatively, where a British Standard does not exist, works will follow industry good practice, e.g. Natural England's Advice on managing, restoring, and creating grassland and agreement will be sought from Wiltshire Council. The AMS shall also define:



					 The root protection area (RPA) and Construction Exclusion Zones (CEZ) of trees to be retained within or immediately adjacent to the order limits and wherever practicable. The approach for working within RPAs, where this cannot reasonably be avoided required. The approach to inspecting, maintaining and managing trees and scrub to be retained. The approach for felling where otherwise not identified in the ES. Compliance with the OEMP (a revised version of which was submitted at Deadline 96 [REP6-011 and REP6-012REP9-013) is secured through the requirement contained in paragraph 4 of Schedule 2 to the draft DCO [REP6-005-and REP6-006REP9-004]. 	
3.34	WR [REP2-115]	6.6.1	Flood risk, groundwater protection, geology and land contaminatio n	The sensitivity of the WHS as a receptor within the Geology and Soils Chapter of the ES was not defined. This is inconsistent with the methodology used for other schemes, such as the A303 Sparkford to Ilchester dualling scheme. In accordance with DMRB methodology, the WHS could be defined to have a 'very high' sensitivity, which may change the outcome of the assessment. The Trust is now content with the assessment, methodology and outcome of assessment in relation to the Geology and Soils Chapter.	DMRB Volume 11 Section 3 Part 11 Geology and Soils refers to only statutory and non-statutory designations specifically related to geology or soils and not designations related to heritage or archaeology. The Sparkford to llchester Dualling Scheme Geology and Soils chapter (ES, Chapter 9) and Table 9.1 refers to WHSs as an example of very high sensitivity receptors but only where they are designated due to their geological importance. The WHS at Stonehenge is not designated for its	Agreed



and a size liver and a size of the size and a size of
geological importance. In the absence of
any geological designations in the study
area, these were scoped out of the
geology and soils assessment as stated
in the ES Chapter 10 Geology and Soils
[APP-048] paragraph 10.6.43 and
agreed with by the Planning Inspectorate
in their Scoping Report responses. The
remaining assessment presented in the
ES is a potential contaminated land
assessment which considers visitors and
workers at the WHS as moderate
sensitivity receptors. The assessment
also considers other receptors within the
WHS like groundwater and the River
Avon which borders the WHS to the
east. The ES [APP-048] in Chapter 10,
paragraph 10.6.90 refers to a low
potential for ground contamination to
exist along the Scheme and whilst
archaeological remains, scheduled
monuments and historic landscapes are
not explicitly stated in the conceptual site
model and Table 10.8 (Summary of
Potentially Sensitive Receptors);
measures contained within the OEMP (a
revised version of which was submitted
at Deadline 69 [REP6-011 and REP6-
012REP9-013]) such as: PW-GEO1
(ground investigation), PW-GEO2
(unexpected contamination), MWGE01
(contamination risks), MW-GE02
(groundwater contamination), MW-GEO3
(soils management strategy), MW-GEO6
(hazardous substances), MW-GEO7
(excavated materials management), and



					MW-GEO8 (construction on and adjacent to land affected by contamination) would all limit the possibility for dispersal and accidental releases of any existing contamination encountered, or any potential polluting materials introduced during construction, to heritage assets (including the WHS which is assessed as of very high value in the Environmental Statement Chapter 6 Cultural Heritage [APP-044]).	
3.35	WR [REP2-115]	6.8.1	Heritage and historic environment – Monitoring of Archaeologic al Mitigation	The appropriate monitoring of archaeological mitigation of the scheme is critical to ensuring the protection of the OUV of the WHS. While there is a commitment to such monitoring within the Applicant's submitted scheme (6.1 Environmental Statement Chapter 6, 6.10.1) it is not specified how, or by whom this would be done. Requirements: the National Trust seeks provision within the dDCO for appropriate consultation with Trust, and HMAG prior to, and as part of, sign off of all archaeological mitigation works within the WHS and for subsequent monitoring, including provision for cost of monitoring. The Trust is in principle content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP and DAMS as updated would provide sufficient controls in respect of the monitoring of archaeological mitigation, subject to the consultation process provided	As stated in the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013]) (e.g. PW-CH1 and MW-CH1 for HMPs), HMAG will be consulted on before Highways England as 'the Authority' or Wiltshire Council (with respect to SSWSIs, archaeological method statements and Heritage Management Plans) approves the plans relating to archaeological mitigation works, such as the Heritage Management Plan. The consultation provided for in the OEMP and the DAMS will ensure that the views of HMAG are taken into account in finalising the documentation, prior to Highways England's or Wiltshire Council's approval. There is therefore no requirement for any external approval by HMAG members. The OEMP [MW-CH7] allows for monitoring arrangements for designated and non-designated heritage assets to be prepared in consultation with HMAG (for sites within the WHS)	Agreed



				that those protections are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere).	and WCAS (for sites outside of the WHS) and approved by The Authority prior to works commencing. Section 7 of the draft DAMS [REP6-013 and REP6-014REP9-017], sets out the monitoring, communications and sign-off of archaeological works procedures including consultation with HMAG (which includes the National Trust).	
3.36	WR [REP2-115]	6.8.1	Heritage and historic environment – Tree planting	Planting of new trees within the WHS can have adverse impacts on both sub-surface archaeology, and on the visual relationships between monuments relating to the OUV of the WHS. The National Trust is therefore concerned to ensure there are no adverse impacts on OUV from tree planting. Requirements: no new tree planting should form part of the scheme within the WHS, and any replacement planting should only be permitted where it replaces existing screening of heritage assets; or provides essential and proportionate mitigation to provide habitat connectivity specifically for bats, providing it does not adversely impact on visual relationships between monuments conveying the attributes of OUV of the WHS; and where such replanting is fully archaeologically mitigated. The National Trust is in principle content that the DCO requirements and design commitments and consultation requirements set out in the final OEMP as updated would provide sufficient controls in respect of tree planting within the World Heritage Site,	The OEMP (as updated [REP6-011 and REP6-012REP9-013]) reference MW-LAN04 states "No new trees shall be planted within the WHS except where required for ecological or visual mitigation (e.g. at Countess Roundabout/Countess Farm), and providing the planting does not adversely impact on visual relationships between monuments conveying the attributes of OUV of the WHS, and such planting is appropriately archaeologically mitigated."	Agreed



				subject to the consultation process provided that those protections, including consultation, are complied with as required throughout detailed designthe life of the scheme development and construction (covered elsewhere).		
4.4 3.37	[RR-2344] WR [REP2-115]	5.1.8 6.7.1 6.8.2 0 6.9.1 6.9.2	Countess Farm Health and wellbeing Grade II listed buildings Landscape and visual effects and design - Assessment of impacts on Countess Farm Sound barrier and screening at Countess Flyover	Health and wellbeing: We are concerned about the impact of the construction on all the occupants of our property at Countess Farm. Requirements: the National Trust seeks clarification on the mitigation to limit the impact of noise, dust, light and disturbance on our tenants. Listed buildings: It is stated that there will be 'permanent adverse effects on the setting of one listed building in the vicinity of Countess Roundabout.'(6.1 Environmental Statement Chapter 16, Table 16.1) However, there is both a Grade II listed farmhouse and an associated group of Grade II listed buildings comprising the farm complex that will also be adversely impacted at Countess Farm. Assessment of impacts: Clarification of the assessment of the impact of the mitigation at Countess Farm by year 15 is sought. In 6.1 Environmental Statement Chapter 7: Landscape and Visual, Table 7.11: Summary of significant effects – construction and Table 7.12: Summary of significant effects – operation year 1, Countess Farm	Agreed Health and Wellbeing: The potential for noise, dust, light and disturbance impacts on Countess Farm as a result of the construction of Countess flyover are assessed in the relevant topic chapters of the ES, including Chapter 5, Air Quality [APP-043], Chapter 7, Landscape and Visual [APP045], Chapter 9, Noise and Vibration [APP-047], Chapter 13, People and Communities [APP-051], and Chapter 15, Cumulative Effects [APP053]. The assessment reported in the ES has concluded that there would be: no significant adverse impacts on air quality; and temporary significant adverse noise effects for nearby residents during construction. The cumulative effects assessment found that in-combination there would be a significant adverse visual, noise and air quality effect during the construction phase at Countess Farm. During construction, impacts will be controlled and reduced as far as reasonably practicable in the vicinity of the Countess	Under- Discussio n-Agreed



(High Receptor Sensitivity) has a Major Impact Magnitude and a Large adverse Residual Effect recorded. In Table 7.13 Summary of significant effects – operation year 15, Countess Farm is predicted to have Moderate Impact Magnitude and Moderate adverse Residual Effect. In 6.1 Chapter 16: Summary: Table 16.1: Summary of effects, the Permanent adverse effects on these listed buildings at the Construction Phase are then not described at the Operational Phase, which appears to the Trust to be contradictory. Additional information is required on this reduction in the Impact Magnitude and Residual Effect and how under the best case scenario, the proposed mitigation of planting will deliver this reduction over 15 years. Currently the proposed planting is restricted to within the soft estate of the existing highway, and in addition an unspecified number of trees are to be removed to create sufficient area for the drainage system (see Fig 2.2 Preliminary design drainage catchments. Countess Pond 1, Countess Catchment 12, Outfall Catchment 15, Countess Pond 3 and Catchment 15), which will limit the space for replacement or additional planting. The visualisations shown in ES Figures [APP -1451 and [APP-146] illustrate the view from the North-East and therefore do not fully show the impact magnitude of the flyover on Countess Farm. We seek additional mitigation in the form of extended fencing and planting including standard trees to maximise the buffering, with ploughzone

Farm through measures contained within the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011] and REP6-012]) to, for example, control noise (PW-NOI1, PW-NOI3, PW-NOI4, PW-NOI5, PW-NOI6, MW-NOI1, MW-NOI3. MW-NOI4. MW-NOI5 and MW-NOI6), dust (PW-AIR1 and MW-AIR1), and artificial lighting (MW-G29). Operational mitigation will be delivered through the use of a thin surfacing system, which results in lower levels of noise generation than a standard hot rolled asphalt surface, as required by D-NOI1 in the OEMP, a 1.8m high noise barriers on the north and south sides of the flyover, as required by reference D-NOI2 in the OEMP: and landscaping of the flyover embankments would be secured through requirement 8 of the draft DCO [REP6-005 and REP6-006]. The Applicant considers that these measures provide adequate mitigation against the impacts of noise, dust, light and disturbance on the tenants of Countess Farm.

Listed Buildings: ES Chapter 6 Cultural Heritage [APP-044, Table 6.11] sets out the significant permanent adverse effect of the construction of the Scheme on the Grade II listed Stables and Barn at Countess Farm (NHLE 1131055). With regards to non-significant effects for the other listed buildings in the complex, which are situated slightly further back



sampling and 100% archaeological mitigation of all humanly made archaeological features in line with the requirements of the DAMS for all works undertaken within the WHS.

Sound barrier and screening: Requirements: further information is required on the type and height of screening and sound barrier that will be attached to the flyover; in addition to the how light and pollution will be mitigated at Countess Farm.

The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP would provide sufficient controls in respect of Countess Farm relating to health and wellbeing, listed buildings, landscape and visual effects and the sound barrier at Countess flyover, provided that those protections are complied with as required throughout the life of the scheme development and construction (covered elsewhere).

from the existing dual carriageway and Countess Roundabout, these are set out in ES Appendix 6.8 - Cultural Heritage -Summary of non-significant effects [APP-217, Table 1.1: Construction phase: temporary; Table 1.4: Construction phase: permanent historic buildings (setting) and Table 1.7: Operational phase: historic buildings (setting)] set out the non-significant effects for the Grade II listed buildings at Countess Farm including Countess Farmhouse and front garden walls (NHLE 1318487), a Large Barn at Countess Farm (NHLE 1131056), a Large Granary at Countess Farm (NHLE 1318488).

Assessment of impacts: The OEMP (as updated for Deadline 6 [REP6-011 and REP6-012]) includes provision at P-LE05 that "Existing highway planting at Countess Junction shall be retained, supplemented by additional tree planting where practicable."

The reduction in the magnitude of impact between operation year 1 ([APP-045] Table 7.12) and operation year 15 ([APP-045] Table 7.13) is due to the establishment of new planting between the elevated section of Countess flyover and the slip road from the proposed A303 to Countess roundabout, as indicated on Section H of the Environmental Masterplan [APP-059], as this planting would be in leaf and taller in height than compared to the year 1



	assessment when the vegeta	tion would
	not be in leaf and smaller and	
	landscape less established ar	
	integrated. In [APP-054]: Sum	
	Effects, Table 16.1: Summary	
	for Cultural Heritage, the pern	
	adverse effects on these lister	d buildings_
	are described as Construction	1
	(permanent) as this approach	allows for
	a thorough and detailed asset	ssment of
	each constituent element of the	ne Scheme
	to be undertaken, acknowledge	ging the
	permanent impacts as a resul	
	construction of the Scheme. 1	
	Applicant considers this appro	
	appropriate and in line with m	
	as set out in DMRB, Volume	
	3, Part 2 (HA208/07) for the a	
	of road schemes in relation to	
	heritage and is therefore not	<u>Gartarar</u>
	contradictory in its approach.	Please
	also refer to the Applicants re	
	Written Question CH.1.9 [REF	
	The construction (temporary)	
	operational (permanent) signi	
	adverse effects to the visual r	-
	included in the Landscape an	
	Impact Assessment section o	
	16.1 [APP-054]. With reference	
	Highways England response	
	Question CH.1.47 [REP2-025	
	planting proposals would scre	
	lower parts of the Countess fl	
1	retaining walls and slip-roads	and soften
1	views of the upper parts of the	e flyover.
	However, the flyover would re	main



		visible and retain a significant visual	
		effect at year 15 of operation as the	
		viaduct and vehicles (including lorries)	
		would be up to 11.5 metres above the	
		grounds of Countess Farm. The detailed	
		design stage of the drainage works, in	
		combination with a detailed tree survey,	
		will establish the likely impact and exact	
		extent of removal; such that it may be	
		that the extent of tree loss could be	
		reduced. The planting will be secured	
		under requirement 8 of Schedule 2 of the	
		draft DCO [REP6-005 and REP6-006]	
		pursuant to which Highways England will	
		be required to submit a detailed	
		landscaping scheme, which must be	
		based on the mitigation measures set	
		out in the ES. Highways England has	
		offered additional off-site planting to	
		which the National Trust are agreeable,	
		as set out in the response to Written	
		Question CH.1.47 [REP2-025]. Requests	
		for extended fencing and the planting to	
		include standard trees are under	
		discussion, along with the detail of any	
		agreement between Highways England	
		and the National Trust regarding	
		archaeological mitigation.	
		Sound barrier and screening: A 1.8-	
		metre-high and absorptive noise barrier	
		is proposed between the slip roads on	
		both the north and south side of	
		Countess flyover as secured in D-NOI2	
		of the OEMP (a revised version of which	
		was submitted at Deadline 6 [REP6-011	
		and REP6-012]). This commitment	
ļ	1	and the object of the community	



					includes reference to the applicable standards that the noise barrier will need to meet: "the current harmonised Specifications Standard BS EN 14388 (2005) and meet the A3 (DLa 8 to 11 dB) and B3 (DLR>24 dB) standards for sound absorption and airborne sound insulation as specified in BS EN 1793 part 1 and 2 (1998), or equivalent future standards approved by the Authority." Lighting during the construction phase must be in accordance with the provisions of item MW-G29 of the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), which sets out that lighting should be designed, positioned and directed so as not to unnecessarily intrude on adjacent buildings, ecological receptors, structures used by protected species and other land uses to prevent unnecessary disturbance, interference with local residents, or passing	
4.10 3.38	WR [REP2-115]	6.2.2	Agriculture - Agricultural access to land during construction	Detail of how tenants are to access land severed during construction for the purposes of moving livestock, machinery, and undertaking routine management such as daily livestock welfare checks has not been provided. Requirements: clarification is required. Clarification has been provided, and further discussions are ongoing relating to accommodation works on north-south	Agreed As noted in Highways England's response to Written Question Ag.1.11 [REP2-022]: "access to premises will be maintained during the operation of the Scheme and during its construction. This is ensured by the scope of the powers available to the undertaker under the DCO. Article 10 of the draft DCO [REP6-005 and REP6-006] makes provision for the stopping up and replacement of private means of access.	Under- discussion Agreed



				movements across the existing A303. The Trust is content that the MW-COM and MW-TRA measures set out in the final OEMP would provide sufficient controls in respect of agricultural access, provided that those protections are complied with as required throughout the life of the scheme development and construction (covered elsewhere).	In accordance with paragraph (2)(a) of that article, a private means -of access that is to be replaced and is listed in Part 3 of Schedule 3, may only be permanently stopped up once the replacement private means of access has been completed to the reasonable satisfaction of the street authority. Article 10(2)(b) makes provision for a temporary alternative route to be put in place, pending the completion of the replacement means of access specified in Part 3 of Schedule 3." No land occupied by National Trust's tenants will be severed during construction. The National Trust's tenants will therefore be able to access land during construction for the purposes of moving livestock, machinery, and undertaking routine management such as daily livestock welfare checks. The OEMP contains specific measures requiring liaison with landowners and occupiers in terms of access (MW-COM1) through the Agricultural Liaison Officer.	
4.11 3.39	<u>WR</u> [REP2-115]	6.2.1	Agriculture and cultural heritage - Impact of the intensificatio n of PRoW (Public Right of Way)	Concerns that the scheme will result in an increase in the anti-social use of the PRoW network have not been resolved. Currently illegal activities including hare coursing, flytipping, camping, and occupation by caravans, vans and motorhomes, already cause issues for land controllers. This includes left rubbish (which can be potentially hazardous for livestock and wildlife), fire sites, unauthorised use of	Highways England's response to Written Question Ag.1.4 ii and iii [REP2- 022] noted: To prevent improper use of the existing and proposed Public Rights of Way (PRoW) network, fences and gates would be provided. The detail of these will follow at the detailed design stage if development consent for the Scheme is granted. At this stage, it is envisaged that fences along public rights of way would be provided to prevent access	Under- Discussio national Agreed



agricultural water supplies, and the obstruction of agricultural access.

Requirements: care should be taken in approval of any detail in relation to the scheme not to encourage increased use of PRoWs by motorised users where that would harm the OUV of the WHS.

The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP would provide sufficient controls in respect of public rights of way, provided that those protections are complied with as required throughout the life of the scheme development and construction (covered elsewhere).

onto private land, grazed grassland or the highway, or to provide a buffer zone to the retained cutting between Longbarrow junction and the western tunnel entrance. Kent Carriage Gaps would be provided at access points to restricted byways, preventing entry by mechanically-propelled vehicles. Equestrian gates would be provided at access points to bridleways and pedestrian gates would be provided at access points to footpaths. This is subject to detailed design of these matters and discussions with Wiltshire Council. Within the WHS, the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), reference D-CH14, requires the provision of fencing and surfacing to be developed in consultation with the National Trust, Historic England, English Heritage and Wiltshire Council. Article 9 of the draft DCO IREP6-005 and REP6-0061 makes provision for the public rights of way provided by the Scheme to be maintained by Wiltshire Council. Wiltshire Council could also use its powers to prevent unlawful use of the existing and proposed Public Rights of Way. Highways England is in discussions with Wiltshire Council concerning matters arising from its maintenance of roads affected by the Scheme. In addition, Highways England has submitted an update to the OEMP at Deadline 6 [REP6-011 and REP6-012]



					which contains additional design commitments, design principles to help guide the development of the detailed design together with a robust stakeholder consultation mechanism to involve heritage stakeholders, including the National Trust, in the development of aspects of the detailed design within the WHS. This includes matters in relation to public rights of way within the WHS, including surfacing, fencing and gating. Compliance with the OEMP is secured via requirement 4 in Schedule 2 to the draft DCO [REP6-005 and REP6-006]. Agreed – Since the drafts of the relevant documents referred to above, further drafts have been produced and agreed dealing with the relevant issues between Highways England and National Trust.	
4.12 3.40	WR [REP2-115]	6.2.5	Agriculture - Fencing and gates	Requirements: a) clarification on the location and specification of new fencing, gates, and all other accommodation works proposed for use on or adjacent to National Trust land interests is required to confirm suitability for agricultural use and to ensure no adverse impact on the OUV of the WHS b) that the design and specification is subject to approval by the Trust where located on or adjacent to Trust land interests. The Trust is in principle content that the DCO requirements and design commitments and consultation requirements set out in the	Highways England's response to Written Question Ag.1.4 ii and iii [REP2-022] noted the detail of fencing and gates "will follow at the detailed design stage if development consent for the Scheme is granted. At this stage it is envisaged that fences along public rights of way would be provided to prevent access onto private land, grazed grassland or the highway, or to provide a buffer zone to the retained cutting between Longbarrow junction and the western tunnel entrance. Kent Carriage Gaps would be provided at access points to restricted byways, preventing entry by mechanically propelled vehicles. Equestrian gates would be provided at	Under-Discussion Agreed



final OEMP as updated would provide access points to bridleways and sufficient controls in respect of the design of pedestrian gates would be provided at the fencing and gating scheme, subject to access points to footpaths. This is the consultation process provided that those subject to detailed design of these protections are complied with as required matters and discussions with Wiltshire throughout detailed designthe life of the Council". The Applicant has developed a series of Design Principles to guide the scheme development and construction detailed design of elements of the (covered elsewhere). Scheme, including the public rights of way within the WHS, which forms part of the OEMP [REP6-011 and REP6-012]. As further noted in the response to Ag.1.4 ii and iii [REP2-022]: "Within the World Heritage Site, the OEMP IAPP-187]," ...(an updated version of which is being submitted at Deadline 6 [REP6-011 and REP6-012]) "...reference D-CH14, requires the provision of fencing and surfacing to be developed in consultation with the National Trust. Historic England, English Heritage and Wiltshire Council". Through the ongoing Heritage Partners Design Review meetings, the Applicant is establishing the principles and developing a process for stakeholder consultation on detailed design of elements of the Scheme, to be incorporated into the updated OEMP as Chapter 4. This was submitted for Deadline 6 [REP6-011 and REP6-012]. Agreed – Since the drafts of the relevant documents referred to above, further drafts have been produced and agreed dealing with the relevant issues between Highways England and National Trust.



4.13 3.41	WR [REP2-115]	6.3.1	Air quality, dust and other emissions - General dust generating activities and range	Areas within the National Trust landholdings and WHS are not identified within the DCO documentation to contain specific activities likely to generate dust and therefore only 'standard' levels of mitigation are recommended in the Air Quality Chapter of the ES. We consider the range of activities most likely to generate dust is too narrow in range. Requirements: a) the Trust seeks discussions on what further mitigation should be considered particularly near to the unique lichen assemblage on the standing stones b) clarification on how dust will be controlled during construction of the flyover which is in close proximity to the agricultural, business and residential premises at Countess Farm c) the implementation of 'further standard' mitigation measures are requested which should be implemented to control and reduce the effects of dust and fine particles provided in Appendix 5.4 Table 5.4.10 of the ES. This matter has now been agreed and resolved.	Construction activities have the potential to generate dust and therefore standard good practice dust mitigation measures, secured through the OEMP, will be implemented across the construction works. The construction works which are envisaged to turn the A303 into the proposed green byway are considered to have a risk of dust egress and can be adequately controlled using standard mitigation measures. The risk of adverse effects is also minimised through these measures for the lichen assemblage on the standing stones as these are located approximately 165m from these works, as discussed in the Stonehenge Lichen Report [APP-234]. The locations where further standard mitigation is proposed are locations where notable sources of dust generation are anticipated (e.g. haul routes, large earthworks and stockpiling etc) and where sensitive receptors (i.e. residential locations) are in close proximity, some within 10 metres (m). This includes activities at Countess roundabout such as the construction of the flyover. The implementation of air quality mitigation is set out in the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013]), specifically in MW-AIR1 and MW-AIR2.	Under-Discussion Agreed
3.42	[REP2-115]	<u> </u>	biological environment	have been identified as bat roosts. The proposed mitigation is planting and inclusion of a noise barrier around the flyover with the	at the Countess roundabout only recorded a total of six bats crossing the A303 in a north or south direction during	Discussio n



intention of it 'likely providing the function of and ecology the six hours of surveys undertaken. Agreed pushing up any bats flying over the A303 to none of which were confirmed to have - Bats emerged / re-entered from the Countess 'safe' heights, or assist in funnelling bats complex [APP-160]. Designs of the through the large underpasses'. It is understood that the noise barrier will not be Countess flyover and Countess junction sufficiently high to prevent bats from flying would be able to incorporate suitable directly into the path of taller traffic on the and proportionate measures to reduce flyover and the proposed planting as the potential impacts on the likely limited suggested is restricted to within the existing number of individual bats that may boundary of the highway. In addition an commute south from the roosts at unspecified number of trees are required to Countess Farm complex. be removed to create sufficient area for the The OEMP (as updated for Deadline 69 drainage system (see Fig 2.2 Preliminary [REP6-011 and REP6-012REP9-013]) design drainage catchments. Countess includes a design principle at P-LE05 Pond 1. Countess Catchment 12. Outfall that "Existing highway planting at Catchment 15, Countess Pond 3 and Countess Junction shall be retained. Catchment 15), which will limit the space for supplemented by additional tree planting replacement or additional planting. where practicable." Requirements: the National Trust seeks Replacement and new planting would be additional essential mitigation in the form of dealt with under the requirement replacement planting by agreement with the contained in paragraph 8 of Schedule 2 Trust with 100% archaeological mitigation to the draft DCO [REP6-005 and REP6for works undertaken within the WHS. 006REP9-004], Highways England will be required to submit a detailed landscaping scheme for approval by the The Trust is content that the requirements set out in the final OEMP and DAMS would Secretary of State which is required to provide sufficient controls in respect of bats be based on the mitigation measures set and replacement planting. out in the ES. This would set out the detailed planting to be delivered by the Scheme. The obligation to act in compliance with this scheme is reflected in item MW-LAN2 of the OEMP and is also a requirement of the draft DCO [REP6-005 and REP6-006REP9-004]. Other measures would separately be

secured by the OEMP (a revised version



					of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013]) through items such as MW-LAN1 (in respect of a Landscape and Ecology Management Plan) and MW-BIO1 onwards. With regard to the archaeological mitigation associated with removal of existing trees and replacement planting, the draft DAMS [REP6-013 and REP6-014REP9-017], sets out the structured, iterative detailed archaeological mitigation strategy. The DAMS is being developed in consultation with HMAG (which includes The National Trust) and the Scientific Committee. It will be finalised prior to the end of the Examination and is secured by Requirement 5 of Schedule 2 of the draft DCO [REP6-005 and REP6-006]. We would expect that archaeological mitigation for additional planting agreed in principle at Countess Farm will be approached in the same way as the rest of the Scheme, subject to numbers, species and location of planting.	
4.1 3.43	[RR-2344]	4.1	Current position	The Trust welcomes the progress made by Highways England to date, and considers that the proposed scheme has the potential to be acceptable and deliver tangible benefits to the WHS. However, we will only support the progression of a scheme which we are sure protects the OUV of the WHS. Given the unique and internationally significant nature of the landscape, we do not consider that the DCO submission from	Highways England continues to work with the National Trust to understand its outstanding concerns. A comprehensive Heritage Impact Assessment has been prepared following ICOMOS guidelines (https://www.icomos.org/world_heritage/HIA_20110201.pdf). The scope and approach of this assessment, which is	Under- Discussio n Agreed



				Highways England currently provides the level of detail required for us to be confident that the approach to design and delivery of the scheme will achieve this essential goal. In addition, there are some areas of the current design approach that we disagree with, as well as important areas of methodology that are yet to be defined. The Trust is content that the DCO requirements and design commitments, design principles, consultation and archaeological mitigation requirements set out in the final OEMP and DAMS would provide sufficient controls, provided that those protections, including consultation, are complied with as required throughout the life of the scheme development, and preliminary and main works and that with these measures in place, the approach and methodology of design will enable the protection of the OUV of the WHS.	reported in ES Appendix 6.1 [APP-195], was endorsed by UNESCO/ICOMOS in their report from their third advisory mission on the scheme early in 2018 (https://whc.unesco.org/en/list/373/docu ments/), and developed in consultation the HMAG. The Applicant considers that the HIA has been carried out accurately and with a full appreciation and understanding of the importance of the WHS and its OUV. Overall, the Scheme is assessed to have a Slight Beneficial effect on the OUV of the WHS as a whole and the OUV of the WHS would be sustained. Further information can be found in the ES Chapter 6, Cultural Heritage [APP-044] and ES Appendix 6.1, Heritage Impact Assessment [APP-195]. The design will be developed through the detailed design stage of the project. Highways England would like to engage with the National Trust on all relevant aspects of the detailed design and delivery of the Scheme. Agreed	
4.2 3.44	[RR-2344] WR [REP2-115]	<u>5.1.2</u> <u>6.8.4</u>	- Document development	The Trust has a strong interest in the development of the key control documents within the DCO including the: • CEMPs (Construction Environmental Management Plan) • CHAMPs (Cultural Heritage Asset Management Plans) and all successor plans produced by the Applicant on a four year cycle	The various documents are required at different times and are prepared by different parties. Highways England has shared a matrix of these various documents with the National Trust in order to clarify the timelines and responsible parties for document development. Further discussions are ongoing regarding the National Trust's	Under- Discussio n Agreed



•	DAMS (Detailed Archaeological
	Mitigation	on Strategy),

- HEMP (Handover Environmental Management Plan)
- HMPs (Heritage Management Plans)
- LEMP (Landscape and Ecology Management Plan)
- Method Statements (specifying requirements for the preservation in situ of archaeological deposits)
- OWSI (Outline Written Scheme of Investigation),
- SSWSIs (Site Specific Written Schemes of Investigation)

The approach defined within these above listed documents will be key in our assessment of the scheme's suitability. As such, we expect to be closely consulted in their development.

The National Trust's position is that these documents do not presently have sufficient detail.

Requirements: in order to better understand the development of these documents the Trust seeks for the Applicant to:

 a) prepare and distribute a road map detailing expected timelines for the development of these documents; showing:

i. points where the Trust, and HMAG will see and have the opportunity to input into these documents

ii. when the Trust, and HMAG will see the finalised versions

involvement, through consultation, on these documents and the terms for that consultation.

The National Trust was previously stated in the OEMP as a consultee on the following documents:

- HMP (Heritage Management
 Plan) for works within the WHS
 (PW-CH1, MW-CH1 and DAMS)
- SSWI (Site Specific Written
 Schemes of Investigation) for
 works within the WHS (PW-CH3,
 PW-CH4, PW-CH5 and DAMS)
- Archaeological Method
 Statements for works within the
 WHS (MW-CH5 and DAMS)
- SMS (Soils Management Strategy) (PW-GEO3 and MW-GEO3)
- Ground Movement Monitoring Strategy (MW-CH8)
- TMP (Traffic Management Plan) (MW-TRA2, MW-TRA4 and MW-TRA5)

The OEMP has been updated (a revised version of which was submitted at Deadline 9 [REP9-013]) to include National Trust as a consultee on:

- HEMP (Handover Environmental Management Plan) (MW-G11)
- EPRP (Emergency
 Preparedness and Response
 Plan) (MW-G20 and MW-WAT4)



b) provide a named person (or role) within the project ultimately responsible for:

- i. the production of each of these documents
- ii. ensuring the requirements or conditions of the document are upheld

c) provision to be made within the dDCO for the Trust and HMAG to be consulted throughout the development of these documents and to be listed as part of the approval regime for final sign off.

The Trust is now content with the approach to the OEMP and DAMS and their requirements and consultation processes for the development of detailed documents.

- CEMP (Construction
 Environmental Management
 Plans) (PW-G1, MW-G5, MW-G6, MW-G16 and MW-G20)
- LEMP (Landscape and Ecology Management Plan) (MW-LAN1)
- AMS (Arboricultural Management Strategy) (MW-LAN3)
- WMP (Water Management Plan) (MW-WAT2 and MW-WAT7)

The OEMP, DCO and DAMS are now agreed with the National Trust.

As set out in the OEMP (a revisedversion of which was submitted at Deadline 6 (REP6-011 and REP6-0121) the CEMPs will be developed by the preliminary works and main works contractors IPW-G1 and MW-G51. Theywill be consulted upon with Wiltshire Council, the Environment Agency. Natural England and Historic England and will append as appropriate the Heritage Management Plan which the National Trust will be consulted upon as part of HMAG (for works within the WHS). As set out in paragraph 6.8.14 of ES Chapter 6 Cultural Heritage [APP-0441. Cultural Heritage Asset Management Plans (CHAMPs) will be prepared every four years by Highways England (or the operating authority) and following DMRB Volume 10 **Environmental Design and Management**



		Section 6 Archaeology, Part 2, HA 117 /	
		08 Cultural Heritage Asset Management	
		Plans (Highways Agency 2008) and as	
		referred to at paragraph 5.1.21 in the	
		draft Detailed Archaeological Mitigation	
		Strategy (DAMS) [REP6-013 and REP6-	
		014], to ensure that cultural heritage	
		assets are protected during the course of	
		highways operation and maintenance	
		works. The draft DAMS [REP6-013 and	
		REP6-014] sets out the structured,	
		iterative detailed archaeological	
		mitigation strategy, including, at part two,	
		the Overarching written scheme of	
		investigation. The DAMS is being	
		developed by Highways England in	
		consultation with the Heritage Monitoring	
		Advisory Group (which includes the	
		National Trust) and the Scientific	
		Committee. It will be finalised prior to the	
		end of the Examination and is secured	
		by Requirement 5 of Schedule 2 of the	
		draft DCO [REP6-005 and REP6-006].	
		Potential impacts from construction will	
		be considered as part of the Heritage	
		Management Plans detailed in the	
		OEMP [PW-CH1 and MW-CH1] which	
		will indicate how the historic environment	
		is to be protected in a consistent and	
		integrated manner including from	
		potential impacts of construction. The	
		National Trust will be consulted upon on	
		these plans (for works within the WHS)	
		as part of HMAG. HEMPs (see	
		paragraphs 1.1.12, 3.1.3 and MW-G11 in	
		the OEMP) will be based on the final	



					CEMPs which will be consulted upon as described above. Section MW LAN1 of the OEMP requires the mains work contractor to prepare a Landscape and Ecology Management Plan (LEMP), which will be appended to the CEMP as appropriate. This will be consulted on with Wiltshire Council and Natural England as the appropriate consultation bodies for such matters. In respect of the other documents set out in National Trust's submissions, consultation with the National Trust is set out in the OEMP in the following items: PW CH3 Site Specific Written Schemes of Investigation, produced in consultation with HMAG for works within the WHS, to describe the mitigation measures that will be carried; and PW CH4 and MW CH5 Method Statements, produced in consultation with HMAG for works within the WHS, to include protective fencing for identified heritage assets and appropriate archaeological mitigation measures.	
<u>4.3</u> <u>3.45</u>	[RR-2344] WR [REP2-115]	5.1.6 6.8.1 9	Land - Restrictions on National Trust land	The Trust has previously stated its concerns over the Tunnel Protection Zone and the restrictive covenants to be affected on the Trust's estate above the tunnel, including concerns in relation to protection of archaeology and future archaeological research. Discussion has been ongoing with the Applicant and HMAG on this issue. The Trust is now recently in possession of	Agreed Highways England await any outstanding concerns.	Under- Discussion Pagreed



4.5 3.46	[RR-2344]	<u>5.1.9</u>	Operational phase –	the draft covenants proposed to be imposed on Trust land, and once we have reviewed this document we will make further comment if any outstanding concerns remain. This restrictive covenant is now agreed. Further clarity is needed around the types and frequency of activities which will need to	The operation of the Scheme, including, for example, the use of the Scheme by	Under- Discussio
			ground monitoring	be carried out once the proposed scheme is operational, how the impact of this activity will be assessed and how the Trust will interact with Highways England and their agents in this regard. The Trust has been provided with information relating to initial proposals for future ground monitoring. It agrees in principle with an approach and methodology that would have minimum impact in installation and removal of equipment. The Trust seeks security on these principles. The Trust is content that the process of developing the Ground Monitoring Movement Strategy and the Heritage Management Plan would enable sufficient controls in respect of how ground monitoring is to be carried out.	road users and the operational plant within the tunnel, is assessed through the EIA, as reported in ES Chapters 5 to 16 [APP-043 – APP-053]. As set out in the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012], which is secured through requirement 4 of Schedule 2 of the draft DCO [REP6-005 and REP6-006], the main works contractor will be required to prepare a HEMP (MW-G11). The HEMP will provide the relevant information on existing and future environmental commitments and objectives that would need to be honoured and define on-going actions and risks that need to be managed and will be consulted upon with the Environment Agency, Wiltshire Council, Natural England and Historic England on matters related to their functions. As with the physical design of the scheme, details of operational activities will be developed through the detailed design process. Where relevant to interests of the National Trust and required by the consultation arrangements agreed between us, the	Agreed



	1		
		details will be developed in consultation	
		with the National Trust.	
		Ground monitoring will be required as	
		part of the tunnel construction works,	
		including baseline monitoring prior to	
		construction and possible continued	
		monitoring following completion of	
		construction and into the operational	
		phase. These movement monitoring	
		stations/points are referenced (alongside	
		the archaeological mitigation associated	
		with them) in the DAMS, and types and	
		frequency of activities will be detailed in	
		the CEMP and Heritage Management	
		Plans.	
		Details on the movement monitoring	
		stations have been included in the	
		DAMS (paragraphs 5.2.8 to 5.2.10),	
		which define that "a zero-ground	
		disturbance, fully reversible surface	
		mounted installation will be adopted" for	
		baseline monitoring. A Ground	
		Movement Management Strategy will be	
		prepared by the Main Works contractor	
		in consultation with the members of	
		HMAG (including National Trust) to	
		describe the monitoring proposed to be	
		carried out.	
		Agreed – Since the drafts of the relevant	
		documents referred to above, further	
		drafts have been produced and agreed	
		dealing with the relevant issues between	
		Highways England and National Trust.	
		To confirm the absence of any adverse	
		influence regardless of predicted effects.	
		monitoring regimes shall be developed	
		<u> інонногіні і гедініе s shall be developed </u>	



					by the appointed contractor. The OEMP requires under reference MW-CH8 that "The main works contractor shall develop a Ground Movement Monitoring Strategy, to be prepared in consultation with the members of HMAG (which includes National Trust) and to be approved by the Authority. The strategy will identify heritage assets that are atrisk from ground vibration from the tunnel, or from ground surface movement caused by settlement. As part of this strategy, the contractor shall develop contingencies and identify measures to ensure the protection of assets: It is anticipated that for settlement, this will include monitoring points (settlement markers) with manual monitoring by carrying out a levelling survey or by a fixed monitoring instrument. The contractor's monitoring during construction will continue until such time as there is no further movement measured.	
4.6 3.47	[RR-2344] WR [REP2-115]	6.1 & 7.1 6.5.5	Land Take – general objection	At this stage, the Trust objects to the acquisition of this [the land owned by the Trust and held inalienably] land on the grounds of the outstanding issues raised. These issues represent significant reasons why land held by the Trust for the benefit of the nation should not be released for the purposes of the scheme until they are adequately resolved to the Trust's satisfaction, and solutions secured in the	Agreed Highways England will continue to work with the National Trust to understand and address its outstanding concerns and work towards the removal of the National Trust's objection. Highways England has set out in the Statement of Reasons [APP 023] why the land owned by the National Trust is required and that there is a compelling case in the public	Under- Discussio n Agreed



				final form of any confirmed DCO documentation. It is a matter of record that the land proposed for acquisition is held inalienably to which the provisions of section 130 Planning Act 2008 apply. The engoing negotiations between National Trust and the Applicant are also allowing the Trust to keep under review the extent of the safeguards generally that are being offered to the Trust in terms of protections available to it and in the light of the robustness of those safeguards, whether the objection that the Trust is presently maintaining to acquisition of its land by compulsion can be withdrawn. The objection to acquisition of National Trust inalienable land by compulsion has now been withdrawn.	interest for this land to be compulsorily acquired. Highways England understands that the land owned by the National Trust which it is proposing to compulsorily acquire pursuant to the DCO is held inalienably.	
<u>4.7</u> <u>3.48</u>	[RR-2344] WR [REP2-115]	7.2 6.5.3 6.8.1 and 6.8.2	DCO - Communicat ion / consultation	The Trust would agree that in so far as their relevant statutory functions are concerned in this regard, where discharge or approval is required, that Historic England or WCAS should be the appropriate bodies to play that role. Within the WHS, the Trust believes that in addition to Historic England, and WCAS, both the National Trust and English Heritage hold important and relevant expertise which should be considered across a range of matters. This is why HMAG too has an important role to play in providing advice, setting requirements, and monitoring archaeological mitigation within the WHS, one which should not be subjugated. Whilst HMAG is tied into several facets of	Alterations have been made throughout the examination to the OEMP, which is secured through requirement 4 of Schedule 2 of the draft DCO [REP6-005-and REP6-006]. The Applicant submitted an update to the OEMP for Deadline 6 [REP6-011 and REP6-012] and the National Trust's role in the updated OEMP is discussed further below. Highways England has included measures within the Scheme to secure engoing involvement with the National Trust (as a member of HMAG) with respect to how the Scheme is carried out	Under- Discussion national Agreed



consultation, there remains an issue about unclear process and consistency in approach of consultation with the Heritage Stakeholders. This is true for both controls within the DAMS and the OEMP. We are working with the Applicant and the other Heritage Stakeholders to resolve this matter. One that in our submission, is not insurmountable. We are awaiting the version of the DAMS that the Applicant is due to submit at DL6, and will be able to comment further in due course.

As noted under 3.44, detailed arrangements have been put in place to cater for consultation on the scheme, including Highways England commitments to consultation of HMAG and the Trust, and so this is now resolved.

and its impact on the WHS. Highways England has also secured the delivery of the design solutions designed to minimise the impact of the Scheme on the WHS, which also involveconsultation with HMAG. Further detailof these measures is provided below. demonstrating the means that are inplace to ensure the Scheme will not be designed or constructed in an inappropriate manner. Consultation with the National Trust is secured in two keyways: Firstly, paragraph 4 of Schedule 2 to the draft DCO IREP6-005 and REP6-0061 requires Highways England to carry out the Scheme in accordance with the OEMP. The OEMP requires the contractor to develop Construction Environmental Management Plans ("CEMP") for the Scheme, which mustbe prepared in accordance with the principles of the OEMP. The OEMP requires the preliminary works CEMP to include for the preliminary works: PW-CH1 -- a Heritage Management-Plan, prepared in consultation with the members of HMAG (of which National Trust is a member) (for works within the WHS) and Wiltshire Council Archaeological Service (for works outside the WHS); PW-CH3 - Site Specific Written Schemes of Investigation, produced inconsultation with members of HMAG. todescribe the mitigation measures that will be carried:



PW-CH4 Method Statements. produced in consultation with members of HMAG for works within the WHS, to include protective fencing for identified heritage assets and appropriate archaeological mitigation measures; PW-CH5 — Site Specific Written— Schemes of Investigation, produced inconsultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written— Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological remains where possible and implement appropriate.	produced in consultation with members of HMAG for works within the WHS, to
of HMAG for works within the WHS, to include protective fencing for identified heritage assets and appropriate archaeological mitigation measures: PW CH5 — Site Specific Written Schemes of Investigation, produced inconsultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW CH6 — Site Specific Written Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate	of HMAG for works within the WHS, to
include protective fencing for identified heritage assets and appropriate archaeological mitigation measures: PW_CH5_Site Specific Written Schemes of Investigation, produced inconsultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW_CH6_Site Specific Written Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate	
heritage assets and appropriate archaeological mitigation measures; PW-CH5 — Site Specific Written Schemes of Investigation, produced in consultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written Schemes of Investigation, developed in consultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	
archaeological mitigation measures: PW-CH5 — Site Specific Written Schemes of Investigation, produced in- consultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written Schemes of Investigation, developed in- consultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	include protective fencing for identified
PW-CH5 — Site Specific Written. Schemes of Investigation, produced inconsultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written. Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures.	heritage assets and appropriate
Schemes of Investigation, produced inconsultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6—Site Specific Written—Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures.	archaeological mitigation measures;
consultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW CH6 — Site Specific Written— Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures.	PW-CH5 - Site Specific Written
consultation with members of HMAG, to include measures to install temporary barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW CH6 — Site Specific Written— Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures.	Schemes of Investigation, produced in
barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written Schemes of Investigation, developed in consultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	
barrier fencing to limit land disturbance at the western portal and eastern portal approaches; PW-CH6 — Site Specific Written Schemes of Investigation, developed in consultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	include measures to install temporary
approaches; PW-CH6—Site Specific Written Schemes of Investigation, developed inconsultation with members of HMAG forworks within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	
PW CH6 Site Specific Written Schemes of Investigation, developed in eonsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	at the western portal and eastern portal
Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	approaches;
Schemes of Investigation, developed inconsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	PW-CH6 Site Specific Written
eonsultation with members of HMAG for works within the WHS, to include measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	
measures to avoid significant archaeological remains where possible and implement appropriate archaeological mitigation measures	consultation with members of HMAG for
archaeological remains where possible and implement appropriate archaeological mitigation measures	works within the WHS, to include
and implement appropriate archaeological mitigation measures	measures to avoid significant
archaeological mitigation measures	archaeological remains where possible
	and implement appropriate
where impacts are unavoidable;	archaeological mitigation measures
	where impacts are unavoidable;
PW-LAN1 – requires consultation with	PW-LAN1 - requires consultation with
members of HMAG prior to the	members of HMAG prior to the
installation of fencing to protect retained	installation of fencing to protect retained
vegetation within the WHS.	vegetation within the WHS.
In respect of the main works the OEMP	In respect of the main works the OEMP
requires the main works CEMP to	requires the main works CEMP to
include:	include:
MW-CH1 - Heritage Management Plan	MW-CH1 - Heritage Management Plan
based on the Detailed Archaeological	
Mitigation Strategy (see requirement 5 of	
Schedule 2 to the draft development	based on the Detailed Archaeological
consent order [REP6-005 and REP6-	based on the Detailed Archaeological Mitigation Strategy (see requirement 5 of
0061), prepared in consultation with the	based on the Detailed Archaeological Mitigation Strategy (see requirement 5 of Schedule 2 to the draft development
members of HMAG and Wiltshire	based on the Detailed Archaeological Mitigation Strategy (see requirement 5 of Schedule 2 to the draft development consent order [REP6-005 and REP6- 006]), prepared in consultation with the



	1		I I
		Council Archaeological Service,	
		indicating how the historic environment	
		is to be protected in a consistent and	
		integrated manner.	
		MW-CH3 requires consultation with the	
		members of HMAG on the type of	
		construction boundary fencing to be-	
		used within the WHS or its setting and to	
		be included in an Archaeological Method	
		Statement forming part of a main works	
		CEMP;	
		MW-CH5 requires the development in	
		consultation with the members of HMAG	
		for works within the WHS, of	
		Archaeological Method Statements	
		describing the appropriate measures to	
		be used where potentially sensitive	
		archaeological remains are required to	
		be buried or sealed beneath fill material;	
		MW-CH6 requires the preparation, in	
		consultation with the members of HMAG	
		for works within the WHS, of Site	
		Specific Written Schemes of	
		Investigation in respect of service/utility	
		corridors requiring excavations, to avoid	
		archaeological remains wherever	
		possible and implement appropriate	
		archaeological mitigation measures	
		where impacts are unavoidable;	
		MW-CH7 requires appropriate	
		monitoring arrangements for all heritage	
		assets during the construction	
		programme, prepared in consultation	
		with the members of HMAG for works	
		within the WHS.	
	•	<u> </u>	1



			Secondly, paragraph 5 of Schedule 2 to	
			the draft DCO [REP6-005 and REP6-	
			0061 requires the Scheme to be carried	
			out in accordance with the DAMS	
			REP6-013 and REP6-014]. Highways	
			England has submitted a document that	
			further clarifies the relationship between	
			the DAMS and the OEMP. As stated in	
			the OEMP e.g. PW-CH1 and MW-CH1	
			for HMPs, members of HMAG will be	
			consulted before Highways England as	
			'the Authority' approves the	
			documentation. The consultation	
			provided for in the OEMP will ensure that	
			the views of HMAG are taken into	
			account in finalising the documentation,	
			prior to Highways England's approval.	
			The OEMP also provides for landowners	
			to be informed of the programme and	
			activities during both the preliminary	
			works phase (see PW-COM1 of the	
			OEMP) and the main works phase (see	
			MW-COM1 of the OEMP). Other key	
			design elements, designed having	
			regard to the impact of the Scheme on	
			the WHS, that are secured via the	
			OEMP include:	
			D-CH8 - requires no signage or other	
			vertical installations (such as CCTV)	
			above the top of the cutting and no	
			lighting of signs at the western end of the	
			Scheme in order to protect the WHS's	
			OUV;	
			D-CH2 and D-CH3 which require the	
			redundant sections of the road surface to	
			the existing A303 and A360 (including	
<u> </u>			and oxiding mode and mode (including	



	1		
		the existing Longbarrow Roundabout) to	
		be broken out, save to the extent they	
		are required for public rights of way;	
		D-CH4 - requires Green Bridge No. 4 to	
		be between 145m and 149.9m wide;	
		D-CH5 — which requires the western	
		approach to the tunnel to be in cutting to	
		a minimum 7m depth with vertical	
		retaining walls;	
		D-CH6 and D-CH7 — which require cut	
		and cover tunnels extending eastwards	
		and westwards from the bored tunnel;	
		D-CH9, D-CH10, D-CH11 and D-CH12	
		which taken together limit the use of	
		highway lighting within the WHS and	
		require improved lighting at Countess	
		roundabout.	
		Iounuapout.	
		Section 4 of the OEMP now also	
		includes the design vision and a range of	
		Scheme wide and WHS specific design	
		principles; and also for consultation with	
		the National Trust (as part of the	
		Stakeholder Design Consultation Group)	
		on key elements of the design with the	
		WHS.	
		The OEMP (a revised version of which	
		was submitted at Deadline 6 [REP6-011	
		and REP6-012]) therefore provides	
		assurance that the design solution will	
		be transmitted into the requirements of	
		the main works contractor and that the	
		National Trust, as a member of HMAG.	
		will be consulted with regards to the	
		design solution. Potential impacts from	
1		accign contact in bacte from	



					construction will be considered as part of the Scheme-wide HMP detailed in the OEMP (PW-CH1 and MW-CH1) which will indicate how the historic environment is to be protected in a consistent and integrated manner including from potential impacts of construction. The implementation of the OEMP is secured by Requirement 4 of schedule 2 of the draft DCO [REP6-005 and REP6-006]. The OEMP (MW-CH7) allows for monitoring arrangements for designated and non-designated heritage assets to be prepared in consultation with the members of HMAG (for sites within the WHS) and WCAS (for sites outside of the WHS) and approved by The Authority prior to works commencing.	
4.8 3.49	WR [REP2-115]	6.8.8	Rights of Way and non- motorised users – Surfacing of new restricted byways on A360	It is not clear from the submitted documentation what the width or the surface treatment of the new restricted byway running north south along the existing alignment of the A360 would be (6.1 Environmental Statement, Chapter 2, 2.3.57). In order to minimise adverse visual impacts on the OUV of the WHS and secure its protection we seek provision that: a) there should be no new bound surface on the new PRoW of the A360. A bound surface (with a maximum width of 3m) could be put in place along the line of the existing A360 (where this road becomes redundant).	The width of the restricted byway is as set out in the design principles in OEMP (D-CH26) as issued at Deadline 9 – where it states that these 'shall be a maximum of 3m in width'. This design principal (D-CH26) also clarifies that the SDCG will be consulted with regards to the surface treatment. P-PROW1 also provides that public rights of way and private means of access will have a surface that is appropriate to their use and location, developed in consultation with the SDCG. Highways England disagrees that any new bound surface on the A360 would represent an adverse impact on the Winterbourne Stoke Crossroads Barrows	Under- discussion Agreed



The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP would provide sufficient controls in respect of public rights of way, provided that those protections are complied with as required throughout the life of the scheme and their setting. The existing A360 already has a major adverse impact on the group. Downgrading to an NMU and realigning the road to the west is assessed as having a Moderate Beneficial effect on the Asset Group in the ES Chapter 6 [APP-044, Table 6.11: Summary of significant effects—
design principles and consultation requirements set out in the final OEMP would provide sufficient controls in respect of public rights of way, provided that those protections are complied with as required the group. Downgrading to an NMU and realigning the road to the west is assessed as having a Moderate Beneficial effect on the Asset Group in the ES Chapter 6 [APP 044, Table 6.11:
requirements set out in the final OEMP would provide sufficient controls in respect of public rights of way, provided that those protections are complied with as required realigning the road to the west is assessed as having a Moderate Beneficial effect on the Asset Group in the ES Chapter 6 [APP 044, Table 6.11:
would provide sufficient controls in respect of public rights of way, provided that those protections are complied with as required assessed as having a Moderate Beneficial effect on the Asset Group in the ES Chapter 6 [APP 044, Table 6.11:
of public rights of way, provided that those protections are complied with as required the ES Chapter 6 [APP-044, Table 6.11:
protections are complied with as required the ES Chapter 6 [APP-044, Table 6.11:
development and construction (covered construction (permanent)) and the
elsewhere). Heritage Impact Assessment [APP-195,
Table 11: Summary of assessed impacts
and effects of the existing A303 and
anticipated impacts and effects of the
Scheme on Asset Groups conveying
Attributes of OUV].
Within the WHS, commitments with
regard to surfacing are set out at items
D-CH2, D-CH3 and D-CH14 of the
OEMP (a revised version of which was
submitted at Deadline 6 [REP6-011 and
REP6-012]) which provide for,
respectively, the breaking up of the
redundant A303 and A360 within the
WHS, and that provision of surfacing
within the WHS shall be developed in
consultation with National Trust, Historic
England, English Heritage and Wiltshire
Council. Through the ongoing Heritage
Partners Design Review meetings, the
Applicant has developed a series of
Design Principles to guide the detailed
design of elements of the Scheme,
including the public rights of way, which
is incorporated into the updated OEMP
as Chapter 4.



<u>4.9</u> <u>3.50</u>	WR [REP2-115]	6.8.8	Rights of Way and non- motorised users – A360 and A303 maintenance strategy Decommissi oning of the A303	d) there must be a maintenance strategy agreed that ensures that the surface approach continues to be applied throughout the maintenance agreement and any successor agreements. And those services providers who may need access to services beneath this surface must be required to make any repairs using the surfacing approach as defined above. Requirements: clarification is sought on the maintenance, management, and future liability responsibilities for the land of what will become the decommissioned A303 The Trust is now in agreement that the consultation arrangements now in place adequately provide means to address this issue.	The future management of the length of decommissioned A303 to become restricted byway will become the responsibility of Wiltshire Council as public rights of way authority and the mechanics for this handover will be dealt with in a legal agreement between Highways England and Wiltshire Council. Highways England intends to retain responsibility for the section of decommissioned A303 to the east of Stonehenge Road – this area is expected to be managed as part of its soft estate. Controls over the extent and design of the works, how they will be carried out and thereafter operated are contained in the OEMP, including in particular provision of a HEMP, an updated version of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013], secured via requirement 4 of Schedule 2 to the draft DCO [REP6-005 and REP6-006 REP9-004]. As per point 3.44, National Trust has now been included as a consultee on the HEMP. This is now agreed.	Under- discussion Agreed
<u>4.14</u> <u>3.51</u>	WR [REP2-115]	6.4.2	Biodiversity, biological environment and ecology - Seed mixtures	ES Chapter 8 Page 8-45 8.4.4 states that 'all green bridges would be sown or planted with suitable plant species to facilitate the movement of the biodiversity features' and ES Chapter 8 Page 8-47 8.8.16 states chalk bunds on green bridges and areas of false cuttings and embankments will be seeded and planted with larval food plants for butterflies. It also states that areas of new calcareous grassland will also be included.	As set out in the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012 REP9-013]), MW-BIO2, the main works contractor must establish the new habitats identified within the Environmental Masterplan (ES Figure 2.5) [APP-059] within the Order limits and manage them accordingly to ensure their establishment and development to	Under- Discussio n Agreed



However, Appendix 8.26 Outline Landscape and Ecology Management Plan Table 6.2 provides detail of a typical wildflower seed mixture that excludes the larval food plants for key chalk grassland butterflies. In order to provide suitable conditions for butterflies and to benefit an expanded range of insect groups (such as moths and pollinators including bees, for which preferential pollen sources and extended food sources of pollen and nectar, including late flowering species, are critical) the National Trust requests the below. Requirements: the National Trust asks that the list of wildflower species is expanded, with a targeted planting scheme implemented along the entire length of the chalk grassland habitat. to include seeds and wildflower plugs of additional species including but not limited to:

Table 1:

Latin Name	Common Name
Succisa pratensis	Devil's-bit scabious
Hippocrepis comosa	Horseshoe vetch
Helianthemum nummularium	Common rockrose
Viola hirta	Hairy violet
Rumex asetosa	Common sorrel
Echium vulgare	<u>Vipers bugloss</u>
Centaurea nigra	Common knapweed

achieve their target purpose(s), through to any handover of the Scheme. In addition, under the requirement in paragraph 8 of Schedule 2 to the draft DCO [REP6-005 and REP6-006REP9-0041, a detailed landscaping scheme must be submitted to the Secretary of State for approval. This must be based on the mitigation measures set out in the ES, including the principles set out in the Outline Landscape and Ecology Management Plan ('OLEMP') [APP-267]. In addition, the OEMP, at item MW-LAN1, requires the development of a Landscape and Ecology Management Plan. The objectives will be to create a mosaic of early-successional habitats ranging from bare ground to species-rich low nutrient swards. The selection of species will be carried out during detailed design and the preparation of the detailed landscaping scheme. As such, no further commitment is required. As per point 3.44, National Trust has now been included as a consultee on the

LEMP. This is now agreed.



				Campanula rotundifolia Knautia arvensis Euphrasia nemerosa Campanula glomerata Stachys officinalis Serratula tinctoria Filipendula vulgaris Odontites vernus Trifolium pratense The Trust is content threquirements and desi design principles and orequirements set out in would provide sufficier of seed mixtures, prov protections are complithroughout the life of the development and conselsewhere).	gn commitments, consultation the final OEMP at controls in respect ided that those ed with as required the scheme		
<u>4.15</u> <u>3.52</u>	WR [REP2-115]	6.4.3	Biodiversity, biological environment and ecology - Scrub encroachme nt	Chapter 8, Page 8.47, will be carried out to possible development of scrub' Requirement: clarificate future management reareas to prevent scrub areas of open grasslant has been identified as	tion is required on the sponsibilities of these encroachment onto	As set out in the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012 REP9-013]), MW-BIO2, the main works contractor must establish the new habitats identified within the Environmental Masterplan (ES Figure 2.5) [APP-059] within the Order limits	Under- Discussio n Agreed



how essential infrastructure such as fencing and manage them accordingly to ensure and water supplies will be provided. their establishment and development to achieve their target purpose(s), through to any handover of the Scheme. The Trust is content that the DCO As described in the OEMP-IREP6-011 requirements and design commitments, and REP6-012], MW-BIO13, botanical design principles and consultation monitoring must be carried out to inform requirements set out in the final OEMP appropriate management of the chalk would provide sufficient controls in respect grassland and other habitats within the of scrub encroachment, provided that those Scheme. This will inform the protections are complied with as required management action of 'grazing, mowing, throughout the life of the scheme control of scrub, and specific habitat development and construction (covered management to create or maintain elsewhere). conditions of characteristic species of chalk grassland and other habitats'. Example management measures which will be confirmed within the detailed Landscaping Scheme to be submitted for approval by the Secretary of State under Requirement 8 of the draft DCO [REP6-005 and REP6-006REP9-004] and the LEMP required to be developed under item MW-LAN1 of the OEMP and could include, where practicable, managing chalk grassland by appropriate grazing to maximise gains in biodiversity. providing, in any areas where chalk grassland is to be managed by grazing, appropriate fencing and stock watering facilities. In addition, where areas of chalk grassland are not managed by grazing, mowing will be used to manage the grassland to achieve biodiversity and other objectives, with periodic control of scrub as necessary (paragraph 7.2.2 of the OLEMP [APP-267]), the principles of



		I			111 201 0 0 11 0 1 0 1	
					which will be reflected in the detailed	
					landscaping scheme, to be submitted.	
					As per point 3.44, National Trust has	
					now been included as a consultee on the	
					LEMP and HEMP. This is now agreed.	
4.16	WR	6.4.4	Biodiversity,	Where land is being acquired on a	The OEMP (a revised version of which	Under
3.53	[REP2-115]		biological	temporary basis, including National Trust	was submitted at Deadline 69 [REP6-	Discussio
	[11212110]		environment	land, detail is required on remediation prior	011 and REP6-012REP9-013], is the	n
			and ecology	to return to landowners, and how delivery of	basis from which detailed, works-specific	Agreed
			-	the ongoing management necessary to	CEMPs will be prepared by the relevant	<u>/ (groot</u>
			Remediation	achieve the successful establishment of	contractors, as is required by the OEMP	
			of land	species rich chalk grassland will be secured.	itself and therefore secured through	
				Where land is being acquired and	paragraph 4 of Schedule 2 of the draft	
				permanently retained a mechanism should	DCO [REP2-033REP9-004]. The OEMP	
				be implemented to ensure land being	sets out the requirement for the main	
				restored to species rich grassland is under	works contractor to prepare a LEMP	
				appropriate ownership to allow for the	(MW-LAN1), in accordance with industry	
				ecological objective to be met. Inadequate	good practice. The principles for the	
				management such as insufficient or	LEMP are set out in the OLEMP [APP-	
				inappropriate timing of grazing or cutting,	267]. Under requirement 8 of Schedule 2	
				failure to remove cuttings, or failure to	of the draft DCO [REP6-005 and REP6-	
				prevent scrub encroachment will prevent the	006REP9-004], Highways England will	
				successful establishment of species rich	be required to submit a detailed	
				chalk grassland. In additional an ongoing	landscaping scheme to the Secretary of	
				programme of monitoring and wildflower	State for approval, which is required to	
				sward supplementation of species not	be on the basis of the mitigation	
				represented is required to ensure species	measures set out in the ES, which	
				rich chalk grassland is created.	includes the OLEMP, and will	
				The Trust is content that the DCO	incorporate management obligations. In	
				requirements and design commitments,	addition, under article 29 of the draft	
				design principles and consultation	DCO, Highways England (subject to	
				requirements set out in the final OEMP	certain exceptions) is under an obligation	
				would provide sufficient controls in respect	to restore land which is subject to	
				of remediation of land, provided that those	temporary possession powers to the	
				protections are complied with as required	reasonable satisfaction of the owners of	
				throughout the life of the scheme	the land before handing it back.	



			development and construction (covered elsewhere).	As per point 3.44, National Trust has now been included as a consultee on the LEMP. This is now agreed.	
4.18 3.54	WR [REP2-115] 6.1	Heritage and historic environment - Ground Settlement impacts	The Applicant states that, 'it is assumed that,' ground settlement will be minimal at the surface, but no evidence is provided to support this 6.1 Environmental Statement Chapter 6, 6.4.1 i) Requirements: given the sensitivity of archaeological deposits and monuments to ground and sub-surface disturbance, we consider that further evidence needs to be submitted by the Applicant to demonstrate the scale of any surface ground settlement and assess the adequacy of proposed mitigation, and to identify any residual impacts on monuments that convey the attributes of OUV of the WHS. The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP and DAMS would provide sufficient controls in respect of ground settlement impacts, provided that those protections are complied with as required throughout the preliminary works and main works phases and detailed design development (covered elsewhere).	The predicted effects of excavation induced ground settlement have been considered as part of a staged assessment used in tunnelling to determine the zone of influence and potential structures and archaeology affected during construction (Land Instability Risk Assessment [APP-278], Section 6.4). The Land Instability Risk Assessment [APP-278] predicts that ground surface movement above the tunnel will be limited to 20-30mm as a maximum. ES Chapter 6 - Cultural Heritage [APP-044] therefore notes: "It is assumed that ground settlement will be minimal at the surface from the boring of the twin bored tunnel and any changes to heritage assets on the surface would be negligible and imperceptible to the eye" ([APP-044] para. 6.4.1 (i)), and "It is assumed that vertical and lateral displacement from the excavation of deep cuttings or the retained cut will be minimal and any changes to heritage assets on the surface would be negligible and imperceptible to the eye" ([APP-044] para. 6.4.1 (i)). Items PW-CH1 and MW-CH1 of the OEMP (a revised version of which was submitted at Deadline 69 [REP6-011 and REP6-012REP9-013]) require the	Under-Discussion-Agreed



	numbination and use and use also use also	
	preliminary works and main works	
	contractors to produce HMPs indicating	
	how the historic environment is to be	
	protected in a consistent and integrated	
	manner, coordinated with all other	
	relevant environmental topics. This	
	includes the potential indirect impacts on	
	heritage from activities such as ground	
	vibration and ground movement /	
	subsidence. Items PW-NOI4 and MW-	
	NOI5 of the OEMP [REP6-011 and	
	REP6-012] identify industry guidance	
	that the preliminary works and main	
	works contractors are to follow in relation	
	to controls and working methods for	
	managing vibration. This guidance	
	specifically refers to ground borne	
	vibration from tunnelling. They also	
	require the preliminary works and main	
	works contractors to identify any	
	potentially vibration sensitive cultural	
	heritage assets and actions to control or	
	mitigate impacts, including monitoring.	
	Notwithstanding the above, in the OEMP	
	(a revised version of which was	
	submitted at Deadline 6 [REP6-011 and	
	REP6-012]) a specific item has been	
	added to require a ground movement	
	monitoring strategy to be developed by	
	the main works contractor.	
	The installation of monitoring equipment	
	and programme of monitoring to monitor	
	ground movement above the tunnel will	
	be included as part of the HMP required	
	by item PW-CH1 and MW-CH1 of the	
	OEMP IREP6-011 and REP6-012] . The	
	OCIVIP IREPO UTI AND REPO UTI . The	



_						
					nonitoring methodology instigated as	
				pa	art of the HMP will consider acceptable	
				le	evels and identify the associated action	
					response as part of a pre-planned	
					ontingency plan. The general principle	
					s to control the works such that	
					nacceptable levels are not breached	
					nd put in place a warning of trends	
					hich may approach unacceptable	
					evels.	
					will be the responsibility of the	
					ontractor to ensure risks are assessed	
					nd mitigated in their safe systems of	
					york during construction, pursuant to the	
					DEMP (a revised version of which was	
					ubmitted at Deadline 6 [REP6-011 and	
					EP6-012]). As part of this plan, the	
					ontractor will develop contingencies	
					sing a suite of tool box items from	
					urther investigation, assessment and	
					nonitoring during construction to identify	
					neasures to ensure the protection of	
				as	ssets. This could range from simply	
				sl	lowing down the TBM to instigating	
				gı	round stabilisation measures including	
				gı	routing. Where the need for ground	
				st	tabilisation is identified this will be	
				uı	ndertaken from inside the main tunnel	
				bo	ore where it is safe and practicable to	
				do	o so in preference to surface	
					ntervention. Other methods for the	
					round stabilisation specifically for	
					onstruction of the cross-passage	
					unnels could include fissure grouting	
					nd local face depressurisation	
					acilitated from the main TBM tunnels;	
	ļ	Į		10	contatod north tho main 1 Divi tallilolo,	



					further enhanced ground support can be	
					provided by the installation of pipe	
					umbrellas or spiles. These methods	
					have been successfully employed on the	
					recent (2013) Crossrail C310 Thames	
					Tunnel project through the chalk aquifer.	
					With these mitigation mechanisms in	
					place, the assumptions as set out in ES	
					Chapter 6 [APP-044], para. 6.4.1 (i) and	
					para. 6.4.1 (j) still stand, and there will	
					be no significant effects on monuments	
					that convey the attributes of OUV of the WHS.	
					As per point 3.44, National Trust has	
					now been included as a consultee on the	
					HMP and Ground Movement Monitoring	
					Strategy. This is now agreed.	
4.19	<u>WR</u>	6.8.1	Heritage and	The creation of intermittent scrub habitat	The scrub proposed within the WHS is to	Under
<u>3.55</u>	[REP2-115]	<u>3</u>	historic	within the WHS, for example on the western	aid connectivity for bats and this is in is	Discussio
			environment	approaches to Green Bridge 4 (6.1	the vicinity of the Eastern Portal. There	<u>n</u>
			- Scrub	Environmental Statement Chapter 6, 6.8.5 d)	is also replacement scrub proposed at	Agreed
				is in direct contradiction with Priority 1 of the	the bottom of the dry valley to the east of	
				Stonehenge & Avebury and Associated	the eastern portal and around the	
				Sites WHS Management Plan (2015) which	drainage basins at Countess junction.	
				requires the management of scrub for the	The requirement contained in paragraph	
				protection of archaeology. The introduction	8 of Schedule 2 to the draft DCO [REP6-	
				of scrub would also introduce a visual	005 and REP6-006REP9-004] requires a	
				intrusion that would have an adverse impact	detailed landscaping scheme to be	
				on the visual relationships between the	submitted for approval by the Secretary	
				Winterbourne Stoke Barrow Group and the	of State. This must reflect the mitigation	
				Diamond Group i.e. the adverse impact on	measures set out in the Environmental	
				OUV that Greenbridge 4 is intended to	Statement, which include the principles	
				mitigate.	set out in the OLEMP [APP-267]. In	
				Requirements: the National Trust therefore	addition, the OEMP contains a number	
1				-		
				seeks assurance that other than for essential and proportional mitigation (where	of landscaping obligations, such as the requirement to develop a LEMP (MW-	



 WR [REP2-115]	6.8.1 6	Heritage and historic environment – Creation of New Earthworks within the	this does not adversely impact OUV) to provide habitat connectivity e.g., for bats, no new scrub is created within the WHS. The Trust is content that the DCO requirements and design commitments, design principles and consultation requirements set out in the final OEMP would provide sufficient controls in respect of scrub, provided that those protections are complied with as required throughout the life of the scheme development and construction (covered elsewhere). The creation of new earthworks within the WHS would create an adverse impact on the Authenticity of the WHS and negatively impact the legibility of existing earthworks forming part of monuments that contribute to the OUV of the WHS. We are therefore concerned that contra to discussions with,	LAN1) and botanical monitoring (MW-BIO13), which makes provision for control of scrub. As such, appropriate habitat and suitable management regime will be put in place through this mechanism. No further requirements are therefore appropriate. The OEMP has been updated in a submission at Deadline 9 [REP9-013] to enable the control of height and spread of scrub of the replacement scrub at the dry valley. This is now agreed. Earthworks are referred to within Table 7.3 of APP-045 to describe the embankments or cuttings that are proposed as part of the changes to landform. The Applicant can confirm that at the detailed design the shallow embankment that crosses the dry valley.	Under- Discussio n Agreed
			and HMAG the Applicant states that new embankments will be created within the WHS scheme (6.1 Environmental Statement Chapter 7, Table 7.3 final paragraph). In Plans and Drawings 2.9 a new section of embankment can be seen above the top of the cut on the northern side of the approach to the eastern portal, and is referred to as, 'new embankment formationsup to 1m above ground level,' between the Eastern Portal and Countess roundabout'(6.1 Environmental Statement Chapter 7, 7.9.13). Here the approach to the portal appears to be placed in a false cutting where the cut crosses the head of the dry valley. This is in a sensitive location within the WHS in	issue would be graded out to tie into existing ground levels and this specific aspect of the Scheme would not negatively impact upon the Authenticity or OUV of the WHS. This detailed design intent is supported by the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), which has been updated to include a requirement that there shall be no permanent raised earthworks within the WHS other than those required for the construction of the Countess flyover (D-CH28) and that new landscaping should reflect and integrate with the	





matters. This is why SCG too has an important role to play, one which should not be subjugated. Whilst SCG is tied into several facets of consultation, there remains an issue about unclear process and consistency in approach of consultation with the Heritage Stakeholders. This is true for both controls within the DAMS and the OEMP. The nature of resolution in cases of disagreement is an element of this discussion. We are working with the Applicant and the other Heritage Stakeholders to resolve this matter and to develop this within the OEMP and if necessary in side agreementvia agreed arrangements outside of the OEMP. b) Schedule 2. Requirement 4: The Trust does still have outstanding concerns in relation to the amended OEMP submitted at DL4 and with the provision for consultation contained therein. We are working with the Applicant to address those concerns: and awaiting the version of the OEMP that the Applicant is due to submit at DL6, and will comment further in due course. The Trust believes that the approval of the CEMP (and HEMP) is of sufficient importance that the Trust should have involvement as a key stakeholder in consultation on its formulation, monitoring, and amendment. c) Schedule 2, Requirement 5: Requirement 5 states that the authorised development must be carried out in accordance with the DAMS. An Outline Archaeological Mitigation Strategy (OAMS) was included with the application as appendix 6.11 to the

b) Discussions between the Applicant and the National Trust during the examination are continuing. The OFMP makes extensive provision for consultation with the National Trust. through its membership of HMAG, on the preparation of elements of the CEMPs. including Heritage Management Plans. Site Specific Written Schemes of Investigation, HEMPs (see paragraphs 1 1 12 3 1 3 and ref MW-G11 in Table 3.2b: REAC tables for the main works, in-Appendix 2.2 OEMP IREP6-011 and REP6-0121) will be based on the final-CEMPs and HMPs, the latter of whichwill be consulted upon with HMAG in relation to matters in the WHS. c) The draft DAMS and accompanying Overarching Written Scheme of Investigation (OWSI) was submitted to the Examination at Deadline 6 [REP6-013 and REP6-0141 The DAMS (including the OWSI) will be developed during the course of the Examination through continuation of regular meetings with the HMAG (which includes the National Trust), in order to produce a finalised DAMS prior to close of Examination. The HMAG meetings willbe informed by further engagement with the Scientific Committee during this process. The final DAMS will be a certified document. The draft DAMS sets out the archaeological strategy and framework for the preparation of SSWSIs, HMPs and Method Statements.



Environmental Statement. The OAMS is stated to be the basis for extensive consultation with members of HMAG in order to produce the final strategy. The DAMS and the accompanying OWSI and SSWSI will be key control documents for the Trust and will need to be reviewed in detail by it. The Trust seeks a commitment from the Applicant to be consulted on the DAMS. OWSI and SSWSI throughout the Examination and for the DCO to ensure that the Trust and HMAG are engaged within final approval of the DAMS, OWSI and SSWSI. The Trust also requires consultation upon and engagement within approval of Method Statements. HMPs and CHAMPS. d) Schedule 2. Requirement 8: Requirement 8 requires a landscaping scheme to be submitted and approved in writing by Secretary of State following consultation with the planning authority. The Trust seeks a commitment from the Applicant to be consulted on the content and approval of the landscaping scheme.

e) Schedule 2, Requirement 9: Requirement 9 of the dDCO sets out that a Traffic Management Plan (TMP) must be approved by the Secretary of State following consultation with the local highway authority. The Trust seeks a commitment from the Applicant to be consulted on the content and approval of the TMP.

The wording of all of these provisions has now been agreed with Highways England.

which will be prepared subsequent to the granting of the DCO. The SSWSIs HMPs and Method Statements will be prepared in consultation with HMAG/ WCAS, prior to any Preliminary Works or Main Works commencing for the Scheme: these processes are provided for in the draft DAMS (see paragraphs 4 1 11-4 1 14 4 2 2 and 5 1 6) and the OEMP (a revised version of which was submitted at Deadline 6 IREP6-011 and REP6-0121) (HMP - PW-CH1 and MW-CH1. SSWSIs - PW-CH3 and Method Statements - PW-G5 and MW-G8). d) Requirement 8 of the DCO IREP6-005 and REP6-0061 provides that the landscaping scheme must be approved by the Secretary of State, in consultation with the planning authority. Wiltshire Council and Historic England on aspects within the WHS. Wiltshire Council are the appropriate consultation body for this requirement due to its role as localplanning authority, which places duties on it to consider, independently, the proposed landscape scheme. The Secretary of State may consider it appropriate, in his or her expert opinion, to further consult other interested parties, but the Applicant does not consider it appropriate to narrow the discretion on this and prescribe further consultees on the face of the DCO. e) The Applicant, in its update to the OEMP submitted at Deadline 6 IREP6-011 and REP6-0121, has amended ref-



					MW-TRA2 to require consultation withowners of significant local visitorattractions (including the National Trustand English Heritage) when developing the Traffic Management Plan. Thisobligation is secured by requirement 4.	
3.58	N/A	N/A	Stonehenge Road design	The National Trust would like continued discussions on the turning head and access arrangements for Stonehenge Road, including access for West Amesbury Farm.	Highways England agree to continue discussions in this regard.	Agreed



4 Matters Under Discussion

Table 4-1 Matters Under Discussion

Ref	Document Reference	Para Ref	Sub- section/ Discipline	National Trust Comment	Highways England Response	Status
4.1	[RR-2344]	4.1	Current- position	The Trust welcomes the progress made by Highways England to date, and considers that the proposed scheme has the potential to be acceptable and deliver tangible benefits to the WHS. However, we will only support the progression of a scheme which we are sure protects the OUV of the WHS. Given the unique and internationally significant nature of the landscape, we do not consider that the DCO submission from Highways England currently provides the level of detail required for us to be confident that the approach to design and delivery of the scheme will achieve this essential goal. In addition, there are some areas of the current design approach that we disagree with, as well as important areas of methodology that are yet to be defined.	Highways England continues to work with the National Trust to understand its outstanding concerns. A comprehensive Heritage Impact Assessment has been prepared following ICOMOS guidelines (https://www.icomos.org/world_heritage/HIA_20110201.pdf). The scope and approach of this assessment, which is reported in ES Appendix 6.1 [APP-195], was endorsed by UNESCO/ICOMOS in their report from their third advisory mission on the scheme early in 2018 (https://whc.unesco.org/en/list/373/documents/), and developed in consultation the HMAG. The Applicant considers that the HIA has been carried out accurately and with a full appreciation and understanding of the importance of the WHS and its OUV. Overall, the Scheme is assessed to have a Slight Beneficial effect on the OUV of the WHS as a whole and the OUV of the WHS would be sustained. Further information can be found in the ES Chapter 6, Cultural Heritage [APP-044] and ES Appendix 6.1, Heritage	Under- Discussion



					Impact Assessment [APP-195]. The design will be developed throughthe detailed design stage of the project. Highways England would like to engagewith the National Trust on all relevant aspects of the detailed design and delivery of the Scheme.	
4.2	[RR-2344] WR [REP2-115]	5.1.2 6.8.4	-Document-development	The Trust has a strong interest in the development of the key control documents within the DCO including the: - CEMPs (Construction—Environmental Management Plan) - CHAMPs (Cultural Heritage Asset—Management Plans) and all—successor plans produced by the—Applicant on a four year cycle - the DAMS (Detailed Archaeological—Mitigation Strategy), - HEMP (Handover Environmental—Management Plan) - HMPs (Heritage Management—Plans) - LEMP (Landscape and Ecology—Management Plan) - Method Statements (specifying—requirements for the preservation in—situ of archaeological deposits) - OWSI (Outline Written Scheme of—Investigation), - SSWSIs (Site Specific Written—Schemes of Investigation) The approach defined within these above—listed documents will be key in our—assessment of the scheme's suitability. As-	The various documents are required at different times and are prepared by different parties. As set out in the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), the CEMPs will be developed by the preliminary works and main works contractors [PW-G1 and MW-G5]. They will be consulted upon with Wiltshire Council, the Environment Agency, Natural England and Historic England and will append as appropriate the Heritage Management Plan which the National Trust will be consulted upon as part of HMAG (for works within the WHS). As set out in paragraph 6.8.14 of ES-Chapter 6 Cultural Heritage [APP-044], Cultural Heritage Asset Management Plans (CHAMPs) will be prepared every four years by Highways England (or the operating authority) and following DMRB Volume 10-Environmental Design and Management, Section 6 Archaeology, Part 2, HA 117 / 08 Cultural Heritage Asset Management Plans (Highways Agency 2008) and as referred to at paragraph 5.1.21 in the draft Detailed Archaeological Mitigation Strategy	Under- Discussion



such, we expect to be closely consulted in	(DAMS) [REP6-013 and REP6-014], to-
their development.	ensure that cultural heritage assets are
The National Trust's position is that these	protected during the course of highways-
documents do not presently have sufficient	operation and maintenance works. The
detail.	draft DAMS [REP6-013 and REP6-014]
Requirements: in order to better understand	sets out the structured, iterative detailed
the development of these documents the	archaeological mitigation strategy,
Trust seeks for the Applicant to:	including, at part two, the Overarching
a) prepare and distribute a road map	written scheme of investigation. The
detailing expected timelines for the	DAMS is being developed by Highways
development of these documents; showing:	England in consultation with the
· · · · · · · · · · · · · · · · · · ·	Heritage Monitoring Advisory Group
i. points where the Trust, and HMAG will	(which includes the National Trust) and
see and have the opportunity to input	the Scientific Committee. It will be
into these documents	finalised prior to the end of the
ii. when the Trust, and HMAG will see	Examination and is secured by
the finalised versions	Requirement 5 of Schedule 2 of the draft
b) provide a named person (or role) within-	DCO [REP6-005 and REP6-006].
the project ultimately responsible for:	Potential impacts from construction will-
i. the production of each of these	be considered as part of the Heritage
documents	Management Plans detailed in the
ii. ensuring the requirements or	OEMP [PW-CH1 and MW-CH1] which
conditions of the document are upheld	will indicate how the historic-
c) provision to be made within the dDCO for	environment is to be protected in a
the Trust and HMAG to be consulted	consistent and integrated manner
throughout the development of these	including from potential impacts of
documents and to be listed as part of the	construction. The National Trust will be
approval regime for final sign off.	consulted upon on these plans (for
approv ar regime for final sign on.	works within the WHS) as part of HMAG.
	HEMPs (see paragraphs 1.1.12, 3.1.3
	and MW-G11 in the OEMP) will be
	based on the final CEMPs which will be
	consulted upon as described above.
	Section MW-LAN1 of the OEMP
	requires the mains work contractor to-
	prepare a Landscape and Ecology



					Management Plan (LEMP), which will be appended to the CEMP as appropriate. This will be consulted on with Wiltshire Council and Natural England as the appropriate consultation bodies for such matters. In respect of the other documents set out in National Trust's submissions, consultation with the National Trust is set out in the OEMP in the following items: OEMP in the following items: PW-CH3 — Site Specific Written Schemes of Investigation, produced in consultation with HMAG for works within the WHS, to describe the mitigation measures that will be carried; and PW-CH4 and MW-CH5 — Method Statements, produced in consultation with HMAG for works within the WHS, to include protective fencing for identified heritage assets and appropriate archaeological mitigation measures.	
4.3	[RR-2344] WR [REP2-115]	5.1.6 6.8.1 9	Land - Restrictions on National Trust land	The Trust has previously stated its concerns over the Tunnel Protection Zone and the restrictive covenants to be affected on the Trust's estate above the tunnel, including concerns in relation to protection of archaeology and future archaeological research. Discussion has been ongoing with the Applicant and HMAG on this issue. The Trust is now recently in possession of the draft covenants proposed to be imposed on Trust land, and once we have reviewed this document we will make further comment if any outstanding	Agreed Highways England await any outstanding concerns.	Under- Discussion



				concerns remain.		
4.4	[RR-2344] WR [REP2-115]	5.1.8 6.7.1 6.8.2 0 6.9.1 6.9.2	Countess Farm Health and wellbeing Grade II listed buildings Landscape and visual effects and design - Assessment of impacts on Countess Farm Sound barrier and screening at Countess Flyover	Health and wellbeing: We are concerned about the impact of the construction on all the occupants of our property at Countess-Farm. Requirements: the National Trust seeks clarification on the mitigation to limit the impact of noise, dust, light and disturbance on our tenants. Listed buildings: It is stated that there will be 'permanent adverse effects on the setting of one listed building in the vicinity of Countess Roundabout.'(6.1 Environmental Statement Chapter 16, Table 16.1) However, there is both a Grade II listed farmhouse and an associated group of Grade II listed buildings comprising the farm complex that will also be adversely impacted at Countess Farm. Assessment of impacts: Clarification of the assessment of the impact of the mitigation at Countess Farm by year 15 is sought. In 6.1 Environmental Statement Chapter 7: Landscape and Visual, Table 7.11: Summary of significant effects—construction and Table 7.12: Summary of significant effects—sensitivity) has a Major Impact Magnitude and a Large adverse Residual Effect recorded. In Table	Health and Wellbeing: The potential for noise, dust, light and disturbance impacts on Countess Farm as a result of the construction of Countess flyover are assessed in the relevant topic chapters of the ES, including Chapter 5, Air Quality [APP 043], Chapter 7, Landscape and Visual [APP045], Chapter 9, Noise and Vibration [APP-047], Chapter 13, People and Communities [APP 051], and Chapter 15, Cumulative Effects [APP053]. The assessment reported in the ES has concluded that there would be: no significant adverse impacts on air quality; and temporary significant adverse noise effects for nearby residents during construction. The cumulative effects assessment found that in-combination there would be a significant adverse visual, noise and air quality effect during the construction phase at Countess Farm. During construction, impacts will be controlled and reduced as far as reasonably practicable in the vicinity of the Countess Farm through measures contained within the OEMP (a revised version of which was submitted at Deadline 6 [REP6 011 and REP6 012]) to, for example, control noise (PW-NOI1,	Under- Discussion-
				7.13 Summary of significant effects operation year 15, Countess Farm is predicted to have Moderate Impact Magnitude and Moderate adverse Residual	PW NOI3, PW NOI4, PW NOI5, PW NOI6, MW NOI1, MW NOI3, MW NOI4, MW-NOI5 and MW-NOI6), dust (PW-	



Effect. In 6.1 Chapter 16: Summary: Table 16.1: Summary of effects, the Permanent adverse effects on these listed buildings at the Construction Phase are then not described at the Operational Phase, which appears to the Trust to be contradictory. Additional information is required on this reduction in the Impact Magnitude and Residual Effect and how under the bestcase scenario, the proposed mitigation of planting will deliver this reduction over 15 vears. Currently the proposed planting is restricted to within the soft estate of the existing highway, and in addition anunspecified number of trees are to be removed to create sufficient area for the drainage system (see Fig 2.2 Preliminary design drainage catchments, Countess Pond 1. Countess Catchment 12. Outfall-Catchment 15. Countess Pond 3 and Catchment 15), which will limit the space for replacement or additional planting. The visualisations shown in ES Figures [APP -145] and [APP-146] illustrate the view from the North-East and therefore do not fully show the impact magnitude of the flyover on Countess Farm. We seek additional mitigation in the form of extended fencingand planting including standard trees to maximise the buffering, with 100% archaeological mitigation for all worksundertaken within the WHS.

Sound barrier and screening:
Requirements: further information isrequired on the type and height of screening

AIR1 and MW-AIR1), and artificial lighting (MW-G29).

Operational mitigation will be delivered through the use of a thin surfacing system, which results in lower levels of noise generation than a standard hotrolled asphalt surface, as required by D-NOI1 in the OEMP, a 1.8m high noise barriers on the north and south sides of the flyover, as required by reference D-NOI2 in the OEMP; and landscaping of the flyover embankments would be secured through requirement 8 of the draft DCO IREP6-005 and REP6-0061. The Applicant considers that these measures provide adequate mitigation against the impacts of noise, dust, lightand disturbance on the tenants of Countess Farm.

Listed Buildings: ES Chapter 6 Cultural Heritage IAPP-044, Table 6,111 sets out the significant permanent adverse effect of the construction of the Scheme on the Grade II listed Stables and Barn at Countess Farm (NHLE 1131055). With regards to non-significant effects for the other listed buildings in the complex. which are situated slightly further backfrom the existing dual carriageway and Countess Roundabout, these are set out in ES Appendix 6.8 - Cultural Heritage -Summary of non-significant effects [APP-217, Table 1.1: Constructionphase: temporary; Table 1.4: Construction phase: permanent -



	and sound barrier that will be attached to	historic buildings (setting) and Table 1.7:
	the flyover; in addition to the how light and	Operational phase: historic buildings
	pollution will be mitigated at Countess Farm.	(setting)] set out the non-significant
		effects for the Grade II listed buildings at
		Countess Farm including Countess
		Farmhouse and front garden walls
		(NHLE 1318487), a Large Barn at
		Countess Farm (NHLE 1131056), a
		Large Granary at Countess Farm (NHLE
		1318488).
		Assessment of impacts: The OEMP (as-
		updated for Deadline 6 [REP6-011 and
		REP6-012]) includes provision at P-
		LE05 that "Existing highway planting at
		Countess Junction shall be retained.
		supplemented by additional tree planting
		where practicable."
		The reduction in the magnitude of
		impact between operation year 1 ([APP-
		045 Table 7.12) and operation year 15
		([APP 045] Table 7.13) is due to the
		establishment of new planting between
		the elevated section of Countess flyover
		and the slip road from the proposed
		A303 to Countess roundabout, as
		indicated on Section H of the
		Environmental Masterplan [APP-059], as
		this planting would be in leaf and taller in
		height than compared to the year 1
		assessment when the vegetation would
		not be in leaf and smaller and the
		landscape less established and
		integrated. In [APP-054]: Summary of
		Effects, Table 16.1: Summary of effects,
		for Cultural Heritage, the permanent
		adverse effects on these listed buildings



are described as Construction (permanent) as this approach allows for a thorough and detailed assessment of each constituent element of the Scheme to be undertaken, acknowledging the permanent impacts as a result of the construction of the Scheme. The Applicant considers this approach to beappropriate and in line with methodology as set out in DMRB. Volume 11. Section 3. Part 2 (HA208/07) for the assessment of road schemes in relation to cultural heritage and is therefore not contradictory in its approach. Please also refer to the Applicants response to Written Question CH.1.9 [REP2-025]. The construction (temporary) and operational (permanent) significant adverse effects to the visual receptor is included in the Landscape and Visual-Impact Assessment section of Table 16.1 [APP-054]. With reference to Highways England response to Written Question CH.1.47 [REP2-025], the planting proposals would screen the lower parts of the Countess flyover retaining walls and slip-roads and soften views of the upper parts of the flyover. However, the flyover would remain visible and retain a significant visual effect at year 15 of operation as the viaduct and vehicles (including lorries) would be up to 11.5 metres above the grounds of Countess Farm. The detailed design stage of the drainage works, incombination with a detailed tree survey,



		will establish the likely impact and exact
		extent of removal; such that it may be
		that the extent of tree loss could be
		reduced. The planting will be secured
		under requirement 8 of Schedule 2 of
		the draft DCO [REP6-005 and REP6-
		006] pursuant to which Highways
		England will be required to submit a
		detailed landscaping scheme, which
		must be based on the mitigation
		measures set out in the ES. Highways
		England has offered additional off-site
		planting to which the National Trust are
		agreeable, as set out in the response to
		Written Question CH.1.47 [REP2-025].
		Requests for extended fencing and the
		planting to include standard trees are
		under discussion, along with the detail of
		any agreement between Highways
		England and the National Trust
		regarding archaeological mitigation.
		Sound barrier and screening: A 1.8-
		metre-high and absorptive noise barrier
		is proposed between the slip roads on
		both the north and south side of
		Countess flyover as secured in D-NOI2
		of the OEMP (a revised version of which
		was submitted at Deadline 6 [REP6-011-
		and REP6-012]). This commitment
		includes reference to the applicable
		standards that the noise barrier will need
		to meet: "the current harmonised-
1		Specifications Standard BS EN 14388
		(2005) and meet the A3 (DLα 8 to 11
		dB) and B3 (DLR>24 dB) standards for
		sound absorption and airborne sound



					insulation as specified in BS EN 1793-part 1 and 2 (1998), or equivalent future standards approved by the Authority." Lighting during the construction phase must be in accordance with the provisions of item MW-G29 of the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), which sets out that lighting should be designed, positioned and directed so as not to unnecessarily intrude on adjacent buildings, ecological receptors, structures used by protected species and other land uses to prevent unnecessary disturbance, interference with local residents, or passing motorists.	
4.5	[RR-2344]	5.1.9	Operational phase ground-monitoring	Further clarity is needed around the types and frequency of activities which will need to be carried out once the proposed scheme is operational, how the impact of this activity will be assessed and how the Trust will interact with Highways England and their agents in this regard. The Trust has been provided with information relating to initial proposals for future ground monitoring. It agrees in principle with an approach and methodology that would have minimum impact in installation and removal of equipment. The Trust seeks security on these principles.	The operation of the Scheme, including, for example, the use of the Scheme by road users and the operational plant-within the tunnel, is assessed through the EIA, as reported in ES Chapters 5 to 16 [APP-043 APP-053]. As set out in the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012], which is secured through requirement 4 of Schedule 2 of the draft DCO [REP6-005 and REP6-006], the main works contractor will be required to prepare a HEMP (MW-G11). The HEMP will provide the relevant information on existing and future environmental commitments and objectives that would need to be honoured and define on-going actions and risks that need to be managed and	Under- Discussion



	will be consulted upon with the
	Environment Agency, Wiltshire Council,
	Natural England and Historic England on
	matters related to their functions.
	As with the physical design of the
	scheme, details of operational activities
	will be developed through the detailed
	design process. Where relevant to-
	interests of the National Trust, the
	details will be developed in consultation-
	with the National Trust.
	Ground monitoring will be required as-
	part of the tunnel construction works,
	including possible continued monitoring
	following completion of construction and
	into the operational phase. These
	movement monitoring stations/points are
	referenced (alongside the archaeological
	mitigation associated with them) in the
	DAMS, and types and frequency of
	activities will be detailed in the CEMP
	and Heritage Management Plans.
	To confirm the absence of any adverse
	influence regardless of predicted effects,
	monitoring regimes shall be developed
	by the appointed contractor. The OEMP
	requires under reference MW-CH8 that
	"The main works contractor shall-
	develop a Ground Movement Monitoring
	Strategy, to be prepared in consultation
	with the members of HMAG (which
	includes National Trust) and to be
	approved by the Authority. The strategy
	will identify heritage assets that are at
	risk from ground vibration from the
	tunnel, or from ground surface-



					movement caused by settlement. Aspart of this strategy, the contractor shall develop contingencies and identify measures to ensure the protection of assets. It is anticipated that for settlement, this will include monitoring points (settlement markers) with manual monitoring by carrying out a levelling survey or by a fixed monitoring instrument. The contractor's monitoring during construction will continue until such time as there is no further movement measured.	
4.6	[RR-2344] WR [REP2-115]	6.1 & 7.1 6.5.5	Land Take —general objection	At this stage, the Trust objects to the acquisition of this [the land owned by the Trust and held inalienably] land on the grounds of the outstanding issues raised. These issues represent significant reasons why land held by the Trust for the benefit of the nation should not be released for the purposes of the scheme until they are adequately resolved to the Trust's satisfaction, and solutions secured in the final form of any confirmed DCO-documentation.	Highways England will continue to work with the National Trust to understand and address its outstanding concerns and work towards the removal of the National Trust's objection. Highways England has set out in the Statement of Reasons [APP-023] why the land owned by the National Trust is required and that there is a compelling case in the public interest for this land to be compulsorily acquired.	Under- Discussion
				It is a matter of record that the land- proposed for acquisition is held inalienably to which the provisions of section 130- Planning Act 2008 apply. The ongoing- negotiations between National Trust and the Applicant are also allowing the Trust to keep under review the extent of the safeguards- generally that are being offered to the Trust-	Highways England understands that the land owned by the National Trust which it is proposing to compulsorily acquire pursuant to the DCO is held inalienably.	



				in terms of protections available to it and in- the light of the robustness of those- safeguards, whether the objection that the- Trust is presently maintaining to acquisition- of its land by compulsion can be withdrawn.		
4.7	[RR-2344] WR [REP2-115]	6.5.3 6.8.1 and 6.8.2	DCO- Communicat ion / consultation	The Trust would agree that in so far as their relevant statutory functions are concerned in this regard, where discharge or approval is required, that Historic England or WCAS should be the appropriate bodies to play that role. Within the WHS, the Trust believes that in addition to Historic England, and WCAS, both the National Trust and English Heritage hold important and relevant expertise which should be considered across a range of matters. This is why HMAG too has an important role to play in providing advice, setting requirements, and monitoring archaeological mitigation within the WHS, one which should not be subjugated. Whilst HMAG is tied into several facets of consultation, there remains an issue about unclear process and consistency in approach of consultation with the Heritage Stakeholders. This is true for both controls within the DAMS and the OEMP. We are working with the Applicant and the other Heritage Stakeholders to resolve this matter. One that in our submission, is not insurmountable. We are awaiting the version of the DAMS that the Applicant is due to submit at DL6, and will be able to comment further in due course.	Alterations have been made throughout the examination to the OEMP, which is secured through requirement 4 of Schedule 2 of the draft DCO [REP6-005 and REP6-006]. The Applicant submitted an update to the OEMP for Deadline 6 [REP6-011 and REP6-012] and the National Trust's role in the updated OEMP is discussed further below. Highways England has included measures within the Scheme to secure ongoing involvement with the National Trust (as a member of HMAG) with respect to how the Scheme is carried out and its impact on the WHS. Highways England has also secured the delivery of the design solutions designed to minimise the impact of the Scheme on the WHS, which also involve consultation with HMAG. Further detail of these measures is provided below, demonstrating the means that are in place to ensure the Scheme will not be designed or constructed in an inappropriate manner. Consultation with the National Trust is secured in two key ways: Firstly, paragraph 4 of Schedule 2 to the draft DCO [REP6-005 and REP6-006] requires Highways England to carry out the Scheme in accordance with the	Under- Discussion



OEMP. The OEMP requires the
contractor to develop Construction-
Environmental Management Plans
("CEMP") for the Scheme, which must
be prepared in accordance with the
principles of the OEMP. The OEMP
requires the preliminary works CEMP to
include for the preliminary works:
PW-CH1 a Heritage Management
Plan, prepared in consultation with the
members of HMAG (of which National
Trust is a member) (for works within the
WHS) and Wiltshire Council
Archaeological Service (for works-
outside the WHS);
PW-CH3 - Site Specific Written
Schemes of Investigation, produced in
consultation with members of HMAG, to
describe the mitigation measures that
will be carried;
PW-CH4 - Method Statements,
produced in consultation with members
of HMAG for works within the WHS, to-
include protective fencing for identified
heritage assets and appropriate
archaeological mitigation measures;
PW-CH5 - Site Specific Written
Schemes of Investigation, produced in
consultation with members of HMAG, to
include measures to install temporary
barrier fencing to limit land disturbance
at the western portal and eastern portal
approaches;
PW-CH6 - Site Specific Written
Schemes of Investigation, developed in
consultation with members of HMAG for



	works within the WHS, to include	
	measures to avoid significant-	
	archaeological remains where possible	
	and implement appropriate	
	archaeological mitigation measures	
	where impacts are unavoidable;	
	PW-LAN1 - requires consultation with	
	members of HMAG prior to the	
	installation of fencing to protect retained	
	vegetation within the WHS.	
	In respect of the main works the OEMP	
	requires the main works CEMP to	
	include:	
	MW-CH1 – Heritage Management Plan	
	based on the Detailed Archaeological	
	Mitigation Strategy (see requirement 5 of	
	Schedule 2 to the draft development	
	consent order [REP6-005 and REP6-	
	006]), prepared in consultation with the	
	members of HMAG and Wiltshire	
	Council Archaeological Service,	
	indicating how the historic environment	
	is to be protected in a consistent and	
	integrated manner.	
	MW-CH3 requires consultation with the	
	members of HMAG on the type of	
	construction boundary fencing to be-	
	used within the WHS or its setting and to	
	be included in an Archaeological Method	
	Statement forming part of a main works	
	CEMP;	
	MW-CH5 requires the development in	
	consultation with the members of HMAG	
	for works within the WHS, of	
	Archaeological Method Statements	
	describing the appropriate measures to-	



		be used where potentially sensitive-	
		archaeological remains are required to	
		be buried or sealed beneath fill material;	
		MW-CH6 requires the preparation, in	
		consultation with the members of HMAG	
		for works within the WHS, of Site-	
		Specific Written Schemes of	
		Investigation in respect of service/utility	
		corridors requiring excavations, to avoid	
		archaeological remains wherever	
		possible and implement appropriate	
		archaeological mitigation measures	
		where impacts are unavoidable;	
		MW-CH7 requires appropriate	
		monitoring arrangements for all heritage	
		assets during the construction	
		programme, prepared in consultation	
		with the members of HMAG for works	
		within the WHS.	
		Secondly, paragraph 5 of Schedule 2 to	
		the draft DCO [REP6-005 and REP6-	
		006] requires the Scheme to be carried	
		out in accordance with the DAMS-	
		[REP6-013 and REP6-014]. Highways-	
		England has submitted a document that	
		further clarifies the relationship between	
		the DAMS and the OEMP. As stated in	
		the OEMP_e.g. PW-CH1 and MW-CH1	
		for HMPs, members of HMAG will be	
		consulted before Highways England as	
		'the Authority' approves the	
		documentation. The consultation-	
		provided for in the OEMP will ensure	
		that the views of HMAG are taken into-	
		account in finalising the documentation,	
		prior to Highways England's approval.	



	The OEMP also provides for landowners
	to be informed of the programme and
	activities during both the preliminary
	works phase (see PW-COM1 of the
	OEMP) and the main works phase (see
	MW-COM1 of the OEMP). Other key-
	design elements, designed having
	regard to the impact of the Scheme on
	the WHS, that are secured via the
	OEMP include:
	D-CH8 requires no signage or other
	vertical installations (such as CCTV)
	above the top of the cutting and no
	lighting of signs at the western end of
	the Scheme in order to protect the
	WHS's OUV;
	D-CH2 and D-CH3 which require the
	redundant sections of the road surface
	to the existing A303 and A360 (including
	the existing Longbarrow Roundabout) to
	be broken out, save to the extent they
	are required for public rights of way;
	D-CH4 – requires Green Bridge No. 4 to
	be between 145m and 149.9m wide;
	D-CH5 — which requires the western-
	approach to the tunnel to be in cutting to
	a minimum 7m depth with vertical
	retaining walls;
	D-CH6 and D-CH7 — which require cut
	and cover tunnels extending eastwards
	and westwards from the bored tunnel;
	D-CH9. D-CH10. D-CH11 and D-CH12
	which taken together limit the use of
	highway lighting within the WHS and
	nignway nghung within the vvrio and



		require improved lighting at Countess	
		roundabout.	
		Section 4 of the OEMP now also-	
		includes the design vision and a range	
		of Scheme wide and WHS specific	
		design principles; and also for	
		consultation with the National Trust (as	
		part of the Stakeholder Design	
		Consultation Group) on key elements of	
		the design with the WHS.	
		U	
		The OEMP (a revised version of which	
		was submitted at Deadline 6 [REP6-011	
		and REP6-012]) therefore provides-	
		assurance that the design solution will-	
		be transmitted into the requirements of	
		the main works contractor and that the	
		National Trust, as a member of HMAG,	
		will be consulted with regards to the	
		design solution. Potential impacts from	
		construction will be considered as part of	
		the Scheme-wide HMP detailed in the	
		OEMP (PW-CH1 and MW-CH1) which	
		will indicate how the historic	
		environment is to be protected in a	
		consistent and integrated manner	
		including from potential impacts of	
		construction. The implementation of the	
		OEMP is secured by Requirement 4 of	
		schedule 2 of the draft DCO [REP6-005-	
		and REP6-006]. The OEMP (MW-CH7)	
		allows for monitoring arrangements for	
		designated and non-designated heritage	
		assets to be prepared in consultation	
		with the members of HMAG (for sites-	
		within the WHS) and WCAS (for sites	
L		within the Willey and Worke for sites	



				outside of the WHS) and approved by The Authority prior to works commencing.	
4.8 WR 4.1 [REF	6.8. P2-115]	Rights of Way and non- motorised users – Surfacing of new restricted byways on A360	It is not clear from the submitted documentation what the width or the surface treatment of the new restricted byway running north south along the existing alignment of the A360 would be (6.1 Environmental Statement, Chapter 2, 2.3.57). In order to minimise adverse visual impacts on the OUV of the WHS and secure its protection we seek provision that: a) there should be no new bound surface on the new PRoW of the A360. A bound surface (with a maximum width of 3m) could be put in place along the line of the existing A360 (where this road becomes redundant). But at the point at which the NMU route diverges from the existing A360 eastwards into the WHS there should be no formal bound surface; in particular in the vicinity of the Winterbourne Stoke Barrow group where any new bound surface would represent an adverse impact on the monuments and their setting.— The Trust accepts that there is a mechanism in place to take forward a discussion concerning this, but as yet the surfacing in this location is not agreed.	Design principle (D-CH26) clarifies that the SDCG will be consulted with regards to the surface treatment, including whether a bound or unbound surface is required in particular locations, such as close to the AG12 Winterbourne Stoke Crossroads Barrows, in order to sustain the OUV of the WHS. SDCG will also be consulted with regards to location, colour and materials of the bound and unbound surfaces of the restricted byways. Highways England disagrees that any new bound surface on the A360 would represent an adverse impact on the Winterbourne Stoke Crossroads Barrows and their setting. The existing A360 already has a major adverse impact on the group. Downgrading to an NMU and realigning the road to the west is assessed as having a Moderate Beneficial effect on the Asset Group in the ES Chapter 6 [APP 044, Table 6.11: Summary of significant effects — construction (permanent)] and the Heritage Impact Assessment [APP 195, Table 11: Summary of assessed impacts and effects of the existing A303 and anticipated impacts and effects of the	Under discussion



					Scheme on Asset Groups conveying Attributes of OUV]. Within the WHS, commitments with regard to surfacing are set out at items D-CH2, D-CH3 and D-CH14 of the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]) which provide for, respectively, the breaking up of the redundant A303 and A360 within the WHS, and that provision of surfacing within the WHS shall be developed in consultation with National Trust, Historic England, English Heritage and Wiltshire Council. Through the ongoing Heritage Partners Design Review meetings, the Applicant has developed a series of Design Principles to guide the detailed design of elements of the Scheme, including the public rights of way, which is incorporated into the updated OEMP	
4.9	WR [REP2-115]	6.8.8	Rights of Way and non- motorised users — A360 and A303- maintenance strategy Decommissi oning of the A303	d) there must be a maintenance strategy agreed that ensures that the surface approach continues to be applied throughout the maintenance agreement and any successor agreements. And those services providers who may need access to services beneath this surface must be required to make any repairs using the surfacing approach as defined above. Requirements: clarification is sought on the maintenance, management, and future	as Chapter 4. The future management of the length of decommissioned A303 to become restricted byway will become the responsibility of Wiltshire Council as public rights of way authority and the mechanics for this handover will be dealt with in a legal agreement between Highways England and Wiltshire Council. Highways England intends to retain responsibility for the section of decommissioned A303 to the east of Stonehenge Road—this area is expected to be managed as part of its soft estate. Controls over the extent and	Under discussion



				liability responsibilities for the land of what will become the decommissioned A303	design of the works, how they will be- carried out and thereafter operated are- contained in the OEMP, including in- particular provision of a HEMP, an- updated version of which was submitted at Deadline 6 [REP6-011 and REP6- 012], secured via requirement 4 of Schedule 2 to the draft DCO [REP6-005- and REP6-006].	
4.10	WR [REP2-115]	6.2.2	Agriculture Agricultural- access to- land-during- construction	Detail of how tenants are to access land- severed during construction for the- purposes of moving livestock, machinery, and undertaking routine management such- as daily livestock welfare checks has not- been provided. Requirements: clarification is required. Clarification has been provided, and further- discussions are ongoing relating to- accommodation works on north-south- movements across the existing A303.	As noted in Highways England's response to Written Question Ag.1.11 [REP2 022]: "access to premises will be maintained during the operation of the Scheme and during its construction. This is ensured by the scope of the powers available to the undertaker under the DCO. Article 10 of the draft DCO [REP6 005 and REP6 006] makes provision for the stopping up and replacement of private means of access. In accordance with paragraph (2)(a) of that article, a private means of access that is to be replaced and is listed in Part 3 of Schedule 3, may only be permanently stopped up once the replacement private means of access has been completed to the reasonable satisfaction of the street authority. Article 10(2)(b) makes provision for a temporary alternative route to be put in place, pending the completion of the replacement means of access specified in Part 3 of Schedule 3." No land occupied by National Trust's tenants will be severed during construction. The National Trust's tenants will therefore be	Under discussion



					able to access land during construction for the purposes of moving livestock, machinery, and undertaking routine-management such as daily livestock-welfare checks. The OEMP contains-specific measures requiring liaison with-landowners and occupiers in terms of access (MW-COM1) through the-Agricultural Liaison Officer.	
4.11	WR [REP2-115]	6.2.1	Agriculture and cultural heritage Impact of the intensificatio n of PRoW (Public Right of Way)	Concerns that the scheme will result in an increase in the anti-social use of the PRoWnetwork have not been resolved. Currently illegal activities including hare coursing, fly tipping, camping, and occupation by caravans, vans and motorhomes, already cause issues for land controllers. This includes left rubbish (which can be potentially hazardous for livestock and wildlife), fire sites, unauthorised use of agricultural water supplies, and the obstruction of agricultural access. Requirements: care should be taken in approval of any detail in relation to the scheme not to encourage increased use of PRoWs by motorised users where that would harm the OUV of the WHS.	Highways England's response to Written Question Ag.1.4 ii and iii [REP2-022] noted: To prevent improper use of the existing and proposed Public Rights of Way (PRoW) network, fences and gates would be provided. The detail of these will follow at the detailed design stage if development consent for the Scheme is granted. At this stage, it is envisaged that fences along public rights of way would be provided to prevent access onto private land, grazed grassland or the highway, or to provide a buffer zone to the retained cutting between Longbarrow junction and the western tunnel entrance. Kent Carriage Gaps would be provided at access points to restricted byways, preventing entry by mechanically propelled vehicles. Equestrian gates would be provided at access points to bridleways and pedestrian gates would be provided at access points to footpaths. This is subject to detailed design of these matters and discussions with Wiltshire Council. Within the WHS, the OEMP (a revised version of which was submitted	Under Discussion



	at Deadline 6 [REP6-011 and REP6-	
	012]), reference D-CH14, requires the	
	provision of fencing and surfacing to be	
	developed in consultation with the	
	National Trust, Historic England, English	
	Heritage and Wiltshire Council. Article 9	
	of the draft DCO [REP6-005 and REP6-	
	006] makes provision for the public	
	rights of way provided by the Scheme to	
	be maintained by Wiltshire Council.	
	Wiltshire Council could also use its	
	powers to prevent unlawful use of the	
	existing and proposed Public Rights of	
	Way. Highways England is in	
	discussions with Wiltshire Council-	
	concerning matters arising from its	
	maintenance of roads affected by the	
	Scheme. In addition, Highways England	
	has submitted an update to the OEMP at	
	Deadline 6 [REP6-011 and REP6-012]	
	which contains additional design	
	commitments, design principles to help-	
	guide the development of the detailed	
	design together with a robust	
	stakeholder consultation mechanism to-	
	involve heritage stakeholders, including-	
	the National Trust, in the development of	
	aspects of the detailed design within the	
	WHS. This includes matters in relation to	
	public rights of way within the WHS,	
	including surfacing, fencing and gating.	
	Compliance with the OEMP is secured-	
	via requirement 4 in Schedule 2 to the	
	draft DCO [REP6-005 and REP6-006].	
	Graft DOO [TELT 0 000 and TELT 0 000].	



4.12	WR	6.2.5	Agriculture -	Requirements:	Highways England's response to Written	Under
	[REP2-115]		Fencing and	a) clarification on the location and	Question Ag.1.4 ii and iii [REP2-022]	Discussion
	[=]		gates	specification of new fencing, gates, and all	noted the detail of fencing and gates	
				other accommodation works proposed for	"will follow at the detailed design stage	
				use on or adjacent to National Trust land	if development consent for the Scheme	
				interests is required to confirm suitability for	is granted. At this stage it is envisaged	
				agricultural use and to ensure no adverse	that fences along public rights of way-	
				impact on the OUV of the WHS	would be provided to prevent access	
				b) that the design and specification is	onto private land, grazed grassland or	
				subject to approval by the Trust where	the highway, or to provide a buffer zone	
				located on or adjacent to Trust land	to the retained cutting between	
				interests.	Longbarrow junction and the western	
					tunnel entrance. Kent Carriage Gaps	
				The Trust is in principle content that the	would be provided at access points to	
				The Trust is in principle content that the design commitments and consultation	restricted byways, preventing entry by	
		requirements set out in the OEMP as updated would provide sufficient controls in respect of the design of the fencing and gating scheme, subject to the consultation process throughout detailed design development (covered elsewhere). Equestrian gates would be access points to bridlewal pedestrian gates would be access points to footpath subject to detailed design matters and discussions.			mechanically propelled vehicles.	
				Equotinal gates would be provided at		
			pedestrian gates would be provided at			
			process throughout detailed design.	access points to footpaths. This is		
					subject to detailed design of these	
				development (covered discurrency).		
					Council". The Applicant has developed a	
		detailed design of elements Scheme, including the put way within the WHS, whice	series of Design Principles to guide the			
			Cohomo including the public rights of			
				Scheme, including the public rights of		
			the OEMP [REP6-011 and REP6-012].			
					As further noted in the response to	
					Ag.1.4 ii and iii [REP2-022]: "Within the	
					World Heritage Site, the OEMP [APP-	
					187],"(an updated version of which is	
				being submitted at Deadline 6 [REP6-		
				011 and REP6-012]) "reference D-		
				CH14, requires the provision of fencing		
					and surfacing to be developed in	



					consultation with the National Trust, Historic England, English Heritage and Wiltshire Council". Through the ongoing- Heritage Partners Design Review- meetings, the Applicant is establishing the principles and developing a process- for stakeholder consultation on detailed design of elements of the Scheme, to be incorporated into the updated OEMP as Chapter 4. This was submitted for Deadline 6 [REP6-011 and REP6-012].	
4.13	WR [REP2-115]	6.3.1	Air quality, dust and other emissions - General dust generating activities and range	Areas within the National Trust landholdings and WHS are not identified within the DCO documentation to contain specific activities likely to generate dust and therefore only 'standard' levels of mitigation are recommended in the Air Quality Chapter of the ES. We consider the range of activities most likely to generate dust is too narrow in range. Requirements: a) the Trust seeks discussions on what further mitigation should be considered particularly near to the unique lichen assemblage on the standing stones. b) clarification on how dust will be controlled during construction of the flyover which is in close proximity to the agricultural, business and residential premises at Countess Farme) the implementation of 'further standard' mitigation measures are requested which should be implemented to control and reduce the effects of dust and fine particles provided in Appendix 5.4 Table 5.4.10 of the ES.	Construction activities have the potential to generate dust and therefore standard good practice dust mitigation measures, secured through the OEMP, will be implemented across the construction works. The construction works which are envisaged to turn the A303 into the proposed green byway are considered to have a risk of dust egress and can be adequately controlled using standard mitigation measures. The risk of adverse effects is also minimised through these measures for the lichen assemblage on the standing stones as these are located approximately 165m from these works, as discussed in the Stonehenge Lichen Report [APP 234]. The locations where further standard mitigation is proposed are locations where notable sources of dust generation are anticipated (e.g. haul routes, large earthworks and stockpiling etc) and where sensitive receptors (i.e. residential locations) are in close proximity, some within 10 metres (m). This includes activities at	Under- Discussion



					Countess roundabout such as the construction of the flyover. The implementation of air quality mitigation is set out in the OEMP (a revised version of which was submitted at Deadline 6-[REP6-011 and REP6-012]), specifically in MW-AIR1 and MW-AIR2.	
4.14	WR [REP2-115]	6.4.2	Biodiversity, biological environment and ecology—Seed mixtures	ES Chapter 8 Page 8-45 8.4.4 states that 'all green bridges would be sown or planted with suitable plant species to facilitate the movement of the biodiversity features' and ES Chapter 8 Page 8-47-8.8.16 states chalk bunds on green bridges and areas of false cuttings and embankments will be seeded and planted with larval food plants for butterflies. It also states that areas of new calcareous grassland will also be included. However, Appendix 8.26 Outline Landscape and Ecology Management Plan Table 6.2 provides detail of a typical wildflower seed mixture that excludes the larval food plants for key chalk grassland butterflies. In order to provide suitable conditions for butterflies and to benefit an expanded range of insect groups (such as moths and pollinators including bees, for which preferential pollensources and extended food sources of pollen and nectar, including late flowering species, are critical) the National Trust-requests the below. Requirements: the National Trust asks that the list of wildflower species is expanded, with a targeted planting scheme implemented along the entire length of the chalk grassland habitat, to include seeds and wildflower plugs of	As set out in the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), MW-BIO2, the main works contractor must establish the new habitats identified within the Environmental Masterplan (ES Figure 2.5) [APP-059] within the Order limits and manage them accordingly to ensure their establishment and development to achieve their target purpose(s), through to any handover of the Scheme. In addition, under the requirement in paragraph 8 of Schedule 2 to the draft DCO [REP6-005 and REP6-006], a detailed landscaping scheme must be submitted to the Secretary of State for approval. This must be based on the mitigation measures set out in the ES, including the principles set out in the Outline Landscape and Ecology-Management Plan ('OLEMP') [APP-267]. In addition, the OEMP, at item MW-LAN1, requires the development of a Landscape and Ecology Management Plan. The objectives will be to create a mosaic of early-successional habitats ranging from bare ground to species rich low nutrient swards. The selection of	Under Discussion



		additional species incl to: Table 1:	uding but not limited	species will be carried out during detailed design and the preparation of the detailed landscaping scheme. As	
		Latin Name	Common Name	such, no further commitment is required.	
		Succisa pratensis	Devil's-bit scabious		
		Hippocrepis- comosa-	Horseshoe vetch		
		Helianthemum- nummularium-	Common rockrose		
		Viola hirta	Hairy violet		
		Rumex asetosa	Common sorrel		
		Echium vulgare	Vipers bugloss		
		Centaurea nigra	Common- knapweed		
		Campanula- rotundifolia-	Harebell		
		Knautia arvensis	Field knapweed		
		Euphrasia nemerosa	Eyebright		
		Campanula- glomerata-	Clustered- bellflower		
		Stachys officinalis	Betony		
		Serratula tinctoria	Saw-wort		
		Filipendula vulgaris	Dropwort		
		Odontites vernus	Red bartsia		
		Trifolium pratense	Red clover		



4.15	₩R	6.4.3	Biodiversity,	Chapter 8, Page 8.47, 8.8.18. 'Management	As set out in the OEMP (a revised	Under
	[REP2-115]		biological	will be carried out to prevent excessive	version of which was submitted at	Discussion
	[. (2 / 10]		environment	development of scrub':	Deadline 6 [REP6-011 and REP6-012]),	
			and ecology	Requirement: clarification is required on the	MW-BIO2, the main works contractor	
			Scrub	future management responsibilities of these	must establish the new habitats	
			encroachme	areas to prevent scrub encroachment onto	identified within the Environmental	
			nt	areas of open grassland, and where grazing	Masterplan (ES Figure 2.5) [APP-059]	
				has been identified as the management tool	within the Order limits and manage them	
				how essential infrastructure such as fencing	accordingly to ensure their	
				and water supplies will be provided.	establishment and development to	
				and water supplies will be provided.	achieve their target purpose(s), through	
					to any handover of the Scheme.	
					As described in the OEMP [REP6-011	
					and REP6-012], MW-BIO13, botanical	
					monitoring must be carried out to inform	
					appropriate management of the chalk	
					grassland and other habitats within the	
					Scheme. This will inform the	
					management action of 'grazing, mowing,	
					control of scrub, and specific habitat	
					management to create or maintain	
					conditions of characteristic species of	
					chalk grassland and other habitats'.	
					Example management measures which	
					will be confirmed within the detailed	
					Landscaping Scheme to be submitted	
ĺ					for approval by the Secretary of State	
					under Requirement 8 of the draft DCO	
					[REP6-005 and REP6-006] and the	
ĺ					LEMP required to be developed under	
					item MW-LAN1 of the OEMP and could	
					include, where practicable, managing	
					chalk grassland by appropriate grazing	
					to maximise gains in biodiversity,	
					providing, in any areas where chalk	
					grassland is to be managed by grazing,	



					appropriate fencing and stock watering facilities. In addition, where areas of chalk grassland are not managed by grazing, mowing will be used to manage the grassland to achieve biodiversity and other objectives, with periodic control of scrub as necessary (paragraph 7.2.2 of the OLEMP [APP-267]), the principles of which will be reflected in the detailed landscaping scheme, to be submitted.	
4.16	WR [REP2-115]	6.4.4	Biodiversity, biological environment and ecology— Remediation of land	Where land is being acquired on a temporary basis, including National Trust land, detail is required on remediation prior to return to landowners, and how delivery of the ongoing management necessary to achieve the successful establishment of species rich chalk grassland will be secured. Where land is being acquired and permanently retained a mechanism should be implemented to ensure land being restored to species rich grassland is under appropriate ownership to allow for the ecological objective to be met. Inadequate-management such as insufficient or inappropriate timing of grazing or cutting, failure to remove cuttings, or failure to prevent scrub encroachment will prevent the successful establishment of species rich chalk grassland. In additional an ongoing programme of monitoring and wildflower sward supplementation of species not represented is required to ensure species rich chalk grassland is created.	The OEMP (a revised version of which was submitted at Deadline 6 [REP6-011-and REP6-012], is the basis from which detailed, works-specific CEMPs will be prepared by the relevant contractors, as is required by the OEMP itself and therefore secured through paragraph 4 of Schedule 2 of the draft DCO [REP2-033]. The OEMP sets out the requirement for the main works-contactor to prepare a LEMP (MW-LAN1), in accordance with industry good practice. The principles for the LEMP are set out in the OLEMP [APP-267]. Under requirement 8 of Schedule 2 of the draft DCO [REP6-005 and REP6-006], Highways England will be required to submit a detailed landscaping scheme to the Secretary of State for approval, which is required to be on the basis of the mitigation measures set out in the ES, which includes the OLEMP, and will incorporate management obligations. In addition, under article 29 of the draft-DCO, Highways England (subject to-	Under Discussion



					certain exceptions) is under an- obligation to restore land which is subject to temporary possession powers to the reasonable satisfaction of the owners of the land before handing it- back.	
4.17	WR [REP2-115]	6.4.7	Biodiversity, biological- environment and ecology Bats	The buildings at the Countess Farm-complex have been identified as bat roosts. The proposed mitigation is planting and inclusion of a noise barrier around the flyover with the intention of it 'likely-providing the function of pushing up any bats flying over the A303 to 'safe' heights, or assist in funnelling bats through the large underpasses'. It is understood that the noise barrier will not be sufficiently high to prevent bats from flying directly into the path of taller traffic on the flyover and the proposed planting as suggested is restricted to within the existing boundary of the highway. In addition an unspecified number of trees are required to be removed to create sufficient area for the drainage system (see Fig 2.2 Preliminary design drainage catchments, Countess Pond 1, Countess Catchment 12, Outfall Catchment 15, Countess Pond 3 and Catchment 15), which will limit the space for replacement or additional planting. Requirements: the National Trust seeks additional essential mitigation in the form of replacement planting by agreement with the Trust with 100% archaeological mitigation for works undertaken within the WHS.	The crossing point surveys undertaken at the Countess roundabout only recorded a total of six bats crossing the A303 in a north or south direction during the six hours of surveys undertaken, none of which were confirmed to have emerged / re-entered from the Countess complex [APP-160]. Designs of the Countess flyover and Countess junction would be able to incorporate suitable and proportionate measures to reduce the potential impacts on the likely limited number of individual bats that may commute south from the roosts at Countess Farm complex. The OEMP (as updated for Deadline 6-[REP6-011 and REP6-012]) includes a design principle at P-LE05 that "Existing highway planting at Countess Junction shall be retained, supplemented by additional tree planting where practicable." Replacement and new planting would be dealt with under the requirement contained in paragraph 8 of Schedule 2 to the draft DCO [REP6-005 and REP6-006], Highways England will be required to submit a detailed landscaping scheme	Under Discussion



					for approval by the Secretary of State	
					which is required to be based on the	
					mitigation measures set out in the ES.	
					This would set out the detailed planting	
					to be delivered by the Scheme. The	
					obligation to act in compliance with this	
					scheme is reflected in item MW-LAN2 of	
					the OEMP and is also a requirement of	
					the draft DCO [REP6-005 and REP6-	
					006]. Other measures would separately	
					be secured by the OEMP (a revised	
					version of which was submitted at	
					Deadline 6 [REP6-011 and REP6-012])	
					through items such as MW-LAN1 (in-	
					respect of a Landscape and Ecology	
					Management Plan) and MW-BIO1	
					onwards.	
					With regard to the archaeological	
					mitigation associated with removal of	
					existing trees and replacement planting,	
					the draft DAMS [REP6-013 and REP6-	
					014], sets out the structured, iterative	
					detailed archaeological mitigation	
					strategy. The DAMS is being developed	
					in consultation with HMAG (which	
					includes The National Trust) and the	
					Scientific Committee. It will be finalised	
					prior to the end of the Examination and	
					is secured by Requirement 5 of	
					Schedule 2 of the draft DCO [REP6-005	
					and REP6-0061.	
4.18	WR	6.8.1	Heritage and	The Applicant states that, 'it is assumed	The predicted effects of excavation-	Under
4.10		0.0.1	historic	that,' ground settlement will be minimal at	induced ground settlement have been	Discussion
	[REP2-115]		environment	the surface, but no evidence is provided to	considered as part of a staged	DISCUSSIOH
			- Ground	support this 6.1 Environmental Statement	assessment used in tunnelling to	
			- Ground	Chapter 6, 6.4.1 i)	determine the zone of influence and	
1				ынарын 6, 6.4. гт)	uetermine the zone of influence and	



Settlement- impacts	Requirements: given the sensitivity of archaeological deposits and monuments to ground and sub-surface disturbance, we consider that further evidence needs to be submitted by the Applicant to demonstrate the scale of any surface ground settlement and assess the adequacy of proposed mitigation, and to identify any residual impacts on monuments that convey the attributes of OUV of the WHS.	potential structures and archaeology affected during construction (Land-Instability Risk Assessment [APP-278], Section 6.4). The Land Instability Risk Assessment [APP-278] predicts that ground surface movement above the tunnel will be limited to 20-30mm as a maximum. ES-Chapter 6 - Cultural Heritage [APP-044] therefore notes: "It is assumed that ground settlement will be minimal at the surface from the boring of the twin bored tunnel and any changes to heritage assets on the surface would be negligible and imperceptible to the eye" ([APP-044] para. 6.4.1 (i)), and "It is assumed that vertical and lateral displacement from the excavation of
		negligible and imperceptible to the eye" ([APP-044] para. 6.4.1 (i)), and "It is- assumed that vertical and lateral-
		potential indirect impacts on heritage from activities such as ground vibration and ground movement / subsidence.



	Items PW-NOI4 and MW-NOI5 of the
	OEMP [REP6-011 and REP6-012]
	identify industry guidance that the
	preliminary works and main works
	contractors are to follow in relation to
	controls and working methods for
	managing vibration. This guidance
	specifically refers to ground borne-
	vibration from tunnelling. They also
	require the preliminary works and main-
	works contractors to identify any
	potentially vibration sensitive cultural
	heritage assets and actions to control or
	mitigate impacts, including monitoring.
	Notwithstanding the above, in the OEMP
	(a revised version of which was-
	submitted at Deadline 6 [REP6-011 and
	REP6-012]) a specific item has been
	added to require a ground movement
	monitoring strategy to be developed by
	the main works contractor.
	The installation of monitoring equipment
	and programme of monitoring to monitor
	ground movement above the tunnel will
	be included as part of the HMP required
	by item PW-CH1 and MW-CH1 of the
	OEMP [REP6-011 and REP6-012]. The
	monitoring methodology instigated as
	part of the HMP will consider acceptable
	levels and identify the associated action
	in response as part of a pre-planned
	contingency plan. The general principle is to control the works such that
	unacceptable levels are not breached
	and put in place a warning of trends-



which may approach unacceptable
levels.
It will be the responsibility of the
contractor to ensure risks are assessed
and mitigated in their safe systems of
work during construction, pursuant to the
OEMP (a revised version of which was
submitted at Deadline 6 [REP6-011 and
REP6-012]). As part of this plan, the
contractor will develop contingencies
using a suite of tool tool-box items from
further investigation, assessment and
monitoring during construction to identify
measures to ensure the protection of
assets. This could range from simply
slowing down the TBM to instigating
ground stabilisation measures including
grouting. Where the need for ground
stabilisation is identified this will be
undertaken from inside the main tunnel
bore where it is safe and practicable to
do so in preference to surface
intervention. Other methods for the
ground stabilisation specifically for
construction of the cross-passage
tunnels could include fissure grouting-
and local face depressurisation
facilitated from the main TBM tunnels;
further enhanced ground support can be
provided by the installation of pipe
umbrellas or spiles. These methods
have been successfully employed on the
recent (2013) Crossrail C310 Thames
Tunnel project through the chalk aquifer.
With these mitigation mechanisms in
place, the assumptions as set out in ES



					Chapter 6 [APP-044], para. 6.4.1 (i) and para. 6.4.1 (j) still stand, and there will be no significant effects on monuments that convey the attributes of OUV of the WHS.	
4.19	WR [REP2-115]	6.8.1	Heritage and historic environment - Scrub	The creation of intermittent scrub habitat-within the WHS, for example on the western approaches to Green Bridge 4 (6.1-Environmental Statement Chapter 6, 6.8.5-d) is in direct contradiction with Priority 1 of the Stonehenge & Avebury and Associated Sites WHS Management Plan (2015) which requires the management of scrub for the protection of archaeology. The introduction of scrub would also introduce a visual intrusion that would have an adverse impact on the visual relationships between the Winterbourne Stoke Barrow Group and the Diamond Group i.e. the adverse impact on OUV that Greenbridge 4 is intended to mitigate. Requirements: the National Trust therefore seeks assurance that other than for essential and proportional mitigation (where this does not adversely impact OUV) to provide habitat connectivity e.g., for bats, no new scrub is created within the WHS.	The scrub proposed within the WHS isto aid connectivity for bats and this is in is the vicinity of the Eastern Portal. There is also replacement scrub proposed at the bottom of the dry valley to the east of the eastern portal and around the drainage basins at Countess junction. The requirement contained in paragraph 8 of Schedule 2 to the draft DCO [REP6-005 and REP6-006] requires a detailed landscaping scheme to be submitted for approval by the Secretary of State. This must reflect the mitigation measures set out in the Environmental Statement, which include the principles set out in the OLEMP [APP-267]. In addition, the OEMP contains a number of landscaping obligations, such as the requirement to develop a LEMP (MW-LAN1) and botanical monitoring (MW-BIO13), which makes provision for control of scrub. Assuch, appropriate habitat and suitable management regime will be put in place through this mechanism. No further requirements are therefore appropriate.	Under Discussion
4.20	WR [REP2-115]	6.8.1 6	Heritage and historic environment — Creation of New-	The creation of new earthworks within the WHS would create an adverse impact on the Authenticity of the WHS and negatively impact the legibility of existing earthworks forming part of monuments that contribute	Earthworks are referred to within Table 7.3 of APP-045 to describe the embankments or cuttings that are proposed as part of the changes to landform. The Applicant can confirm that	Under- Discussion



4.24	N/D	0.40	Earthworks within the WHS	to the OUV of the WHS. We are therefore concerned that contra to discussions with, and assurances given to, the National Trust and HMAG the Applicant states that new embankments will be created within the WHS scheme (6.1 Environmental Statement Chapter 7, Table 7.3 final paragraph). In Plans and Drawings 2.9 a new section of embankment can be seen above the top of the cut on the northern side of the approach to the eastern portal, and is referred to as, 'new embankment formationsup to 1m above ground level,' between the Eastern Portal and Countess roundabout'(6.1 Environmental Statement Chapter 7, 7.9.13). Here the approach to the portal appears to be placed in a false cutting where the cut crosses the head of the dry valley. This is in a sensitive location within the WHS in proximity to a number of monuments contributing to its OUV, including both the Stonehenge Avenue and a number of round barrows. Requirements: the Trust therefore seeks the removal by the Applicant of all above ground earthwork components of the scheme within the WHS, to ensure its protection.	at the detailed design the shallow- embankment that crosses the dry valley- between the eastern tunnel portal and- Countess junction mentioned in this- issue would be graded out to tie into- existing ground levels and this specific- aspect of the Scheme would not- negatively impact upon the Authenticity- or OUV of the WHS. This detailed- design intent is supported by the OEMP- (a revised version of which was- submitted at Deadline 6 [REP6-011 and- REP6-012]), which has been updated to- include a requirement that there shall be no permanent raised earthworks within- the WHS other than those required for- the construction of the Countess flyover- (D-CH28) and that new landscaping- should reflect and integrate with the- original landscape i.e. rolling species- rich downland, and not seek to imitate- the monuments within the landscape; including grading out of the- embankments and rounding off the top- of cuttings, in order to reflect the existing- natural landform (P-LE02)	
4.21	WR [REP2-115]	6.12. 5ii	Draft DCO Requirement s relating to Design and Control Documents	Based on the scheme as currently conceived, and the dDCO as submitted, the National Trust is seeking certain changes to be made as set out above and cross-referenced here for ease of reference:	The Applicant responds as follows: a) As noted in the National Trust's response, this has been a matter discussed between the parties. As noted elsewhere in this response the Applicant has updated the OEMP (a revised-	Under Discussion



a) Schedule 2. Requirement 3: Notwithstanding the latest updates to Section 4 at DL4 (including a suggested section which includes mechanism for consultation on some areas of detailed design), which has been a positive progression; adequate and comprehensive consultation on matters of detail across the scheme remains a key concern for the Trust. In so far as the WHS, the Trustbelieves that in addition to Historic England. and WCAS, both the National Trust and English Heritage hold important and relevant expertise which should be considered across a range of matters. This is why SCG too has an important role to play, one which should not be subjugated. Whilst SCG is tied into several facets of consultation, there remains an issue about unclear process and consistency inapproach of consultation with the Heritage Stakeholders. This is true for both controls within the DAMS and the OEMP. The nature of resolution in cases of disagreement is an element of this discussion. We are working with the Applicant and the other Heritage Stakeholders to resolve this matter and to develop this within the OEMP and if necessary in side agreement outside of the OEMP.

b) Schedule 2, Requirement 4: The Trustdoes still have outstanding concerns inrelation to the amended OEMP submitted at DL4 and with the provision for consultationcontained therein. We are working with the Applicant to address those concerns; and version of which was submitted at Deadline 6 [REP6-011 and REP6-012]), to include a mechanism for consultation-with the National Trust, and other key-heritage stakeholders, on aspects of the detailed design of the Scheme within the WHS, as well as securing design commitments and design principles that will apply in the detailed design of the Scheme.

b) Discussions between the Applicant and the National Trust during the examination are continuing. The OEMP makes extensive provision for consultation with the National Trust through its membership of HMAG, onthe preparation of elements of the **CEMPs, including Heritage Management** Plans, Site Specific Written Schemes of Investigation. HEMPs (see paragraphs 1.1.12, 3.1.3 and ref MW-G11 in Table 3.2b: REAC tables for the main works, in Appendix 2.2 OEMP IREP6-011 and REP6-0121) will be based on the final-CEMPs and HMPs, the latter of which will be consulted upon with HMAG in relation to matters in the WHS.

e) The draft DAMS and accompanying Overarching Written Scheme of Investigation (OWSI) was submitted to the Examination at Deadline 6 [REP6-013 and REP6-014]. The DAMS-(including the OWSI) will be developed during the course of the Examination through continuation of regular meetings with the HMAG (which includes the



awaiting the version of the OEMP that the Applicant is due to submit at DL6, and will comment further in due course. The Trustbelieves that the approval of the CEMP (and HEMP) is of sufficient importance that the Trust should have involvement as a keystakeholder in consultation on itsformulation, monitoring, and amendment. c) Schedule 2, Requirement 5: Requirement 5 states that the authorised development must be carried out in accordance with the DAMS. An Outline Archaeological Mitigation Strategy (OAMS) was included with the application as appendix 6.11 to the Environmental Statement. The OAMS is stated to be the basis for extensive consultation with members of HMAG inorder to produce the final strategy. The DAMS and the accompanying OWSI and SSWSI will be key control documents for the Trust and will need to be reviewed indetail by it. The Trust seeks a commitmentfrom the Applicant to be consulted on the DAMS. OWSI and SSWSI throughout the Examination and for the DCO to ensure that the Trust and HMAG are engaged withinfinal approval of the DAMS. OWSI and SSWSI. The Trust also requires consultation upon and engagement withinapproval of Method Statements, HMPs and CHAMPS.

d) Schedule 2, Requirement 8: Requirement 8 requires a landscaping scheme to be submitted and approved in writing by Secretary of State following consultation with the planning authority. The Trust seeks

National Trust), in order to produce a finalised DAMS prior to close of Examination. The HMAG meetings will be informed by further engagement with the Scientific Committee during this process. The final DAMS will be a certified document. The draft DAMS sets out the archaeological strategy and framework for the preparation of SSWSIs. HMPs and Method Statements, which will be prepared subsequent to the granting of the DCO. The SSWSIs. HMPs and Method-Statements will be prepared in consultation with HMAG/ WCAS, prior toany Preliminary Works or Main Works commencing for the Scheme; these processes are provided for in the draft DAMS (see paragraphs 4.1.11-4.1.14, 4.2.2 and 5.1.6) and the OEMP (a revised version of which was submitted at Deadline 6 [REP6-011 and REP6-0121) (HMP - PW-CH1 and MW-CH1. SSWSIs - PW-CH3 and Method Statements - PW-G5 and MW-G8). d) Requirement 8 of the DCO IREP6-005 and REP6-0061 provides that the landscaping scheme must be approved by the Secretary of State, in consultation with the planning authority, Wiltshire Council and Historic England on aspects within the WHS. Wiltshire Council are the appropriate consultation body for this requirement due to its role as local planning authority, which places duties on it to consider, independently, the



		a commitment from the Applicant to be- consulted on the content and approval of- the landscaping scheme. e) Schedule 2, Requirement 9: Requirement 9 of the dDCO sets out that a Traffic- Management Plan (TMP) must be approved by the Secretary of State following- consultation with the local highway- authority. The Trust seeks a commitment- from the Applicant to be consulted on the- content and approval of the TMP.	parties, but the Applicant does not
--	--	---	-------------------------------------



5 Matters Not Agreed

5.1.1 There are no matters Not Agreed <u>between National Trust and Highways England</u>. at the present time.