

**M54 to M6 Link Road**

**TR010054**

**Volume 6**

**6.3 Environmental Statement**

**Appendices**

**Appendix 11.1 Noise and Vibration  
Terminology**

Regulation 5(2)(a)

Planning Act 2008

Infrastructure Planning (Applications: Prescribed  
Forms and Procedure) Regulations 2009

January 2020

Infrastructure Planning

Planning Act 2008

**The Infrastructure Planning  
(Applications: Prescribed Forms and  
Procedure) Regulations 2009**

**M54 to M6 Link Road  
Development Consent Order 202[ ]**

---

**6.3 Environmental Statement Appendices  
Appendix 11.1 Noise and Vibration Terminology**

---

<b>Regulation Number</b>	Regulation 5(2)(a)
<b>Planning Inspectorate Scheme Reference</b>	TR010054
<b>Application Document Reference</b>	6.3
<b>Author</b>	M54 to M6 Link Road Project Team and Highways England

<b>Version</b>	<b>Date</b>	<b>Status of Version</b>
1	January 2020	DCO Application

## Appendix 11.1: Noise and Vibration Terminology

### 1 Noise Terminology

- 1.1.1 Between the quietest audible sound and the loudest tolerable sound there is a million to one ratio in sound pressure (measured in pascals, Pa). Because of this wide range a noise level scale based on logarithms is used in noise measurement called the decibel (dB) scale. Audibility of sound covers a range of approximately 0 to 140 dB.
- 1.1.2 The human ear system does not respond uniformly to sound across the detectable frequency range and consequently instrumentation used to measure noise is weighted to represent the performance of the ear. This is known as the 'A weighting' (and commonly annotated as dB(A)). Table A11.1.1 below lists the A-weighted sound pressure level in dB for common situations.

**Table A11.1.1: Sound Pressure Levels for a Range of Situations**

Typical A-weighted Sound Pressure Levels (dB)	Example
0	Threshold of hearing
30	Rural area at night, still air
40	Public library Refrigerator humming at 2 m
50	Quiet office, no machinery Boiling kettle at 0.5 m
60	Normal conversation
70	Telephone ringing at 2 m Vacuum cleaner at 3 m
80	General factory noise level
100	Pneumatic drill at 5 m
120	Discotheque – 1 m in front of loudspeaker
140	Threshold of pain

- 1.1.3 The noise level at a measurement point is rarely steady, even in rural areas, and varies over a range dependent upon the effects of local noise sources. Close to a busy road, the noise level may vary over a range of 5 dB, whereas in a suburban area this may increase up to 40 dB and more due to the multitude of noise sources in such areas (cars, dogs, aircraft etc.) and their variable operation. Furthermore, the range of night time noise levels will often be smaller and the levels significantly reduced compared to daytime levels.
- 1.1.4 The equivalent continuous A-weighted sound pressure level,  $L_{Aeq}$ , is the single number that represents the average sound energy measured over that period. The  $L_{Aeq}$  is the sound level of a notionally steady sound having the same energy as a fluctuating sound over a specified measurement period.
- 1.1.5 With regards to road traffic noise the parameter  $L_{A10}$  is prescribed by the relevant guidance and legislation.  $L_{A10}$  is the A-weighted noise level exceeded for 10% of

the measurement period. The  $L_{A10,18h}$  is defined in the Calculation of Road Traffic Noise as the arithmetic average of the individual 1 hour  $L_{A10,1h}$  levels between 06:00 - 00:00.

- 1.1.6 A parameter that is widely accepted as reflecting human perception of the ambient noise is the background noise level,  $L_{A90}$ . This is the A-weighted noise level exceeded for 90 % of the measurement period and generally reflects the noise level in the lulls between individual noise events. Over a one hour period, the  $L_{A90}$  will be the A-weighted noise level exceeded for 54 minutes.
- 1.1.7 The  $L_{Amax}$  noise level is a measure of the maximum A-weighted noise level during the monitoring period.
- 1.1.8 Human subjects are generally only capable of noticing changes in steady levels of no less than 3 dB. It is generally accepted that a change of 10 dB in an overall, steady noise level is perceived to the human ear as a doubling or halving of the noise level. These findings do not necessarily apply to transient or non-steady noise sources.
- 1.1.9 Most environmental noise measurements and assessments are undertaken for 'free-field', away from any existing reflecting surfaces (other than the ground). However, it is sometimes necessary to consider noise levels immediately external to a façade when considering the impact on residents inside properties and this requires the addition of 2.5 or 3.0 dB (as appropriate to the standard being used) to the predicted or measured free-field level due to noise reflection from the façade.

## 2 Vibration Terminology

- 2.1.1 BS 5228 advises that vibrations, even of very low magnitude can be perceptible to people. It is often assumed that if vibration can be felt then building damage will occur, however much higher levels of vibration are required to damage buildings. Therefore vibration from construction works can cause anxiety as well as annoyance. Some individuals are more sensitive to vibration than others.
- 2.1.2 Vibration from construction is commonly described in terms of the Peak Particle Velocity (PPV) measured in mm/s. This is a measurement of the maximum ground particle movement speed during a given time interval. If measurements are made in 3-axis then the resultant PPV is the vector sum of the maximum velocity components, i.e. the square root of the summed squares of the maximum velocities, regardless of when in the time history those occur.