

# MetroWest\*

# **Portishead Branch Line (MetroWest Phase 1)**

### TR040011

Applicant: North Somerset District Council
Response to the Planning Inspectorate's letter of advice under s 51 of the Planning Act 2008 and dated 24 January 2020
Planning Act 2008

Author: Jacobs
Date: March 2020

















# MetroWest\*

Portishead Branch Line (MetroWest Phase 1) DCO Scheme

#### Response to the Planning Inspectorate's letter of advice under s 51 of the Planning Act 2008 and dated 24 January 2020 ("s 51 Letter")

This document sets out North Somerset District Council's ("the Applicant's") response to the Planning Inspectorate's request for information contained in the s 51 Letter.

#### Planning Inspectorate's comment

The Planning Inspectorate has undertaken an initial review of the Flood Risk Assessment ("FRA") submitted as part of the Portishead Branch Line (MetroWest Phase 1) Development Consent Order (DCO) application. See APP-076 to APP-092, duplicated in APP-173 to APP-189. Some concerns were identified during the acceptance stage relating to the FRA and the Inspectorate has raised the following issues and has requested a response from the Applicant:

#### Flood Risk Assessment Currency

The Inspectorate has identified apparent inconsistencies within the FRA relating to the climate change allowances used in modelled scenarios. The inconsistencies relate to allowances for rainfall intensity, peak river flow and sea level rise. Section 5 of the Applicant's FRA Report states that projected climate change allowances were derived following the NPPF 2013 guidance (which is based on DEFRA 2006 climate change guidance). The Inspectorate notes that the NPPF was updated in February 2019, and revised in line with UK Climate Projections 2018, prior to the DCO application being made in November 2019

The inconsistences are broadly as highlighted in the tables below.

| Rainfall in | ntensity: Applic | NPPF Guidance recommendation |          |                     |  |
|-------------|------------------|------------------------------|----------|---------------------|--|
| Year        | 2075             | 2115                         | 2040 to  | 2070 to 2115 (2080s |  |
|             |                  |                              | 2069     |                     |  |
|             |                  |                              | (2050s)  |                     |  |
| Allowance   | 20%              | 30%                          | UE = 20% | UE = 40%            |  |
|             |                  |                              | C = 10%  | C = 20%             |  |

The guidance states that central and upper end allowances should be used in flood risk assessments to understand the range of impact.

| Peak river flow ( Applicant's Asse | -    |      | NPPF Guidance recommendation    |                                 |  |  |
|------------------------------------|------|------|---------------------------------|---------------------------------|--|--|
| Year                               | 2075 | 2115 | 2040 to 2069<br>(2050s)         | 2070 to 2115<br>(2080s)         |  |  |
| Allowance                          | 20%  | 20%  | UE = 40%<br>HC = 25%<br>C = 20% | UE = 70%<br>HC = 35%<br>C = 25% |  |  |

The guidance states that upper end allowances should be used for essential infrastructure in flood zones 2 or 3a.

#### The Applicant's response

#### Section A

It is clear that the climate change allowances in the Inspectorate's tables have been taken from paragraph 5.1.5 of the FRA which states:

"The following climate change allowances have been applied in the modelling undertaken for this FRA:

- Extreme rainfall depths: +20% for 2075; +30% for 2115
- Extreme river flows: +20% for 2075 and 2115
- Sea level rise: +0.59 m between 1990 and 2075; +1.14 m between 1990 and 2115
- Extreme wind speed: +10%
- Extreme wave height: +10%. "

Whilst the Inspectorate has used the correct allowances in the tables provided in the s 51 letter, the Applicant wishes to explain that these were not the climate change allowances applied in the modelling for all the catchments and for all parts of the Proposed Development:

- 1. The allowances for rainfall intensity (or extreme rainfall depths) for small catchments (< 5km²) fluvial models (Drove Rhyne and Easton-in-Gordano Stream) are 20% for 2075 and 30% for 2115 as referred to above. However, for Longmoor and Colliter's Brooks (catchment areas 8.6km<sup>2</sup> and 5.4km<sup>2</sup> respectively) a 25% allowance was applied for both 2075 and 2115. This is because the FRA uses Bristol City Council's (BCC) Central Area Flood Risk Assessment (CAFRA) model to assess fluvial flood risk in Longmoor and Colliter's Brooks (as well as River Avon tidal flood risk). The CAFRA model fluvial climate change allowances specified in the model boundary conditions were retained (+25%) as this was consistent with BCC's CAFRA modelling. Also, the climate change allowances applied in the drainage design for the permanent development sites at Portishead and Pill Station car parks, haul roads and compounds was 40% (see document APP 192 - 6.26 Surface Water Drainage Strategy for Portishead and Pill Stations, Haul Roads and Compounds) which is the Upper End for 2070 to 2115 in the updated NFFP guidance (December 2019 NPPF Guidance – see - https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances). Also, the Applicant's climate change allowance was 30% for the stations and platforms and 20% for the track (see section 8.3 FRA). This was because Network Rail's GRIP 3 design uses a 30% allowance for station buildings and platforms and 20% for track. However, the Applicant formally acknowledges that at detailed design at GRIP 5 it will need to consider a design capacity reflecting an allowance of 40% for climate change which may be enforced through Requirement 11 of the draft DCO.
- 2. For the **peak river flow** the allowance of 20% referred to in paragraph 5.1.5 of the FRA is not correct. As described in the FRA, the only element of the Applicant's modelling that applied river flow allowances was the fluvial simulations undertaken with CAFRA hydraulic model. This modelling applied a 25% allowance for both 2075 and 2115 (to be consistent with the CAFRA modelling). The Applicant has however explained the implications of using the December 2019 NPPF Guidance climate change allowances in Tables 1 and 2 in Appendix 1. The tables show that the Applicant has run further models using the December 2019 NPPF. Guidance for sea level rises (tidal River Avon flooding), and increased rainfall allowances (applied in the Longmoor and Colliter's Brooks and Easton-in-Gordan Stream fluvial models). Furthermore, notwithstanding the reference to the small size of the catchments (see table 1) the Applicant will also re-run the simulation with a 70% allowance for fluvial flooding as an "upper limit" sensitivity test.


#### **NPPF Guidance recommendation**

# Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

| Planning Inspe                    | ctorate's co  | omment      |            |            |            |             |                                  | The Applicant's response   |
|-----------------------------------|---------------|-------------|------------|------------|------------|-------------|----------------------------------|--|
| Sea level                         |               |             |            |            |            |             |                                  | 3. Rainfall intensity and peak river flow have some but not a significant impact on flood risk (see implications in Tables 1   |
| <b>Applicant</b><br>Year          | -             | -           | 2000       | 2036       | 2066       | 2096        | Cumulative 2000 to 212           | and 2 in Appendix 1). The most significant impact of future projected climate change on flood risk will be an increase in  |
|                                   | to            | to          | to         | to         | to         | to          | (m)                              | paragraph 5.1.5 of the FRA denotes the increases in sea levels to 2075 and 2115 due to climate change (0.59m and   |
|                                   | 2075          | 2115        | 2035       | 2065       | 2095       | 2125        | ,                                | 1.14m) used in the CAFRA model. The December 2019 NPPF Guidance levels are generally higher but as the   |
|                                   |               |             | (mm)       | (mm)       | (mm)       | (mm)        |                                  | Inspectorate acknowledges, these figures were only updated in December 2019 after the DCO application was made. A  |
| Allowance                         | 0.59m         | 1.14m       | HC =       | HC =       | HC =       |             | HC = 1.21                        | copy of the sea level rise guidance adopted at the time of the study (pre-December 2019 guidance) is provided in   |
|                                   |               |             | 5.8        | 8.8        | 11.7       | 13.1        | UE = 1.62                        | Appendix 3. These were the sea level rise allowances that were current at the time of submitting the DCO application   |
|                                   |               |             | UE =       | UE =       | UE =       | UE =        |                                  | and it was therefore a pragmatic and reasonable approach to have taken. The Applicant also explains in paragraph   |
|                                   |               |             | 7          | 11.4       | 16         | 18.4        |                                  | 4.2.17 and table 4.4 of the FRA, the Environment Agency ( <b>EA</b> ) Coastal Flood Boundary ( <b>CFB</b> ) 2018 Extreme Water   |
|                                   |               |             |            |            |            | 61 11       |                                  | Levels ( <b>EWL</b> ) at Avonmouth was compared with those of the CFB 2011 dataset (applied in the CAFRA modelling). This  |
| · ·                               |               |             |            | -          | -          |             | owances have not been            | comparison shows the revised CFB 2018 EWLs are lower than equivalent CFB 2011 EWLs, by 0.09 m for the 20 year  |
|                                   | _             |             |            | -          |            |             | er guidance on their use was     | return period EWL. This indicates that whilst the CAFRA modelling uses the climate change allowances derived from  |
|                                   |               | -           |            |            |            |             | hat updates to NPPF guidance     | the NPPF 2013 guidance it overstates "present day" tidal flood risk compared to the more recent 2018 CFB EWLs. Also  |
| for sea level w                   | ere made ii   | n Decembe   | er 2019, a | iter the D | со аррііс  | ation was   | made.                            | Section C together with Tables 3 and 4 in Appendix 1 below compares EWLs at Avonmouth applied in the Portishead  |
|                                   |               |             |            |            |            |             |                                  | Branch Line (MetroWest Phase 1) tidal River Avon modelling (as a downstream boundary condition) with those derived by applying the values of the current CFB 2018 EWLs adjusted to future years with the current sea level rise allowances |
|                                   |               |             |            |            |            |             |                                  | for flood risk assessments (as updated in the December 2019 NPPF Guidance). In other words using the climate change  |
|                                   |               |             |            |            |            |             |                                  | allowances in the Inspectorate's table for sea level rises opposite.   |
|                                   |               |             |            |            |            |             |                                  | anowarioes in the inspectorate 5 table for sea level rises opposite.   |
|                                   |               |             |            |            |            |             |                                  | The Applicant however readily acknowledges that ideally the most recent climate change allowances should have been used  |
|                                   |               |             |            |            |            |             |                                  | throughout where possible. The reason for this omission is mainly due to the FRA having being conducted over a number of   |
|                                   |               |             |            |            |            |             |                                  | years prior to the February 2019 NPPF guidance. The Applicant's consultants also agreed with the EA use of the NPPF2013  |
|                                   |               |             |            |            |            |             |                                  | allowances in September 2015. Subsequently the EA undertook several model reviews as referred to in section 6.2 of the FRA   |
|                                   |               |             |            |            |            |             |                                  | to July 2019 and at no stage were the climate change allowance discrepancies raised.   |
|                                   |               |             |            |            |            |             | n and agreement has been         | Section B  |
|                                   |               |             |            |            |            | d scope o   | f the assessment, however no     | The Applicant has consulted with the EA throughout development of the FRA as detailed in Section 6 of the FRA. This has  |
| specific eviden                   | ce of agree   | ements rea  | cned nas   | been pro   | vided.     |             |                                  | included several submissions of the draft FRA and hydraulic modelling for review. The EA is currently reviewing modelling undertaken to assess the proposed floodplain compensation at the Clanage Road compound site.                     |
|                                   |               |             |            |            |            |             |                                  | The Applicant accepts that there has been no final agreement with the EA but is in dialogue and is aiming to progress with a   |
|                                   |               |             |            |            |            |             |                                  | Statement of Common Ground.  |
| (i) Frequency o                   | f incidents i | of flooding |            |            |            |             |                                  | Statement of Common Ground.  |
|                                   |               |             |            | rom Rive   | r Avon tid | al flooding | g indicates that this section of | Section C  |
|                                   |               |             | -          |            |            |             | 10 years for the assessment      | To respond to the Inspectorate's specific query for Bower Ashton, the Applicant has prepared tables 3 and 4 in Appendix 1  |
| •                                 |               | •           |            |            |            | -           | re (scenarios 2075 and 2115)     | which compares EWLs at Avonmouth applied in the Portishead Branch Line (MetroWest Phase 1) tidal River Avon modelling (as  |
| , ,                               | ,             |             |            | •          | _          |             | ation). In preparation for the   | a downstream boundary condition) with those derived by applying the values of the current CFB2018 EWLs adjusted to future  |
|                                   |               |             |            |            |            |             | e application of the revised     | years with the current sea level rise allowances for flood risk assessments (as updated in the December 2019 NPPF Guidance.)   |
|                                   | -             |             |            |            |            |             | ard. In particular, whether      | The tables have been prepared for the whole of the Proposed Development but naturally includes Bower Ashton as the first   |
| such detail wo<br>the design life |               | •           |            |            | more freq  | uent inter  | vals and at earlier points in    | part of the operational railway which may be susceptible to flooding due to its close proximity to the River Avon.   |
| 5.551511 1116                     | · · · op      |             |            |            |            |             |                                  | The graph below compares EWLs applied in the MetroWest modelling with those derived applying the current CFB dataset   |
|                                   |               |             |            |            |            |             |                                  | (CFB2018) adjusted to future years with the current upper end sea level rise allowances for flood risk assessments, for the 10   |
|                                   |               |             |            |            |            |             |                                  | year and 200 year return periods. This shows that up to approximately 2065 the EWLs applied in the MetroWest modelling are   |
|                                   |               |             |            |            |            |             |                                  | higher than those derived using the current CFB 2018 values and December 2019 NPPF Guidance climate change allowances -  |

#### Portishead Branch Line (MetroWest Phase 1) DCO Scheme



# Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

| Planning Inspectorate's comment | The Applicant's response  |
|---------------------------------|---|
|                                 | The higher central and upper end allowances are both precautionary. As the MetroWest simulated 2075 River Avon tidal EWLs               |
|                                 | are consistently higher than the equivalent updated CFB2018 values with higher central allowance applied, and only 0.03m to             |
|                                 | 0.05m below the upper end allowances (for the 2 year to 200 year return periods), the associated FRA conclusions are                    |
|                                 | considered robust.  |
|                                 | Table 4 in Appendix 1 details an assessment of the calculated future frequency of flooding to the proposed railway. The                 |
|                                 | calculated frequency of future flooding of the proposed railway is approximately:   |
|                                 | - 1 to 2 times per year in 2075 applying the higher central sea level rise allowances,  |
|                                 | - 2 to 3 times per year in 2075 applying the upper end sea level rise allowances.   |
|                                 | - Once every 1 to 2 years in 2060 applying the higher central sea level rise allowances,  |
|                                 | - Once per year in 2060 applying the upper end sea level rise allowances  |
|                                 | These estimates are considered precautionary as the sea level rise allowances are precautionary. The Applicant has also                 |
|                                 | applied the impact of frequency of future flooding on the proposed train service timetable for 2075 at Appendix 2. As is                |
|                                 | demonstrated the impact of flooding on the operation of the proposed train service is negligible.                                       |
|                                 | 2115 (longer climate change horizon simulated as sensitivity test)  |
|                                 | The 2115 FRA simulations were undertaken as a sensitivity test (the scheme design life is represented by the 2075 simulations).         |
|                                 | The 2115 EWLs applied in the MetroWest FRA tidal River Avon modelling are between the current CFB 2018 values with higher               |
|                                 | central and upper end allowances applied, and closer to the values with the higher central allowance applied.                           |
|                                 | As the higher central and upper end allowances are both precautionary, and the MetroWest simulated 2115 River Avon tidal                |
|                                 | EWLs are consistently higher than the equivalent CFB 2018 values with higher central allowance applied, the 2115 sensitivity            |
|                                 | test simulations and associated FRA conclusions are considered robust.  |
|                                 | The calculated frequency of future (2115) flooding of the proposed railway was calculated in the same way as for 2075                   |
|                                 | (described above). The calculated frequency of future (2115) flooding is approximately 5 to 6 times per year applying the               |
|                                 | higher central sea level rise allowances, and approximately 8 times per year applying the upper end sea level rise allowances.          |
|                                 | However, these estimates are considered precautionary as the sea level rise allowances are precautionary. Before Bristol urban          |
|                                 | areas were exposed to this frequency of flooding, it is likely there would be a strategic intervention to reduce flood risk to Bristol. |
|                                 |   |
|                                 | Therefore taking into account updated climate change allowances, including sea level rises, into consideration there is a small         |
|                                 | but not significant increase in anticipated tidal River Avon flood events at more frequent intervals (see Table 4 in Appendix 1)        |
|                                 | but not, as demonstrated in the above graph, at earlier points in the design life of the Proposed Development until after 2065.         |
|                                 | Appendix 2 also shows the impact of frequency of future flooding on the proposed train service timetable for 2115,                      |

# Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

| Planning Inspectorate's comment  | The Applicant's response  |
|--|---|
| (ii) Potential need for compensation   |   |
| The Clanage Road maintenance and access compound will include access ramps         | Section D   |
| to the main road and to the railway. These ramps displace existing floodplain      | The Applicant has now undertaken further modelling to assess whether the proposed floodplain compensation at Bower Ashton (lowering ground  |
| storage. The Applicant proposes compensation to address this displacement by       | levels within the Clanage Road compound site) provides the required compensation – applying the current tidal boundary conditions in the model (i.e.  |
| lowering ground levels within the compound site. In preparation for the            | applying the current CFB 2018 dataset and the current climate change allowances as updated in December 2019 NPPF Guidance.  |
| examination the Inspectorate seeks to understand the extent to which the           | This modelling demonstrates the proposed floodplain compensation at Bower Ashton does fully compensate for the ramps to the main road and   |
| application of the revised climate change allowances may (or may not) affect       | railway with no simulated increase in offsite flood risk up to the 200 year tidal River Avon flood in 2075 and 2115, applying the December 2019 NPPF  |
| the findings in this regard. In particular whether such detail would result in a   | Guidance Upper end sea level rise allowances.   |
| need for increased levels of flood compensation to address greater levels of       | In any event, as the design life of the proposed development is 2075, the mitigation proposed and the tide levels used to undertake an assessment are   |
| floodplain storage being displaced.  | greater than those which are required. An assessment has been completed using 2115 tidal predictions which are in excess of those required for an   |
|  | equivalent assessment of a 2075 design life (both Higher Central and Upper End) and is therefore considered to be conservative.   |
|  | The EA is currently considering the Applicant's further modelling. In the meantime therefore, the FRA conclusions are considered robust in this regard.   |
| The Applicant also proposes to increase the footprint of the railway               | Section E   |
| embankment within the Easton-in-Gordano Stream floodplain which would              | The December 2019 NPPF Guidance on climate change guidance specifies for small catchments such as the Easton-in-Gordano Stream catchment  |
| result in displacement of potential floodplain storage, south of the railway. The  | (<5km²) rainfall climate change allowances should be applied rather than river flow allowances. Assessment of the central and upper end rainfall  |
| Applicant therefore proposes floodplain storage compensation. In preparation       | allowances is required (20% and 40% respectively for both the 2075 and 2115 simulated future years). As mentioned above, the MetroWest Phase 1  |
| for the examination the Inspectorate seeks to understand the extent to which       | FRA modelling of Easton-in-Gordano Stream applies a 20% climate change allowance for 2075 and 30% allowance for 2115.   |
| the application of the revised climate change allowances may (or may not)          | We have now undertaken simulations applying the December 2019 NPPF Guidance upper end climate change allowance (applying 40% uplift for both  |
| affect the findings in this regard. In particular whether such detail would result | the 2075 and 2115 simulated future years). Results of these simulations show that the proposed floodplain storage compensation within the Easton-in-  |
| in a need for increased levels of flood compensation to address greater levels of  | Gordano Stream floodplain does provide mitigation when applying the current upper end climate change allowance of 40%.  |
| floodplain storage being displaced.  | The proposed floodplain storage compensation provides compensation for fluvial flood events up to a peak level of 8.3mAOD. The simulated 100 year   |
|  | return period fluvial flood peak level with 40% climate change allowance is 8.28 mAOD in 2075 and 8.29 mAOD in 2115 i.e. no additional floodplain   |
|  | compensation is required beyond what is proposed in the DCO application.  |
| More generally the Inspectorate is keen to understand the extent to which the      | Section F   |
| application of revised climate change allowances may influence the findings of     | The significance on the findings of the FRA modelling of applying the climate change allowances in the December 2019 NPPF Guidance (and where   |
| the assessment and/or the design of the Proposed Development, including any        | relevant, the current Coastal Flood Boundary 2018 dataset) is summarised in Tables 1 to 6 of Appendix 1.  |
| potential consequential needs for lands, rights or powers to deliver mitigation    | Applying the December 2019 NPPF Guidance climate change allowances and current CFB 2018 dataset does not result in a requirement to change the  |
|  | alignment or elevation of the proposed railway and associated development.  |
|  | The significance in terms of floodplain compensation requirements is summarised in Sections D and E above for two critical areas raised by the  |
|  | Inspectorate; Clanage Road compound and Easton in Gordano railway embankment. The floodplain compensation areas proposed in the FRA are   |
|  | sufficient for these two areas and the proposed development generally i.e. no additional lands, rights or powers are required above what is proposed  |
|  | in the DCO application.   |
|  | The December 2019 NPPF Guidance climate change allowances will be applied in the drainage design during the "GRIP 5" detailed design stage. The   |
|  | Applicant's principal consultant team have also given initial thought to whether it is likely the additional percentage specification at GRIP 5 stage might:  |
|  | (a) lead to either the need for additional land outside of the existing Order land;   |
|  | (b) lead to additional material works being required; and/or  |
|  | (c) give rise to significant environmental effects beyond those contemplated in the Applicant's ES.  The conclusions were that no additional land or material new works are required. No additional significant environmental effects are contemplated. |
|  | The conclusions were that no additional land or material new works are required. No additional significant environmental effects are contemplated.  |



## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

| Planning Inspectorate's comment  | The Applicant's response  |
|--|---|
| (iii) Update on view of the Environment Agency                                   |   |
| The Inspectorate recommends the Applicant responds to the specific points        | Section G   |
| addressed above and in doing so explains if/how climate change allowances        | Responses to the specific points above are presented in this document.  |
| applied in the FRA, are robust and sufficient, taking into account any departure | Tables 1 to 6 provide further detail of the significance to the FRA of the differences between the climate change allowances applied in the FRA and |
| from the allowances proposed in existing guidance. The Applicant should          | those in the December 2019 NPPF Guidance.   |
| provide confidence with regard to the robustness of the FRA and ideally          | Further to the FRA modelling, additional model simulations have been undertaken to inform responses to the specific points above, applying current  |
| demonstrate agreement with the Environment Agency on the scope of the            | climate change allowances.  |
| assessment.  | Whilst there has not yet been final agreement with the EA, we are in dialogue and are aiming to progress with a Statement of Common Ground.         |
|  |   |



Portishead Branch Line (MetroWest Phase 1) DCO Scheme

#### **APPENDICES**

### Appendix 1

Table 1: Peak river flow climate change allowances

| Peak river flow (Sev      | vern)   |   |   |
|---------------------------|---|---|---|
| Epoch                     | *17 December 2019 guidance  | Allowances applied in MetroWest Phase 1 FRA   | Significance of differences   |
| '2080s'<br>(2070 to 2115) | December 2019 NPPF Guidance specifies the Upper end allowance should be applied for Essential Infrastructure projects in Flood Zones 2, 3a or 3b. | 2075: +25%** 2115: +25%**  ** The MetroWest Phase 1 FRA uses Bristol City Council's (BCC) Central Area Flood Risk Assessment (CAFRA) model to assess fluvial flood risk in Longmoor and Colliter's Brooks (as well as River Avon tidal flood risk). The CAFRA   | For small catchments (< 5km2), the climate change allowances specified for rainfall intensity are considered more appropriate than those specified for river flows*. As the Longmoor and Colliter's Brooks catchment areas are only slightly larger (Flood Estimation Handbook catchment areas 8.6km2 and 5.4km2 respectively) the peak rainfall allowances are considered more representative for these watercourses than the peak river flow allowances, which are considered representative of larger catchments.  Longmoor and Colliter's Brooks climate change allowances are therefore considered in Table 2, under peak rainfall allowances. |
|                           | +70% (Upper end allowance)  | model fluvial climate change allowances specified in the model boundary conditions were retained (+25%) as this was consistent with BCC's CAFRA modelling. In the River Avon flood risk in the vicinity of the MetroWest Phase 1 project is tidally dominated and so determined by the tidal (rather than fluvial) simulated events. Simulated River Avon tide conditions are considered in Tables 3 and 4. |   |
| '2050s'<br>(2040 to 2069) | +40% (Upper end allowance)  | Epoch not included in assessment  | Epoch not included in assessment  |

<sup>\* 17</sup> December 2019 guidance taken from https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

Table 2: Peak rainfall climate change allowances

| Peak rainfall intensi |                                   | 1                               |  |
|-----------------------|-----------------------------------|---------------------------------|--|
| Epoch                 | *December 2019 NPPF               | Allowances applied in           | Significance of differences  |
|                       | Guidance                          | MetroWest Phase 1 FRA           |  |
| '2080s'               | Guidance* specifies:              | For small catchments            | Drove Rhyne and Easton-in-Gordano Stream:  |
| (2070 to 2115)        | "For flood risk assessments and   | (< 5km2) fluvial models (Drove  | The December 2019 NPPF Guidance specifies the central and upper end allowances (20% and 40% for both the 2075 and 2115 simulated future years). The MetroWest            |
|                       | strategic flood risk assessments, | Rhyne and Easton-in-Gordano     | Phase 1 modelling of Drove Rhyne and Easton-in-Gordano Stream applies a 20% climate change allowance for 2075 and 30% allowance for 2115.                                |
|                       | assess both the central and       | Stream):                        | Drove Rhyne  |
|                       | upper end allowances to           | 2075: +20%                      | At the railway crossing of Drove Rhyne locations, simulated 1000 year return period peak flood levels (with a 30% climate change allowance) are more than 0.4m below     |
|                       | understand the range of           | 2115: +30%                      | the railway level. The differences between simulated 1000 year peak flood levels with a 20% allowance and 30% allowance are only approximately 0.01m at the railway      |
|                       | impact."                          | For Longmoor and Colliter's     | crossing. Increasing the climate change allowance to 40% is therefore not expected to significantly increase simulated peak flood levels, and therefore is not expected  |
|                       | +20% (Central allowance)          | Brooks (catchment areas         | to impact the railway (and as there is no proposed change to the railway footprint below the flood level the railway would not affect flood risk elsewhere). The         |
|                       | +40% (Upper end allowance)        | 8.6km2 and 5.4km2               | conclusions of the FRA would therefore be unlikely to change if a 40% allowance were applied in the Drove Rhyne modelling. The FRA conclusions are therefore             |
|                       |                                   | respectively):                  | considered robust in this regard.  |
|                       |                                   | 2075: +25%**                    | Easton-in-Gordano Stream   |
|                       |                                   | 2115: +25%**                    | At the railway crossing of Easton-in-Gordano Stream, the simulated 1000 year return period peak flood level (with a 30% climate change allowance) is more than 0.2m      |
|                       |                                   | ** The MetroWest Phase 1        | below the railway level. The difference between simulated 1000 year peak flood levels with a 20% allowance and 30% allowance is only approximately 0.02m at the          |
|                       |                                   | FRA uses Bristol City Council's | railway crossing. Increasing the climate change allowance to 40% is therefore not expected to significantly increase simulated peak flood levels, and therefore is not   |
|                       |                                   | (BCC) Central Area Flood Risk   | expected to impact the railway.  |
|                       |                                   | Assessment (CAFRA) model to     | The MetroWest phase 1 FRA details proposed floodplain compensation on land to the south of (i.e. upstream of) the railway crossing of Easton-in-Gordano Stream, to       |
|                       |                                   | assess fluvial flood risk in    | mitigate a proposed slight increase in railway footprint in the Easton-in-Gordano Stream fluvial floodplain. Table 8.1 in the FRA lists the displaced floodplain storage |
|                       |                                   | Longmoor and Colliter's         | volumes within 0.1 m level ranges, and the compensation volumes provided up to 8.3 mAOD. Table 8.1 in the FRA shows that the proposed floodplain compensation            |
|                       |                                   | Brooks (as well as River Avon   | provides more than the enough compensation for flood levels up to 8.3 mAOD.  |
|                       |                                   | tidal flood risk). The CAFRA    | We have now simulated the 100 year return period Easton-in-Gordano Stream fluvial flood event in 2075 and 2115, applying the December 2019 NPPF Guidance                 |
|                       |                                   | model fluvial climate change    | climate change allowance (+40% for both the 2075 and 2115 simulations) and with increased tidal boundaries according to the current climate change guidance. This        |
|                       |                                   | allowances specified in the     | gives peak 100 year fluvial flood levels in the floodplain directly south of the railway of 8.28mAOD for 2075 and 8.29mAOD for 2115. The proposed flood compensation     |
|                       |                                   | model boundary conditions       | area is therefore shown to be sufficient when applying the December 2019 NPPF Guidance climate change allowances.  |
|                       |                                   | were retained (+25%) as this    | The FRA conclusions are therefore considered robust in this regard.  |
|                       |                                   | was consistent with BCC's       | Longmoor and Colliter's Brooks   |
|                       |                                   | CAFRA modelling.                | The December 2019 NPPF Guidance specifies the central and upper end allowances (20% and 40% for both the 2075 and 2115 simulated future years). The MetroWest            |
|                       |                                   |                                 | Phase 1 modelling of Longmoor and Colliter's Brooks applies a 25% climate change allowance for both 2075 and 2115.   |
|                       |                                   |                                 | We have now simulated flooding in the Longmoor and Colliter's Brooks applying the December 2019 NPPF Guidance climate change allowances (40% uplift in model             |
|                       |                                   |                                 | inflows and current sea level rise allowances applied). Applying these climate change and sea level rise allowances has not resulted in a change in the simulated future |
|                       |                                   |                                 | frequency of closure of the railway at Longmoor and Colliter's Brooks in 2075 and 2115. This remains at once every 50 to 75 years (i.e. as assessed in the FRA). The FRA |
|                       |                                   |                                 | conclusions are therefore considered robust in this regard.  |
| '2050s'               | +10% (Central allowance)          | Epoch not included in           | Epoch not included in assessment   |
| (2040 to 2069)        | +20% (Upper end allowance)        | assessment                      |  |

<sup>\* 17</sup> December 2019 guidance taken from https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances



Table 3: Comparison of EWLs applied in MetroWest Phase 1 tidal River Avon modelling with EWLs applying the current CFB2018 dataset and December 2019 NPPF climate change guidance\*

|         | *CFB 2018 EW | Ls adjusted f | or future yea | ır                       |          | EWLs appli       | applied in MetroWest Differences: EWLs applied in MetroWest tidal River Avon modelling minus CFB2018 EWLs adjusted with December 2019 NPPl |       |                                |                               |                                | 2019 NPPF climate change |  |
|---------|--------------|---------------|---------------|--------------------------|----------|------------------|--|-------|--------------------------------|-------------------------------|--------------------------------|--------------------------|--|
|         | (mAOD)       |               |               | Phase 1 tidal River Avon |          |                  | climate change allowances  |       |                                |                               |                                |                          |  |
|         |              |               |               |                          |          | modelling (mAOD) |  |       | (m)                            | (m)                           |                                |                          |  |
| Return  | Base year    | adjusted      | adjusted      | adjusted                 | adjusted | 2015             | 2075   | 2115  | 2075:                          | 2075:                         | 2115:                          | 2115:                    |  |
| period  | 2017         | to 2075       | to 2075       | to 2115                  | to 2115  |                  |  |       | MetroWest EWLs – CFB2018 EWLs  | MetroWest EWLs – CFB2018 EWLs | MetroWest EWLs – CFB2018 EWLs  | MetroWest EWLs – CFB2018 |  |
| (years) |              |               |               |                          |          |                  |  |       | with Higher central adjustment | with Upper end adjustment     | with Higher central adjustment | EWLs with Upper end      |  |
|         |              | UKCP18        | UKCP18        | UKCP18                   | UKCP18   |                  |  |       |                                |                               |                                | adjustment               |  |
|         |              | Higher        | Upper         | Higher                   | Upper    |                  |  |       |                                |                               |                                |                          |  |
|         |              | central       | end           | central                  | end      |                  |  |       |                                |                               |                                |                          |  |
| 2       | 8.22         | 8.71          | 8.85          | 9.20                     | 9.54     | 8.30             | 8.81   | 9.36  | 0.10                           | -0.04                         | 0.15                           | -0.18                    |  |
| 5       | 8.37         | 8.86          | 9.00          | 9.35                     | 9.69     | 8.46             | 8.97   | 9.52  | 0.11                           | -0.03                         | 0.16                           | -0.17                    |  |
| 10      | 8.49         | 8.98          | 9.12          | 9.47                     | 9.81     | 8.58             | 9.09   | 9.64  | 0.11                           | -0.03                         | 0.16                           | -0.17                    |  |
| 20      | 8.61         | 9.10          | 9.24          | 9.59                     | 9.93     | 8.70             | 9.21   | 9.76  | 0.11                           | -0.03                         | 0.16                           | -0.17                    |  |
| 50      | 8.79         | 9.28          | 9.42          | 9.77                     | 10.11    | 8.88             | 9.39   | 9.94  | 0.11                           | -0.03                         | 0.16                           | -0.17                    |  |
| 200     | 9.07         | 9.56          | 9.70          | 10.05                    | 10.39    | 9.14             | 9.65   | 10.20 | 0.09                           | -0.05                         | 0.14                           | -0.19                    |  |
| 1000    | 9.43         | 9.92          | 10.06         | 10.41                    | 10.75    | 9.46             | 9.97   | 10.52 | 0.05                           | -0.09                         | 0.10                           | -0.23                    |  |

<sup>\*</sup> Sea Level Rise allowances have been applied using the December 2019 NPPF Guidance) to adjust CFB2018 EWLs (base year 2017) at Avonmouth to future years

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

Table 4: Interpretation of comparison of tidal River Avon EWLs presented in Table 3

| Simulation                          | Comparison  | Significance   |
|-------------------------------------|---|--|
| Present day                         | MetroWest simulated 2015 River Avon tidal EWLs are consistently higher than the CFB2018 values  | Based on the MetroWest simulations undertaken, the FRA concludes that the MetroWest railway floods at  |
|                                     | (with base year 2017)   | Bower Ashton approximately once every 5 to 10 years on average for the present day. The MetroWest FRA  |
|                                     |   | present day simulations overstate flood risk compared to the current CFB2018 EWLs i.e. the FRA values are  |
|                                     |   | slightly more precautionary than the current guidance.   |
|                                     |   | The FRA conclusions are therefore considered robust in this regard.  |
| 2075 (DCO scheme design life year)  | Higher central allowance:   | The December 2019 NPPF Guidance* states: "For flood risk assessments and strategic flood risk assessments,   |
| , , ,                               | MetroWest simulated 2075 River Avon tidal EWLs are consistently higher than the CFB2018 values  | assess both the central and upper end allowances to understand the range of impact."   |
|                                     | adjusted to 2075 applying the higher central allowance* by 0.09m to 0.11m (2 year to 200 year   | The 2075 EWLs applied in the MetroWest FRA modelling are between the current CFB2018 values with higher  |
|                                     | return periods) and by 0.05m (1000 year return period).   | central and upper end allowances applied, and closer to the values with the upper end allowance applied.   |
|                                     |   | The higher central and upper end allowances are both precautionary. As the MetroWest simulated 2075 River  |
|                                     | Upper end allowance:  | Avon tidal EWLs are consistently higher than the equivalent CFB2018 values with higher central allowance   |
|                                     | MetroWest simulated 2075 River Avon tidal EWLs are consistently lower than the CFB2018 values   | applied, and only 0.03m to 0.05m below the upper end allowances (for the 2 year to 200 year return periods),   |
|                                     | adjusted to 2075 applying the upper end allowance* by 0.03m to 0.05m (2 year to 200 year return | the associated FRA conclusions are considered robust.  |
|                                     | periods) and by 0.09m (1000 year return period).  | Since the completion of the FRA, the Applicant has undertaken an assessment of the anticipated frequency of  |
|                                     |   | flooding of the proposed railway at Bower Ashton in 2075 as follows:   |
|                                     |   | - Downloaded quality controlled Avonmouth tidal gauge monthly extremes from the British  |
|                                     |   | Oceanographic Data centre  |
|                                     |   | (https://www.bodc.ac.uk/data/hosted data systems/sea level/uk tide gauge network/processed/)   |
|                                     |   | - From this dataset, derived tide levels that are exceeded on average 1, 2, 3, 4, 5, 6, 8 and 10 times per   |
|                                     |   | year. This was based on data for the period 2003 to 2011 and so is considered to represent a base  |
|                                     |   | year of 2007.  |
|                                     |   | <ul> <li>Adjusted these calculated 2007 tidal levels to future years (including 2075) by applying the current</li> </ul>   |
|                                     |   | specified FRA sea level allowances   |
|                                     |   | - The MetroWest FRA modelling indicates there would be flooding of the proposed railway when   |
|                                     |   | Avonmouth tide levels reach approximately 8.46mAOD to 8.58mAOD (these are the 5 year and 10  |
|                                     |   | year tide levels in 2015 applied in the MetroWest FRA tidal River Avon modelling, for which the 5  |
|                                     |   | year simulation does not result in flooding to the proposed railway whilst the 10 year simulation  |
|                                     |   | does).   |
|                                     |   | ,  |
|                                     |   | - The approximate future (2075) frequency of flooding of the railway at Bower Ashton is taken to be  |
|                                     |   | the same as the calculated frequency of tide levels exceeding this approximate range in 2075.  |
|                                     |   | The calculated frequency of future flooding of the proposed railway is approximately:  |
|                                     |   | - 1 to 2 times per year in 2075 applying the higher central sea level rise allowances,   |
|                                     |   | - 2 to 3 times per year in 2075 applying the upper end sea level rise allowances.  |
|                                     |   | - Once per year in 2060 applying the higher central sea level rise allowances,   |
|                                     |   | - Once every 1 to 2 years in 2060 applying the upper end sea level rise allowances   |
|                                     |   | Office every 1 to 2 years in 2000 applying the apperent sea revertise allowances   |
|                                     |   | These estimates are considered amounting and the second size of the se |
| 2115 (longer climate change horizon | Higher central allowance:   | These estimates are considered precautionary as the sea level rise allowances are precautionary.  The 2115 FRA simulations were undertaken as a sensitivity test (the scheme design life is represented by the   |
| , ,                                 | MetroWest simulated 2115 River Avon tidal EWLs are consistently higher than the CFB2018 values  |  |
| simulated as sensitivity test)      | adjusted to 2115 applying the higher central allowance* by 0.14m to 0.16m (2 year to 200 year   | 2075 simulations). The 2115 EWLs applied in the MetroWest FRA tidal River Avon modelling are between the current CFB2018   |
|                                     |   |  |
|                                     | return periods) and 0.10m (1000 year return period).  | values with higher central and upper end allowances applied, and closer to the values with the higher central  |
|                                     | Linner and allowance  | allowance applied.  As the higher central and upper and allowances are both pressutionary, and the MetroWest simulated 2115.   |
|                                     | Upper end allowance:  | As the higher central and upper end allowances are both precautionary, and the MetroWest simulated 2115  |
|                                     | MetroWest simulated 2075 River Avon tidal EWLs are consistently lower than the CFB2018 values   | River Avon tidal EWLs are consistently higher than the equivalent CFB2018 values with higher central   |
|                                     | adjusted to 2075 applying the upper end allowance from the December 2019 NPPF Guidance by       | allowance applied, the 2115 sensitivity test simulations and associated FRA conclusions are considered robust.   |
|                                     | 0.17m to 0.19m (2 year to 200 year return periods) and by 0.23m (1000 year return period).      |  |

# Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

| Simulation                             | Comparison | Significance  |
|--|------------|---|
|  |            | The calculated frequency of future (2115) flooding of the proposed railway was calculated in the same way as    |
|  |            | for 2075 (described above). The calculated frequency of future (2115) flooding is approximately 5 to 6 times    |
|  |            | per year applying the higher central sea level rise allowances, and approximately 8 times per year applying the |
|  |            | upper end sea level rise allowances. However, these estimates are considered precautionary as the sea level     |
|  |            | rise allowances are precautionary.  |
| Floodplain compensation within the     |            | The Applicant has now undertaken further modelling to assess whether the proposed floodplain                    |
| Clanage Road compound at Bower Ashton  |            | compensation at Bower Ashton (lowering ground levels within the Clanage Road compound site) provides the        |
| to mitigate displacement of floodplain |            | required compensation – applying the current tidal boundary conditions in the model (i.e. applying the          |
| storage by access ramp at Clanage Road |            | current EA CFB 2018 dataset and the December 2019 NPPF Guidance climate change allowances.                      |
|  |            | This modelling demonstrates the proposed floodplain compensation at Bower Ashton does fully compensate          |
|  |            | for the ramps to the main road and railway with no simulated increase in offsite flood risk up to the 200 year  |
|  |            | tidal River Avon flood in 2075 and 2115, applying the current Upper end sea level rise allowances.              |
|  |            | The FRA conclusions are therefore considered robust in this regard.   |



Table 5: Comparison of EWLs applied in MetroWest Phase 1 coastal modelling with EWLs applying the current CFB2018 dataset and December 2019 NPPF climate change guidance\*

|                             |                   | 5  |   | EWLs applied in MetroWest coastal model at Avonmouth (mAOD) |   |      | Differences: EWLs applied in MetroWest coastal modelling minus CFB2018 EWLs adjusted with December 2019 NPPF climate change allowances (m) |       |  |   |  |  |
|-----------------------------|-------------------|--|---|---|---|------|--|-------|--|---|--|--|
| Return<br>period<br>(years) | Base year<br>2017 | adjusted<br>to 2075<br>UKCP18<br>Higher<br>central | adjusted<br>to 2075<br>UKCP18<br>Upper<br>end | adjusted<br>to 2115<br>UKCP18<br>Higher<br>central          | adjusted<br>to 2115<br>UKCP18<br>Upper<br>end | 2015 | 2075   | 2115  | 2075:<br>MetroWest EWLs — CFB2018 EWLs<br>with Higher central adjustment | 2075:<br>MetroWest EWLs – CFB2018 EWLs<br>with Upper end adjustment | 2115: MetroWest EWLs – CFB2018 EWLs with Higher central adjustment | 2115:<br>MetroWest EWLs – CFB2018<br>EWLs with Upper end<br>adjustment |
| 25                          | 8.65              | 9.14   | 9.28  | 9.63  | 9.97  |      |  | 9.87  |  |   | 0.24   | -0.09  |
| 50                          | 8.79              | 9.28   | 9.42  | 9.77  | 10.11   |      |  | 10.00 |  |   | 0.23   | -0.10  |
| 100                         | 8.92              | 9.41   | 9.55  | 9.90  | 10.24   |      |  | 10.13 |  |   | 0.23   | -0.10  |
| 200                         | 9.07              | 9.56   | 9.70  | 10.05   | 10.39   |      | 9.71   | 10.26 | 0.16   | 0.01  | 0.21   | -0.12  |
| 1000                        | 9.43              | 9.92   | 10.06   | 10.41   | 10.75   | 9.44 |  | 10.58 |  |   | 0.17   | -0.16  |

<sup>\*</sup> Sea Level Rise allowances have been applied using the December 2019 NPPF Guidance to adjust CFB2018 EWLs (base year 2017) at Avonmouth to future years

## Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

Table 6: Interpretation of comparison of coastal EWLs presented in Table 5

| Simulation   | Comparison  | Significance  |  |  |  |  |
|--|---|---|--|--|--|--|
| Present day  | The MetroWest simulated 1000 year return period coastal EWL in 2015 is 0.01m higher than the CFB2018 value (base year 2017).  | For this coastal flood event the DCO scheme is outside of the MetroWest FRA simulated flood extent. As the EWL applied in the FRA is higher than the equivalent CFB2018 EWL, the FRA conclusions are considered robust in this regard.  |  |  |  |  |
| 2075 (DCO scheme design year)                                      | The MetroWest simulated 200 year return period coastal EWL in 2015 is 0.16m and 0.01m higher than the CFB2018 value with higher central and upper end allowances applied respectively.  | For the 200 year return period coastal flood event in 2075, the DCO scheme is outside of the MetroWest FRA simulated flood extent. As the EWL applied in the FRA is higher than the equivalent CFB2018 EWL applying both the higher central and upper end allowances, the FRA conclusions are considered robust in this regard.   |  |  |  |  |
| 2115 (longer climate change horizon simulated as sensitivity test) | Higher central allowance:  MetroWest simulated 2115 coastal EWLs are consistently higher than the CFB2018 values adjusted to 2115 applying the higher central allowance* by 0.21m to 0.24m (25 year to 200 year return periods) and 0.17m (1000 year return period).  Upper end allowance:  MetroWest simulated 2075 coastal EWLs are consistently lower than the CFB2018 values adjusted to 2115 applying the upper end allowance* by 0.09m to 0.12m (2 year to 200 year return periods) and by 0.16m (1000 year return period). | The 2115 FRA simulations were undertaken as a sensitivity test (the scheme design life is represented by the 2075 simulations).  The 2115 EWLs applied in the MetroWest FRA coastal modelling are between the current CFB2018 values with higher central and upper end allowances applied, and closer to the values with the upper end allowance applied.  As the higher central and upper end allowances are both precautionary, and the MetroWest simulated 2115 coastal EWLs are consistently higher than the equivalent CFB2018 values with higher central allowance applied, the 2115 sensitivity test simulations and associated FRA conclusions are considered robust.  Applying CFB2018 values adjusted to 2115 applying the upper end allowance would change the assessed frequency of coastal flooding of the proposed MetroWest railway in 2115 from approximately once every 100 to 200 years to approximately once every 50 to 100 years, and may slightly increase the frequency of inundation of Portishead station, car parks and the crossing of Portbury ditch from approximately once every 1000 years on average to e.g. once every 200 years on average (estimated). |  |  |  |  |



#### Appendix 2

|   | Frequency of flooding   | Flooding frequency<br>annualised equivalent<br>(occurrences per year) | Number of<br>high tides for<br>each<br>occurrence <sup>1</sup> | Aggregate flooding occurrences per year |          | year | hours of t | flooding per | Total hours of passenger train operation (Portishead Line) per year <sup>3</sup> | Percentag<br>operating<br>per year of<br>flooding <sup>4</sup> | hour<br>due to | s lost |
|---|---|---|--|---|----------|------|------------|--------------|--|--|----------------|--------|
| Present Day   | 1 occurrence every 5 to 10 years on average   | 0.1 to 0.2  | 2  | 0.2 to 0.4                              | 12 hours | 2.4  | to         | 4.8          | 6082   | 0.04%  | to             | 0.08%  |
| 2075 (DCO Scheme<br>design life year)                           | 1 to 2 occurrences in<br>2075 with higher central<br>sea level rise allowances        | 1 to 2  | 2  | 2 to 4                                  | 12 hours | 24   | to         | 48           | 6082   | 0.39%  | to             | 0.79%  |
|   | 2 to 3 occurrences in<br>2075 with upper end sea<br>level rise allowances             | 2 to 3  | 2  | 4 to 6                                  | 12 hours | 48   | to         | 72           | 6082   | 0.79%  | to             | 1.18%  |
|   | 1 occurrence every 1 to 2 years in 2060 with higher central sea level rise allowances | 0.5 to 1  | 2  | 1 to 2                                  | 12 hours | 12   | to         | 24           | 6082   | 0.20%  | to             | 0.39%  |
|   | 1 occurrence per year in<br>2060 with upper end sea<br>level rise allowance           | 1   | 2  | 2                                       | 12 hours | 24   |            |              | 6082   | 0.39%  |                |        |
| 2115 (Longer climate change horizon simulated sensitivity test) | 5 to 6 occurrences in<br>2115 with the higher<br>central sea level rise<br>allowances | 5 to 6  | 2  | 10 to 12                                | 12 hours | 120  | to         | 144          | 6082   | 1.97%  | to             | 2.37%  |
|   | 8 occurrences in 2115<br>with the upper end sea<br>level rise allowances              | 8   | 2  | 16                                      | 12 hours | 192  |            |              | 6082   | 3.16%  |                |        |

<sup>&</sup>lt;sup>1</sup> The frequency of flooding was calculated based on historic monthly tidal extremes data rather than a sub-daily time series dataset, which results in a slight bias towards underestimating frequency of flooding. To compensate for this, the number of high tides has been adjusted (i.e. doubled). This is likely to over-compensate and hence the calculated "Percentage of train operating hours lost per year due to flooding" values are likely to be overestimates.

<sup>&</sup>lt;sup>2</sup> 12 hours comprising of 2 hours either side of high tide and 8 hours for Network Rail to inspect the section line affected and remove any debris.

<sup>&</sup>lt;sup>3</sup> Total hours of passenger train operation (Portishead Line) per year, was calculated as table below:

<sup>&</sup>lt;sup>4</sup> Percentage of train operating hours lost per year due to flooding is overstated because the calculation assumes that flooding always coincides with when trains operate, however trains will operate a maximum of 18 hours in a 24 hour day. File: 674946CH.CY.76/91/007/001

# Memorandum

## Portishead Branch Line (MetroWest Phase 1) DCO Scheme

|                      | Level of service   | Hours of operation per day | Hours of operation per week | Total hours of operation per year (less Christmas Day, Boxing Day and New Years day) |
|----------------------|--|----------------------------|-----------------------------|--|
| Mondays to Saturdays | Monday to Saturday first<br>train 06XX, then hourly<br>to 23XX | 18                         | 108                         | 5562   |
| Sundays              | Sunday first train 10XX,<br>then hourly to 18XX                | 10                         | 10                          | 520  |
| Total                |  |                            |                             | 6082   |



#### Appendix 3

Sea level rise allowances that were current at the time of submitting the DCO application – copied from the February 2019 version of the FRA climate change allowances guidance:

<a href="https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances">https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances</a> (note the website now only includes the current allowances updated in December 2019). For the MetroWest Phase 1 FRA modelling, the South West allowances were applied.

Table 3 sea level allowance for each epoch in millimetres (mm) per year with cumulative sea level rise for each epoch in brackets (use 1990 baseline)

| Area of England                            | 1990 to<br>2025      | 2026 to<br>2055 | 2056 to<br>2085     | 2086 to<br>2115     | Cumulative rise 1990 to 2115 / metres (m) |
|--|----------------------|-----------------|---------------------|---------------------|---|
| East, east midlands,<br>London, south east | 4 (140<br>mm)        | 8.5 (255<br>mm) | 12 (360<br>mm)      | 15 (450<br>mm)      | 1.21 m                                    |
| South West                                 | 3.5<br>(122.5<br>mm) | 8 (240<br>mm)   | 11.5<br>(345<br>mm) | 14.5<br>(435<br>mm) | 1.14 m                                    |
| North west, north east                     | 2.5 (87.5<br>mm)     | 7 (210<br>mm)   | 10 (300<br>mm)      | 13 (390<br>mm)      | 0.99 m                                    |