Appendix 9.3 - Model Verification

Model verification studies are undertaken in order to check the performance of dispersion models and, where modelled concentrations are significantly different to monitored concentrations, a factor can be established by which the modelled results can be adjusted in order to improve their reliability. The model verification process is detailed in LAQM TG(16).

According to LAQM TG(16), adjustment is not necessary where:

- There is no systematic under or over prediction
- Predictions at sites where monitoring shows concentrations are close to the objective show good comparison; and
- The majority of results lie within 25% (as a minimum preferably within 10%) of monitored concentrations.

Model verification can only be undertaken where there is sufficient roadside monitoring data in the vicinity of the subject scheme being assessed. LAQM TG(16) recommends that a combination of automatic and diffusion tube monitoring data is used; although this may be limited by data availability.

Background concentrations were based on UK-AIR data for the corresponding year.

Vehicle speeds were estimated based on LAQM TG(16), the outputs of the NTSM2 model and the practitioners driving experience; it was ensured that vehicle speeds used in model verification and the modelling scenarios were directly comparable.

As the assessment for Northampton Gateway covered a number of different study areas, a verification study was undertaken for each area separate area, where appropriate. These are summarised below, in the following format:

- Model verification inputs and summary;
- Table showing comparison of modelled and monitored data;
- Graph with trend line (Modelled vs Monitored NO_x) and equation (adjustment factor) (unless no adjustment was required); and
- Table showing comparison of adjusted modelled and monitored data

Northampton AQMA No.1 and NSSUE, Collingtree

- Year(s) of verification: 2016
- Verification factor(s):
 - 0 3.02

Table A9.3.1: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count			Concentrations (µg.m ⁻³)		
Monitor Location	Point	Туре	Monitored	Modelled	(%)	
Project Tube 1	58373	DT	32.7	19.1	-41.7%	
Project Tube 2	58373	DT	29.1	16.6	-42.9%	
Project Tube 3	58373	DT	27.8	15.3	-44.8%	
Project Tube 4	58373	DT	38.0	22.6	-40.5%	

Figure A9.3.1: Monitored vs Modelled NO_x




Table A9.3.2: Comparison of Monitored and Adjusted Modelled Total NO₂

Monitor Location	Tymo	Concentration	Difference (9/)	
Monitor Location	Туре	Monitored	Modelled	Difference (%)
Project Tube 1	DT	32.7	32.1	-1.8%
Project Tube 2	DT	29.1	25.5	-12.4%
Project Tube 3	DT	27.8	21.9	-21.2%
Project Tube 4	DT	38.0	41.3	8.6%

Northampton AQMA No.5, Wootton

• Year(s) of verification: 2015 & 2016

Verification factor(s):

2015: 2.302016: 2.91

Table A9.3.3: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count	DfT Count Point Type	Concentrations (µg.m ⁻³)		Difference			
	Point		Monitored	Modelled	(%)			
2015								
Hermitage Way	77419	DT	38.1	23.4	-38.5%			
Chestnut Avenue	77419	DT	31.6	22.3	-29.5%			
2016								
Hermitage Way	77419	DT	43.0	23.0	-46.5%			
Chestnut Avenue	77419	DT	36.6	21.9	-40.1%			

Figure A9.3.2: Monitored vs Modelled NO_x




Table A9.3.4: Comparison of Monitored and Adjusted Modelled Total NO₂

Monitor Location	DfT Count Tyme	Concentration	Difference				
Monitor Location	Point	Туре	Monitored	Modelled	(%)		
2015							
Hermitage Way	77419	DT	38.1	31.7	-16.9%		

Chestnut Avenue	77419	DT	31.6	29.8	-5.9%
		201	6		
Hermitage Way	77419	DT	43.0	37.2	-13.6%
Chestnut Avenue	77419	DT	36.6	34.9	-4.7%

AQMQ No.4, Kingsthorpe

• Year(s) of verification: 2015 & 2016

Verification factor(s):

o **2015**

Leeward: 6.23Windward: 3.94

o **2016**:

Leeward: 5.92Windward: 4.82

• Harborough Road scoped out of MV as adjacent to bus stop and suspected limited air flow around DT.

Table A9.3.5: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count	Time	Concentration	ons (µg.m ⁻³)	Difference			
Monitor Location	Point	Туре	Monitored	Modelled	(%)			
2015								
Harborough Road 2	99145	DT	35.9	23.7	-34.0%			
Harborough Road 3	99145	DT	36.7	19.4	-47.1%			
Harborough Road 5	99145	DT	44.8	19.6	-56.4%			
Harborough Road 6	99145	DT	45.1	22.5	-50.2%			
Harborough Road 7	46546	DT	40.7	24.5	-39.7%			
Harborough Road 11	28261	DT	35.0	20.9	-40.3%			
Kingsthorpe Grove 1	26539	DT	37.9	19.0	-49.9%			
Harborough Road 8	46546	DT	37.3	21.7	-41.8%			
Harborough Road 4	99145	DT	44.1	21.4	-51.4%			
Kingsthorpe Grove 2	26539	DT	32.6	20.3	-37.8%			
		2016						
Harborough Road 2	99145	DT	41.0	23.7	-42.2%			
Harborough Road 3	99145	DT	35.1	19.6	-44.2%			
Harborough Road 5	99145	DT	45.0	19.7	-56.2%			

Harborough Road 6	99145	DT	48.7	22.5	-53.9%
Harborough Road 7	46546	DT	44.4	24.5	-44.9%
Harborough Road 11	28261	DT	46.9	20.8	-55.8%
Kingsthorpe Grove 1	26539	DT	41.1	19.0	-53.8%
Harborough Road 8	46546	DT	41.2	22.2	-46.2%
Harborough Road 4	99145	DT	48.5	21.3	-56.0%
Kingsthorpe Grove 2	26539	DT	38.8	20.1	-48.2%

Figure A9.3.3: Monitored vs Modelled NO_x




Table A9.3.6: Comparison of Monitored and Adjusted Modelled Total NO₂

Manitan Lagation	DfT Count	DfT Count	DfT Count	Tuna	Concentration	ons (µg.m ⁻³)	Difference
Monitor Location	Point	Туре	Monitored	Modelled	(%)		
2015							
Harborough Road 2	99145	DT	35.9	42.9	19.6%		
Harborough Road 3	99145	DT	36.7	34.8	-5.1%		

Harborough Road 5	99145	DT	44.8	35.5	-20.8%
Harborough Road 6	99145	DT	45.1	38.9	-13.8%
Harborough Road 7	46546	DT	40.7	45.6	12.0%
Harborough Road 11	28261	DT	35.0	33.5	-4.2%
Kingsthorpe Grove 1	26539	DT	37.9	32.3	-14.7%
Harborough Road 8	46546	DT	37.3	46.4	24.3%
Harborough Road 4	99145	DT	44.1	35.4	-19.8%
Kingsthorpe Grove 2	26539	DT	32.6	31.5	-3.5%
		2016			
Harborough Road 2	99145	DT	41.0	49.2	19.9%
Harborough Road 3	99145	DT	35.1	36.5	3.9%
Harborough Road 5	99145	DT	45.0	37.1	-17.6%
Harborough Road 6	99145	DT	48.7	44.5	-8.6%
Harborough Road 7	46546	DT	44.4	51.9	16.9%
Harborough Road 11	28261	DT	46.9	37.7	-19.6%
Kingsthorpe Grove 1	26539	DT	41.1	33.4	-18.7%
Harborough Road 8	46546	DT	41.2	48.6	17.9%
Harborough Road 4	99145	DT	48.5	40.1	-17.4%
Kingsthorpe Grove 2	26539	DT	38.8	35.1	-9.6%

Northampton AQMA No.2, Victoria Promenade

• Year(s) of verification: 2015 & 2016

Verification factor(s):
 2015: 1.66
 2016: 2.85

Table A9.3.7: Comparison of Monitored and Modelled Total NO₂

Manifest Landing	DfT Count	T	Concentration	Concentrations (µg.m ⁻³)			
Monitor Location	Point	Туре	Monitored	Modelled	(%)		
2015							
Bridge Street 2	74755	DT	37.1	32.5	-12.3%		
Bridge Street 3	74755	DT	43.0	33.3	-22.5%		
Plough 1	74752 & 74755	DT	38.8	36.1	-7.1%		
Plough 2	74752	DT	39.1	34.8	-10.9%		
Victoria Promenade	36486	DT	32.0	30.5	-4.8%		
		201	6				
Bridge Street 2	74755	DT	46.9	31.9	-32.0%		
Bridge Street 3	74755	DT	46.4	32.7	-29.5%		
Plough 1	74752 & 74755	DT	47.5	35.3	-25.7%		
Plough 2	74752	DT	46.6	34.0	-27.0%		
Victoria Promenade	36486	DT	34.6	29.7	-14.0%		

Figure A9.3.4: Monitored vs Modelled NO_x




Table A9.3.8: Comparison of Monitored and Adjusted Modelled Total NO₂

	Dit Count		Concentration	ons (µg.m ⁻³)	D:#arrange				
Monitor Location	DfT Count Point	Туре	Monitored	Adjusted Modelled	Difference (%)				
	2015								
Bridge Street 2	74755	DT	37.1	36.3	-2.2%				
Bridge Street 3	74755	DT	43.0	37.6	-12.5%				
Plough 1	74752 & 74755	DT	38.8	41.9	8.0%				
Plough 2	74752	DT	39.1	40.0	2.2%				
Victoria Promenade	36486	DT	32.0	33.0	3.1%				
		201	6						
Bridge Street 2	74755	DT	46.9	42.1	-10.2%				
Bridge Street 3	74755	DT	46.4	44.2	-4.8%				
Plough 1	74752 & 74755	DT	47.5	50.6	6.5%				
Plough 2	74752	DT	46.6	47.4	1.8%				

Victoria Promenade 36486	DT	34.6	36.5	5.4%
--------------------------	----	------	------	------

Northampton AQMA No.6, Campbell Square

• Year(s) of verification: 2015 & 2016

Verification factor(s):2015: 4.11

o 2016: 5.85

Table A9.3.9: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count	T	Concentrations (µg.m ⁻³)		Difference		
Monitor Location	Point	Туре	Monitored	Modelled	(%)		
		201	5				
Campbell Square 2	7707	DT	37.5	23.8	-36.5%		
Campbell Square 4	7707	DT	35.2	23.7	-32.7%		
Campbell Square 5	7723	DT	40.6	24.9	-38.7%		
Campbell Square 2	7707	DT	48.6	23.2	-52.4%		
Campbell Square 4	7707	DT	39.6	23.0	-41.8%		
Campbell Square 5	7723	DT	43.5	24.3	-44.1%		

Figure A9.3.5: Monitored vs Modelled NO_x




Table A9.3.10: Comparison of Monitored and Adjusted Modelled Total NO₂

Monitor Location	DfT Count	Туре	Concentrations (µg.m ⁻³)		Difference	
	Point		Monitored	Modelled	(%)	
		201	5			
Campbell Square 2		DT	37.5	36.6	-2.3%	
Campbell Square 4		DT	35.2	36.3	3.0%	
Campbell Square 5		DT	40.6	40.5	-0.3%	
2016						
Campbell Square 2		DT	48.6	41.9	-13.8%	
Campbell Square 4		DT	39.6	41.4	4.5%	
Campbell Square 5		DT	43.5	47.4	9.0%	

Northampton AQMA No.8, St Michaels Road

• Year(s) of verification: 2015, 2016

• No DfT traffic data available for verification.

• Verification factor(s):

2015: 12016: 1

Roade Bypass and West Lodge Cottages

• Year(s) of verification: 2015 (Roade), 2016 (West Lodge Cottages)

Verification factor(s):

o Roade: 3.84

o West Lodge Cottages: 5.35

Table A9.3.11: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count Point	Туре	Concentrations (µg.m ⁻³)		Difference	
			Monitored	Modelled	(%)	
		Roade)			
S Northants Tube_RO2	57251	DT	31.1	17.0	-45.3%	
S Northants Tube_RO3	57251	DT	26.6	14.0	-47.4%	
S Northants Tube_RO1	7724	DT	22.5	13.9	-38.4%	
S Northants Tube_RO6	7724	DT	31.7	14.9	-53.2%	
West Lodge Cottages						
Project Tube 6	57251	DT	36.2	16.1	-55.5%	

Figure A9.3.6: Monitored vs Modelled NO_x




Table A9.3.12: Comparison of Monitored and Modelled Total NO₂

Monitor Location	DfT Count Point Typ	Type	Concentration	ons (µg.m ⁻³)	Difference	
		туре	Monitored	Modelled	(%)	
		Roade)			
S Northants Tube_RO2	57251	DT	31.1	34.5	10.9%	
S Northants Tube_RO3	57251	DT	26.6	24.4	-8.3%	
S Northants Tube_RO1	7724	DT	22.5	23.9	6.1%	
S Northants Tube_RO6	7724	DT	31.7	27.3	-13.9%	
West Lodge Cottages						
Project Tube 6	57251	DT	36.2	36.2	-0.1%	

Bilsworth and Milton Malsor

- Year(s) of verification: 2015
- No DfT traffic data available for verification; as such, adjustment factor for Roade has been used.
- Verification factor(s):
 - o 2015: 3.84 (Roade)

Towcester

- Year(s) of verification: 2015
- Parts of Towcester modelled as a simple Canyon.
- A number of DT not considered in verification as not considered representative of residential
 use
- Verification factor(s):
 - o 2015: 2.97 (Canyon), 7.35 (Not Canyon)

Table A9.3.13: Comparison of Monitored and Modelled Total NO₂

Monitor Location	ion DfT Count Point	Туре	Concentrations (µg.m ⁻³)		Difference
Monitor Location			Monitored	Modelled	(%)
TK1	49051	DT	47.2	24.1	-49.0%
TK7	49051	DT	22.1	12.3	-44.5%
TK9	49051	DT	31.8	12.8	-59.8%

Figure A9.3.7: Monitored vs Modelled NO_x




Table A9.3.14: Comparison of Monitored and Adjusted Modelled Total NO₂

Manitar Lagation	DfT Count	I IVNA –	Concentration	Difference	
Monitor Location	Point		Monitored	Modelled	(%)
TK1	49051	DT	47.2	47.0	-0.4%
TK7	49051	DT	22.1	25.7	16.4%
TK9	49051	DT	31.8	28.9	-9.0%

Hartwell

- Year(s) of verification: 2015
- Verification factor(s): 1
- Modelled results were greater than monitored; to ensure a conservative assessment no adjustment factor was applied to the results.

Table A9.3.15: Comparison of Monitored and Modelled Total NO₂

Monitor Location DfT Count Point	Type	Concentrations (µg.m ⁻³)		Difference	
	Point	Туре	Monitored	Modelled	(%)
H1	73811	DT	21.3	22.9	7.4%

Note: "DT" = diffusion tube.-

Grafton Regis and Potterspury

- Year(s) of verification: 2015
- No DfT traffic data available for verification; as such, adjustment factor for Roade has been used.
- Verification factor(s): 3.84 (Roade)