### **Tritax Symmetry (Hinckley) Limited**

# HINCKLEY NATIONAL RAIL FREIGHT INTERCHANGE

## The Hinckley National Rail Freight Interchange Development Consent Order

**Project reference TR050007** 

## **SoCG between the Applicant and Environment Agency**

Document reference: 19.9

**Revision: 01** 

#### **24 October 2023**

Planning Act 2008

The Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009 Regulation 5(2)(q)

#### October 2023

### **Planning Act 2008**

#### TRITAX SYMMETRY (HINCKLEY) LIMITED

# PROPOSED HINCKLEY NATIONAL RAIL FREIGHT INTERCHANGE OFF M69 JUNCTION 2, LEICESTERSHIRE

**DOC REF: 19.9** 

Statement of Common Ground between
Tritax Symmetry (Hinckley) Limited
and the Environment Agency

# Matters Agreed Matters Not Agreed

#### **Ecology Version Control**

Version	Date	Issued by
01	18.05.2023	TSL
02	05.06.2023	Environment Agency
03	15.06.2023	TSL

Geology, Soils and Groundwater Version Control

Geology, John and Groundwater Version Control		
01	14.05.2023	TSL
02	25.05.2023	<b>Environment Agency</b>
03	19.06.2023	TSL
04	29/06/2023	<b>Environment Agency</b>

#### **Flood Risk Version Control**

01	16/05/2023	BWB Consulting	
02	22/06/2023	Environment Agency	
03	28/06/2023	BWB Consulting	
04	26/09/2023	Environment Agency	

#### **Collated SoCG Version Control**

Collated Soco Version Control			
01	26/09/2023	TSL	
02	16/10/2023	EA	
03	19/10/2023	TSL	

#### **CONTENTS**

- 1. MATTERS OF AGREEMENT AND DISAGREEMENT
- 1.1. Flood Risk
- 1.2. Ecology
- 1.3. Geology, Soils and Groundwater
- 2. AGREEMENT ON THIS SOCG

#### 1. MATTERS OF AGREEMENT AND DISAGREEMENT

## Flood Risk Matters agreed

Ref.	Matter agreed	Record of agreement
1.	The Flood Risk Assessment and ES Chapter	Agreed through this
	14 have been prepared in accordance with	SoCG
	the National Policy Statement for	
	National Networks (NPSNN).	
2.	The submitted surface water and flood risk ES Chapter 14 includes an agreed	Agreed through this SoCG
	methodology and approach to assessment of flood risk including the effects of climate change.	
3.	The proposed scheme is at an acceptable	Agreed through this
	level of flood risk and, subject to the	SoCG
	implementation of the flood risk	
	management principles outlined in the	
	Flood Risk Assessment, and the surface	
	water drainage principles agreed with	
	the Lead Local Flood Authority, the	
	proposed scheme will seek to	
	appropriately mitigate flood risk in line	
	with best practice guidance	
4.	Matters contained in the CEMP	Agreed through this
	(document reference 17.1) in relation to	SoCG
	water resources and flood risk	
	(paragraphs 1.94 - 1.109) are considered	
	appropriate to address the construction	
	phase of the Proposed Development.	
5.	In accordance with requirement 7 of the	Agreed through this
	draft DCO, phase specific CEMPs to be	SoCG
	prepared prior to the construction of	
	each development phase. This will	
	include details of any necessary	
	temporary (or otherwise) flood risk and	
	surface water quantity and quality	
, ,	management measures. The	
	performance of implemented measures	
	should be monitored and changes made	
	where appropriate in order to maintain	

	water quality and adequately mitigate flood risk during the construction period.	
6.	The Environment Agency are comfortable with the content of the draft DCO relating to flood risk and water environment.	Agreed through this SoCG

## Matters not agreed.

Ref.	Matter not agreed
1.	None

## **Ecology Matters agreed**

Ref.	Matter Agreed	Record of Agreement
1.	A Preliminary WFD Assessment	Correspondence
	(Document reference: 12.1) has been	24/05/22 and agreed
	undertaken and was provided to the	through this SoCG
	Environment Agency. The Environment	
	Agency confirmed on 24 May 2022 that	
	on review of the submitted report, there	
2	were "no adverse comments to make".	
	No further assessment is therefore	
	required.	
2.	A comprehensive Biodiversity Net Gain	Agreed through this SoCG
	assessment has been undertaken (see	
	Appendix 12.2 'Biodiversity Impact	
	Assessment Calculations', document	
	reference 6.2.12.2), which details where	
	gains have been achieved. This includes an	
2 4	assessment of hedgerow, stream and wet	
	ditch habitat (i.e. linear habitat). The	
	onsite habitats have been designed to	
	maximise benefits where possible. Off-	
	site compensation land has been provided	
	in the closest area possible to the site in	
	order to provide the gains required in the	
	locality.	
	Current calculations show a net loss of	
	river habitat. Further River Corridor	
	Assessment (RCA) works and hydrology	
	modelling works are underway in order	
	to maximise river unit gains/minimise	
	unit losses on-site wherever possible.	
	Off-site solutions are also being explored.	
3.	The CEMP (Appendix 17.1, document	Agreed through this SoCG
	reference: 17.1) has been produced taking	
	into consideration the feedback received	
	from the Environment Agency including	
	pollution prevention. Pollution prevention	
	around surface water and hydrogeology	
* 1 th s	are covered specifically in the CEMP under	
	the surface water and hydrogeology	
	section.	
October 20		

#### Matters not agreed.

Ref.	Matter not agreed	
1.	None	

The agree that water retains of

## Geology, Soils and Groundwater Matters agreed

Ref.	Matter agreed	Record of agreement
1.	ES Chapters 15 and 16 have been prepared	Agreed through this
	in accordance with the National Policy	SoCG
	Statement for National Networks	
	(NPSNN).	
2.	The contaminated land requirement's	Agreed through this SoCG
	are agreed.	
	Requirement will be added to	
	Requirement 15 of the Draft DCO, it	
	reads:	
	"Prior to each phase of development	
	being brought into use, a verification	
	report demonstrating the completion of	
	works set out in the approved	
	remediation strategy and the	
	effectiveness of the remediation shall,	
	after consultation with the Environment	
	Agency, be submitted to and approved	
	by the relevant planning authority.	
		· 1 · 1
	The report shall include results of	
	sampling and monitoring carried out in accordance with the approved	
	verification plan to demonstrate that	
	the site remediation criteria have been	
	met."	
3.	Paragraphs 1.110 - 1.115 under the	Agreed through this
J.	section Ground Conditions,	SoCG
	Contamination and Hazardous Material	
	of the CEMP is agreed.	
4.	The assessment methodology has been	Agreed through this
٦.	accepted comprising a	SoCG
	Preliminary risk assessment	
	Preliminary risk assessment     Preliminary ground investigation	
	Detailed ground investigation	
	and risk assessment to be	
	completed after Examination and	
	publication of DCO	
	Remediation Strategy	

	Verification Plan     Verification Report	
5.	<ul> <li>Verification Report         Agreed that the preliminary ground investigation is adequate to characterise the site for the purposes of the application.     </li> </ul>	Agreed through this SoCG
6.	Remediation Strategy to be prepared and submitted to the EA and HBC and HBBC EHO for approval as part of detailed design. To be completed after detailed investigation. Some areas may be inaccessible until the demolition of existing buildings.	Agreed through this SoCG
7.	The development will include good practice measures to prevent pollution from any stored chemicals or contaminated run off entering controlled waters. The measures will include, but not be limited to, the incorporation of interceptors and sealed drainage systems in operational areas, yards and bunding of all chemical storage areas. The measures shall be regularly monitored during the lifetime of the development to ensure that the measures can prevent any pollution entering the underlying groundwater or surface waters for the lifetime of the development.	Agreed through this SoCG
8.	There would be a watching brief during removal of any existing tanks during decommissioning and demolition.	Meeting with HBBC, BDC and LCCC EHO 23 November 2022. Confirmed within the Construction Environmental Management Plan (document reference: 17.1). Requirements 7 and 15 of the Draft DCO (document reference 3.1).

		Agreed through this SoCG.
9.	The scope of detailed investigation will be within Requirement 15 of the draft DCO Requirement for site wide and phase specific investigations.	Requirement 15 as listed within the Draft DCO (document reference: 3.1)

#### Matters not agreed.

Ref.	Matter not agreed
1.	None

## 2. AGREEMENT ON THIS SOCG

This Statement of Common Ground has been jointly prepared and agreed by:

Name:	Sinead Turnbull
Signature:	Janes - Control of
Position:	Planning Director
On behalf of:	Tritax Symmetry (Hinckley) Limited
Date:	24 october 2023
Name:	Nick Wakefield
Signature:	
Position:	Planning Specialist
On behalf of:	The Environment Agency
Date:	24 October 2023.